

**Section 4.0 - Specification for Community Monitoring  
Amendment  
Submission Date: May 07, 2008**

**Title**            **Section 4.0 - Specification for Community Monitoring**

<b>Amendment #1</b>
---------------------

**Reason for the Amendment:**

The demolition of the roof is schedule to commence. Our approved plan describes lowering the roof community monitoring stations with the demolition schedule. As such, we are requesting approval to move station #7 on the southern end of the east side of the roof and station #8 on the north side of the roof to the scaffold. Station #7 will be placed on the southern end of the east side of the 9<sup>th</sup> floor scaffold and become station #9 and station #8 will be placed on the north side of the 9<sup>th</sup> floor scaffold and become station #10. These moves are to allow for demolition activities on the roof and the change in designation is to allow for more accurate data management.

Although the approved plan calls for a 4 floor buffer zone between demolitions activities and other activities below this cannot be adhered to for the community monitoring.

Immediately before any activities at the community monitoring locations are to be performed the construction manager and the demolition contractor will be notified. The construction manager and the demolition contractor have agreed to cease all work above any community monitoring activities for the duration of these activities. This notification and suspension of activities will take place multiple times throughout a given work day.

**Sub-sections of the Specification affected:**

**Section 2.0**

Sub-section 2.0, paragraph 5;

Change 8 locations to 10 locations

Change sites #3 - #8 to sites #3 - #10

Sub-section 3.0, paragraph 1, list of community monitoring locations;

Add to #7 & #8 – decommissioned on (Implementation Date)

Add #9 – Former station #7 moved on (Implementation Date) to Southern end of the east side of the 9<sup>th</sup> floor scaffold

Add #10 – Former station #8 moved on (Implementation Date) North side of the 9<sup>th</sup> floor scaffold

Sub-section 3.0 – “Elevation Air Monitoring Stations” diagram;

Add attached diagram for stations #9 & #10 on the 9<sup>th</sup> floor.

Sub-section 5.0 – List at the end of the paragraph 1;

Edit #7 to read “Station moved down to Station #9 on (Implementation Date) per the demolition schedule

Edit #8 to read “Station moved down to Station #10 on (Implementation Date) per the demolition schedule

Add #9 – Former station #7 moved on (Implementation Date) to Southern end of the east side of the 9<sup>th</sup> floor scaffold

Add #10 – Former station #8 moved on (Implementation Date) North side of the 9<sup>th</sup> floor scaffold

Sub-section 6.0 – paragraph 7;

Delete sites #3 - #8 and add sites #3 - #10

Sub-section 6.0 – paragraph 9;

Delete sites #3 - #8 and add sites #3 - #10

## Section 4.0

Sub-Section 2.0, 5<sup>th</sup> to last paragraph

Delete sites #3 - #8 and add sites #3 - #10

See attached diagram of the proposed #9 & #10 monitoring locations on the 9<sup>th</sup> floor.

Date Implemented: To Be Determined

# Elevation Air Monitoring Locations

