

# **Air Quality Assessments and Monitoring Programs for the Central Artery / Tunnel Project Boston, Massachusetts**

**John Formosa**

**Federal Highway Administration – Boston, MA**

**Alex Kasprak**

**Massachusetts Turnpike Authority – CA/T Project**



9 LAPS  
NEW YORK OUTPOST  
THINKING BEING FOR ME

WHEN THE NEWS BREAKS  
WE PUT IT TOGETHER.  
NEWSWIRE 1  
WE ARE THE CITY

180,000 Vehicles

POINTS  
SOUTH

EXIT 23  
DOWNTOWN  
BOSTON

EXIT 24  
CALLAHAN TUNNEL  
DOCK SQ.

# Central Artery / Tunnel Highlights

- ◆ 2 Two-lane tunnels under Boston Harbor (I-90)
- ◆ 2 Five-lane tunnels through downtown Boston (I-93)
- ◆ Ten lane cable-stayed bridge over Charles River
- ◆ 6 Ventilation Buildings
- ◆ 8 Longitudinally ventilated exit ramps





























# Construction Highlights

Within 7.5 mile corridor

- ◆ 160 Lane-miles of new highways
- ◆ 80 Lane-miles of new tunnels
- ◆ 150 Acres of new parks
- ◆ 13 million cu-yards of excavated material
- ◆ 4 million cu-yards of concrete poured
- ◆ Over 200 pieces of construction equipment in simultaneous operation



# Construction Period 1992-2005

- ◆ 1992 Utility Relocation
- ◆ 1992 Ted Williams Tunnel (TWT) started
- ◆ 1995 TWT opened to commercial traffic
- ◆ 1997 Downtown tunnels started
- ◆ 1998 Charles River Bridge started

# Opening Schedule

- ◆ September 2002 TWT / I-90
- ◆ November 2002 I-93 Northbound
- ◆ November 2003 I-93 Southbound  
(north section)
- ◆ November 2004 I-93 Southbound  
(south section)



# History of Environmental Assessments

- ◆ 1985 EIS/R
- ◆ 1990 Supplemental EIS/R (14 Volumes)
- ◆ 1991 ROD – FHWA/MHD
- ◆ 1994 Charles River Crossing SEIS/R
- ◆ 1995 FHWA Longitudinal Ventilation
- ◆ 1995-2000 Over 10 NPCs/ERs

# Critical Environmental Aspects

- ◆ Disposal of excavated material
- ◆ Marine and aquatic impacts
- ◆ Pest control program
- ◆ Water quality on discharged waters
- ◆ Noise and vibration control
- ◆ Air Pollution control



# Air Quality Analysis

- ◆ Regional (area-wide) emissions assessment
  - *Carbon Monoxide (CO), Nitrogen Oxides (NO<sub>x</sub>), Non-methane Hydrocarbons (NMHC), Particulate Matter (PM<sub>10</sub>)*
- ◆ Localized (microscale) impacts at intersections
  - *CO*
- ◆ Impacts of ventilation system emissions
  - *CO, NO<sub>2</sub>, PM<sub>10</sub>*
- ◆ Impacts of construction activities
  - *CO, PM<sub>10</sub>*

# National & State Ambient Air Quality Standards (NAAQS)

## ♦ CO

- *One-hour = 35 ppm*
- *Eight-hour = 9 ppm*

## ♦ NO<sub>2</sub>

- *Annual 100 ug/m<sup>3</sup>*
- *One-hour 320 ug/m<sup>3</sup> (DEP Policy Guideline)*

## ♦ PM<sub>10</sub>

- *Annual 50 ug/m<sup>3</sup>*
- *24-hour 150 ug/m<sup>3</sup>*



# Air Quality Analysis

## 1990 SEIS/R Construction Period

- ◆ Localized CO modeling at intersections
  - *Year 1994*
  - *19 intersections*
  - *Highest 8-hour level = 11.1 ppm*
  - *3 Intersections above NAAQS*
- ◆ PM<sub>10</sub> modeling at construction areas
  - *Excavation, earth moving, truck traffic,*
  - *3.7 acre, 5,300 tons/day, 250 trucks/day*
  - *Highest 24-hour PM<sub>10</sub> = 160 ug/m<sup>3</sup>*

# Construction Air Quality Committee (CAQC)

- ◆ Formed 1991 as part of FHWA ROD
- ◆ Represented by:
  - *FHWA, MTA, EPA, DEP, City of Boston*
- ◆ Evaluates air quality impact studies
- ◆ Determines monitoring activities
- ◆ Recommends mitigation and control programs

# CO Monitoring Program

## Started 1992 ongoing

- ◆ Sites include most congested intersections
- ◆ Areas most affected by construction detours
- ◆ 4 – 8 sites - 3 weeks every winter
- ◆ Location: light poles – 10 feet height
- ◆ Two 8-hour periods per day
- ◆ Portable MiniVOL CO air samplers
- ◆ Air samples measured with NDIR analyzer







  
**Street  
Cleaning**  
2:01am-7:00am  
**Tow Zone**

**TOW ZONE**







# **CO Monitoring Program**

## **Results 1992-2002**

- ◆ 32 locations during 11 years
- ◆ 3,600 eight-hour samples collected
- ◆ Peak hour traffic 2,000 to 6,000 vehicles
- ◆ PM period higher than AM 90% of time
- ◆ Three highest locations 1993-1995
  - 5.6 to 7.1 ppm
- ◆ Same locations 2000-2002
  - 2.5 to 3.5 ppm

# Dust Control Program

- ◆ Contract specific requirements
- ◆ Truck wheel wash stations
- ◆ Extensive use of watering trucks
- ◆ Dust suppression agents (Soil-Sement)
- ◆ Dust screens and barriers
- ◆ Vacuum sweepers on paved roads
- ◆ Hydro seeding of stockpiles
- ◆ Crushed stones at ingress/egress roads

































WATER

CHRYSLER  
CHRYSLER SUPPLY CO.  
1-800-342-2279



















# **Dust Control Inspection Program**

- ◆ Inspect three times/week all sites
- ◆ Observable dust and diesel emissions
- ◆ Dirt tracking onto public roads
- ◆ Compliance with Dust Control Specification
- ◆ Enforcement (Deficiency Reports)

# **PM<sub>10</sub> Monitoring Program**

## **1992 - Ongoing**

- ◆ One permanent station
- ◆ 8-10 portable MiniVOL samplers
- ◆ 3 weeks/year (1992-1996)
- ◆ 4 months/year (1997 -2001)
  - Twice a week – June to October
- ◆ Over 400 24-hours samples/year



# **PM<sub>10</sub> Monitoring Program**

## **Site Selection Criteria**

- ◆ Level of construction activity
- ◆ Sensitive abutters
- ◆ Downwind from construction areas
- ◆ High levels measured in previous years
- ◆ Community concerns

# PM<sub>10</sub> Monitoring Equipment

- ◆ AIRMetrics MiniVOL Samplers
- ◆ CAHN C-33 Microbalance
- ◆ TEOM 1400 monitor
- ◆ RS-232 Data Logger











SALEM ST

RAVELLO

Flee

MOBILE  
WEBCONFERENCING  
ONLY FROM

NO  
TURN  
ON RED

BUSES  
EXCLUDED

BUSES  
EXCLUDED

DETOUR  
AHEAD

FREE  
mix

















# PM<sub>10</sub> Results

- ◆ Permanent rooftop monitoring station
  - *25 – 70 ug/m<sup>3</sup>*
- ◆ Sidewalk monitors
  - *30 – 330 ug/m<sup>3</sup>*
- ◆ Mean construction impacts
  - *< 100 feet from construction area 10 – 80 ug/m<sup>3</sup>*
  - *100-250 feet from construction 10 – 40 ug/m<sup>3</sup>*




# Construction Effects on PM<sub>10</sub> Levels

- ◆ Effects of construction activities localized
  - *(less 250 feet)*
- ◆ Largest source of PM<sub>10</sub> re-suspended dust from exiting trucks
- ◆ Additional mitigation and enforcement reduces peak increments by 50 %
- ◆ Background PM<sub>10</sub> monitored levels constant during last 10 years ( $\sim 30 \text{ ug/m}^3$  annual average)
- ◆ Highest PM<sub>10</sub> levels cut by half from 1997 to 2001
  - *(330 ug/m<sup>3</sup> to 168 ug/m<sup>3</sup>)*

# Diesel Emission Control Program

- ◆ Assigned staging zones for waiting trucks
- ◆ Limit diesel idling to less than 5 minutes while not operating
- ◆ Retrofit construction equipment with oxidation catalysts





# Downtown Construction – Proximity to Pedestrians

ONE WAY

**CAUTION**  
LOOK  
LEFT  
Before  
Crossing

**CAUTION  
PEDESTRIANS**  
TRUCKS MAKING  
WIDE TURNS  
STOP HERE





Parking  
Only

**ATTENTION  
TRUCK DRIVERS:**

**STATE  
REGULATION  
ENGINE IDLING  
TIME LIMITED  
TO:  
5 MINUTES  
MAXIMUM**

ONE WAY



CHEVROLET

MASSACHUSETTS  
173-LYK



# Downtown Tunnel Construction



# **Diesel Retrofit Program for Construction Equipment**

- ◆ Reduce diesel impacts on abutters and construction workers.
- ◆ Help CA/T Project meet its environmental commitments.
- ◆ Reduce regional emissions.
- ◆ Good public relations.



# Diesel Retrofit Program

- ◆ Originated in fall 1998 in collaboration with the Massachusetts DEP and NESCAUM.
- ◆ Only off-road equipment retrofitted.
- ◆ Focus on equipment near:
  - *Residential communities.*
  - *Hospitals.*
  - *Building fresh air intakes.*
  - *Underground areas (worker health & safety)*

# **Oxidation Catalysts Instead of Diesel Particulate Filters**

- ◆ Reduce CO, HC, PM
- ◆ Ease of installation and maintenance
- ◆ Lower unit cost (\$ 2,000 versus \$ 13,000)
- ◆ Proven technology (over 1 million in use)



# Retrofit Program Phase 1

- ◆ 8 pieces of equipment retrofitted
- ◆ 3 contractors participated
- ◆ Oxidation catalysts provided by MECA
- ◆ Contractors contributed installation costs
- ◆ Equipment manufacturers provided written assurance on engine warranty

# Retrofit Program Phase 2

- ◆ Retrofitted 60 additional pieces of equipment
- ◆ CA/T paid  $\frac{1}{2}$  the cost of each oxidation catalyst
- ◆ Contractors paid remaining cost and installation costs



# Equipment Retrofitted

- ◆ 50 – 300 HP range engines
  - cranes
  - lifts
  - excavators
  - bulldozers
  - generators
  - compressors







D6R LGP

MODERN

# **Retrofit Program Costs & Operational Issues**

- ◆ Oxidation Catalysts cost \$1,000 to \$3,000 per unit (\$2,500 average)
- ◆ Installation time < 2 hours.
- ◆ No adverse effects on equipment performance.
- ◆ 60 installed during Phase 2
- ◆ Warranty concerns (resolved in Phase 1)



# Future CA/T Retrofits

- ◆ Retrofitting incorporated into Odor Control Specification 721.562
- ◆ 75 to 100 additional pieces of off-road pieces to be retrofitted between 2001 - 2004

**CAT** REGD

**TH83**



**THIS MACHINE  
IS EQUIPPED WITH  
AN AIR POLLUTION  
CONTROL DEVICE**

**NOTICE**

IMPROPER LIFTING OR  
CAN ALL OR LEAD TO  
CAUSE INJURY AND DEATH.  
1. ALWAYS USE PROPER LIFTING  
TECHNIQUE TO MAINTAIN A BALANCE  
2. NEVER LIFT WITH YOUR BACK  
3. NEVER LIFT WITH YOUR KNEES  
4. NEVER LIFT WITH YOUR ARMS  
5. NEVER LIFT WITH YOUR FEET  
6. NEVER LIFT WITH YOUR SHOULDERS  
7. NEVER LIFT WITH YOUR WRISTS  
8. NEVER LIFT WITH YOUR ELBOWS  
9. NEVER LIFT WITH YOUR ANKLES  
10. NEVER LIFT WITH YOUR NECK  
11. NEVER LIFT WITH YOUR HEAD  
12. NEVER LIFT WITH YOUR CHEST  
13. NEVER LIFT WITH YOUR STOMACH  
14. NEVER LIFT WITH YOUR THIGHS  
15. NEVER LIFT WITH YOUR BUTTOCKS  
16. NEVER LIFT WITH YOUR FEET  
17. NEVER LIFT WITH YOUR KNEES  
18. NEVER LIFT WITH YOUR ARMS  
19. NEVER LIFT WITH YOUR WRISTS  
20. NEVER LIFT WITH YOUR ELBOWS  
21. NEVER LIFT WITH YOUR ANKLES  
22. NEVER LIFT WITH YOUR NECK  
23. NEVER LIFT WITH YOUR HEAD  
24. NEVER LIFT WITH YOUR CHEST  
25. NEVER LIFT WITH YOUR STOMACH  
26. NEVER LIFT WITH YOUR THIGHS  
27. NEVER LIFT WITH YOUR BUTTOCKS  
28. NEVER LIFT WITH YOUR FEET  
29. NEVER LIFT WITH YOUR KNEES  
30. NEVER LIFT WITH YOUR ARMS  
31. NEVER LIFT WITH YOUR WRISTS  
32. NEVER LIFT WITH YOUR ELBOWS  
33. NEVER LIFT WITH YOUR ANKLES  
34. NEVER LIFT WITH YOUR NECK  
35. NEVER LIFT WITH YOUR HEAD  
36. NEVER LIFT WITH YOUR CHEST  
37. NEVER LIFT WITH YOUR STOMACH  
38. NEVER LIFT WITH YOUR THIGHS  
39. NEVER LIFT WITH YOUR BUTTOCKS  
40. NEVER LIFT WITH YOUR FEET  
41. NEVER LIFT WITH YOUR KNEES  
42. NEVER LIFT WITH YOUR ARMS  
43. NEVER LIFT WITH YOUR WRISTS  
44. NEVER LIFT WITH YOUR ELBOWS  
45. NEVER LIFT WITH YOUR ANKLES  
46. NEVER LIFT WITH YOUR NECK  
47. NEVER LIFT WITH YOUR HEAD  
48. NEVER LIFT WITH YOUR CHEST  
49. NEVER LIFT WITH YOUR STOMACH  
50. NEVER LIFT WITH YOUR THIGHS  
51. NEVER LIFT WITH YOUR BUTTOCKS  
52. NEVER LIFT WITH YOUR FEET  
53. NEVER LIFT WITH YOUR KNEES  
54. NEVER LIFT WITH YOUR ARMS  
55. NEVER LIFT WITH YOUR WRISTS  
56. NEVER LIFT WITH YOUR ELBOWS  
57. NEVER LIFT WITH YOUR ANKLES  
58. NEVER LIFT WITH YOUR NECK  
59. NEVER LIFT WITH YOUR HEAD  
60. NEVER LIFT WITH YOUR CHEST  
61. NEVER LIFT WITH YOUR STOMACH  
62. NEVER LIFT WITH YOUR THIGHS  
63. NEVER LIFT WITH YOUR BUTTOCKS  
64. NEVER LIFT WITH YOUR FEET  
65. NEVER LIFT WITH YOUR KNEES  
66. NEVER LIFT WITH YOUR ARMS  
67. NEVER LIFT WITH YOUR WRISTS  
68. NEVER LIFT WITH YOUR ELBOWS  
69. NEVER LIFT WITH YOUR ANKLES  
70. NEVER LIFT WITH YOUR NECK  
71. NEVER LIFT WITH YOUR HEAD  
72. NEVER LIFT WITH YOUR CHEST  
73. NEVER LIFT WITH YOUR STOMACH  
74. NEVER LIFT WITH YOUR THIGHS  
75. NEVER LIFT WITH YOUR BUTTOCKS  
76. NEVER LIFT WITH YOUR FEET  
77. NEVER LIFT WITH YOUR KNEES  
78. NEVER LIFT WITH YOUR ARMS  
79. NEVER LIFT WITH YOUR WRISTS  
80. NEVER LIFT WITH YOUR ELBOWS  
81. NEVER LIFT WITH YOUR ANKLES  
82. NEVER LIFT WITH YOUR NECK  
83. NEVER LIFT WITH YOUR HEAD  
84. NEVER LIFT WITH YOUR CHEST  
85. NEVER LIFT WITH YOUR STOMACH  
86. NEVER LIFT WITH YOUR THIGHS  
87. NEVER LIFT WITH YOUR BUTTOCKS  
88. NEVER LIFT WITH YOUR FEET  
89. NEVER LIFT WITH YOUR KNEES  
90. NEVER LIFT WITH YOUR ARMS  
91. NEVER LIFT WITH YOUR WRISTS  
92. NEVER LIFT WITH YOUR ELBOWS  
93. NEVER LIFT WITH YOUR ANKLES  
94. NEVER LIFT WITH YOUR NECK  
95. NEVER LIFT WITH YOUR HEAD  
96. NEVER LIFT WITH YOUR CHEST  
97. NEVER LIFT WITH YOUR STOMACH  
98. NEVER LIFT WITH YOUR THIGHS  
99. NEVER LIFT WITH YOUR BUTTOCKS  
100. NEVER LIFT WITH YOUR FEET



# Emission Reduction Potential

Estimated % reduction according to EPA  
certification list

- ♦ CO = 40%
- ♦ HC = 50%
- ♦ PM = 20%

# Emission Reductions of Retrofit Program

- ◆ For the year 2000:
  - *90 Kg/day (36 tons/yr) of CO*
  - *30 Kg/day (12 tons/yr) of HC*
  - *8 Kg/day (3 tons/yr) of  $PM_{10}$*
- ◆ Based on 88 pieces of equipment retrofitted
- ◆ Reductions double between 2001 -2004
- ◆ Slowly decrease to 2000 levels after 2004





# **Discussion of Results**

## **Construction Effects**

### **Diesel Emission Control Program**

- ◆ Very cost/effective way to reduce emissions
- ◆ Cost of oxidation catalysts 1-2 % of construction equipment
- ◆ Benefits 20-50 % emission reductions
- ◆ Elimination of diesel odors



# Air Quality Trend

## 10 Years of Monitoring Data

- ◆ CO Downward ~ 50 %
- ◆ NO<sub>2</sub> Stable and down ~ 20 %
- ◆ PM<sub>10</sub> Stable and down ~ 15 %
- ◆ O<sub>3</sub> Less NAAQS exceedances per year

# Clean Fuel

- ◆ Use PuriNOx in diesel powered construction equipment
- ◆ PuriNOx - emulsified diesel fuel
  - *No. 2 Diesel + Additive + Water*
- ◆ Reduces NOx and black smoke
- ◆ Slight engine tuning required



# PuriNOx Test

- ◆ Caterpillar 311B excavator
  - Model year 2000 – 79 HP Engine
- ◆ Three weeks – 16 hours/day
- ◆ 600 gallons of PuriNOx
- ◆ Tests compared No. 2 Diesel with winter blend of PuriNOx

# PuriNOx Test Results

- ◆ NOx reductions 24% - 30%
- ◆ Black Smoke reductions 93% - 97%
- ◆ No performance problems
- ◆ Required slightly more power in deep mud conditions
- ◆ Fuel consumption slightly increased



# COSTS

## Oxidation Catalysts Vs Clean Fuel

- ◆ Oxidation Catalysts @ \$ 8/HP
- ◆ PuriNOx @ \$ 0.15/Gallon above No.2 Diesel

# CA/T Environmental Oversight Committee

- ◆ Meets by-weekly to address community concerns/problems
- ◆ Consists of Project and City staff
- ◆ Provides window and dust treatment mitigation measures

