## **Attachment D**

New Source Review (NSR) Settlements in v.2.1.6

|               |                    | Settlement Action                      |                |                 |                       |                |               |                     |                |
|---------------|--------------------|--|----------------|-----------------|-----------------------|----------------|---------------|---------------------|----------------|
|               |                    | Retire/Repower                         |                | SO2             |                       |                | NOx           |                     |                |
| Company/Plant | Unit               | Action                                 | Effective Date | Equipment       | Removal<br>Efficiency | Effective Date | Equipment     | Rate<br>(Ibs/Mmbtu) | Effective Date |
| TECO          |                    |  | •              |                 |                       | •              |               |                     | •              |
| Gannon        | 6 coal steam units | Repower to 550<br>MW Combined<br>Cycle | 2005           |                 |                       |                |               |                     |                |
| Big Bend      | Coal Steam Unit 1  |  |                | Scrubber        | 95%                   | 2005           | Annual<br>SCR | 0.1                 | 2010           |
|               | Coal Steam Unit 2  |  |                | Scrubber        | 95%                   | 2005           | Annual<br>SCR | 0.1                 | 2010           |
|               | Coal Steam Unit 3  |  |                | Scrubber        | 95%                   | 2005           | Annual<br>SCR | 0.1                 | 2010           |
|               | Coal Steam Unit 4  |  |                | Scrubber        | 95%                   | 2005           | Annual<br>SCR | 0.1                 | 2005           |
| PSEG          |                    |  |                |                 |                       |                |               |                     |                |
| Mercer        | Coal Steam Unit 1  |  |                | Dry<br>Scrubber | 90%                   | 2013           | Annual<br>SCR | 0.084               | 2001           |
|               | Coal Steam Unit 2  |  |                | Dry<br>Scrubber | 90%                   | 2011           | Annual<br>SCR | 0.084               | 2004           |
| Hudson        | Coal Steam Unit 2  |  |                | Dry<br>Scrubber | 90%                   | 2007           | Annual<br>SCR | 0.046               | 2007           |

Note: Subsequent to the completion of v.2.1.6, an agreement was finalized with VEPCO which included a set of requirements for adding scrubbers and SCRs beyond those already in place. Equipment in place or being installed like the scrubbers and SCR controls at VEPCO's Mount Storm plant and previously announced actions like VEPCO's decision to repower Possum Point coal steam units 3 and 4 to natural gas combined cycle were included in v.2.1.6.