

# Dust Suppression and Soil Stabilization Products

Drew Trenholm, MRI March 13, 2002



### Background


Why verify dust suppressants and soil stabilizers?

- 1.5 million miles of unpaved roads in U.S.
- Dust generated from unpaved roads contributes to fine PM air pollution issues
- New products are coming onto the market
- States and counties want demonstrations



### PM <sub>2.5</sub> Emissions

#### Direct PM<sub>2.5</sub> Emissions – 1997





### Joint Program with CERF

- CERF is research affiliate of American Society for Civil Engineers
  - EvTEC ETV program
  - HITEC Highway Innovative Technology Evaluation Center
- Joint protocol
- APCT Center conducting verification testing




#### Fall 2001 Fort Leonard Wood Test

- Air pollutant dust emissions only
- Correlating mobile dust sampler with profiling
- Seven products three vendors
- Four test series over 3 months
- Completed field work in January
- Currently
  - Completing data analyses and QA review
  - Started drafting reports



#### Fort Leonard Wood Test Site





# **Dust Suppressant Application**





# **Profiling Towers**





## Mobile Dust Sampler







# What We Learned – Mobile Dust Sampler

- Single test runs poor precision
- Mean of multiple test runs " \_\_\_% with 90% confidence
- Can do a test run in an hour



### What We Learned - Protocol

- Removed Method 9 VE observations
- Removed "watering" baseline
- Removed uncommon, expensive toxicity tests
- Made laboratory tests of products optional
- Vendor can provide laboratory analyses



#### **Next Verification Tests**

- Tests will run 12 months
- Include control efficiency tests, dust suppression functionality and soil stabilization testing options
- Testing with Mobile Dust Sampler only
- Sites are
  - Maricopa County, Arizona
  - Fort Leonard Wood, Missouri



#### Schedule

 Site survey and vendor meetings March

 Product application uncontrolled testing May – June

 Control efficiency tests Quarterly

Verification statements/reports Summer 2003