

DIVISION 1 - GENERAL REQUIREMENTS

SECTION 01310 - PROGRESS SCHEDULES

PART 1 - GENERAL

1.01 - WORK SEQUENCE

- A. A complete project "Time and Progress" schedule should be developed in detail by Prime Contractor. The schedule shall include work of all trades and subcontractors including Shop Drawings. The schedule shall indicate all areas of work and dates for such work. The schedule shall be reviewed by the EPA On-Site Representative and Architect. Modifications and changes shall be incorporated as required. The final revised schedule shall be the guide for all work of all trades and shall be adhered to by all parties.

Construction schedule to include shop drawings schedule and submissions.

All construction must be accomplished at the convenience of the EPA. No work shall be undertaken which has not been previously scheduled on the date of the Time and Progress Schedule. If access to occupied areas is required which is not indicated on Time and Progress schedule, person to person notice must be given to the EPA's On-Site Representative fourteen (14) calendar days prior to necessary access. Such access may be granted as conditions permit. Original Time and Progress schedule shall be revised and updated biweekly or as necessary, all revisions shall be reviewed and approved by all parties concerned.

1.02 - WORKING CONDITIONS

- A. All work in large parking areas or involving trenching of main driveways shall be performed between the hours of 6:00 p.m. and 6:00 a.m. Monday through Friday or anytime Saturday, Sunday or federal holidays. Upon daily completion of the work, all parking areas shall be restored to operable conditions (on a daily basis). All other work shall be performed during normal working hours. All debris must be removed on a daily basis. A dumpster will not be used on this project. All trenching of driveways shall be plated over daily and made passable to vehicular traffic.

- B. No drinking of alcoholic beverages will be permitted on premises. Smoking shall be permitted except within seventy feet of building entrances or within building.

1.03 - EPA'S REPRESENTATIVE

- A. The EPA shall appoint an individual as a designated On-Site Representative for this project.

END