DIVISION 1 - GENERAL REQUIREMENTS

SECTION 01400 - QUALITY CONTROL

PART 1 - GENERAL

1.01 - QUALITY ASSURANCE

- A. QUALIFICATION OF MANUFACTURER
 Products used on the work of this project shall be
 produced by manufacturers regularly engaged in
 manufacture of similar items and with a history of
 successful production acceptable to the EPA's On-Site
 Representative.
- B. QUALIFICATION OF INSTALLERS

 Use adequate number of <u>SKILLED WORK PERSONS</u> who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this project.
- C. SINGLE SOURCE
 All like materials, or equipment involved in this project shall be produced by a single manufacturer unless otherwise approved by the EPA's On-Site Representative.

1.02 - JOB CONDITIONS

A. DUST AND WORK AREA ACCESS CONTROL

Use all means necessary to control dust from and access to and near the work and on and near all off-site areas if such dust is caused by the Contractor's operations during performance of the work or if resulting from the condition in which the Contractor leaves the site. All temporary partitions for work inside buildings shall be approved by the EPA and shall allow EPA access to adjacent areas so as to conduct normal operations activity in non-construction areas.

B. PROTECTION

Use all means necessary to protect all materials before, during, and after installation and to protect all objects designated to remain. In event of damage, immediately make all repairs and replacements necessary to the approval of the EPA's On-Site Representative and at no additional cost to the EPA.

C. NOISE CONTROL

Use all means necessary to keep noise levels as low as possible. Make the EPA aware of any equipment which produces loud noises.

1.03 - STANDARDS

A. APPLICABLE STANDARDS
Listed in Michigan State Building Code.

1.04 - TESTING

- A. All testing required by each section to be performed by independent certified testing laboratories. Cost by contractor, unless otherwise specified.
- B. Testing laboratory to be approved by EPA's On-Site Representative.

END