

DIVISION 1 - GENERAL REQUIREMENTS

SECTION 01515 - CONSTRUCTION LIMITS AND ENCLOSURES

PART 1 - GENERAL

1.01 - GENERAL

- A. Construction limits are shown on the Drawing. No Contractor activity is permitted beyond these limits except as defined in the Contract Documents without the written permission of the EPA which may be withheld at the EPA's discretion.

1.02 - LIMITS OF WORK AREA

- A. Areas outside the construction limits may not be used by the Contractor for a staging area, storage of materials or any other purpose, except as designated in the Contract Documents. If the area so designated is deemed by the Contractor to be insufficient for the proper execution of his work, he shall so advise in writing with the submittal of his Bid. The areas designated at the time of execution of the Contract between the EPA and the Contractor shall be strictly adhered to. Such designated areas shall be restored by the Contractor to their previous condition upon completion of the work as directed by the EPA.
- B. Contractor must notify the EPA of additional areas which must be temporarily closed off to accommodate the transporting of materials or equipment to or from a work area. Such closure shall be performed only with the EPA's approval and under such restrictions as it feels are necessary.

1.03 - MATERIAL AND EQUIPMENT DELIVERY AND STORAGE

- A. No material may be stored outside of the construction limits unless otherwise designated on the Drawings. Refer to individual Specification Sections for limits on amounts of materials stored in work areas and other storage restrictions.
- B. EPA reserves the right to refuse to allow any material it considers to be a fire hazard to be stored within any area on the EPA's property except as may be otherwise specified elsewhere.

- C. All storage areas shall be cleaned and restored to their original condition in the same manner as any area within the construction limits.

PART 2 - PRODUCTS - NOT APPLICABLE

PART 3 - EXECUTION - NOT APPLICABLE

END