

## **DIVISION 2 - SITE WORK**

### **SECTION 02065 - CLEARING OF SITE**

#### **PART 1 - GENERAL**

##### **1.01 - DESCRIPTION**

- A. For other requirements see General Conditions and General Requirements (Division 1).
- B. SCOPE OF WORK
  - 1. Removal and hauling from site of trash or any other debris encountered, etc. as required to perform the work. Contractor must obtain written approval from the EPA prior to removal of any trees or shrubs. Disposal shall be in accordance with Local and Federal Governing Agencies.
  - 2. Removal and temporary on-site storage of existing topsoil material during construction.
  - 3. Protection of existing utilities.

##### **1.02 - QUALITY CONTROL**

- A. CONTRACTOR QUALIFICATIONS  
Contractor to be experienced in this type of work for not less than five (5) years. Contractor to own operable equipment to perform the work efficiently. Submit references if required by the EPA.

##### **1.03 - REFERENCE STANDARDS**

- A. American Society for Testing of Materials (ASTM).
- B. Michigan Department of Transportation, except as noted otherwise.

##### **1.04 - BUILDING CODES AND REQUIREMENTS**

- A. All work to comply with the State of Michigan, all Federal requirements and all local applicable codes and requirements.

##### **1.05 - COORDINATION**

- A. All the work to be scheduled with the EPA. No interference with building operations will take place.

## **1.06 - EXISTING CONDITIONS**

- A. Visit site and verify earthwork requirements prior to commencing work.

## **PART 3 - EXECUTION**

### **3.01 - EXISTING UTILITIES AND OTHER APPURTENANCES**

- A. Locate any underground utilities by careful hand excavation before starting operations. If utilities are to remain in place, provide protection from damage during construction operations.

All Contractors to call two (2) days before digging to 'Utilities Protection Service' for location of all underground utilities before starting excavation. Contractor to notify non-service utility protection location service companies directly.

- B. Should uncharted, or incorrectly charted, piping or other utilities be encountered during excavation, consult the EPA's On-Site Representative immediately for directions. Cooperate with the EPA and utility companies to keep services and facilities in operation. Repair damaged utilities to satisfaction of the utility, without cost to the EPA.
- C. Do not interrupt existing utilities except when permitted, in writing, by EPA's On-Site Representative, and then only after temporary utility services have been provided, if required.
- D. Walks, etc. to remain shall be properly protected during construction by Contractor. Repair at no additional cost if damaged during construction.
- E. Keep private and city streets and drives clean, free of mud or trash.

### **3.02 - CLEAN-UP**

- A. Remove all trash, debris, not suitable materials, etc. as specified from property, including construction equipment, after finishing the work.
- B. Burning or burial in the property will not be allowed.

END