

Closure and Post-Closure Plan

NAME: Gilbert & Bennett
I.D. NO.: S-L001162372
FILE LOC: L1E
OTHER: 1 of 2 VOLUME

**BY-PRODUCT
MANAGEMENT AREA**

Prepared For:
The Gilbert and Bennett Manufacturing Company
Main Street
Georgetown, Connecticut 06829

April 1992
Revised January 1994
Revised January 1995
Project # 1835-04-4

**MALCOLM
PIRNIE** ENVIRONMENTAL ENGINEERS, SCIENTISTS AND PLANNERS

TABLE OF CONTENTS

<u>Section</u>		<u>Page</u>
1.0	INTRODUCTION	1-1
1.1	Background	1-1
1.2	Regulatory History	1-2
1.3	Closure and Post-Closure Intent	1-3
2.0	WASTE CHARACTERIZATION AND INVENTORY	2-1
2.1	Introduction	2-1
2.2	Site Characterization Activities	2-1
2.2.1	Historic Activities	2-1
2.2.2	Recent Activities	2-2
2.3	Waste Characterization	2-5
2.3.1	Waste Description	2-5
2.3.2	Site Description	2-7
2.3.3	Appropriate and Relevant Criteria	2-8
2.3.4	Extent of Contamination	2-9
2.4	Inventory of By-Product and Impacted Materials	2-12
3.0	HYDROGEOLOGY INVESTIGATION	3-1
3.1	Background	3-2
3.1.1	Site Description	3-2
3.1.2	Bedrock Geology	3-3
3.1.3	Surficial Geology	3-3
3.2	Field Testing	3-4
3.2.1	Monitoring Well Installations	3-4
3.2.2	Groundwater Monitoring	3-5
3.2.3	Permeability Testing	3-6
3.2.4	Private Well Survey and Pump Tests	3-6
3.3	Groundwater Quality	3-8
3.3.1	Overview	3-8
3.3.2	Surficial Aquifer	3-9
3.3.3	Bedrock Aquifer	3-11
3.3.4	Surface Water	3-12
3.4	Site Hydrogeology	3-13
3.4.1	Groundwater Flowpaths	3-13
3.4.2	Mass Loading to the Norwalk River	3-13
3.5	Summary and Conclusions	3-14
4.0	GEOTECHNICAL EVALUATION	4-1
5.0	CLOSURE PLAN	5-1
5.1	Closure Approach	5-1
5.1.1	Description	5-1
5.1.2	Closure Performance Standard	5-3
5.1.3	Comparison With Other Alternatives	5-5
5.2	Waste Stabilization/Capping Plan	5-6

TABLE OF CONTENTS (Continued)

<u>Section</u>		<u>Page</u>
5.2.1	Waste Excavation and Stabilization	5-6
5.2.2	Post-Excavation Soil Sampling and Analysis Plan	5-12
5.2.2.1	Soil Sampling Plan	5-12
5.2.2.2	Soil Analysis Plan	5-13
5.2.3	Capping Plan	5-15
5.2.4	Decontamination of Equipment and Structures	5-18
5.3	Run-on/Run-off Control	5-18
5.4	Flood Protection	5-18
5.5	Construction/Inspection Program Description	5-20
5.5.1	Cap Construction-QA/QC Program	5-20
5.5.1.1	Synthetic Membrane QA/QC Plan	5-20
5.5.1.2	Fabrication Quality Control	5-20
5.5.1.3	Field Quality Control	5-21
5.5.1.4	Liner Installation	5-21
5.5.1.5	Inspection Personnel	5-23
5.5.1.6	Project Meetings	5-23
5.5.2	Compaction	5-23
5.5.3	Equipment, Soil, Miscellaneous Decontamination Procedures	5-24
5.5.4	Environmental Controls	5-25
5.5.5	Health and Safety Plan	5-26
5.6	General Closure Requirements	5-27
5.6.1	Certification Statement	5-27
5.6.2	Survey Plat	5-28
5.6.3	Amendment of Closure Plan	5-28
5.6.4	Post-Closure Notices	5-28
5.7	Cost Estimate	5-29
5.8	Schedule	5-29
6.0	POST-CLOSURE PLAN	6-1
6.1	General Requirements	6-1
6.1.1	Post-Closure Period Length	6-1
6.1.2	Security	6-1
6.1.3	Property Use	6-1
6.1.4	Availability of Post-Closure Plan	6-2
6.1.5	Post-Closure Plan Amendment	6-2
6.1.6	Post-Closure Care Certification	6-3
6.2	Post-Closure Maintenance	6-3
6.3	Post-Closure Groundwater Monitoring	6-3
6.4	Post-Closure Cost Estimate	6-4

LIST OF TABLES

<u>Table No.</u>	<u>Description</u>	<u>Following Page</u>
2-1	Site Background Soils Analytical Data Summary	2-5
2-2	Analytical Data Summary - North End Borings	2-5

TABLE OF CONTENTS (Continued)

LIST OF TABLES (Continued)

<u>Table No.</u>	<u>Description</u>	<u>Following Page</u>
2-3	Constituents of Concern Analytical Data Summary Central Area Borings	2-5
2-4	Constituents of Concern Analytical Data Summary - South End	2-5
2-5	Constituents of Concern Analytical Data Summary - Areas D & E	2-5
2-6	TCLP Data Summary	2-5
2-7	Appropriate and Relevant Criteria	2-8
2-8	Waste Inventory	2-12
3-1	Private Well Sampling	3-7
3-2	Summary of Groundwater Analytical Data - September 26-27, 1991	3-8
3-3	Summary of Groundwater Analytical Data - October 30, 1991	3-8
3-3B	Summary of Groundwater Analytical Data - April 15, 1993	3-8
3-4	Summary of Surface Water Data - September 26, 1991 & October 30, 1991	3-9
5-1	Constituents of Concern and Media Closure Criteria	5-12
5-2	Hazardous Waste Limits	5-14
5-3	10 X DWS Limits	5-14
5-4	Analytical Methods	5-14
5-5	HELP Model Results Summary	5-15
5-6A	Closure Cost Estimate (Alternative No. 1)	5-29
5-6B	Closure Cost Estimate (Alternative No. 2)	5-29
5-7	By-Product Area Closure Construction Schedule	5-29
6-1	Post-Closure Inspection Schedule	6-3
6-2	Field Inspection Log	6-3

TABLE OF CONTENTS (Continued)

LIST OF TABLES (Continued)

<u>Table No.</u>	<u>Description</u>	<u>Following Page</u>
6-3	Post-Closure Routine Maintenance Schedule	6-3
6-4	Post-Closure Monitoring Schedule	6-4
6-5	Annual Post-Closure Groundwater Monitoring Cost Estimate	6-4
6-6	Annual Post-Closure Care and Monitoring Cost Estimate	6-4
6-7	Residential Wells to be Monitored Under Post-Closure Groundwater Monitoring	6-4

LIST OF FIGURES

<u>Figure No.</u>	<u>Description</u>	<u>Following Page</u>
1-1	General Location Map	1-1
2-1	Site Characterization Boring and Test Excavation Location Plan	2-3
2-2	By-Product Management Area Historic Activities	2-7
2-3	General Section A-A - North End of Site	2-7
2-4	General Section B-B - Central Portion of Site	2-7
2-5	General Section C-C - South End of Site	2-7
2-6	General Section N-S	2-7
2-7	Extent of By-Product Below Grade	2-7
2-8	Extent of By-Product Below Groundwater Table	2-7
2-9	Cinder Fill Below Grade	2-7
3-1	Geologic Cross-Section A-A'	3-3
3-2	Geologic Cross-Section B-B'	3-3
3-3	Geologic Cross-Section C-C'	3-3
3-4	Groundwater Table Contour Map - September 26, 1991	3-5

TABLE OF CONTENTS (Continued)

LIST OF FIGURES (Continued)

<u>Figure No.</u>	<u>Description</u>	<u>Following Page</u>
3-5	Groundwater Table Contour Map - October 30, 1991	3-5
3-6	Groundwater Table Contour Map - April 15, 1993	3-5
5-1	Channel Encroachment Lines	5-18
5-2	500-Year Floodway	5-19
6-1	Residential Well Locations	6-4

LIST OF DRAWINGS

<u>Sheet No.</u>	<u>Title</u>
1 of 8	Existing Topography and Piping
2 of 8	Excavation Plan - Alternative No. 1
3 of 8	Excavation Plan - Alternative No. 2
4 of 8	Final Grading Plan - Alternative No. 1
5 of 8	Final Grading Plan - Alternative No. 2
6 of 8	Cross-Sections and Cap Details
7 of 8	Sections and Details
8 of 8	Sections and Details

LIST OF APPENDICES

<u>Appendix</u>	<u>Description</u>
A	NPDES Permit
B	Part A Permit
C	9/28/90 NOD, 11/30/92 Request for Information, 9/11/93 Letter from CTDEP and 11/12/94 Request for Information
D	Site Characterization Program Findings Report
E	Geotechnical Evaluation and Analytical Data

TABLE OF CONTENTS (Continued)

LIST OF APPENDICES (Continued)

<u>Figure No.</u>	<u>Description</u>
F	Malcolm Pirnie Preliminary Stabilization Study
G	Hydrogeologic Investigation Report
H	HELP Model Output
I	QA/QC Plan and Technical Specifications
J	RCRA Cap Runoff Calculations and Drainage Swale Design Calculation
K	FEMA Report Evaluation
L	Closure and Post-Closure Certification Documents
M	RCRA Cap Soil Erosion Calculations
N	Groundwater Sampling Program Protocol
O	Test Excavation Program Findings Report
P	Geosynthetic Bentonite Liner Documentation
Q	500-Year Flood Groundwater Impact Assessment