## Alternatives 3 and 4 Option A

Bunker Hill

Acid Mine Drainage

Disposal of Raw Sludge in CIA Disposal Beds

Order of Magnitude Cost Opinion (Quantity reduced by 10%)

DATE: 11/22/2000 PROJECT NO.: 152215.FS.02 ESTIMATE BY: D. Bunte

N. Gulensoy

Order of Magnitude Cost Opinion (Quantity reduced	a by 10%)				N. Guiensoy
		QTY		TOTAL	
		Reduced by		UNIT	TOTAL
DESCRIPTION	QTY	10%	UNIT	COST	COST
Subgrade Stabilization	10,500	9,450		4.00	\$37,800
Liner Protection Sand	8250	.,	C. Y.	10.00	\$74,250
Drain Rock	1,950	1,755	C. Y.	18.00	\$31,590
Ditch Lining Geotextile	21,200	19,080	S. Y.	1.65	\$31,482
GCL	18,100	16,290	S. Y.	4.05	\$65,975
H D P E Geomembrane	18,100	16,290	S. Y.	5.40	\$87,966
HDPEPipe, 10"	550	495	L. F.	23.00	\$11,385
Erosion Control Matting	11800	10,620	S.Y.	1.50	\$15,930
Perf Pipe, 4"	2000	1,800	L. F.	2.00	\$3,600
Perf Pipe, 6"	580	522	L. F.	3.00	\$1,566
HDPE Pipe, 6"	130	117	L. F.	2.50	\$293
Strip Drains	700	630	L. F.	1.75	\$1,103
Valves, 6" Knife Gate	2		Each	700.00	\$1,400
Valves, 10" Knife Gate	6		Each	1,000.00	\$6,000
Air/Vacuum Release Valve	1		Each	2,000.00	\$2,000
Valve Vault	6		Each	1,950.00	\$11,700
Water Tight Manhole	1		Each	3,500.00	\$3,500
Vertical Filtrate Drains	6		Each	4,000.00	\$24,000
Cleanouts	2		Each	750.00	\$1,500
Perimeter Road Embankment (not reduced)	28275	28,275	C. Y.	10	\$282,750
Chain Link Fence and Gates (not reduced)	1000	1,000	L.F.	12	\$12,000
Crushed Rock Surfacing (not reduced)	1500	1,500	C. Y.	15	\$22,500
SUBTOTAL					\$975,539
MISC ALLOWANCE	10%				\$97,554
SUBTOTAL					\$1,073,092
CONTINGENCY	30%				\$321,928
SUBTOTAL					\$1,395,020
MOBILIZATION	15%				\$209,253
CONSTRUCTION TOTAL					\$1,604,273
SALES TAX ON MATERIALS	5.0%				\$25,622
ENGINEERING AND SUPPORT	20%				\$320,855
CONSTRUCTION MANAGEMENT	8%			*	\$128,342
CAPITAL COST SUBSEQUENT BEDS TOTAL (R	OUNDED)				\$2,080,000
ANNUAL O&M COST FOR OPERATING BED				\$42,000	
NPV OF ANNUAL O&M COSTS (30 YEARS @ 7%	6 INTEREST)				\$518,000
NPV OF INITIAL AND SUBSEQUENT BEDS & CL	OSURES CAPITA	L COSTS @ 7%	INTERE	:ST	\$6,590,000
		- 0 / //	•		
TOTAL 30-YEAR PRESENT WORTH COST @ 7%	INTEREST				\$7,108,000

## NOTES:

Misc Allowance markup is to include items known to exist but cannot be quantified at this time. Contingency is for scope changes that are presently unforeseen.

Mobilization includes bonds, insurance, temporary facilities, health & safety, demobilization, etc.

NOTE: The above cost opinion is in November 2000 dollars and does not include escalation. The order of magnitude cost opinion shown has been prepared for guidance in project evaluation at the time of preparation. The final costs of the project will depend on actual labor and material costs, actual site conditions, productivity, competitive market conditions, final project scope, final schedule and other variable factors. As a result, the final project costs will vary from those presented above. Because of these factors, funding needs must be carefully reviewed prior to making specific financial decisions or establishing final budgets.

SPK/BH RAC/FS.02/Cost Appendix/ Sludge Disposal/BH-AMD-Sludge Alt 3 & 4 Opt A.xls

02/20/2001 7:05 AM

152215.FS.02

## Alternative 3 and 4 Option C

Bunker Hill Acid Mine Drainage

Disposal of Raw Sludge in Smelter Closure Area Disposal Beds

DATE: 11/29/2000 PROJECT NO.: 152215.FS.02 ESTIMATE BY: D. Bunte

			QTY	1	TOTAL	N. Gulensoy
	and the state of the state of the		Reduced by		UNIT	TOTAL
	DESCRIPTION	QTY	10%	UNIT	COST	COST
	COST FOR NEW CELLS IN FUTU					
(DOES N	OT INCLUDE PUMPING AND PIPI	NG COST)				
-	osal Bed (per each)					
Excavatio		25,000	22,500		3.30	\$74,2
-	Preparation	5		Acres	3,300.00	\$14,8
•	Stabilization	10,500		C. Y.	4.40	\$41,5
	ection Sand	8250		C. Y.	19.80	\$147,0
Drain Roc		1,950		C. Y.	19.80	\$34,
	ng Geotextile	21,200	19,080		1.82	\$34,6
GCL		18,100	16,290		4.46	\$72,5
	Geomembrane	18,100	16,290		5.94	\$96,
HDPEF	•	550	495		25.30	\$12,
	ontrol Matting	11800	10,620		1.65	\$17,
Perf Pipe,		2000	1,800		2.20	\$3,9
Perf Pipe,		580	522		3.30	\$1,7
HDPE Pip	·	130	117		2.75	\$3
Strip Drain		700	630		1.93	\$1,3
	' Knife Gate	2		Each	770.00	
	0" Knife Gate	6		Each	1,100.00	
	m Release Valve	1		Each	2,200.00	
Valve Vau		6		Each	2,145.00	
-	ht Manhole	1		Each	3,850.00	
	iltrate Drains	6		Each	4,400.00	
Cleanouts		2		Each	825.00	
	Road Embankment (not reduced)	28275	28,275		11.00	\$311,0
	k Fence and Gates (not reduced)	1000	1,000	L.F.	13.20	\$13,
	ater Monitoring Wells (not reduced) Rock Surfacing (not reduced)	2 1500	4 500	Each	6,600.00	\$13,
Ordaned I	Cock durading (not reduced)	1500	1,300	C. Y.	16.50	\$24,7
SUBTOTA	AL.					\$1,151,6
	LOWANCE	10%				\$115,1
SUBTOTA		,5			-	\$1,266,7
CONTING		30%				\$380,0
SUBTOTA					-	\$1,646,8
MOBILIZA	ATION	15%				\$247,0
CONSTR	UCTION TOTAL				-	\$1,893,8
SALES TA	AX ON MATERIALS	5.0%				\$27,5
ENGINEE	RING AND SUPPORT	20%				\$378,7
CONSTR	UCTION MANAGEMENT	8%			_	\$151,5
CAPITAL	COST SUBSEQUENT BEDS TOTA	AL (ROUNDED)				\$2,450,0
ANNUAL	O&M COST FOR OPERATING BE	D			\$67,000	
NPV OF A	ANNUAL O&M COSTS (30 YEARS	@ 7% INTEREST	)			\$829,0
NPV OF INITIAL AND SUBSEQUENT BEDS & CLOSURES CAPITAL COSTS @ 7% INTEREST						\$11,054,0
	D-YEAR PRESENT WORTH COST					\$11,883,0

## NOTES:

Misc Allowance markup is to include items known to exist but cannot be quantified at this time.

Contingency is for scope changes that are presently unforeseen.

Mobilization includes bonds, insurance, temporary facilities, health & safety, demobilization, etc.

NOTE: The above cost opinion is in November 2000 dollars and does not include escalation. The order of magnitude cost opinion shown has been prepared for guidance in project evaluation at the time of preparation. The final costs of the project will depend on actual labor and material costs, actual site conditions, productivity, competitive market conditions, final project scope, final schedule and other variable factors. As a result, the final project costs will vary from those presented above. Because of these factors, funding needs must be carefully reviewed prior to making specific financial decisions or establishing final budgets.

SPK/BH RAC/FS.02/Cost Appendix/ Sludge Disposal/BH-AMD-Sludge Alt 3 & 4 Opt C.xls

02/22/2001 10:18 AM

152215.FS.02