Sanborn, Head & Associates

*Consulting Engineers & Scientists*

Click here to return to Administrative Record Index

# FEASIBILITY STUDY REPORT

**Beede Waste Oil / Cash Energy Site**
**Plaistow, New Hampshire**
**Volume I - Text**

*Prepared for*
**New Hampshire Department of Environmental Services**

*Prepared by*
**Sanborn, Head & Associates, Inc.**

File 1371
January 2002

*Paul M. Sanborn ■ Charles L. Head ■ R. Scott Shillaber ■ Charles A. Crocetti*
*Mathew A. DiPilato ■ Daniel B. Carr ■ Duncan W. Wood ■ Joseph G. Engels*

**Sanborn, Head & Associates, Inc.**
6 Garvins Falls Road ■ Concord, New Hampshire 03301
e-mail: concord@sanborn-head.com ■ **www.sanborn-head.com**
Fax (603) 229-1919 ■ **Phone (603) 229-1900**

# INSTRUCTIONS FOR USE OF LINKS THROUGHOUT THIS REPORT:

Each section of this document can be accessed by clicking directly on the Table of Contents.

Some of the Appendix sections contain sub-sections which can be accessed by clicking Bookmark headings.

In each section and sub-section page 1 contains a link which takes the user back to the Table of Contents or the page which contains the section's Bookmarked links.

Click on a row to go to the corresponding section

# TABLE OF CONTENTS

## VOLUME I


EXECUTIVE SUMMARY . . . . . i

List of Abbreviations, Acronyms, and Symbols . . . . . I

1.0 INTRODUCTION . . . . . 1

1.1 Purpose of the FS and Organization of the FS Report . . . . . 1

1.2 Site Background . . . . . 2
1.2.1 Site Description . . . . . 2
1.2.2 Site History . . . . . 5
1.2.3 Previous Site Investigations and Remedial Activities . . . . . 9

1.3 Site Hydrogeology . . . . . 16
1.3.1 Site Climate . . . . . 16
1.3.2 Site Geology . . . . . 16
1.3.3 Surface Water Hydrology . . . . . 16
1.3.4 Groundwater Hydrology . . . . . 17

1.4 Nature and Extent of Contamination . . . . . 18
1.4.1 Contaminant Source Areas . . . . . 19
1.4.2 Distribution of Contaminants in Soil . . . . . 20
1.4.3 Distribution of Contaminants in Free Product . . . . . 21
1.4.4 Distribution of Contaminants in Groundwater . . . . . 21
1.4.5 Distribution of Contaminants in Surface Water and Sediment . . . . . 22

1.5 Contaminant Transport and Fate . . . . . 23

1.6 Baseline Human Health and Ecological RAs . . . . . 25
1.6.1 Human Health RA . . . . . 25
1.6.2 Ecological RA . . . . . 26

2.0 IDENTIFICATION/DEVELOPMENT OF ARARs AND TBCs, RAOs, GENERAL RESPONSE ACTIONS AND VOLUMES OF CONTAMINATED MEDIA . . . . . 28

2.1 Identification and Compilation of ARARs and TBCs . . . . . 28
2.1.1 Chemical-Specific ARARs and TBCs . . . . . 29
2.1.2 Location-Specific ARARs and TBCs . . . . . 29
2.1.3 Action-Specific ARARs and TBCs . . . . . 29
2.1.4 Policy Considerations . . . . . 30

Click on a row to go to the corresponding section


2.2 Development of RAOs . . . . . 30
2.2.1 Development of Soil RAOs . . . . . 31
2.2.1.1 Soil COCs . . . . . 31
2.2.1.2 Soil PRGs . . . . . 34
2.2.1.3 Soil RAOs . . . . . 35
2.2.2 Development of Groundwater RAOs . . . . . 36
2.2.2.1 Groundwater COCs . . . . . 36
2.2.2.2 Groundwater PRGs . . . . . 36
2.2.2.3 Groundwater RAOs . . . . . 37
2.2.3 Development of Sediment (and Surface Water) RAOs . . . . . 38
2.2.3.1 Sediment COCs . . . . . 38
2.2.3.2 Sediment RAOs . . . . . 38

2.3 Development of General Response Actions . . . . . 39
2.3.1 Soil General Response Actions . . . . . 39
2.3.2 Groundwater General Response Actions . . . . . 39
2.3.3 Sediment General Response Actions . . . . . 39

2.4 Areas and Volumes of Contaminated Media . . . . . 39
2.4.1 Areas and Volumes of Contaminated Soil . . . . . 40
2.4.2 Areas and Volumes of Landfill and Associated Contaminated Soil . . . 42
2.4.3 Areas and Volumes of Contaminated Groundwater . . . . . 42
2.4.4 Area and Volume of Contaminant Sediment . . . . . 43

3.0 SCREENING AND EVALUATION OF TECHNOLOGIES AND PROCESS OPTIONS . . . . . 44

3.1 Identification and Screening of Technologies and Process Options . . . . . 44
3.1.1 Soil and Sediment . . . . . 44
3.1.2 Groundwater . . . . . 45

3.2 Evaluation and Selection of Technologies and Process Options . . . . . 47
3.2.1 Evaluation and Selection of Technologies and Process Options for Soil . . . . . 48
3.2.1.1 No Action . . . . . 48
3.2.1.2 Limited Action . . . . . 49
3.2.1.3 Containment . . . . . 52
3.2.1.4 Disposal . . . . . 56
3.2.1.5 Ex-Situ Treatment . . . . . 59
3.2.1.6 In-Situ Treatment . . . . . 68
3.2.1.7 Summary of Selected Technologies and Process Options for Soil . . . . . 75
3.2.2 Evaluation and Selection of Technologies and Process Options for Groundwater . . . . . 76
3.2.2.1 No Action . . . . . 76
3.2.2.2 Limited Action . . . . . 77
3.2.2.3 Containment . . . . . 79

Click on a row to go to the corresponding section


3.2.2.4 Collection . . . . . 83
3.2.2.5 Ex-Situ Treatment . . . . . 84
3.2.2.6 Discharge . . . . . 97
3.2.2.7 In-Situ Treatment . . . . . 101
3.2.2.8 Summary of Selected Technologies and Process Options for Groundwater . . . . . 103

4.0 DEVELOPMENT OF REMEDIAL ACTION ALTERNATIVES . . . . . 105

4.1 Rationale for Development of Remedial Action Alternatives . . . . . 106
4.1.1 Statutory and Policy Guidance . . . . . 107
4.1.2 Protection of Human Health . . . . . 107
4.1.3 Protection of Groundwater . . . . . 107
4.1.4 Protection of Ecological Receptors . . . . . 108
4.1.5 Floodplain/Wetland Considerations . . . . . 109
4.1.6 Future Reuse of the Property . . . . . 110

4.2 Common Actions . . . . . 110

4.3 SC Alternatives Descriptions . . . . . 115
4.3.1 Alternative SC-1: No Action . . . . . 115
4.3.2 Alternative SC-2: Limited Action . . . . . 116
4.3.3 Alternative SC-3: Hot Spot Removal, Capping, and In-Situ Treatment . . . . . 117
4.3.3.1 Key Considerations . . . . . 118
4.3.3.2 Surface/Shallow Soil “Hot Spot” Removal . . . . . 120
4.3.3.3 Permeable Soil Cover . . . . . 122
4.3.3.4 Capping of On-Site Landfill . . . . . 123
4.3.3.5 Sediment Excavation and Disposal . . . . . 126
4.3.3.6 Wetlands Restoration/Compensatory Wetlands Construction . . . . . 129
4.3.3.7 In-Situ Treatment of Deep Soil . . . . . 130
4.3.4 Alternative SC-4: Off-Site Treatment/Disposal . . . . . 138
4.3.4.1 Key Considerations . . . . . 139
4.3.4.2 Soil Pile Removal and Disposal . . . . . 140
4.3.4.3 Surface/Shallow and Subsurface Soil Excavation and Disposal . . . . . 141
4.3.4.4 Deep Soil Excavation and Disposal . . . . . 146
4.3.4.5 Landfill Excavation and Disposal . . . . . 150
4.3.4.6 Sediment Excavation and Disposal . . . . . 153
4.3.4.7 Wetlands Restoration . . . . . 153
4.3.4.8 Post-Excavation Activities . . . . . 155
4.3.5 Alternative SC-5: Off-Site Treatment/Disposal (0 - 10 feet bgs Soil) and In-Situ Treatment (>10 feet bgs Soil) . . . . . 155
4.3.5.1 Soil Pile Removal and Disposal . . . . . 157
4.3.5.2 Surface/Shallow and Subsurface Soil Excavation and Disposal . . . . . 157
4.3.5.3 Landfill Excavation and Disposal . . . . . 157

Click on a row to go to the corresponding section


4.3.5.4 Sediment Excavation and Disposal . . . . . 157
4.3.5.5 Wetlands Restoration . . . . . 158
4.3.5.6 Post-Excavation Activities . . . . . 158
4.3.5.7 In-Situ Treatment of Deep Soil . . . . . 159
4.3.6 Alternative SC-6A: On-Site Ex-Situ Thermal Treatment . . . . . 160
4.3.6.1 Ex-Situ Indirect-Heated Thermal Desorption Treatment . . . . 162
4.3.6.2 Soil Pile Treatment and Disposal . . . . . 165
4.3.6.3 Surface/Shallow and Subsurface Soil Excavation, Treatment, and Disposal . . . . . 167
4.3.6.4 Deep Soil Excavation, Treatment, and Disposal . . . . . 171
4.3.6.5 Landfill Excavation and Treatment/Disposal . . . . . 173
4.3.6.6 Sediment Excavation and Treatment/Disposal . . . . . 174
4.3.6.7 Wetlands Restoration . . . . . 174
4.3.6.8 Post-Excavation Activities . . . . . 175
4.3.7 Alternative SC-6B: On-Site Ex-Situ Thermal Treatment (0 - 10 feet bgs Soil) and In-Situ Treatment (>10 feet bgs Soil) . . . . . 175
4.3.7.1 Ex-Situ Indirect-Heated Thermal Desorption Treatment . . . . 177
4.3.7.2 Soil Pile Treatment and Disposal . . . . . 177
4.3.7.3 Surface/Shallow and Subsurface Soil Excavation, Treatment, and Disposal . . . . . 177
4.3.7.4 Landfill Excavation and Treatment/Disposal . . . . . 178
4.3.7.5 Sediment Excavation and Treatment/Disposal . . . . . 178
4.3.7.6 Wetlands Restoration . . . . . 178
4.3.7.7 Post-Excavation Activities . . . . . 179
4.3.7.8 In-Situ Treatment of Deep Soil . . . . . 179

4.4 MOM Alternatives Descriptions . . . . . 181
4.4.1 Alternative MOM-1: No Action . . . . . 181
4.4.2 Alternative MOM-2: Limited Action . . . . . 182
4.4.3 Alternative MOM-3: Groundwater Collection and Treatment (Higher Pumping Rate) . . . . . 183
4.4.3.1 Pre-Design Investigations . . . . . 183
4.4.3.2 Conceptual Design of Groundwater Collection and Treatment System (High Pumping Rate) . . . . . 184
4.4.3.3 Clean-up Time Frame . . . . . 190
4.4.3.4 Natural Attenuation of Selected Source Areas/ Contaminated Groundwater Plumes . . . . . 190
4.4.3.5 Demobilization/Decommission . . . . . 192
4.4.4 Alternative MOM-4: Groundwater Collection and Treatment (Lower Pumping Rate) . . . . . 193
4.4.4.1 Pre-Design Investigations . . . . . 194
4.4.4.2 Conceptual Design of Groundwater Collection and Treatment System (Low Pumping Rate) . . . . . 194
4.4.4.3 Clean-up Time Frame . . . . . 196
4.4.4.4 Natural Attenuation of Selected Source Areas/ Contaminated Groundwater Plumes . . . . . 196
4.4.4.5 Demobilization/Decommissioning . . . . . 196
4.4.5 MOM Alternative Not Carried Forward . . . . . 197

Click on a row to go to the corresponding section


5.0 DETAILED ANALYSIS OF ALTERNATIVES . . . . . 198

5.1 Criteria for Evaluation of Alternatives . . . . . 198

5.2 Individual Analysis of SC Alternatives . . . . . 202
5.2.1 Alternative SC-1: No Action . . . . . 202
5.2.2 Alternative SC-2: Limited Action . . . . . 204
5.2.3 Alternative SC-3: Hot Spot Removal, Capping and In-Situ Treatment . . . . . 207
5.2.4 Alternative SC-4: Off-Site Treatment/Disposal . . . . . 212
5.2.5 Alternative SC-5: Off-Site Treatment/Disposal (0 - 10 feet bgs Soil) and In-Situ Treatment ((> 10 feet bgs Soil) . . . . . 216
5.2.6 Alternative SC-6: On-Site Treatment . . . . . 221

5.3 Comparative Analysis of SC Alternatives . . . . . 226
5.3.1 Overall Protection of Human Health and the Environment . . . . . 226
5.3.2 Compliance with ARARs . . . . . 227
5.3.3 Long-Term Effectiveness and Permanence . . . . . 227
5.3.4 Reduction of Toxicity, Mobility and/or Volume Through Treatment . . . . . 228
5.3.5 Short-Term Effectiveness . . . . . 229
5.3.6 Implementability . . . . . 231
5.3.7 Cost . . . . . 233

5.4 Individual Analysis of MOM Alternatives . . . . . 234
5.4.1 Alternative MOM-1: No Action . . . . . 234
5.4.2 Alternative MOM-2: Limited Action . . . . . 236
5.4.3 Alternative MOM-3: Groundwater Collection and Treatment (High Pumping Rate) . . . . . 239
5.4.4 Alternative MOM-4: Groundwater Collection and Treatment (Low Pumping Rate) . . . . . 244

5.5 Comparative Analysis of MOM Alternatives . . . . . 249
5.5.1 Overall Protection of Human Health and the Environment . . . . . 249
5.5.2 Compliance with ARARs . . . . . 250
5.5.3 Long-Term Effectiveness and Permanence . . . . . 250
5.5.4 Reduction of Toxicity, Mobility and/or Volume Through Treatment . . . . . 251
5.5.5 Short-Term Effectiveness . . . . . 251
5.5.6 Implementability . . . . . 252
5.5.7 Cost . . . . . 253

6.0 REFERENCES . . . . . 254

Click on a row to go to the corresponding section

**VOLUME II**

TABLES

Table 2-1 Contaminants of Concern for Soils
Table 2-2 Preliminary Remediation Goals for Soil
Table 2-3 Summary of Soil PRGs for VOCs Based on Soil Leaching to Groundwater
Table 2-4 Recommended Soil Preliminary Remediation Goals
Table 2-5 Contaminants of Concern for Groundwater
Table 2-6 Preliminary Remediation Goals for Groundwater
Table 2-7 Recommended Groundwater Preliminary Remediation Goals
Table 2-8 Contaminants of Concern for Sediment
Table 2-9 Remedial Action Objectives, General Response Actions, Technology Types and Process Options
Table 2-10 Summary of Contaminated Soil Volumes
Table 2-11 Summary of Landfill Volumes

Table 3-1 Initial Screening of Technologies and Process Options for Soil and Sediment (Including Soil Piles, Surface/Shallow Soil, Subsurface Soil and Deeper Soil)
Table 3-2 Initial Screening of Technologies and Process Options for Groundwater
Table 3-3 Evaluation of Process Options for Soil and Sediments (Including Soil Piles, Surface/Shallow Soil, Subsurface Soil and Deeper Soil)
Table 3-4 Evaluation of Process Options for Groundwater

Table 4-1 Assumed Groundwater Treatment System Influent Concentrations

Table 5-1 ARAR Summary for Alternative SC-1, No Action
Table 5-2 ARAR Summary for Alternative SC-2, Limited Action
Table 5-3 ARAR Summary for Alternative SC-3, Hot Spot Removal, Capping and In-Situ Treatment
Table 5-4 ARAR Summary for Alternative SC-4, Off-Site Treatment/Disposal
Table 5-5 ARAR Summary for Alternative SC-5, Off-Site Treatment/Disposal (0 - 10 feet bgs Soil) and In-Situ Treatment (> 10 feet bgs Soil)
Table 5-6 ARAR Summary for Alternative SC-6, On-Site Treatment (SC-6A - On-Site Ex-Situ Thermal Treatment) (SC-6B - On-Site Ex-Situ Thermal Treatment [0 - 10 feet bgs Soil] and In-Situ Treatment [> 10 feet bgs Soil])
Table 5-7 Comparative Analysis of Source Control (SC) Alternatives
Table 5-8 ARAR Summary for Alternative MOM-1, No Action
Table 5-9 ARAR Summary for Alternative MOM-2, Limited Action
Table 5-10 ARAR Summary for Alternative MOM-3, Groundwater Collection and Treatment (High Pumping Rate)
Table 5-11 ARAR Summary for Alternative MOM-4, Groundwater Collection and Treatment (Low Pumping Rate)
Table 5-12 Comparative Analysis of Management of Migration (MOM) Alternatives



Click here to return to Administrative Record Index

Click on a row to go to the corresponding section

FIGURES


Figure 1.1 Locus Plan
Figure 1.2 Site Vicinity Plan
Figure 1.3 General Site Features Plan
Figure 1.4 General Site Features Plan, Parcel 1 Detail
Figure 1.5 Groundwater Elevation Contour Plan - Shallow Groundwater, September 1998
Figure 1.6 Distribution of PCB Surface Soil Contamination
Figure 1.7 Distribution of PCB Surface Soil Contamination - Parcel 1 Detail
Figure 1.8 Distribution of Lead Surface Soil Contamination
Figure 1.9 Distribution of Lead Surface Soil Contamination - Parcel 1 Detail
Figure 1.10 Distribution of Deeper Soil Contamination and Other Source Areas
Figure 1.11 Distribution of VOCs in Subsurface/Deeper Soils
Figure 1.12 Distribution of Total AVOC Concentrations in Groundwater: AGQS Exceedances Noted
Figure 1.13 Distribution of Total CVOC Concentrations in Groundwater: AGQS Exceedances Noted
Figure 1.14 Summary of Contaminant Groundwater Plumes
Figure 1.15 Summary of Wetland Sampling Locations and Proposed Area of Sediment Excavation

Figure 4.1 Delineation of Proposed Groundwater Management Zone (GMZ)
Figure 4.2 Alternative SC-3: 'Hot Spot' Excavation and Site Soil Cover
Figure 4.3 Alternative SC-3: Composite (RCRA) Landfill Cap, Sediment Excavation and Compensatory/Restored Wetlands
Figure 4.4 Alternatives SC-3, SC-5, and SC-6B Steam Injection/SVE System Wells and Piping Conceptual Layout
Figure 4.5 Alternatives SC-3, SC-5, and SC-6B Steam Injection/SVE System Conceptual Process Flow Schematic
Figure 4.6 Alternatives SC-4, SC-5, SC-6A and SC-6B: Soil Proposed for Excavation-Surface/Shallow and Subsurface (0-10' bgs)
Figure 4.7 Alternatives SC-4 and SC-6A: Soil Proposed for Excavation - Deep (>10' bgs)
Figure 4.8 Alternatives SC-6A and SC-6B on-Site Indirect-Heated Thermal Desorption System
Figure 4.9 Alternatives MOM-3 & MOM-4 Groundwater Extraction/Treatment System Well/Piping Layout
Figure 4.10 Alternatives MOM-3 & MOM-4 Groundwater Treatment System Conceptual Process Flow Diagram

Click on a row to go to the corresponding section

## VOLUME III

APPENDICES


Appendix A Limitations
Appendix B Potential Applicable or Relevant and Appropriate Requirements (ARARs) and To-Be-Considered Guidelines (TBCs)
Appendix C Numerical and Analytical Groundwater Flow and Contaminant Transport Modeling
- C.1 Numerical Groundwater Flow Model Development and Modeling Results
- C.2 Effects of Potential Rate-Limiting Processes on Dissolved Phase Contaminant Recovery
- C.3 Impact of Contaminated Groundwater Plume Discharge on Kelly Brook Water Quality
- C.4 Estimation of Source Area Persistence Under Pumping Conditions and No Source Control Measures
- C.5 Development of Leaching to Groundwater-Based PRGs for Soil

Appendix D Media Volume Estimate Calculations
- D.1 November 11, 1999 Memorandum - Sampling and Analysis Program to Evaluate Soil Potentially Hazardous for Lead and Other Characteristics
- D.2 Soil Volume Calculations
- D.3 Landfill Volume Calculations
- D.4 Groundwater Volume Calculations

Appendix E Source Control (SC) Alternatives - Cost Estimates and Supporting Information
- E.1 SC-1: No Action Alternative
- E.2 SC-2: Limited Action Alternative
- E.3 SC-3: Hot Spot Removal, Capping, and In-Situ Treatment of Deep Soil
- E.4 SC-4: Off-Site Treatment/Disposal
- E.5 SC-5: Off-Site Treatment/Disposal (0-10 feet bgs Soil) and In-Situ Treatment (>10 feet bgs Soil)
- E.6 SC-6A: On-Site Ex-Situ Thermal Treatment
- E.7 SC-6B: On-Site Ex-Situ Thermal Treatment (0-10 feet bgs Soil) and In-Situ Treatment (>10 feet bgs Soil)

Appendix F Management of Migration (MOM) Alternatives - Cost Estimates and Supporting Information
- F.1 MOM-1: No Action Alternative
- F.2 MOM-2: Limited Action Alternative
- F.3 MOM-3: Groundwater Collection and Treatment (High Pumping Rate)
- F.4 MOM-4: Groundwater Collection and Treatment (Low Pumping Rate)
  - F.4.1 MOM-4: 80 gpm Groundwater Collection and Treatment System (Alternative Carried Forward)
  - F.4.2 MOM-4: 30 to 40 gpm Groundwater Collection and Treatment System with Slurry Wall and Cap (Alternative not Carried Forward)

Appendix G Post-RI Water Quality Results
- G.1 Groundwater Quality Data - Volatile Organic Compounds (including July 1999 and September 2000 monitoring rounds by NHDES)
- G.2 Groundwater Quality Data - Natural Attenuation/Water Quality Parameters (including July 1999 and September 2000 monitoring rounds by NHDES)
- G.3 NHDES Residential Well Data Through October 2000




Click here to return to Administrative Record Index

Click on a row to go to the corresponding section

G.4 Analytical Results for 'Background' Surface Water Samples Collected November and December 1999
Appendix H PRG Memorandum Dated November 10, 2000 from Menzie-Cura & Associates, Inc.
Appendix I Revisions to NHDES RCMP Dated October 2000

S:\DATA\1300s\1371\FS Report\2002 Final Report\0102 Text\FS TOC.wpd