#### American Creosote Works Pensacola, FL

June 6, 2012

Pete Thorpe

#### Outline

- Overview
- Recent Stormwater Line Activities
- Operable Units
- Proposed containment strategy
- Next Steps


#### **ACW Aerial Photo**



#### **Stormwater Line Project**

- Project will make the PYC ditch dry, resulting in easier cleanup and remediation of the ditch
- Improve the water quality of the storm water entering Pensacola Bay
- Will require dewatering for some portions of the project
  - common practice in Pensacola


#### **Groundwater Pumping**




16 feet to 135 feet Radius of Influence range

#### 2009 Vapor Intrusion Study

15 shallow groundwater samples



# Sample Point B-5 Acenaphthene - 41 ug/L (GTCL 20 ug/L) Naphthalene - 32 ug/L (GTCL 14 ug/L)



## Dewatering Area



#### Monitoring Well Network

- The wells are screened below what could have been effected by the pumping
- ACW-C2-MW-06 screened 11-21 ft
- ▶ ACW-C9-MW-05 screened 26-36 ft
- No contaminants in either 2011 or 2012 sampling event.

#### Horizontal Bore



#### Horizontal Bore (cont.)

- The stormline will be installed using a horizontal drill rig
- The environmental by-product will be soil cutting
- Soil cutting will be transported back to the site to be incorporated into the final design
- City's contractor will be performing air monitoring
- EPA's contractor will have air monitoring on ACW and will verify the air monitoring at the work site

# Connection of old and new Stormwater Lines

- Must dewater to connect the old and new stormwater lines
- EPA will be treating the groundwater during the dewatering
- Pre-work sample to determine what is going to be pumped
- Air Strippers will remove contaminants before onsite reinjection
  - Similar to groundwater treatment system
  - Treatment will remove 99% Benzene, 73% Naphthalene
- Duration of 1to 2 days

# Questions?

#### ACW Operable Units (OUs)


- Three Operable Units
  - OU1: Sludge, soil and sediment
  - OU2: Groundwater
  - OU3: Offsite dioxin– contaminated soil (2007)
- Current goal is to write a Site wide ROD contains all three OUs

#### Sitewide Feasibility Study


- Soil
  - ACW soils (on facility)
  - Off facility residential soils
- Groundwater
  - Source Area (dipping ponds)
  - On facility DNAPL impacted area
  - Off facility DNAPL impacted area

### Proposed Containment Remedy

- Containment Strategy for the Source
   Area Former Dipping Ponds
- Install barrier wall down to 100'+ and cap the surface
  - Clay layer found beneath the site at 100' BLS
  - 8 borings that have contact with the clay layer
  - Several soil samples show low permeabilities



# Slurry Wall



#### Permeability Values of Clay

Clay permeabilities		cm/second	ft/yr
∘ B-3A	108' BLS	$1.09 \times 10^{-8}$	0.001
• SB516	104'-112' BLS	$1.9 \times 10^{-9}$	0.002
• SB518	113.5'-117' BLS	$2.0 \times 10^{-9}$	0.002
<ul><li>SB522</li></ul>	82' - 85' BLS	$1.1 \times 10^{-8}$	0.01

Soil permeabilities

• 15TG46	41' BLS	$4.34 \times 10^{-7}$	0.46
• 18TG9	7.1' BLS	$6.79 \times 10^{-7}$	0.70

▶ Rule of Thumb 1 X  $10^{-6}$  cm/sec  $\approx 1$  ft/yr

## Cutter Soil Mixing equipment



#### **DNAPL** Areas

Treatment Strategy for the extended DNAPL plume onsite and extended DNAPL plume offsite

Extended DNAPL plume onsite (outside of barrier wall) has two major zones, 40' to 85' and 135' to 145'

### National Remedy Review Board

- Presentation required for all remedies over \$25 million
- Presentation in front of all 10 EPA Regions
- Highlights the site

#### **Next Steps**

#### Next Steps – Short Term

Optimal Project Schedule

Provide Sitewide Feasibility Study for FDEP review – late June 2012

Finalize Sitewide Feasibility Study – July 2012

Present at National Remedy Review Board, Issue Proposed Plan – August 2012

Public Comment Period – August/September 2012

Site Wide ROD – September 2012

#### **Next Steps**

#### Next Steps – Long Term

Optimal Project Schedule

#### Site Wide OU1/OU2/OU3

- Remedial Design Fall 2012 to Fall 2013
- Remedial Action Starts Winter 2014

# Questions?