United States
Environmental Protection
Agency

Office of Emergency and
Remedial Response
Washington, DC 20460

9355.0-04B
PB95-963307
EPA 540/R-95/059
June 1995

Remedial Design/Remedial Action Handbook

Printed on Recycled Paper

Disclaimer

The policies and procedures set forth here are intended as guidance to Agency and other Government employees. They do not constitute rulemaking by the Agency and may not be relied on to create a substantive or procedural right enforceable by any other person. The Government may take action that is at variance with the policies and procedures in this manual.

Additional Copies

Additional copies of this report may be obtained from the following source:

National Technical Information Service (NTIS)
U.S. Department of Commerce
5285 Port Royal Road
Springfield, VA 22161
(703) 487-4650

Acknowledgements

This handbook is the product of the U.S. Environmental Protection Agency's (EPA's) Office of Emergency and Remedial Response (OERR). The EPA Work Assignment Manager was Richard Jeng of the Hazardous Site Control Division (HSCD), Design and Construction Management Branch (DCMB). Lieutenant Commander Jo Ann Griffith, U.S. Public Health Service, was the original author.

Special recognition is extended to the following co-authors for their ongoing support, essential technical expertise, and invaluable recommendations and insight:

Kenneth J. Erickson, P.E., USEPA, Region IX

Jo Ann Cola, USEPA, Region IX

Frances Costanzi, USEPA, Region III

Gene Wingert, USEPA, Region III

William J. Bolen, USEPA, Region V

Kenneth Skahn, P.E., USEPA, HQ HSCD/DCMB

Robert Curnyn, P.E., U.S. Army Corps of Engineers

The authors express their appreciation to the following persons for their contributions to the depth of information embodied in the handbook: Tracy Hopkins, P.E., USEPA, HQ HSCD/DCMB, and Gary L. Johnson, USEPA, QAD/RTP-NC.

Table of Contents

Chapter 1 Introduction

1.1 Purpose of the Handbook 1

1.2 Overview of the Handbook 1

Chapter 2 Project Management

2.1 Introduction 3

2.2 Definition of Project Management 3

2.2.1 Scope of Work 3

2.2.2 Project Budget, Funding, and Costs 3

2.2.3 RD/RA Schedule 3

2.2.4 Project Team 3

2.3 Skills of a Successful Project Manager 4

2.3.1 Knowledge of Project Management Principles 4

2.3.2 Competency as a Manager in a Project Environment 4

2.3.3 Leadership 4

2.3.4 Technical Competence 4

2.4 Project Management 4

2.4.1 Monitoring the RD/RA 4

2.4.2 Managing the RD/RA 5

2.5 General RPM Responsibilities During RD/RA 6

2.5.1 Responsibilities During RD/RA Planning 7

2.5.2 Responsibilities During RD/RA Execution 8

2.5.3 Responsibilities During RD/RA Closeout 8

2.5.4 Limits of Authority 8

2.5.5 Potential RPM Liability 9

Chapter 3 RD/RA Project Planning

3.1 Introduction 11

3.2 Developing the Project Management Plan 11

3.3 Establishing the RD/RA Lead for Federal-Lead Projects 12

3.4 Assembling a Technical Review Team 12

3.5 Developing a Communications Strategy 14

3.6 Collecting Predesign Information 14
3.7 Analyzing Project Constraints 15
3.7.1 General Constraints 16
3.7.2 Property Access Issues 18
3.7.3 Record of Decision Changes 19
3.8 Scheduling the RD/RA 20
3.8.1 Gantt Chart Method 20
3.8.2 Critical Path Method 21
3.9 Developing the RD/RA Budget 21
3.10 Developing a Contracting Strategy for the RD and RA 22
3.10.1 Schedule Acceleration 23
3.10.2 RD/RA Design Approach 24
3.10.3 RA Contracts 25
3.10.4 RA Procurement Strategies 26
3.11 Coordinating with the State 27
3.11.1 State Support Role in Federal-Lead RD/RA 27
3.11.2 Developing the Superfund State Contract 27
3.12 Maximizing Community Relations 28

Chapter 4 Federal-Lead Remedial Design

4.1 Introduction 31
4.2 Deciding to Task the RD to an EPA Contractor or USACE 31
4.3 Developing the Statement Of Work 31
4.3.1 Preparing the Remedial Design Statement of Work 33
4.3.2 Developing a Preliminary Remedial Design Schedule 35
4.3.3 Developing the Remedial Design Independent Government Cost Estimate 36
4.4 Tasking the Remedial Design 36
4.4.1 Tasking the Remedial Design to an EPA Contractor 37
4.4.2 Tasking the Remedial Design to USACE 38
4.4.3 Managing the Progress of the Remedial Design 40
4.5 Procuring a USACE Designer 42
4.6 Reviewing and Approving the Work Plan (ARCS/RACs) 43
4.6.1 Reviewing the Work Plan 43
4.6.2 Negotiating with the Contractor 44
4.6.3 Approving the Work Plan 45

4.7 Overseeing the Design Development 45
4.7.1 Design Review Procedures 45
4.7.2 Predesign Phase Submittals 46
4.7.3 Treatability Studies 50
4.7.4 Preliminary Design Phase 51
4.7.5 Intermediate Design Phase 55
4.7.6 Prefinal/Final Design 58
4.8 Value Engineering During Remedial Design 61
4.8.1 VE Screen 61
4.8.2 VE Study Team 61
4.8.3 VE Study 62
4.9 Post-Design Activities 63

Chapter 5 Federal-Lead Remedial Action

5.1 Introduction 65
5.1.1 Preparation for the Remedial Action 65
5.1.2 Responsibilities of Key Participants Involved in the Remedial Action 65
5.2 Remedial Action Planning Activities 67
5.2.1 Revising the Project Management Plan 68
5.2.2 Assembling the Technical Review Team 68
5.2.3 Finalizing the Superfund State Contract and Defining State Involvement During the Remedial Action 68
5.2.4 Developing the Remedial Action Statement of Work 69
5.2.5 Developing the IGCE 70
5.2.6 Developing the Remedial Action Schedule 71
5.2.7 Issuing the RA Work Assignment or Executing the Interagency Agreement 71
5.3 Managing the Remedial Action 71
5.3.1 Managing the RA Work Assignment or Terms of the Interagency Agreement 71
5.3.2 Community Relations During the Remedial Action 72
5.3.3 Reviewing the EPA Contractor's Remedial Action Work Plan 72
5.4 The Remedial Action Procurement Process 73
5.4.1 Sealed Bidding 73
5.4.2 Negotiated Procurement 74
5.4.3 Two-Step Sealed Bidding 74
5.4.4 Non-Competitive (Sole-Source) Procurement 75
5.4.5 The Remedial Project Manager's Role in the Procurement Process 75

5.4.6 Approving the EPA Contractor's Selected Constructor 75
5.4.7 Construction Contract Award Controversies 75

5.5 Preconstruction Activities 76
5.5.1 Issuing the Notice to Proceed 76
5.5.2 Conducting the Preconstruction Conference 76
5.5.3 Delivering the Preconstruction Submittals 77
5.5.4 Providing Site Security 77
5.5.5 Mobilizing the Constructor 77
5.5.6 Posting EPA Signs at the Site 77

5.6 Construction Implementation 77
5.6.1 Inspection and Testing 78
5.6.2 Monitoring Construction Progress 78
5.6.3 Reviewing Record Drawings 80
5.6.4 Changes to the Construction Contract 80
5.6.5 Managing Claims 81
5.6.6 Value Engineering During Construction 81

5.7 Contractor Completion Activities 82
5.7.1 Achieving an Operational and Functional Remedy 82
5.7.2 Prefinal Construction Conference 82
5.7.3 Prefinal and Final Inspections 82
5.7.4 Contractual Acceptance of the Project and Warranty 83
5.7.5 Remedial Action Report 84

5.8 State Operation and Maintenance 84

5.9 Site Closeout Process 85
5.9.1 Construction Completion Activities 85
5.9.2 Site Completion Activities 87
5.9.3 Site Deletion Activities 89

Appendix A Glossary A-1

Appendix B Transmittal Forms B-1

Appendix C Design Review Checklists C-1

Appendix D Model RD, RA, and Technical Assistance IAGs D-1

Appendix E Model RD, RD Oversight, RA, and RA Oversight SOWs E-1

Appendix F RD/RA Fact Sheets and Other Guidance F-1

Appendix G State-Lead G-1

Appendix H Enforcement-Lead H-1

Appendix I Operations and Maintenance I-1

List of Figures

Figure 2-1. Skills of a Successful Project Manager 4
Figure 2-2. Remedial Project Management Responsibilities 7
Figure 3-1. Project Management Plan 11
Figure 3-2. Potential Technical Review Team Members 13
Figure 3-3. Example of a Communications Matrix 15
Figure 3-4. Typical Collection of Predesign Information 15
Figure 3-5. Examples of ROD Changes 19
Figure 3-6. Gantt Chart 21
Figure 3-7. Gantt Chart with Critical Path Identified 22
Figure 3-8. Construction Bond Requirements 26
Figure 4-1. RPM Responsibilities During Remedial Design 32
Figure 4-2. EPA Contractor RD Standard Tasks (RACs) 33
Figure 4-3. USACE Standard Design Specifications 34
Figure 4-4. Principal Remediation Categories for RD Schedules 36
Figure 4-5. Components of a Work Plan 43
Figure 4-6. Components of the HASP 47
Figure 4-7. Field Sampling Plan Contents 48
Figure 4-8. Suggested Format for the QAPP 49
Figure 4-9. Suggested Format for a Pilot-Scale Treatability Study 50
Figure 4-10. Preliminary Design Phase Submittal Components 52
Figure 4-11. Intermediate Design Phase Submittal Components 55
Figure 4-12. Prefinal/Final Design Phase Submittal Components 58
Figure 4-13. Value Engineering Screening 62
Figure 5-1. Preremedial Action Checklist 65

Figure 5-2. Remedial Action Process 66
Figure 5-3. Contractual Relationships in the Remedial Action Process 67
Figure 5-4. Roles and Responsibilities of the Resident Engineer 68
Figure 5-5. RAC and ARCS Contract RA Standard Tasks 69
Figure 5-6. Preconstruction Conference Activities 77
Figure 5-7. EPA Contractor Progress Reports 79
Figure 5-8. Site Completion and Deletion Processes 86
Figure 5-9. Contents of the Preliminary Closeout Report 87
Figure 5-10. Final Closeout Report Summary 88
Figure 5-11. Contents of the Notice of Intent to Delete 90

Acronyms and Abbreviations

A, B

A/E	Architect/Engineer
ARARs	Applicable or Relevant and Appropriate Requirements
ARCS	Alternative Remedial Contracting Strategy
BAFO	Best and Final Offer

C

CA	Cooperative Agreement
CBD	*Commerce Business Daily*
CCE	Construction Cost Estimate
CD	Consent Decree
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CERCLIS	CERCLA Information System
CFR	*Code of Federal Regulations*
CM	Construction Manager
CO	Contracting Officer
CPAF	Cost-Plus-Award-Fee
CPM	Critical Path Method
CQAP	Construction Quality Assurance Plan
CRC	Community Relations Coordinator
CRP	Community Relations Plan
CSI	Construction Specification Institute
CWE	Current Working Estimate

D

D&CA	Design and Construction Advisor
D&F	Determination and Finding
DBA	Davis-Bacon Act
DQO	Data Quality Objective

E

EL	Expenditure Limit
EPCRA	Emergency Planning and Community Right-to-Know Act
ERP	Emergency Response Plan
ESD	Explanation of Significant Differences

F

FAR	*Federal Acquisition Regulation*
FCOR	Final Closeout Report
FR	*Federal Register*
FRP	Federal Response Plan
FS	Feasibility Study
FSP	Field Sampling Plan
FY	Fiscal Year

G, H

GAO	General Accounting Office
HASP	Health and Safety Plan
HTRW	Harzardous, Toxic, and Radioactive Waste

I

IAG	Interagency Agreement
IDT	Indefinite Delivery
IFB	Invitation for Bids
IGCE	Independent Government Cost Estimate

L

LAN	Local Area Network
LEPC	Local Emergency Planning Committee
LOE	Level-of-Effort

LTCS	Long-Term Contracting Strategy
LTRA	Long-Term Response Action

M

MOU	Memorandum of Understanding
MSW	Municipal Solid Waste

N

NCP	National Contingency Plan
NOID	Notice of Intent to Delete
NPL	National Priorities List
NRC	National Response Center
NTCRA	Non-Time-Critical Removal Action

O

O&M	Operations and Maintenance
OERR	Office of Emergency and Remedial Response
OGC	Office of General Counsel
OIG	Office of Inspector General
OMB	Office of Management and Budget
ORC	Office of Regional Counsel
ORD	Office of Research and Development
OSC	On-Scene Coordinator
OSHA	Occupational Safety and Health Administration
OSWER	Office of Solid Waste and Emergency Response
OU	Operable Unit

P

P&ID	Piping and Instrumentation Diagram
PCOR	Preliminary Closeout Report
PFD	Process Flow Diagram

PPE	Personal Protective Equipment
PO	Project Officer
PR	Procurement Request
PRP	Potentially Responsible Party

Q

QA	Quality Assurance
QAPP	Quality Assurance Project Plan
QC	Quality Control

R

RA	Remedial Action
RAC	Response Action Contract
RACS	Response Action Contracting Strategy
RCRA	Resource Conservation and Recovery Act
RD	Remedial Design
RE	Resident Engineer
REPR	Real Estate Planning Report
RFP	Request for Proposal
RI	Remedial Investigation
ROC	Regional Off-Site Contract
ROD	Record of Decision
RPM	Remedial Project Manager

S

S/RPOD	Superfund/RCRA Procurement Operations Division
SACM	Superfund Accelerated Clean-Up Model
SAP	Sampling and Analysis Plan
SARA	Superfund Amendments and Reauthorization Act
SAVE	Society of American Value Engineers
SCA	Service Contract Act
SF	Standard Form
SMOA	State Memorandum of Agreement

SMP	Site Management Plan
SOP	Standard Operating Procedure
SOW	Statement of Work
SSC	Superfund State Contract

T

TA	Technical Assistance
TAG	Technical Assistance Grant
TD	Technical Direction
TERC	Total Environmental Restoration Contract
TQM	Total Quality Management
TRT	Technical Review Team

U

UAO	Unilateral Administrative Order
USACE	United States Army Corps of Engineers

V

VE	Value Engineering
VECP	Value Engineering Change Proposal
VEP	Value Engineering Proposal

W, X, Y, Z

WA	Work Assignment
WACN	Work Assignment Closeout Notification
WACR	Work Assignment Completion Report
WAF	Work Assignment Form
WAM	Work Assignment Manager
WAP	Work Assignment Package
WBS	Work Breakdown Structure
WP	Work Plan