SP2/ 4/27/2016

W.O. 1617480

Page 1 of 18

# W.O.# 1617480

# STATION B STACK COV TESTING WITH IVS AND UVFS

#### CONTENTS

1.0	PURPOSE/SCOPE	. 2
	SPECIAL TOOLS/EQUIPMENT/MATERIALS	
3.0	PRECAUTIONS/LIMITATIONS	. 2
4.0	PREREQUISITES	4
5.0	PERFORMANCE	6
6.0	TESTING AND RESTORATION1	10

W.O. 1617480 Page 2 of 18

#### 1.0 PURPOSE/SCOPE

This Work Control Document (WCD) provides instructions for performing a pitot tube traverse on Station B stack exhaust flow, as requested per vendor instructions. The traverse will record data from velocity, temperature, and pressure.

# 2.0 SPECIAL TOOLS/EQUIPMENT/MATERIALS MATERIAL LIST

Item	Material Description	Qty	Unit	Pr / Whse Stock No.
1	Solution of water and mild soap	AR	EA	N/A
2	Denatured alcohol OR Contact cleaner	AR	EA	X-12-0-5120 X-12-00010
3	Compressed air	AR	EA	N/A

<sup>\* -</sup> Required Item, all other as required

W.O. 1617480 Page 3 of 18

# PERSONAL PROTECTIVE EQUIPMENT (PPE)

Description	
*Safety glasses with side shields.	
*Hard Hat	
*Hearing Protection	
*Nitrile gloves	
*Fall Protection Harness	
*Safety Toe Shoes	

<sup>\* -</sup> Required Item, all other as required.

# **TOOLS AND EQUIPMENT**

Description	
*70" or greater standard Pitot tube	
*Airdata TEW-19 19" temperature extension wand	
*Airdata TRC-16 temperature probe extension cord	
*Calculator	
*Man lift or ladder	

<sup>\* -</sup> Required Item, all other as required.

# **MEASUREMENT & TESTING EQUIPMENT (M&TE)**

Description
*Process Calibrator (Temperature and Pressure), Calibrated

W.O. 1617480 Page 4 of 18

## 3.0 PRECAUTIONS/LIMITATIONS

#### 3.1 PRECAUTIONS

**EYE, FOOT, HEAD, HAND HAZARDS** exist. Personnel may be exposed to hazard while performing work throughout site. Don cut-resistant/mechanics gloves as needed.

**FALLS FROM ELEVATION HAZARD** exists. Personnel may be exposed to falls from elevation due to working from elevated work platform. Use Fall Protection PPE in accordance with WP 12-IS.01-10, Industrial Safety Program – Fall Protection and Prevention when working from aerial man lift platform. Hard hat must be worn while working on and around work platform. Utilize barriers and barricades per WP 12 IS.01-1 procedure. Ensure aerial lift is run by a qualified operator and a spotter is present throughout the progression of the work evolution.

MOVING/FALLING OBJECTS FROM HEIGHT HAZARD exists. Personnel may be exposed to hazard while performing maintenance near aerial lift. Use Fall Protection PPE in accordance with WP 12-IS.01-10, Industrial Safety Program – Fall Protection and Prevention when working from aerial man lift platform. Hard hat must be worn while working on and around work platform. Utilize barriers and barricades per WP 12 IS.01-1 procedure.

**PINCH POINTS HAZARD** exist. Personnel may be exposed to pinch points hazard while performing maintenance. Don mechanics/cut-resistant gloves throughout procedure.

RADIOLOGICAL HAZARD exists. Craft may be exposed to Radiological Hazards if equipment is in a radiological area. Work to be performed in accordance with the approved Radiological Work Permit (RWP). A radiological survey will be required per each traverse and probe measurement. RCT will check for levels commencurate.

**SLIPS AND TRIPS HAZARD** exists. Craft may be exposed to slips and tripping hazards while accessing work area and around the work area Care should be taken while moving about the work area.

W.O. 1617480 Page 5 of 18

#### 3.2 OPERATIONAL RESTRICTIONS AND INTERIM CONTROLS

ESS-2015-01 Controls

The Controls shall be established and maintained as Programmatic Administrative Controls

- The Fire Protection Program (FPP) is relied upon to protect the FW, CW, and MOI.
  - Restrict and minimize combustibles in the vicinity (within 25 ft.) of the Exhaust Filter Building (Building 413) and the above ground UVS exhaust ductwork. Necessary combustibles to support planned work must be evaluated and the allowed configurations SHALL be preapproved by the Fire Protection Engineer (FPE).

#### 4.0 PREREQUISITES

- Field Work Supervisor (FWS) CONDUCT pre-job brief per WP 04-AD3030.
- OBTAIN items shown in Section 2.0, Special Tools/Equipment/Materials.
- REQUEST RADCON be at work site to perform RWP surveys and determinations as needed.

W.O. 1617480 Pag		
¥ <del></del>		NOTE
		es are found during the performance of this Work Order, document leficiencies on the Work Status Log and notify the FWS.
5.0	PERFOR	MANCE
	5.1 RV	P EVALUATION AND RADCON SURVEY
	[]5.1.1	Rad Con Operations (RCO) – <b>PERFORM</b> a RWP evaluation <b>AND RECORD</b> RWP number below.
		RWP #:
	6	
	RCS	DATE
	[]5.1.2	IF RWP is required, THEN RCT and all personnel READ AND DISCUSS the RWP, radiological hazards, precautions, and mitigating actions to be taken as documented in the RWP, THEN SIGN the RWP. MARK N/A if not required.
	CRAFT	DATE /
	CRAFT	DATE
	RCT	

/.O. 1617480	Page 7 of 18
	NOTE
During the repea	work evolution, the temperature/pressure probe and pitot tube will be atedly in and out of the access ports, per contractors instruction.
[]5.1.3	Rad Con Tech (RCT) – <b>SURVEY</b> probe/tube and gloved hands AFTER EACH exit from the access ports to ensure the levels are commencurate.
	<b>IF</b> contamination is found and per RCT request, <b>THEN</b> work <b>WILL BE STOPPED</b> and the Rad Con Supervisor (RCS) will be notified.
-	
RCT	DATE
5.2 PI	TOT TUBE PREPERATION
[ ] 5.2.1	CONTACT Radcon for pitot tubes.
[]5.2.2	INSPECT tube for:
	□ Visible damage
	☐ Tip deformation
	☐ Tip clogging
	Obstruction of ports
CRAFT	DATE
[ ] 5.2.3	<b>IF</b> Pitot tube does not pass inspections, <b>THEN REPLACE</b> the Pitot tube.

W.O. 1	617480	Page 8 of 18
	] 5.2.4	MARK insertion depths on probe, (if needed, as close as possible) as follows:
		3.0 inches
		□ 8.0 inches
		14.0 inches
		24.0 inches
		☐ 48.0 inches
		□ 57.5 inches
		64.75 inches
		69.5 inches
		<i>I</i>
	CRAFT	DATE
	5.3 WC	ORK AREA CONFIGURATION
, ]	[ ] 5.3.1	<b>UTILIZE</b> barricades and barriers per WP 12 IS.01-1, Industrial Safety Program – Barricades and Barriers.
	[ ] 5.3.2	(\$) ENSURE Firewatch and fire extinguisher are in place BEFORE MOVING aerial lift into position to perform tasks. [ESS-2015-01]
		1
1	CRAFT	/
116	[ ] 5.3.3	<b>REQUEST</b> Facility Operations shut down Building 413 HVAC System.
0900		1
	CRAFT	DATE
	[]5.3.4	<b>ENSURE</b> 413-HD-321-003 damper is open and debris screen is free of obstructions.
		REQUEST fans 41-B-960A and 41-B-960B are placed in-service

# Template 4.0

W.O.	1617480	Page 9 of 18
0930	[ ] 5.3.6	REQUEST Facility Operations ensure flow through in-service 860 fan is 57,000 cfm to 60,000 cfm.  860 C (south) in service
6930	[ ] 5.3.7	ALLOW flow to stabilize before performing pitot tube traverse.
0133	[ ] 5.3.8	<b>VERIFY</b> Station B mass flow monitoring indicates a nominal flow of 114 KCFM with both 960 fans and in-service 860 fan <b>AND RECORD</b> read value below.
	CRAFT	/
	Nominal Flo	ow Reading kCFM

W.O. 1617480 Page 10 of 18

# 5.4 PITOT TUBE TRAVERSE AT STATION B

#### NOTE

Use traverse points 90 degrees from each other for data collection. The points may be adjusted per subcontractor instructions.

No more than 2 plugs should be removed at a time. If more are removed, an adverse flow condition will be created that will affect calibration data.

The contractor may have sufficient data points prior to full completion of section 5.4. Per contractors request, you may N/A the incomplete steps of section 5.4 and skip to step [ ] 5.4.2.32.




Figure 1 – Station B Traverse Penetrations Orientation

6937 [ ] 5.4.1 SELECT AND REMOVE penetration plugs from traverse pitot access ports at Station B.

## Template 4.0

W.O. 1617480

Page 11 of 18

[ ] 5.4.2

PERFORM pitot tube traverses as varied in Data Blocks for Station
B.

[ ] 5.4.2.1 INSERT Pitot tube into an open access port.

#### **NOTE**

When recording nominal exhaust flow rate for the UVS and IVS, use CMS point AP2415 for Loop 41A001W2001.

[]5.4.2.2	VARY probe depth AND RECORD data for each block as indicated in applicable Data Block per operational 860 fan.
[ ] 5.4.2.3	REMOVE Pitot Tube.
[ ] 5.4.2.4	<b>INSERT</b> Temperature/Pressure probe into closest adjacent access port.
[]5.4.2.5	<b>RECORD</b> temperature and pressure readings per applicable Data Block.
[ ] 5.4.2.6	REMOVE probes.

1015 - Redeo- swipes of equipment

W.O. 1617480 Page 12 of 18

## **NOTE**

Per steps [ ] 5.4.2.7 and [ ] 5.4.2.20:

- Control Damper 413-HD-056-10A and 413-HD-056-10B are the dampers for fan 41-B-860A
- Control Damper 413-HD-056-11A and 413-HD-056-11B are the dampers for fan 41-B-860B
- Control Damper 413-HD-056-12A and 413-HD-056-12B are the dampers for fan 41-B-860C

•

[ ] 5.4.2.7	WHEN complete with pitot traverse, REQUEST Facops to:
[ ] 5.4.2.8	<b>SECURE</b> 41-B-960A and 41-B-960B.
[ ] 5.4.2.9	SECURE Insevice 860 fan.
[ ] 5.4.2.10	<b>ENSURE</b> to FULLY CLOSE both the inlet and outlet control damper on all off 860 fans.
[]5.4.2.11	PLACE standby 860 fan in-service.
[ ] 5.4.2.12	<b>REQUEST</b> fans 41-B-960A and 41-B-960B are placed in-service with a flow rate of 26,500 cfm to 27,500 cfm through each fan.
[ ] 5.4.2.13	<b>VERIFY</b> Station B mass flow monitoring indicates a nominal flow of 114 KCFM with both 960 fans and inservice 860 fan <b>AND RECORD</b> read value below.
	//
CRAFT	DATE
Nominal Flo	w Read kCFM
[ ] 5.4.2.14	<b>INSERT</b> Pitot tube into an open access port.
[ ] 5.4.2.15	VARY probe depth AND RECORD data for each block as indicated in applicable Data Block per operational 860 fan.
[ ] 5.4.2.16	REMOVE Pitot tube.

W.O. 1617480

[ ] 5.4.2.17	INSERT Temperature/Pressure probe into closest adjacent access port.
[ ] 5.4.2.18	RECORD temperature and pressure readings per applicable Data Block.
[]5.4.2.19	REMOVE probes.
[ ] 5.4.2.20	<b>WHEN</b> complete with pitot traverse, <b>NOTIFY</b> Facops to:
[ ] 5.4.2.21	SECURE 41-B-960A and 41-B-960B.
[ ] 5.4.2.22	SECURE Insevice 860 fan.
[ ] 5.4.2.23	<b>ENSURE</b> to FULLY CLOSE both the inlet and outlet control damper on all off 860 fans.
[]5.4.2.24	PLACE standby 860 fan in-service,
[]5.4.2.25	<b>REQUEST</b> fans 41-B-960A and 41-B-960B are placed in-service with a flow rate of 26,500 cfm to 27,500 cfm through each fan.
[ ] 5.4.2.26	<b>VERIFY</b> Station B mass flow monitoring indicates a nominal flow of 114 KCFM with both 960 fans and inservice 860 fan <b>AND RECORD</b> read value below.
	/
CRAFT	/
Nominal Flo	w ReadkCFM
[ ] 5.4.2.27	INSERT Pitot tube into an open access port.
[ ] 5.4.2.28	VARY probe depth AND RECORD data for each block as indicated in applicable Data Block per operational 860 fan.
[ ] 5.4.2.29	REMOVE Pitot tube.
[ ] 5.4.2.30	<b>INSERT</b> Temperature/Pressure probe into closest adjacent access port.
[ ] 5.4.2.31	<b>RECORD</b> temperature and pressure readings per applicable Data Block.
[ ] 5.4.2.32	<b>REMOVE</b> probes and <b>SECURE</b> penetration plugs in original configuration.

Page 13 of 18

6.0

1617480			Page 14 of 18
5.5	VEND	OR REQUEST	
	[]5.5	Per Vendor request, <b>IF</b> more reading <b>REPERFORM</b> section 5.4 as need Work Status Log. <b>N/A</b> if not applications.	ed and <b>RECORD</b> data in
		1	
		VENDOR DATE	
	[ ] 5.5	<b>VERIFY</b> all testing is complete for '	Nork Package.
		CE/RE DATE	
5.6 RADCON PITOT TUBE			
	[ ] 5.0	6.1 RCT – <b>SURVEY</b> pitot tube and <b>EN</b>	SURE it is commencurate
	8 8	with site radiological restrictions.	
		RCT / DATE	=
		RCT DATE	
TES	TING A	ND RESTORATION	
6.1	POS	T-JOB RESTORATION	
		<b>NOTIFY</b> Facops that work on Station B Pit complete.	ot Tube Traverse is
		/	
FWS		DATE	
[]6.1	.2	<b>SECURE</b> fans 41-B-960A and 41-B-960B.	
[]6.1.3 <b>REMO</b>		<b>REMOVE</b> barriers and barricades.	
[ ] 6.1.4 <b>REQU</b>		REQUEST Facops restore building 413 H	VAC system.
[ ] 6.1.5 <b>RESTORE</b> 413-HD-321-003 damper back to it's original configuration.		to it's original	

# Template 4.0

W.O. 1617480		Page 15 of 18
6.2 PO	ST-JOB REVIEW	
[]6.2.1	FWS CONDUCT post-job review per	WP 04-AD3030.
CRAFT	DATE	

[ ] 6.2.2 All personnel affixing initials to these work instructions **PROVIDE** the information listed in the PERSONNEL DATA table below:

# **PERSONNEL DATA**

PRINTED NAME	SIGNATURE	INITIALC	DATE
	OIGHATORE	INITIALS	DATE
		1	

Data Block 1 - Traverse Data per 860A fan

Depth (inches)	Block 1 – Traverse Data p Traverse velocity fpm	Traverse velocity fpm	Traverse velocity fpm
VERTICLE	(860A fan operational)	(860A fan operational)	(860A fan operational)
•======================================	1	2	3
3.0			
8.0			
14.0			
24.0			
48.0			
57.5			
64.75			
69.5			
Temperature (F°)			
Pressure (inWC)			
Depth (inches) HORIZONTAL	Traverse velocity fpm (860A fan operational)	Traverse velocity fpm (860A fan operational) 2	Traverse velocity fpm (860A fan operational)
3.0			
8.0			
14.0			
24.0			
48.0			
57.5			
64.75			
69.5			
Temperature (F°)			
Pressure (inWC)			

W.O. 1617480

Page 17 of 18

# Data Block 2 - Traverse Data per 860B fan

Depth (inches)	Traverse velocity fpm	•	Travaraa valaaitu fam
VERTICLE	(860B fan operational)	Traverse velocity fpm (860B fan operational) 2	Traverse velocity fpm (860B fan operational)
3.0		_	
8.0			
14.0			
24.0			
48.0			
57.5			
64.75			
69.5			
Temperature (F°)			
Pressure (inWC)			
Depth (inches) HORIZONTAL	Traverse velocity fpm (860B fan operational)	Traverse velocity fpm (860B fan operational) 2	Traverse velocity fpm (860B fan operational)
3.0		_	3
8.0			
14.0			
24.0			
48.0			
57.5			
64.75			
69.5			
Temperature (F°)			
Pressure (inWC)		\$	

Page 18 of 18

Data Block 3 - Traverse Data per 860C fan

Depth (inches) VERTICLE	Traverse velocity fpm (860C fan operational)	Traverse velocity fpm (860C fan operational)	Traverse velocity fpm (860C fan operational)
VERTICE	1	2	3
3.0			
8.0			
14.0			
24.0			
48.0			
57.5			
64.75			
69.5			
Temperature (F°)			
Pressure (inWC)			
Depth (inches) HORIZONTAL	Traverse velocity fpm (860C fan operational)	Traverse velocity fpm (860C fan operational) 2	Traverse velocity fpm (860C fan operational) 3
3.0			
8.0			
14.0			
24.0			
48.0			
57.5			
64.75			
69.5			
Temperature (F°)			
Pressure (inWC)		- i	