

ID	Source Name	NOx	CO	PM10 (tpy)	SO2	VOC
Concrete Batch Plant (Ready Mix Plant)						
NA	Batch drop operations to aggregate storage			0.283		
04-5005/5006	Aggregate transfer to elevated bins			0.283		
04-5009	Aggregate transfer to weigh hoppers			0.283		
04-5010	Aggregate transfer to feed hopper			0.283		
NA	Batch drop operations to sand storage			0.064		
04-5007/5008	Sand transfer to elevated bins			0.064		
04-5011	Sand transfer to weigh hoppers			0.064		
04-5012	Sand transfer to feed hopper			0.064		
	Cement transfer to storage silos			0.009		
	Cement transfer to weigh hoppers			0.347		
	Mixer truck loading			1.278		
NA	Aggregate storage piles			2.19E-04		
NA	Sand storage piles			0.003		
Crushing and Screening Operations						
NA	Batch Drop Operation			0.335		
01-3004B	Feed Hopper			0.255		
99-8001	Feed Hopper			0.064		
99-8002	Feed Hopper			0.042		
01-3004A	Primary Crusher			0.662		
04-3005E	Secondary Crusher			0.662		
04-3005F	Screen			1.459		
99-8002	Screen			0.324		
99-8001	Screen			0.486		
04-3017	Stacker			0.335		
99-3009	Stacker			0.261		
99-8002	Stacker			0.074		
NA	Conveyor transfer points (aggregate)			1.025		
Wet Plant						
NA	Batch Drop Operation			0.127		
01-4002	Screen			0.486		
01-4006	Stacker			0.072		
01-4009	Stacker			0.072		
01-4008	Stacker			0.072		
01-4007	Stacker			0.072		
NA	Conveyor transfer points (aggregate)			0.273		
Facility wide Total				10.18322		

Note:

PTE based upon information contained in application for ADEQ Class II minor source permit, 5/22/2009.

The ADEQ permit application and terminated permit were provided by permit applicant to EPA in supplemental package 2/19/2018