

## **Build a Firewood Storage Shed**

Cost of Materials (price dependant on locality) \$290

- Holds about one cord of wood
- Easy to fabricate
- Takes two people about 5 hours to build
- · Light enough to move by hand

View a 6 minute "how-to" video: www.epa.gov/burnwise/videos





## Firewood Storage Shed Material List

ITEM	QTY	DESCRIPTION	UNIT COST	SUBTOTAL
2" x 6" x 8' Treated Pine	2	Floor Frame	\$6.67	\$13.34
1" x 4" x 8' Treated Pine	13	Floor Slats, Side & Back Slats	\$4.17	\$54.21
2" x 4" x 8' Treated Pine	8	Floor Frame, Joists, Roof Rafters	\$3.88	\$31.04
4" x 4" x 12' Treated Pine	3	Posts	\$16.98	\$50.94
4' x 8' x ½" OSB Plywood	1	Roof	\$20.05	\$20.05
<sup>1</sup> /4" x 5" Hex Lag Screws	12	Secure posts to 2" x 6" & 2" x 4" Floor Frame	\$0.54	\$6.48
3" Galvanized Deck Screws	1lb.Box	Secure Floor Frame, Joists & Roof Rafters	\$9.37	\$9.37
1 <sup>1</sup> / <sub>2</sub> " Galvanized Deck Screws	1lb.Box	Secure Floor Slats, Side & Back Slats, Roof	\$9.89	\$9.89
Liquid Roofing	1 Gal	Weather Protection	\$48.00	\$48.00
12" Concrete Deck Blocks	6	Raise the woodshed off ground	\$7.24	\$43.44
			TOTAL	\$286.76

## **Recommended Tools:**



😥 ladder 🛛 🔎 tape measure 🔤 🎦 drill with 1/4 inch driver level  $\pi\pi$  sawhorses  $\widehat{\mathbf{A}} \cong \widehat{\mathbf{C}}$  eye and hearing protection triangle square square for applying liquid roofing

(1) 4' x 8' x ½" OSB Plywood Roof Attach with 1½" deck screws every 6" along each rafter. Apply liquid roof to top side of roof.		
(6) 2" x 4" x 4' Roof Rafters Attach with (2) 3" deck screws at each post.		
(4) 1" x 4" x 89" Rear Slats Attach with (2) 3" deck screws at each post.		
(8) 1" x 4" x 45" Side Slats Attach with (2) 1½" deck screws at each post.		
(3) 4' x 4' x 6' Posts in the Front of Shed Attach each post with (2) ¼" x 5" hex lag screws.		
(3) 4' x 4' x 5' 6" Posts in the Rear of Shed Attach each post with (2) ¼" x 5" hex lag screws.		
(5) 1" x 4" x 8' Floor Slats Attach with (2) 1½" deck screws at each floor.		
(8) 2" x 4" x 4' Floor Joists Attach with (2) 3" deck screws to 2 x 6 x 8' floor frame.		
(2) 2" x 6" x 8' Front and Rear Floor Frame Attach to sides of floor frame with 3" deck screws.	ALL LAND	
(2) 2" x 4" x 45" Floor Frame Sides Attach to front/rear floor frame with 3" deck screws.		
(6) 12" Concrete Deck Blocks		

Adapted from the Makah Tribe's Modular Wood Shed design

EPA-456/F-18-002 August 2018