#### IN THE UNITED STATES DISTRICT COURT FOR THE SOUTHERN DISTRICT OF INDIANA

#### UNITED STATES OF AMERICA,

and

#### THE STATE OF INDIANA,

Plaintiffs,

v.

THE CITY OF INDIANAPOLIS, INDIANA, A Municipal Corporation, SEB-TAB No. 1:06-cv-01456-DFH-JMS

Defendant.

#### SECOND AMENDMENT TO 2006 CONSENT DECREE

WHEREAS, this Court approved and entered a Consent Decree in this matter on December 19, 2006 ("2006 Consent Decree"). That Consent Decree required the City of Indianapolis ("City" or "Indianapolis"), among other things, to construct 31 Combined Sewer Overflow ("CSO") Control Measures and perform other activities, in accordance with the Descriptions, Design Criteria, and dates for Completion of the Bidding Process and Achievement of Full Operation of the 31 CSO Control Measures. The control measures were set forth in Table 7-5 of Section 7 of the City's Long Term Control Plan ("LTCP"), attached to the 2006 Consent Decree as Exhibit 1 (hereinafter "Exhibit 1").

WHEREAS, on April 23, 2009, the Court approved and entered a First Amendment to the 2006 Decree, which modified CSO Control Measure 16 to require the City, in lieu of constructing a shallow inter-plant connector sewer, to undertake construction of a conveyance and storage tunnel that would be constructed approximately 200 feet below ground (the "Deep Rock Tunnel Connector" or "DRTC"). When completed, the DRTC will provide several improvements over the shallow inter-plant connector sewer. First, the Tunnel will significantly increase the system's storage capacity and thereby improve the City's ability to control CSOs, whereas the shallow inter-plant connector was primarily a conveyance mechanism. In that regard, the DRTC would provide a minimum storage volume of 54 million gallons, and a minimum peak conveyance and dewatering capacity of 150 million gallons per day ("MGD") of CSO flow to the Southport Advanced Water Treatment facility ("AWT"), thus improving the City's ability to control CSOs. Further, the DRTC would enable the City to capture discharges from CSO Outfall 008 three and one-half years earlier than had been possible under the 2006 Consent Decree. The early capture of CSO 008 was expected to result in the capture of an estimated 1 billion gallons of additional CSO volume over the life of the CSO control program. Historically, CSO Outfall 008 has been the outfall in Indianapolis with one of the greatest annual volumes of untreated CSO discharge.

WHEREAS, the First Amendment to the 2006 Consent Decree resulted from a comprehensive engineering review, conducted by the City beginning in 2008, of the City's 2006 LTCP and the 31 Control Measures ("CM") described in Exhibit 1. In that review, the City employed detailed hydraulic modeling, additional treatment plant operating and stress test data, and preliminary design and cost evaluations.

WHEREAS, the City undertook an additional engineering review of the LTCP using advanced modeling capabilities and in May 2009, presented to EPA and IDEM additional proposed modifications to the LTCP, denominated as a comprehensive "Enhancement Plan." After lengthy, in-depth, negotiations, the City, EPA and IDEM agreed on the terms of a "Modified Enhancement Plan" under which 14 of the original 31 Control Measures would be

-2-

modified, two of the original Control Measures would be eliminated, and one Control Measure (No. 32) would be added.

WHEREAS, in furtherance of the Modified Enhancement Plan, the 2006 Consent Decree, as amended in 2009, is further amended for the reasons, and in the manner, discussed below:

#### 1. Collection System and Tunnels

#### a. Control Measures 15, 16 and 20

The City's 2009 redesign of Control Measure 16, *i.e.*, the replacement of the shallow interplant connector sewer with the DRTC, as approved in Amendment No. 1, allowed the City to revise its overall strategy of capture and treatment of CSOs.

The DRTC will allow the City to capture the flows from CSO 008 and combined sewer flows from the west side of the White River in the deep tunnel system rather than separately in shallow sewers, and maximize the City's management of the system's combined storage and treatment capacity. The DRTC will also enable the City to harmonize the timing of flows and loads between the Belmont and Southport AWT facilities, optimize the overall tunnel system (as well as the size of many of the components of the two AWT facilities), balance the storage and treatment capacities of the system, and insure early capture of CSO flows. This balancing will also allow the City to design an expanded tunnel system consisting of the DRTC, Fall Creek, White River, Pleasant Run, and Lower Pogues Run Tunnels, which will function in a more holistic manner. As expanded, the entire tunnel system volume will achieve a storage capacity of 250 MG, while the Southport AWT's treatment capacity will increase from 150 MGD to 250 MGD, peak wet weather flow. Additionally, the design of the DRTC pump station flow was modified to require a peak pumping rate of 90 MGD.

-3-

Through its re-analysis of the system, the City determined that the DRTC can be extended one additional mile north from its originally-planned north termination point, which would allow for the early capture of CSO 118 (also one of the largest CSOs in the system) in addition to the early capture of CSO 008, discussed above. Incorporating this one mile-long extension into the DRTC project required that the bid date for the Connector project be postponed from May 31, 2011 to the end of 2011, and that the schedule for Achievement of Full Operation of the Connector project be extended from May 31, 2016 to the end of 2017, as provided in this Second Amendment to the 2006 Consent Decree.

CSO 008 will now be captured two (2) years earlier than scheduled under the 2006 Consent Decree, and CSO 118 will be captured four (4) years earlier than scheduled under the 2006 Consent Decree. The overall result of these improvements to the DRTC Project, in conjunction with the remainder of the improvements in the Modified Enhancement Plan, will be the capture of approximately 3.5 billion gallons more CSO volume than would have been achieved under the original LTCP. Thus, any deferral of environmental benefits that may result from the extension of the schedule for the Deep Rock Tunnel Connector will be more than balanced by the accelerated capture of CSOs 008 and 118. The changes to the DRTC project are reflected in the modifications to Control Measure 16. See Tables below.

#### b. Control Measures 18 and 29

As in the case of the shallow interceptor sewer that formerly constituted Control Measure 16, the City's re-analysis of the LTCP resulted in a determination that it would be more cost effective to not replace the projects to convert the existing Pogues Run box into a storage facility (Control Measure 18) and to construct the interceptor sewer comprising Control Measure 29, <del>butto instead extend</del> with an extension of the deep tunnel system up the Lower Pogues Run

-4-

watershed and Lower Pleasant Run watershed to capture certain CSOs. The Lower Pogues Run box conversion project would have presented both operational challenges and a high risk of flooding in downtown Indianapolis. Extending the deep tunnel system up the Lower Pogues Run and Lower Pleasant Run will allow the City to eliminate the Lower Pogues Run box conversion project entirely.

Construction of the extended deep tunnel segment up the Lower Pogues Run watershed will require an additional nine years (from 2012 to 2021) to achieve full operation of that portion of the system; however, the efficiencies of the tunnel extension, and the elimination of the problems that would have resulted from converting the Pogues Run Box far outweigh any environmental benefits that might be lost by extending a part of the compliance schedule. In any event, the City has determined that the schedule extension required for construction of the extended tunnel segment will not jeopardize the City's ability to comply with the schedule for completion of the deep tunnel system that will serve Lower Pleasant Run. The changes to these two projects are reflected in the modifications to Control Measures 18 and 29. See Tables below.

#### c. Control Measure 30

The City, EPA and IDEM agreed that several aspects of Control Measure 30, the Eagle Creek watershed project, should be modified. In particular, the City discovered an alternative route for the originally-proposed Belmont West Cutoff to the Eagle Creek Interceptor - the City will now use the Belmont North Relief Interceptor (a project that was not part of the LTCP) to convey flows to that portion of the Belmont Interceptor system leading to the Belmont AWT. This change will allow the City to modify the flows in the Eagle Creek overflow collector system. See Tables below.

--5-

#### d. Control Measure 31

The City's detailed modeling efforts allowed the Parties to agree on ranges for the storage volumes and flow rates of the facilities for the Upper Pogues Run improvements to replace the "approximate" values that had been in the original Table 7-5. See Tables below.

#### 2. <u>Southport AWT</u> (Control Measures 22, 23, 24, 26, 27, and 28)

The peak wet weather treatment capacity of the Southport AWT facility will be increased to 250 MGD, and additional changes will be made to the Control Measures pertaining to the facility's headworks and its primary treatment, secondary treatment and disinfection systems.

The planned modification of the DRTC project (discussed above in regard to Control Measure 16) will allow the City to take better advantage of the existing infrastructure at the Southport AWT; existing facilities will be refurbished, enhanced and expanded slightly to allow the facility to provide 250 MGD of secondary treatment capacity for wet weather flows. The changes to the Southport AWT are reflected in the modifications to Control Measures 22, 23, 24 and 26. See Tables below.

In addition, the City determined through more detailed modeling that Control Measure 27 (new pump station for additional dewatering of captured CSO), and Control Measure 28 (enhanced high rate clarification treatment), could be eliminated, because those additional treatment projects will no longer be necessary to allow the City to provide 250 MGD of secondary treatment capacity for wet weather flows. See Tables below.

#### 3. Belmont AWT

#### a. <u>Control Measure 25</u>

The changes to the Belmont AWT design include modification of the influent peak wet weather flow rates to maximize the utilization of the existing wet weather storage and

-6-

equalization basins that were built as early action projects, and rerouting of the existing Wet Weather Pump Station to the existing Wet Weather Storage Basin No. 1. See Tables below.

#### b. Control Measure 32 (New)

The City is designing a new Control Measure 32, to be comprised of two new projects to be added to the LTCP. The first project consists of construction of a Primary Effluent Pump Station, which will be able to transfer up to 35 MGD of excess primary effluent flows from the Belmont AWT to the Southport AWT facility during both dry and wet weather conditions to balance flows and loads at the two AWT facilities. The second project will consist of a new Plant Drain Pump Station, which will convey up to 20 MGD of plant drain flows to primary treatment during wet weather, and will effectively increase the raw pumping capacity of the Belmont AWT's influent screw pumps to 330 MGD. See Tables below.

#### c. Control Measures 17 and 21.

The City will modify the treatment process for the Belmont Wet Weather Secondary Expansion by substituting an Air Nitrification System/Oxygen Nitrification System process for the original Trickling Filter/Secondary Clarifier process. That change will allow the City to eliminate a separate wet weather outfall, consolidate all the flows in a single treatment process train, and modify the disinfection system. These changes are detailed in Control Measures 17 and 21. See Tables below.

WHEREAS, the 2010 modifications to Exhibit 1 are set forth in the following tables. The text of both the original and modified, or new, endnotes are set forth following the tables.

## (Table 7-5; Exhibit 1, with 2010 modifications)

Original 2006	CSO Control Measure <sup>1</sup>		Control Measure <sup>1</sup> Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
	15	Fall Creek Tunnel, Collector Pipes and Watershed Projects	Deep storage tunnel, consolidation sewers, elimination of CSO 103, dam removal, aeration <sup>8</sup>	Provide a storage volume of 110 MG	When incorporated with the rest of the Fall Creek watershed, achieve 97 percent capture and 2 overflow events <sup>6</sup>	Bid Year – 2006 Achievement of Full Operation - 2025
2010 Modification	15	Fall Creek Tunnel, Collector Pipes and Watershed Projects	Deep storage tunnel, consolidation sewers, elimination of CSO 103 and dam removal aeration. <sup>8</sup>	Provide a total effective <sup>11</sup> storage volume of 250 MG in the Fall Creek, White River, Pogues Run, Pleasant Run and DRTC tunnel system <sup>10</sup>	When incorporated with the rest of the Fall Creek watershed, achieve 97 percent capture and 2 overflow events on Fall Creek Watershed <sup>6</sup>	Bid Year - 2006 Achievement of Full Operation - 2025

## 2. 2010 Modification of CSO Control Measure No. 16

	CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
First Amendment (2009)	16	Deep Rock Tunnel Connector, Deep Tunnel Pumping Station and Screening Facilities, and Connection of CSO 008 to the Deep Rock Tunnel Connector	Deep rock tunnel originating near CSO 117 and terminating near the headworks of the Southport facility <sup>8</sup> deep tunnel pumping station and screening facilities located near the Southport treatment facility, and structures necessary to tie CSO 008 flows into the Deep Rock Tunnel Connector	Provide a minimum storage volume of 54 MG within the entire Tunnel Connector project and a minimum peak conveyance and dewatering capacity of 150 MGD CSO flow to Southport	Maximize delivery of flow from White River Tunnel to Southport AWT Plant. Optimize capture of CSO 008 and CSO 117	Bid Year - May 31, 2011 Achievement of Full Operation - May 31, 2016
2010 Modification	16	Deep Rock Tunnel Connector, Deep Tunnel Pumping Station and Screening Facilities, and Connection of CSO 008, <u>CSO 117</u> and <u>CSO 118</u> to the Deep Rock Tunnel Connector	Deep rock tunnel originating near <u>CSO 118</u> and terminating near the headworks of the Southport facility <sup>8</sup> deep tunnel pumping station and screening facilities located near the Southport treatment facility, and structures necessary to tie CSO 008, <u>CSO 117</u> <u>and CSO 118</u> flows into the Deep Rock Tunnel Connector	Provide a minimum total effective <sup>11</sup> storage volume of 54 MG- within the entire Tunnel Connector- project and 250 MG in the Fall Creek, White River, Pogues Run, Pleasant Run and DRTC tunnel system <sup>16</sup> with a minimum peak conveyance and dewatering capacity of 150 MGB <u>20 MGID</u> CSO flow to Southport	Maximize delivery of flow from White River Tunnel to Southport AWT Plant. Optimize capture of CSO 008, and CSO 117, and CSO 118.	Bid Year - <del>May 31</del> , 2011 Achievement of Full Operation - <del>May 31, 2016</del> 2017

#### (Table 7-5; Exhibit 1, with 2010 modifications)

-8-

	CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
Original (2006)	17	Belmont AWT - Wet-Weather Treatment (Trickling Filters/Solids Contact: New acration tanks and intermediate clarifiers)	Provide secondary biological treatment of the Belmont PE Bypass	Provide parallel peak biological treatment rate of 150 MGD	When incorporated with the rest of the Belmont improvements, facility complies with current NPDES permit	Bid Year - 2009 Achievement of Full Operation - 2012
2010 Modification	17	Belmont AWT -Wet- Weather Treatment- (Trickling Filters/Solids Context:New acration tanks and intermediate- clarifiers) (New acration tanks)	Provide secondary biological treatment of the Belmont PE Bypass	Provide parallel <u>in</u> <u>series</u> peak biological treatment rate of <del>150</del> MGD <u>300 MGD</u>	When incorporated with the rest of the Belmont improvements, facility complies with current NPDES permit	Bid Year – 2009 Achievement of Full Operation - 2012

#### (Table 7-5; Exhibit 1, with 2010 modifications)

#### 4. Modification of CSO Control Measure No. 18

	CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Mílestones <sup>3</sup>
Original (2006)	18	Lower Pogues Run Improvements – Continued	Conversion of existing Pogues Run Box into CSO storage facility ranging from t.5 to 10 MG and interceptor	Diversion of CSO to White River Tunnel	When incorporated with the rest of the Pogues Run and White River watersheds, achieve 95 percent capture and 4 overflow events <sup>a</sup>	Bid Year - 2010 Achievement of Full Operation - 2012
2010 Modification	18	Lower Pogues Run Improvements- <del>Continued</del>	Deep Storage Tunnel and consolidation sewers <sup>8</sup>	Provide a total effective <sup>11</sup> storage volume of 250 MG in the Fall Creek, White River, Pogues Run, Pleasant Run and DRTC tunnel system <sup>10</sup>	When incorporated with the rest of the Pogues Run and White River watersheds, achieve 95 percent capture and 4 overflow events <sup>a</sup>	Bid Year - <del>2010</del> 2011 Achievement of Full Operation – <del>2012</del> 2021

(Table 7-5; Exhibit 1, with 2010 modifications)

	CSO Control Measure <sup>1</sup>		Description Design	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
Original (2006)	20	White River Tunnel (Central Tunnel and Pump Station) and Watershed Projects	Central tunnel and pump station, consolidation sewers, sewer separation, dam modifications, and aeration <sup>5</sup>	Provide storage volume of 114 MG	When incorporated with the rest of the White River watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year - 2010 Achievement of Full Operation - 2021
2010 Modification	20	White River Tunnel (Central Tunnel) and Watershed Projects	Central tunnel, consolidation sewers, sewer separation and dam modifications <sup>8</sup>	Provide a total effective <sup>11</sup> storage volume of 250 MG in the I <sup>all</sup> Creek, White River, Pogues Run, Pleasant Run and DRTC tunnel system <sup>10</sup>	When incorporated with the rest of the White River watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year - 2010 Achievement of Full Operation - 2021

### (Table 7-5; Exhibit 1, with 2010 modifications)

# 6. Modification to CSO Control Measure No. 21

	CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
Original (2006)	21	Belmont AWT – Wet Weather Chlorination/ Dechlorination (Chlorine Disinfection Tank and Re-establish Existing Outfall)	New wet-weather disinfection system and new discharge to White River	Additional peak disinfection treatment rate of 150 MGD	When incorporated with the rest of the Belmont improvements, facility complies with current NPDES permit	Bid Year – 2010 Achievement of Full Operation - 2012
2010 Modification	21	Belmont AWT – Wet Weather Chlorination/ Dechlorination (Chlorine Disinfection Tank and Re-establish Existing Outfall)	New wet-weather disinfection system and new discharge to White River	Additional peak- disinfection treatment rate of 150 MGD Additional peak disinfection treatment rate of 150 MGD for- a total of 300 MGD peak disinfection treatment capacity consistent with applicable disinfection requirements of current NPDES permit <sup>2</sup>	When incorporated with the rest of the Belmont improvements, facility complies with current NPDES permit	Bid Year - 2010 Achievement of Full Operation - 2012

(Table 7-5; Exhibit 1, with 2010 modifications)

	CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
Original (2006)	22	Southport Advanced Wastewater Treatment Plant Improvements – Air Nitrification System (ANS) Expansion	Expansion of ANS from 30 MGD to 150 MGD, fine bubble acration, new blowers, new final clarifiers, and new process/yard piping	When incorporated with the rest of the Southport Improvements, provide total peak treatment rate of 300 MGD. Provide maximum pumping rate of 350 MGD	When incorporated with the rest of the Southport improvements, facility complies with current NPDES permit	Bid Year – 2010 Achievement of Full Operation - 2016
2010 Modification	22	Southport Advanced Wastewater Treatment Plant Improvements - Air- Nitrifleation System (ANS)- Secondary Treatment System Expansion	Expansion of ANS- from 30 MGD to 150 MGD, fine bubble- acration, new blowers, new final elarifiers, and new process/yard piping Expansion of Secondary Treatment System from 150 MGD to 250 MGD	When incorporated with the rest of the Southport Improvements, provide total peak- treatment rate of 3000 MGD-secondary and disinfection treatment rate of 230 MGD consistent with applicable disinfection requirements of current NPIDIS permit. Provide maximum pumping rate of 345 345 MGD/ <sup>2</sup>	When incorporated with the rest of the Southport improvements, facility complies with current NPDES permit	Bid Year – <del>2010</del> <u>2012</u> Achievement of Full Operation - <del>2016</del> <u>2017</u>

	CSO	Control Measure <sup>1</sup>	Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
Original (2006)	23	Southport Advanced Wastewater Treatment Plant Improvements – Wet Weather Disinfection	New disinfection facility, pump station, 25 MG equalization basin with acrators, and new process/yard piping	When incorporated with the rest of the Southport Improvements, provide total peak treatment rate of 300 MGD. Provide maximum pumping rate of 350 MGD	When incorporated with the rest of the Southport improvements, facility complies with current NPDES permit	Bid Year – 2011 Achievement of Full Operation - 2016
2010 Modification	23	Southport Advanced Wastewater Treatment Plant Improvements – Wet Weather Disinfection	New disinfection facility <del>pump station, 25 MG- equalization basin with aerators, <u>and new process/yard</u> <u>piping</u></del>	When incorporated with the rest of the Southport Improvements, provide tetal peak- reate of 300 MGD. <u>secondary and</u> <u>disinfection treat- ment rate of 250</u> <u>MGD consistent</u> with applicable <u>disinfection</u> <u>requirements of</u> <u>current NPIDES</u> <u>permit</u> . Provide maximum pumping rate of 350 <u>315</u> MGD <sup>12</sup>	When incorporated with the rest of the Southport improvements, facility complies with current NPDES permit	Bid Year - <del>2011</del> - 2012 Achievement of Full Operation - <del>2016</del> - 2017

	CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
Original (2006)	24	Southport Advanced Wastewater Treatment Plant Improvements – Primary Clarifier Expansion	Expansion of primary clarification facility, and new process/yard piping	When incorporated with the rest of the Southport Improvements, provide peak primary treatment capacity of 300 MGD. Provide maximum pumping rate of 350 MGD	When incorporated with the rest of the Southport improvements, facility complies with current NPDES permit	Bid Year – 2012 Achievement of Full Operation - 2017
2010 Modification	24	Southport Advanced Wastewater Treatment Plant Improvements Primary Clarifier Expansion	Expansion Enhancement of primary clarification facility, and new process/yard piping	When incorporated with the rest of the Southport Improvements, provide peak primary treatment capacity of <u>350 MGD: as</u> <u>required to support</u> <u>secondary treatment</u> <u>design, and peak</u> <u>secondary and</u> <u>disinfection treatment</u> <u>capacity of 250 MGD</u> <u>consistent with</u> <u>applicable</u> <u>disinfection</u> <u>requirements of</u> <u>current NPDES</u> <u>permit.</u> Provide maximum pumping rate of <del>350 <u>345</u></del> MGD <sup>12</sup>	When incorporated with the rest of the Southport improvements, facility complies with current NPDES permit	Bid Year – 2012 Achievement of Full Operation - 2017

	CSO Control Measure <sup>1</sup>	Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
Original (2006)	25 Belmont Advanced Wastewater Treatment Plant Improvements – Headworks and Grit Removal including Screens	Rehabilitation of the original headworks, new process/yard piping and supplemental disinfection from existing equalization basins	When incorporated with the rest of the Belmont Improvements, provide total peak primary and biological treatment rate of 300 MGD. Provide peak pumping rate of 450 MGD. Additional Disinfection of equalization outflow up to a peak rate of 150 MGD	When incorporated with the rest of the Belmont improvements, facility complies with current NPDES permit	Bid Year – 2015 Achievement of Full Operation – 2019
2010 Modification	25 Belmont Advanced 25 Wastewater Treatment Plant Improvements - Headworks and Grit- Removal including- Sereens <u>Raw Wastewater</u> <u>Pumping Capacity</u> <u>Expansion</u>	Rerouting of the existing Wet Weather Pump Station (WWPS) to the existing wet weather storage basin (WWSB No.1)	When incorporated with the rest of the Belmont Improvements, provide total peak primary and biological treatment rate of 300 MGD. Provide peak pumping rate of 450 <u>330</u> MGD <sup>12</sup> . Additional- Disinfection off equalization outflow- up to a peak rate of 150 MGD	When incorporated with the rest of the Belmont improvements, facility complies with current NPDES permit	Bid Year2015 2011 Achievement of Full Operation - 2019 2012

	CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
Original (2006)	26	Southport Advanced Wastewater Treatment Plant Improvements – Headworks	Expansion of headworks, screening, grit removal, and new process/yard piping	When incorporated with the rest of the Southport Improvements, provide total peak treatment rate of 300 MGD. Provide peak pumping rate of 350 MGD	When incorporated with the rest of the Southport improvements, facility complies with current NPDES permit	Bid Year - 2015 Achievement of Full Operation - 2018
2010 Modification	26	Southport Advanced Wastewater Treatment Plant Improvements Headworks	Expansion of headworks, screening, grit removal, and new process/yard piping	When incorporated with the rest of the Southport Improvements, provide total peak secondary and disinfection treatment rate of <del>300</del> 250 MGD <u>consistent with</u> <u>applicable</u> <u>disinfection</u> <u>requirements of</u> <u>current NPIDES</u> <u>permit.</u> Provide peak pumping rate of <del>350</del> <u>345</u> MGD <sup>12</sup>	When incorporated with the rest of the Southport improve- ments, facility complies with current NPDES permit	Bid Year —2015- 2012 Achievement of Full Operation -2017 2017

## (Table 7-5; Exhibit 1, with 2010 modifications)

#### 12. Modification to CSO Control Measure No. 27

	CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
Original (2009 Modification)	27	Southport Advanced Waste-water Treatment Plant Improvements – CSO Pump Station	New pump station for additional dewatering of captured CSO from the Deep Rock Tunnel Connector (fka Interplant Connection)	Additional 75 MGD for routing to Enhanced High Rate Clarifiers (EHRC)	When incorporated with the rest of the Southport improve- ments, facility complies with current NPDES permit	Bid Year – 2022 Achievement of Full Operation - 2025
2010 Modification	279	Deleted	Deleted	Deleted	Deleted	Deleted

	CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>	
Original (2009 Modificatio n)	28	Southport Advanced Wastewater Treatment Plant Improvements – EHRC Facility <sup>7</sup>	New enhanced high rate clarifiers, and new process/yard piping	Additional 75 MGD EHRC treatment for dewatering of captured CSO from the Deep Rock Tunnel Connector (fka Interplant Connection)	When incorporated with the rest of the Southport improve- ments, facility complies with current NPDES permit	Bid Year - 2022 Achievement of Full Operation - 2025	
2010 Modificatio п	28 <sup>7 &amp; 9</sup>	Deleted	Deleted	Deleted	Deleted	Deleted	

## (Table 7-5; Exhibit 1, with 2010 modifications)

## 14. Modification to CSO Control Measure No. 29

CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>	
Original (2006)	29	Pleasant Run Overflow Collector Pipe (CSO Collector Pipe)	Collection interceptor and sewer separation. Collection interceptor is approximately 46,000 feet of pipe <sup>8</sup>	Provide approximate instantaneous peak flow rate of 125 MGD at the downstream end	When incorporated with the rest of the Pleasant Run watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2010 Achievement of Full Operation – 2025
2010 Modification	29	Pleasant Run Deep Tunnel aud Overflow Collector Pipe	Deep tunnel. <u>connection sewers</u> , <u>collection interceptor</u> , <u>and sewer separation</u> . <u>Tunnel connects to</u> <u>area of White River and</u> <u>DRTC Tunnels and</u> <u>extends to the area of</u> <u>CSO 084<sup>8</sup></u>	Provide a total effective <sup>11</sup> storage volume of 250 MG in the Fall Creek, White River, Pogues Run, Pleasant Run and DRTC tunnel system <sup>10</sup>	When incorporated with the rest of the Pleasant Run watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2010 Achievement of Full Operation – 2025

(Table 7-5; Exhibit 1, with 2010 modifications)

	CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
Original (2006)	30	Eagle Creek Overflow Collector Pipe (CSO Collector Pipe and Belmont West Cutoff)	Collection interceptor and relief interceptor. Collection interceptor and relief interceptor are approximately 40,000 feet of pipes	Provide approximate instantaneous peak flow rate of 50 MGD at the downstream end	When incorporated with the rest of the Eagle Creek and White River watersheds, achieve 95 percent capture and 4 overflow eventss	Bid Year - 2013 Achievement of Full Operation - 2018
2010 Modification	30	Eagle Creek Overflow Collector Pipe (CSO Collector Pipe <del>and</del> Belmont West Cutoff via the Belmont North <u>Relief Interceptor</u> <u>Systemi</u>	Collection interceptor and rolief interceptor. Collection interceptor and relief interceptor are approximately. 40,000 feet of pipes system and relief interceptor to achieve Performance Criteria <sup>8</sup>	Provide instantaneous peak flowrate of 38 MGD in the Belmont North Relief Interceptor System. Provide instantaneous peak flowrate of 25 to 50 MGD at the downstream end of the Eagle Creek Overflow Collector Pipe.	When incorporated with the rest of the Eagle Creek and White River watersheds, achieve 95 percent capture and 4 overflow events <sup>4</sup>	Bid Year – 2013 Achievement of Full Operation - 2018

## (Table 7-5; Exhibit 1, with 2010 modifications)

## 16. Modification to CSO Control Measure No. 31

	CSO Control Measure <sup>1</sup>		Description	Design Criteria	Performance Criteria	Critical Milestones <sup>3</sup>
Original (2006)	31	Upper Pogues Run Improvements	Off-line storage facility, collection interceptor. Collection interceptor is approximately 9000 feet of pipes	Provide approximate instantaneous peak flowrate of 65 MGD. Provide approximate storage volume of 9.5 MG	When incorporated with the rest of the Pogues Run watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2017 Achievement of Full Operation – 2021
2010 Modification	31	Upper Pogues Run Improvements	Off-line storage facility, collection interceptor to achieve Performance Criteria <sup>#</sup> . Collection interceptor- is approximately 9000 feet of pipes	Provide instantaneous peak flowrate of 65- MGD- <u>40 to 80 MGD</u> . Provide approximate storage volume of <u>9-5-</u> MGD- <u>1 to 3 MG</u>	When incorporated with the rest of the Pogues Run watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2017 Achievement of Full Operation – 2021

#### 17. New CSO Control Measure No. 32

	CSO Control Measure <sup>1</sup>	Description	Design Criteria	Performance Criteria	Critical Mílestones <sup>3</sup>
Control Measure	32 Belmont Advanced Wastewater Treatment (AWT) Plant Improvements	Rerouting of in-plant recycle flows from the headworks to primary treatment via the Plant Drain Pump Station (PDPS). Diversion of the primary effluent from Belmont AWT to Southport AWT via the Primary Effluent Pump Station (PEPS).	When incorporated with the rest of the Belmont AWT improvements, provide total peak primary and secondary treatment rate of 300 MGD. Provide peak headworks pumping rate of 330 MGD.	When incorporated with the rest of the Belmont improvements, facility complies with current NPDES permit	Bid Year - 2008 Achievement of Full Operation - 2009

#### (Table 7-5; Exhibit 1, with 2010 modifications)

#### 18. Modifications to Footnotes

Exhibit 1 has a number of explanatory "footnotes," several of which have been added, modified or deleted, as set forth below (additions/revisions are italicized and underlined;

deletions are stricken):

<sup>1</sup> Upon full implementation, the CSO Control Measures listed in Table 7-5 are expected to result in at least the Performance Criteria of 95 percent capture and 4 CSO events on the White River, Pleasant Run, Pogues Run, and Eagle Creek and 97 percent capture and 2 CSO events on Fall Creek, as evaluated in accordance with footnote 6. Either a revision to Indiana's current water quality standards or some other legal mechanism is necessary to authorize overflows due to storms exceeding those levels of control. In Section 9 of the LTCP, the City of Indianapolis is requesting a revision to the applicable water quality criteria consistent with this level of control through the establishment of a CSO wet weather limited use sub category supported by a Use Attainability Analysis ("UAA"). The design and construction of CSO Control Measures 1 through 14 ("Phase I" Projects) are not dependent upon the level of control ultimately determined, and therefore the City will implement CSO Control Measures 1 through 14 according to the terms and schedule set forth in this Table. IDEM and U.S. EPA acknowledge that the City is scheduled to start investing heavily in CSO Control Measures 15 through 3232, which are level of control-dependent, in the years following approval of the City's LTCP. Accordingly, all parties intend that the UAA process be completed within five years of LTCP approval. If the

-18-

UAA process is not completed within five years, IDEM and U.S. EPA agree that, under certain circumstances, the City can seek a modification of the implementation schedule.

<sup>2</sup>2 The Description and Design Criteria are based upon LTCP-level planning estimates and may be subject to revision during facility planning and design. One of the conditions of Descriptions and Design Criteria, applicable to all of the facilities set forth in this Table 7-5 is that the specific facility will be designed in accordance with good engineering practices to ensure that corresponding facility-specific, watershed-wide, and systemwide Performance Criteria will be achieved. Footnote 2 deleted.

<sup>3</sup> The term "Bid Year" means "Completion of the Bidding Process."

<sup>4</sup> The CSO control measure is not expected to achieve 95 or 97 percent capture on its own and will work in conjunction with other CSO control measures at the specified CSO outfalls to achieve the performance criteria.

<sup>5</sup> Consistent Operation: Performs as designed on a regular basis. Failure to perform correctly is infrequent.

<sup>6</sup> CSO Control Measures will be designed *in accordance with the Design Criteria set forth in Table 7-5, and they shall also* to achieve *at least the* Performance Criteria of 97 percent capture for the Fall Creek watershed and 95 percent capture for other CSO receiving waters, and 2 CSO events for the Fall Creek watershed and 4 CSO events for each of the other CSO receiving waters in a "typical year." "Typical year" performance, and achievement of Performance Criteria, shall be assessed in accordance with Section 8.4 (Post Construction Monitoring) using the average annual statistics generated by the collection system model for the representative five-year simulation period of 1996 to 2000 (or another five-year simulation period subsequently proposed by the City and approved by IDEM and U.S. EPA).

<sup>7</sup> The Southport EHRC facility will be constructed only if required to achieve the performance criteria for the Fall Creek and White River watersheds. *Footnote 7 deleted.* 

<sup>8</sup> The collection interceptor may be installed as multiple interceptors with the combined capacity as described in the Design Criteria.

<sup>9</sup> Control Measures 27 and 28 deleted.

-19-

<sup>10</sup> Control Measures 15, 16, 18, 20 and 29 have a combined Design Criteria of 250 MG of 'effective' (as defined below) storage in the Fall Creek, White River, Pogues Run, Pleasant Run and DRTC Tunnel System. This total effective available system storage of 250 MG includes adits and deaeration chambers, which are tunnel connections from drop shafts to the mainline tunnels.

<sup>11</sup> 'Effective' as identified for Control Measures 15, 16, 18, 20 and 29 is defined as the storage volume that will be designed and operated to ensure 250 MG of wet-weather flow may be reliably stored in the tunnel system provided Indianapolis has received sufficient precipitation to capture 250 MG of wetweather flow in a single event or two or more sequential events.

<sup>12</sup> Control Measures 21, 22, 23, 24, 25 and 26 have flowrates as noted within the Design Criteria for each Control Measure. Control Measures 22, 23, 24 and 26 have a secondary treatment capacity of 250 MGD and a disinfection capacity of 250 MGD (consistent with applicable disinfection requirements of the City's current NPDES permit), which includes in-plant return flows. Control Measures 21 and 25 have a secondary treatment capacity of 300 MGD and a disinfection capacity of 300 MGD (consistent with applicable disinfection requirements of the City's current NPDES permit), which includes in-plant return flows.

The new Exhibit 1 (Table 7-5), as modified by this Second Amendment to 2006 Consent Decree, is attached hereto as Exhibit 1. All references in the 2006 Consent Decree to "Exhibit 1" shall be to this new Exhibit 1.

The Court finds there is no just reason for delay and therefore enters this Second

Amendment to 2006 Consent Decree.

SO ORDERED

Aud Carris Brike

SARAH EVANS BARKER, JUDGE United States District Court Southern District of Indiana

Date: 01/27/2011

(

Date: 11/2/10

# FOR THE UNITED STATES OF AMERICA

IGNACIA S. MORENO Assistant Attorney General Environment and Natural Resources Division

Date:

GREGORY L. SUKYS Senior Attorney Environmental Enforcement Section United States Department of Justice P.O. Box 7611 Ben Franklin Station Washington, D.C. 20044-7611 Phone: (202) 514-2068/616-6584 (FAX)

#### TIMOTHY M. MORRISON United States Attorney

Date:

By: THOMAS E. KIEPER Assistant United States Attorney Southern District of Indiana 10 West Market Street, Suite 2100 Indianapolis, Indiana 46204 (317) 229-2415/(419) 259-6360 (FAX)

# FOR THE UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Date: 10/7/10

MARK POLLINS Director, Water Enforcement Division U.S. Environmental Protection Agency 1200 Pennsylvania Ave., NW Washington, DC 20460

# FOR THE UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Date: 9/20/10

SUSAN HEDMAN Regional Administrator U.S. EPA Region 5

Date: 9/16/10

ROBERT A. KAPLAN Regional Counsel U.S. EPA Region 5 77 W. Jackson Blvd. Chicago, Illinois 60604

-24--

#### FOR THE STATE OF INDIANA

GREGORY F. ZOELLER Attorney General of Indiana

Date: SETTEMBER 13, 2010

THOMAS W. EASTERLY Commissioner Indiana Department of Environmental Management 100 North Senate Avenue IGCN 1301 Indianapolis, Indiana 46204

Date: <u>September</u> 10, 2010

PATRICIA ORLOFF ERDMANN Chief Counsel for Litigation Office of the Indiana Attorney General 302 W. Washington Street, IGCS-5th Floor Indianapolis, Indiana 46204

#### FOR THE CITY OF INDIANAPOLIS, INDIANA

Date: 9/7/10

DAVID R. SHERMAN Director Department of Public Works City of Indianapolis 200 East Washington Street Suite 2460 Indianapolis, Indiana 46204

Date: 9/7/10

SAMANTHA KARN Corporation Counsel City of Indianapolis 200 East Washington Street Suite 1601 Indianapolis, Indiana 46204

	SO Control	Description <sup>2</sup>	Design Criteria <sup>2</sup>	Performance	Critical
	Measure <sup>1</sup>	Description	Design Criteria	Criteria	Milestones <sup>3</sup>
1	White River Screen at IUPUI (CSO 039)	Horizontal screen with automatic clearing for removal of floatables	Provide instantaneous peak screening flow rate of 63 MGD	Capture most floatables greater than 4 mm in size	Bid Year – 2001 Achievement of Full Operation – 2002
2	Fall Creek Inflatable Dams (CSOs 063, 063A, and 065) <sup>4</sup>	Construction of three inflatable dams	Provide in-system storage capacity of approximately 4.6 MG	Consistent Operation <sup>5</sup>	Bid Year – 2001 Achievement of Full Operation – 2006
3	Modifications to Lift Station 507 at Riviera Club	Modifications to CSO 156 to take advantage of available storage volume in LS 507	Maximize in-system storage	Diversion of flow from CSO 156 to LS 507. When incorporated with the rest of the White River watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2002 Achievement of Full Operation – 2002
4	Real-time Overflow Controls in Neighborhoods (CSOs 080, 084,118) <sup>4</sup>	Construction of three inflatable dams	Provide in-system storage capacity of approximately 0.5 MG	Consistent Operation <sup>5</sup>	Bid Year – 2002 Achievement of Full Operation – 2003
5	Pogues Run Inflatable Dam at Brookside Park (CSO 101) <sup>4</sup>	Construction of one inflatable dam	Provide in-system storage capacity of approximately 0.4 MG	Consistent Operation <sup>5</sup>	Bid Year – 2003 Achievement of Full Operation – 2004
6	White River East Bank Storage Tank at IUPUI/White River State Park <sup>4</sup>	Overflow storage for CSO 039	Provide storage capacity of 3 MG	When incorporated with the rest of the White River watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2003 Achievement of Full Operation (CSO 39 Only) – 2004
7	Belmont Advanced Wastewater Treatment (AWT) Plant Improvements Wet-Weather Storage and Primary Clarifiers	Wet-weather storagc basins (30 and 4 MG), two new primary clarifiers, and new process/yard piping	When incorporated with the rest of the Belmont Improvements, provide peak primary and biological treatment rate of 300 MGD	When incorporated with the rest of the Belmont improvements, facility complies with current NPDES permit	Bid Year – 2003 Achievement of Full Operation – 2007

**TABLE 7-5** (Revised September 1, 2010)

# CSO Control Measures, Design Criteria, Performance Criteria, and Critical Milestones

C	SO Control Measure <sup>1</sup>	Description <sup>2</sup>	Design Criteria <sup>2</sup>	Performance Criteria	Critical Milestones <sup>3</sup>
8	Lower Pogues Run Improvements - Minimize Overflows near IPS Schools	Consolidation of outfalls 034 and 035 to Pogues Run Tunnel. Consolidation sewer is approximately 5200 feet of pipe	Provide approximate instantaneous peak flowrate of 40 MGD upstream. Provide approximate maximum instantaneous peak flowrate of 150 MGD downstream	When incorporated with the rest of the Pogues Run watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2004 Achievement of Full Operation – 2006
9	Belmont AWT Gravity Belt Thickeners	Installation of four gravity belt thickeners	Produce a thickened sludge concentration of 5% total solids (TS)	Reduction of sludge volumes and improved sludge dewatering operations.	Bid Year – 2006 Achievement of Full Operation – 2008
10	Sewer Separation - White River and Thompson Road (CSO 275)	Separation and rehabilitation of sewers to reduce stormwater flow and minimize CSO 275	Storm drains designed as per Indianapolis Stormwater Standards. Sanitary sewer designed as per Indianapolis Sanitary Standards and Ten State Standards	Separation of sewers to minimize CSO 275.	Bid Year – 2006 Achievement of Full Operation - 2008
11	Sewer Separation - Lick Creek (CSO 235)	Separation and rehabilitation of sewers to reduce storm water flow and minimize CSO 235	Storm drains designed as per Indianapolis Stormwater Standards. Sanitary sewer designed as per Indianapolis Sanitary Standards and Ten State Standards	Separation of sewers to minimize CSO 235.	Bid Year – 2006 Achievement of Full Operation - 2008
12	Real Time Overflow Control Study, Phase II	Develop next phase of RTC to further maximize the existing combined sewer system	Evaluate RTC for combined sewer system	Completed Study	Commence study - 2007 Complete study - 2008
13	Rerouting of Overflows on Upper White River to Lift Station 507 at Riviera Club (CSO 205)	Relocation of CSO 205 outfall to Lift Station 507. Includes rehabilitation of upstream sewers to eliminate clearwater infiltration	Provide approximate instantaneous peak flowrate of 25 MGD	When incorporated with the rest of the White River watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2008 Achievement of Full Operation – 2010
14	Riviera Club Improvements to Overflow Storage Tank	Add wet-weather disinfection to existing satellite storage facility	Provide approximate instantaneous peak disinfection flow rate of 53 MGD	When incorporated with the rest of the White River watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2009 Achievement of Full Operation – 2011

	SO Control	Description <sup>2</sup>	Design Criteria <sup>2</sup>	Performance	Critical
	Measure <sup>1</sup>			Criteria	Milestones <sup>3</sup>
15	Fall Creek Tunnel, Collector Pipes and Watershed Projects	Deep storage tunnel, consolidation sewers, elimination of CSO 103 and dam removal <sup>8</sup>	Provide a total effective <sup>11</sup> storage volume of 250 MG in the Fall Creek, White River, Pogues Run, Pleasant Run and DRTC tunnel system <sup>10</sup>	When incorporated with the rest of the Fall Creek watershed, achieve 97 percent capture and 2 overflow events on Fall Creek Watershed <sup>6</sup>	Bid Year – 2006 Achievement of Full Operation – 2025
16	Deep Rock Tunnel Connector, Deep Tunnel Pumping Station and Screening Facilities, and Connection of CSO 008, CSO 117 and CSO 118 to the Deep Rock Tunnel Connector	Deep rock tunnel originating near CSO 118 and terminating near the headworks of the Southport facility <sup>8</sup> , deep tunnel pumping station and screening facilities located near the Southport treatment facility, and structures necessary to tie CSO 008, CSO 117 and CSO 118 flows into the Deep Rock Tunnel Connector	Provide a total effective <sup>11</sup> storage volume of 250 MG in the Fall Creek, White River, Pogues Run, Pleasant Run and DRTC tunnel system <sup>10</sup> with a minimum peak conveyance and dewatering capacity of 90 MGD CSO flow to Southport	Maximize delivery of flow from White River Tunnel to Southport AWT Plant. Optimize capture of CSO 008, CSO 117 and CSO 118	Bid Year – 2011 Achievement of Full Operation – 2017
17	Belmont AWT - Wet-Weather Treatment (New aeration tanks)	Provide secondary biological treatment of the Belmont PE Bypass	Provide in series peak biological treatment rate of 300 MGD	When incorporated with the rest of the Belmont improvements, facility complies with current NPDES permit	Bid Year – 2009 Achievement of Full Operation - 2012
18	Lower Pogues Run Improvements	Deep Storage Tunnel and consolidation sewers <sup>8</sup>	Provide a total effective <sup>11</sup> storage volume of 250 MG in the Fall Creek, White River, Pogues Run, Pleasant Run and DRTC tunnel system <sup>10</sup>	When incorporated with the rest of the Pogues Run and White River watersheds, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2011 Achievement of Full Operation – 2021

				· .	
	) Control	<b>Description</b> <sup>2</sup>	Design Criteria <sup>2</sup>	Performance	Critical
	easure <sup>1</sup>	Description	Design Criteria	Criteria	Milestones <sup>3</sup>
	Pogues Run -	Sewer separation that	Storm drains designed	Separation of	Bid Year – 2010
	Sewer	minimizes CSO 143	as per Indianapolis	sewers to	Achievement of
S	Separation at		Stormwater Standards.	minimize CSO	Full Operation -
F	Forest Manor		Sanitary sewer	143	2012
F	Park (CSO 143)		designed as per		
			Indianapolis Sanitary		
			Standards and Ten		
			State Standards		
-	White River	Central tunnel,	Provide a total	When	Bid Year – 2010
	Funnel (Central	consolidation sewers,	effective <sup>11</sup> storage	incorporated	Achievement of
	Funnel) and	sewer separation and dam modifications <sup>8</sup>	volume of 250 MG in	with the rest of	Full Operation –
- 1	Watershed	dam modifications	the Fall Creek, White	the White River	2021
	Projects		River, Pogues Run, Pleasant Run and	watershed, achieve 95	
			DRTC tunnel system <sup>10</sup>	percent capture	
		-	DICI C tullici system	and 4 overflow	
				events <sup>6</sup>	
I	Belmont AWT –	New wet-weather	Additional peak	When	Bid Year - 2010
-   v	Wet Weather	disinfection system and	disinfection treatment	incorporated	Achievement of
	Chlorination /	new discharge to White	rate of 150 MGD for a	with the rest of	Full Operation -
I	Dechlorination	River	total of 300 MGD peak	the Belmont	2012
	(Chlorine		disinfection treatment	improvements,	
	Disinfection		capacity consistent	facility complies	
1	Tank and Re-		with applicable	with current	
	establish		disinfection	NPDES permit	
1	Existing Outfall)		requirements of current NPDES		
			permit <sup>12</sup>		
1	Southport	Expansion of Secondary	When incorporated	When	Bid Year - 2012
	Advanced	Treatment System from	with the rest of the	incorporated	Achievement of
	Wastewater	150 MGD to 250 MGD	Southport	with the rest of	Full Operation -
	Treatment Plant		Improvements, provide	the Southport	2017
1	Improvements -		total peak secondary	improvements,	
	Secondary		and disinfection	facility complies	
	Treatment		treatment rate of 250	with current	
	System		MGD consistent with	NPDES permit	
[]	Expansion		applicable disinfection		
		•	requirements of		
			current NPDES		
			permit. Provide maximum pumping		

.

23     Southport Advanced Westewater Treatment Plant Improvements - Wet Weather Disinfection     New disinfection facility and new process/yard piping     When incorporated Southport Improvements, provide maximum punping readment sof Current NPDES permit. Provide maximum punping Treatment Plant mew process/yard piping     When incorporated advanced West weater     When incorporated is Southport and disinfection     Unternation with the rest of the Southport readment rate of 2.0 MOD consistent with applicable disinfection requirements of Current NPDES permit. Provide maximum punping rate of 345 MGD <sup>12</sup> When incorporated with the rest of the Southport Improvements, provide maximum punping rate of 345 MGD <sup>12</sup> Bid Year - 2012 Achievement of Full Operation - 2017       24     Southport Advanced Wastewater Treatment Plant Improvements - Primary Clarifier     Enhancement of primary treatment design, and disinfection treatment capacity of 250 MGD consistent with applicable disinfection requirements of current NPDES permit. Provide maximum punping rate of 345 MGD <sup>12</sup> When incorporated with the rest of the southport improvements, facility complies with current NPDES permit     Bid Year - 2012 Achievement of Full Operation - 2017       25     Belmont Advanced Wastewater Pump Station (WWPS) Treatment Plut Improvements - Rew     Rerouting of the existing Wet Weater Pump Station (WWPS) Treatment Plut Reparation     When incorporated with the rest of the Bellont Treatment for full Operation - 2012     Bid Year -2011 Achievement of Full Operation - 2012		CSO Control Measure <sup>1</sup>	Description <sup>2</sup>	Design Criteria <sup>2</sup>	Performance Criteria	Critical Milestones <sup>3</sup>
24Southport Improvements - Primary Clarifier ExpansionEnhancement of primary clarification facility, and new process/yard pipingSouthport Improvements, and disinfection requirements of current NPDES permit. Provide maximum pumping rate of 345 MGD 12When incorporated with current NPDES permitBid Year - 2012 Achievement of Full Operation - 201724Southport Advanced Wastewater Primary Clarifier ExpansionEnhancement of primary clarification facility, and new process/yard pipingEnhancement of primary explored by the incorporated improvements, facility complies with currentWhen incorporated with the rest of the southport limprovements, facility complies with currentBid Year - 2012 Achievement of Full Operation - 201725Belmont Advanced Wastewater Frammer Plant ExpansionRerouting of the existing wet Weather Pump Station (WWPS) in the exist of the support secondary maximum pumping rate of 345 MGD 12When incorporated with current when incorporated with current with current incorporated with terst of the support secondary and disinfection requirements of current NPDES permit Provide maximum pumping rate of 345 MGD 12Bid Year - 2011 Achievement of Full Operation - 201725Belmont Maystewater Pumping CapacityRerouting of the existing wet Weather Pump Station (WWPS) weather storage basin (WWSB No.1)When incorporated with current rate of 300 MGD Provide peak pumping read of 330 MGD 12Bid Year - 2011 Achievement of Full Operation - 2012	23	Southport		1 ~	When	Bid Year – 2012
24Southport Advanced Wastewater Treatment Plant Improvements Primary Clarifier ExpansionEnhancement of primary clarification facility, and new process/yard pipingWhen incorporated with the rest of the Southport Improvements, provide peak primary treatment capacity as required to support secondary and disinfection treatment capacity of 250 MGD consistent with applicable disinfection requirements of current NPDES permit. Provide maximum pumping rate of 345 MGD12When incorporated with the rest of the southport improvements, 		Wastewater Treatment Plant Improvements Wet Weather		Southport Improvements, provide total peak secondary and disinfection treatment rate of 250 MGD consistent with applicable disinfection requirements of current NPDES permit. Provide maximum pumping	with the rest of the Southport improvements, facility complies with current	Full Operation -
Advanced Wastewaterexisting Wet Weather Pump Station (WWPS)with the rest of the Belmontincorporated with the rest of the BelmontAchievement of Full Operation – 2012Treatment Plant Improvements - Raw Wastewater Pumping Capacityexisting Wet Weather Pump Station (WWPS)with the rest of the Belmontincorporated with the rest of the BelmontAchievement of Full Operation – 2012Wastewater Pumping Capacityweather storage basin (WWSB No.1)total peak primary and biological treatment rate of 300 MGD.improvements, facility complies with current NPDES permit2012		Advanced Wastewater Treatment Plant Improvements Primary Clarifier Expansion	clarification facility, and new process/yard piping	When incorporated with the rest of the Southport Improvements, provide peak primary treatment capacity as required to support secondary treatment design, and peak secondary and disinfection treatment capacity of 250 MGD consistent with applicable disinfection requirements of current NPDES permit. Provide maximum pumping rate of 345 MGD <sup>12</sup>	incorporated with the rest of the Southport improvements, facility complies with current NPDES permit	Achievement of Full Operation - 2017
	25	Advanced Wastewater Treatment Plant Improvements - Raw Wastewater Pumping Capacity	existing Wet Weather Pump Station (WWPS) to the existing wet weather storage basin	with the rest of the Belmont Improvements, provide total peak primary and biological treatment rate of 300 MGD. Provide peak pumping	incorporated with the rest of the Belmont improvements, facility complies with current	Achievement of Full Operation –
	ана (1997) 1997 — Полона 1997 — Полона (1997)					

C	SO Control Measure <sup>1</sup>	Description <sup>2</sup>	Design Criteria <sup>2</sup>	Performance Criteria	Critical Milestones <sup>3</sup>	
26	Southport Advanced Wastewater Treatment Plant Improvements Headworks	Expansion of headworks, screening, grit removal, and new process/yard piping	When incorporated with the rest of the Southport Improvements, provide total peak secondary and disinfection treatment rate of 250 MGD consistent with applicable disinfection requirements of current NPDES permit. Provide peak pumping rate of 345 MGD <sup>12</sup>	When incorporated with the rest of the Southport improvements, facility complies with current NPDES permit	Bid Year – 2012 Achievement of Full Operation - 2017	
279	Deleted	Deleted	Deleted	Deleted	Deleted	
289	Deleted	Deleted	Deleted	Deleted	Deleted	
29	Pleasant Run, Deep Tunnel and Overflow Collector Pipe	Deep tunnel, connection sewers, collection interceptor and sewer separation. Tunnel connects to area of White River and DRTC Tunnels and extends to the area of CSO 084 <sup>8</sup>	Provide a total effective <sup>11</sup> storage volume of 250 MG in the Fall Creek, White River, Pogues Run, Pleasant Run and DRTC tunnel system <sup>10</sup>	When incorporated with the rest of the Pleasant Run watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2010 Achievement of Full Operation – 2025	
30	Eagle Creek Overflow Collector Pipe (CSO Collector Pipe). Belmont West Cutoff via the Belmont North Relief Interceptor System	Collection interceptor system and relief interceptor to achieve Performance Criteria <sup>8</sup>	Provide instantaneous peak flowrate of 38 MGD in the Belmont North Relief Interceptor System. Provide instantaneous peak flowrate of 25 to 50 MGD at the downstream end of the Eagle Creek Overflow Collector Pipe.	When incorporated with the rest of the Eagle Creek and White River watersheds, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2013 Achievement of Full Operation - 2018	
31	Upper Pogues Run Improvements	Off-line storage facility, collection interceptor to achieve Performance Criteria <sup>8</sup> .	Provide instantaneous peak flowrate of 40 to 80 MGD. Provide storage volume of 1 to 3 MG	When incorporated with the rest of the Pogues Run watershed, achieve 95 percent capture and 4 overflow events <sup>6</sup>	Bid Year – 2017 Achievement of Full Operation – 2021	

	SO Control Measure <sup>1</sup>	Description <sup>2</sup>	Design Criteria <sup>2</sup>	Performance Criteria	Critical Milestones <sup>3</sup>
32	Belmont Advanced Wastewater Treatment (AWT) Plant Improvements	Rerouting of in-plant recycle flows from the headworks to primary treatment via the Plant Drain Pump Station (PDPS). Diversion of the primary effluent from Belmont AWT to Southport AWT via the Primary Effluent Pump Station (PEPS).	When incorporated with the rest of the Belmont AWT improvements, provide total peak primary and secondary treatment rate of 300 MGD. Provide peak headworks pumping rate of 330 MGD.	When incorporated with the rest of the Belmont improvements, facility complies with current NPDES permit	Bid Year – 2008 Achievement of Full Operation – 2009

<sup>1</sup>Upon full implementation, the CSO Control Measures listed in Table 7-5 are expected to result in at least the Performance Criteria of 95 percent capture and 4 CSO events on the White River, Pleasant Run, Pogues Run, and Eagle Creek and 97 percent capture and 2 CSO events on Fall Creek, as evaluated in accordance with footnote 6. Either a revision to Indiana's current water quality standards or some other legal mechanism is necessary to authorize overflows due to storms exceeding those levels of control. In Section 9 of the LTCP, the City of Indianapolis is requesting a revision to the applicable water quality criteria consistent with this level of control through the establishment of a CSO wet weather limited use subcategory supported by a Use Attainability Analysis ("UAA"). The design and construction of CSO Control Measures 1 through 14 ("Phase I" Projects) are not dependent upon the level of control ultimately determined, and therefore the City will implement CSO Control Measures 1 through 14 according to the terms and schedule set forth in this Table. IDEM and U.S. EPA acknowledge that the City is scheduled to start investing heavily in CSO Control Measures 15 through 32, which are level of control-dependent, in the years following approval of the City's LTCP. Accordingly, all parties intend that the UAA process be completed within five years of LTCP approval. If the UAA process is not completed within five years, IDEM and U.S. EPA agree that, under certain circumstances, the City can seek a modification of the implementation schedule.

<sup>2</sup>Footnote 2 deleted.

<sup>3</sup> The term "Bid Year" means "Completion of the Bidding Process."

<sup>4</sup> The CSO control measure is not expected to achieve 95 or 97 percent capture on its own and will work in conjunction with other CSO control measures at the specified CSO outfalls to achieve the performance criteria.

<sup>5</sup> Consistent Operation: Performs as designed on a regular basis. Failure to perform correctly is infrequent.

<sup>6</sup> CSO Control Measures will be designed in accordance with the Design Criteria set forth in Table 7-5, and they shall also achieve at least the Performance Criteria of 97 percent capture for the Fall Creek watershed and 95 percent capture for other CSO receiving waters, and 2 CSO events for the Fall Creek watershed and 4 CSO events for each of the other CSO receiving waters in a "typical year." "Typical year" performance, and achievement of Performance Criteria, shall be assessed in accordance with Section 8.4 (Post Construction Monitoring) using the average annual statistics generated by the collection system model for the representative five-year simulation period of 1996 to 2000 (or another five-year simulation period subsequently proposed by the city and approved by IDEM and U.S. EPA).

<sup>7</sup> Control Measure 28 deleted.

<sup>8</sup> The collection interceptor may be installed as multiple interceptors with the combined capacity as described in the Design Criteria.

<sup>9</sup> Control Measure 27 and 28 deleted.

<sup>10</sup> Control Measures 15, 16, 18, 20 and 29 have a combined Design Criteria of 250 MG of 'effective' (as defined below) storage in the Fall Creek, White River, Pogues Run, Pleasant Run and DRTC Tunnel System. This total effective available system storage of 250 MG includes adits and deaeration chambers, which are tunnel connections from drop shafts to the mainline tunnels.

<sup>11</sup> Effective' as identified for Control Measures 15, 16, 18, 20 and 29 is defined as the storage volume that will be designed and operated to ensure 250 MG of wet-weather flow may be reliably stored in the tunnel system provided Indianapolis has received sufficient precipitation to capture 250 MG of wet-weather flow in a single event or two or more sequential events.

<sup>12</sup> Control Measures 21, 22, 23, 24, 25 and 26 have flowrates as noted within the Design Criteria for each Control Measure. Control Measures 22, 23, 24 and 26 have a secondary treatment capacity of 250 MGD and a disinfection capacity of 250 MGD (consistent with applicable disinfection requirements of the City's current NPDES permit), which includes in-plant return flows.