### For assistance in accessing this document, contact R3\_UIC\_Mailbox@epa.gov



January 22, 2025

Mr. James C. Bennett Source Water & UIC Section Water Division U.S. EPA Region 3 Four Penn Center 1600 John F. Kennedy Blvd. Philadelphia, PA 19103

Mr. Bennett:

EnerVest is submitting this permit application to renew proposed Permit #VAS2D955BBUC Class II-D fluid disposal well in the Prater area of Buchanan County, Virginia. Attachment 1 details information included for updating the UIC permit renewal application.

Please contact me with any questions and/or further requested information (276) 730-5617.

Sincerely,

Jon Lawson

Sr. HSE Specialist

jlawson@enervest.net



### UNDERGROUND INJECTION CONTROL

## PERMIT RENEWAL APPLICATION

## FOR CLASS II-D PRODUCTION FLUID DISPOSAL WELL

# EXISTING WELL 900146 SWD EPA # VAS2D955BBUC

NORA/HAYSI FIELD BUCHANAN COUNTY, VIRGINIA

**JANUARY 2025** 



United States Environmental Protection Agency

For Official Use Only	
Date Received	
Permit Number	
VAS2D955BBUC	

<b>⊕EP</b>	A Per	ss II Well	Date Received							
()LI	(Collect	cted under the authority o Sections 1421, 1422, a	of the Safe Drink	ing Water Act.	Permit Nu VAS2D	umber 0955BBUC				
		Read Attached In	structions E	efore Startin	g					
I. Owner Name, Address	, Phone Number and	/or Email	II. Ope	ator Name, Addre	ess, Phone	Number and/or Ema	il			
EnerVest Operating, I 809 Happy Valley Dr Clintwood, VA 24228 276-926-1300 jlawson@enervest.net			809 Ha Clintw 276-92	EnerVest Operating, LLC 809 Happy Valley Dr Clintwood, VA 24228 276-926-1300 jlawson@enervest.net						
III. Commercial Facility	IV. Ownership	V. Permit Action Reques	sted		VI	. SIC Code(s)	VII. Indian Country			
Yes X No					Yes X No					
VIII. Type of Permit (For I	nultiple wells, use ad	dditional page(s) to provide	e the information	requested for ea	ch addition	nal well)				
X A. Individual B. Area    Number of Wells   Well Field and/or Project Names   NORA										
IX. Class and Type of W	ell (see reverse)									
A. Class II D	r code(s)) C. If type	e code is "X," explain.								
X. Well Status			XI. Well In	formation						
A. Operating  Date Injection Started	B. Conversion  Date Well Constr			API Number						
XII. Location of Well or,	for Multiple Wells, A	pproximate Center of Fie	ld or Project							
Surface Location  1/4 of  ft. from (N	Longitude 92 12 15 W									
		X	III. Attachments							
С	lass) on separate	s form, complete Atta e sheets. Submit comp s, maps or other figure	plete informat	ion, as require						
			(IV. Certification							
and that, based on my	y inquiry of those ind te. I am aware that t 40 CFR § 144.32)	re personally examined an dividuals immediately respectively respectively respectively enalesse Type or Print) Sign	ponsible for obt	aining the inform	ation, I bel	lieve that the informa	ation is true,			
Kevin Miller, VP	Tomciai Title (Frea	, ,,,,,	•	Date Signed 12/04/2024						

#### **INSTRUCTIONS FOR FORM 7520-6 (CLASS II WELLS)**

A permit application must be completed by all owners or operators of current or proposed Class I, II, and III wells, and some Class V injection wells subject to the requirement to obtain an Underground Injection Control (UIC) permit as described at 40 CFR 144.31 and others directed by a UIC official to apply for a UIC permit. Please note that the information needs vary by well class. These instructions are specific to Class III wells; other versions are available for other well classes. If the application covers multiple wells, use additional pages as necessary to provide all the requested information.

- **I. OWNER NAME, ADDRESS, PHONE AND/OR EMAIL:** Enter the name and street address, city/town, state, and ZIP code of the owner of the well, well field, or company. Also provide an email address (if available) and/or a phone number.
- **II. OPERATOR NAME, ADDRESS, PHONE AND/OR EMAIL:** Enter the name and street address, city/town, state, and ZIP code of the operator of well or well field; also provide an email address (if available) and/or a phone number. If the operator is the same as the owner, enter "same as owner."
- **III. COMMERCIAL FACILITY:** Check the appropriate box to indicate the type of facility. A commercial facility is a single or multiple well facility that is specifically engaged in the business of injecting waste fluids generated by third party producers that is originated off-site and transported to the facility by truck for a fee or compensation.
- **IV. OWNERSHIP:** Check the appropriate box to indicate whether the owner of the well/facility is a private, Federal, or State/Tribal/Municipal entity.
- V. TYPE OF PERMIT ACTION REQUESTED: Check "new permit" if the well has never been subject to a UIC permit (e.g., for a newly constructed or converted well). Check "permit renewal" for an application associated with extending an expiring UIC permit. Check "modification" for an application to modify an existing permit that is not expiring. Check "add well to area permit" if additional wells are to be covered under an existing UIC area permit. Check "other," if needed and describe the situation.
- VI. SIC CODES: List at least one and no more than four Standard Industrial Classification (SIC) Codes that best describe the nature of the business in order of priority. A list of SIC codes is available from the U.S. Department of Labor at <a href="https://www.osha.gov/pls/imis/sicsearch.html">https://www.osha.gov/pls/imis/sicsearch.html</a>.
- VII. INDIAN COUNTRY: Check yes if the well is located in Indian country. Indian country (as defined in 18 U.S.C. 1151) includes: all land within the limits of any Indian reservation under the jurisdiction of the U.S. government; all dependent Indian communities within the borders of the U.S.; and all Indian allotments, the Indian titles to which have not been extinguished.
- **VIII. TYPE OF PERMIT:** Check "Individual" or "Area" to indicate the type of permit requested. Individual permits cover a single injection well, while area permits may cover more than one injection well. Note that area permits are issued at the discretion of the Director and that wells covered by an area permit must: be at one contiguous site, be under the control of one entity, and may not inject hazardous waste. If an area permit is requested, enter the **number of wells** to be included in the permit. In the case of a project or field that crosses State lines, it may be possible to consider an area permit if EPA has jurisdiction in all affected States (each such case will be considered individually). Also provide the **name of the well field or project.**
- **IX. CLASS AND TYPE OF WELL:** Enter the class (as defined in 40 CFR 144.6) and type of injection well for which a permit is requested. Use the most pertinent code selected from the table below. When selecting type "X", please explain in the space provided.

#### **TABLE OF CLASS II WELL TYPES**

- A Annular Disposal Well.
- D Produced Fluid Disposal Well.
- H Hydrocarbon Storage Well (excluding natural gas).
- R Enhanced Recovery Well.
- X Other Class II Wells (not included in Type "A," "D," "H," or "R").
- **X. WELL STATUS:** Check **Box A, Operating** if the well currently operates as an injection well (e.g., if a permit renewal is requested or a permit is sought for an existing rule-authorized injection well). Check **Box B, Conversion** for an existing well not currently being utilized for injection that is proposed to be converted to an injection well. Check **Box C, Proposed** for an underground injection well not yet constructed or completed. Provide relevant dates if A or B are checked.
- XI. WELL INFORMATION: Enter the *API number* (the number assigned by the local jurisdiction (usually a State Oil and Gas Agency) using the American Petroleum Institute standard numbering system). Enter the *Permit or EPA ID number* assigned to the injection well by the EPA or the permitting authority. If you do not have a number (e.g., for a new well), this will be provided by EPA or the permitting authority, and you can leave the field blank. Also enter the *Full Name of the Well* or project.
- XII. LOCATION: For individual permit applications, in the fields provided, enter the location of the well using latitude and longitude and/or the Public Land Survey System. When using latitude and longitude, use decimal degrees to five or six places after the decimal, if possible; be sure to include a negative sign for the longitude of a well in the Western Hemisphere and a

negative sign for the latitude of a well in the Southern Hemisphere. When using the Public Land Survey System, fill in the complete township, range, and section to the nearest quarter-quarter section. A township is north or south of the baseline, and a range is east or west of the principal meridian (e.g., T12N, R34W). Also include the distance, in feet, from the nearest north or south line and nearest east or west line of the quarter-section. For area permit applications, provide the latitude and longitude of the approximate center of the area.

**XIII. ATTACHMENTS:** Specific instructions for completing the attachments are presented on pages 3 through 6. Place the permit or EPA ID number (or, if none has been assigned, other identifying information such as an API number or the project name) in the upper right hand corner of each page of the attachments.

**XIV. CERTIFICATION:** All permit applications must be signed by either: a responsible corporate officer for a corporation, by a general partner for a partnership, by the proprietor of a sole proprietorship, or by a principal executive or ranking elected official for a public agency, or a duly authorized representative of that person. Please note that this form must be signed by a responsible entity as described at 40 CFR 144.32, even if the attachments are prepared by contractors or service companies.

PAPERWORK REDUCTION ACT NOTICE: The public reporting and recordkeeping burden for this collection of information is estimated to average 61 hours per response for a Class II well permit application. Burden means the total time, effort, or financial resource expended by persons to generate, maintain, retain, or disclose or provide information to or for a Federal Agency. This includes the time needed to review instructions; develop, acquire, install, and utilize technology and systems for the purposes of collecting, validating, and verifying information, processing and maintaining information, and disclosing and providing information; adjust the existing ways to comply with any previously applicable instructions and requirements; train personnel to be able to respond to the collection of information; search data sources; complete and review the collection of information; and, transmit or otherwise disclose the information. An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB control number. Send comments on the Agency's need for this information, the accuracy of the provided burden estimates, and any suggested methods for minimizing respondent burden, including the use of automated collection techniques to Director, Collection Strategies Division, U.S. Environmental Protection Agency (2822), 1200 Pennsylvania Ave., NW, Washington, DC 20460. Include the OMB control number in any correspondence. Do not send the completed forms to this address.

#### Instructions for Completing Attachments to Form 7520-6 (Class II Wells)

The Underground Injection Control (UIC) program, as promulgated under the Safe Drinking Water Act (SDWA), is designed to prevent injection activity from allowing the movement of fluid containing any contaminant into underground sources of drinking water (USDWs), if the presence of that contaminant may cause a violation of any primary drinking water regulation or may otherwise adversely affect the health of persons as found at Title 40 of the Code of Federal Regulations (40 CFR) section 144.12. Any applicant for a permit under this program shall have the burden of showing that their proposed construction, operation, maintenance, conversion, plugging, abandonment, and injection activity, does not endanger USDWs.

The attachments below have been constructed to provide applicants with clear expectations as to what information EPA needs to make a determination that an applicant's proposed activities will not endanger USDWs.

#### **Pre-Application Coordination**

Coordination between the UIC program and the permit applicant prior to submittal of the permit application is an important step for efficient and effective permitting. Early discussions will ensure that the applicant is aware of all the permit application requirements, including state specific requirements found at 40 CFR part 147. These discussions may also help the applicant plan how to invest time and resources needed to develop a comprehensive and complete permit application.

Applicants are encouraged to contact their EPA regional UIC program for a pre-application coordination meeting.

Note: If the owner or operator of existing rule authorized Class II UIC well(s) is required by the EPA to apply for a permit (40 CFR § 144.25), consult with EPA staff during the pre-application coordination for additional requirements that may apply.

When completing each attachment, please be sure to specify the units reported, e.g., of depth, pressure, temperature, etc.

#### Attachment A. Map(s) and Area of Review

#### Part I. Well Location(s)

<u>For Individual Permits</u>: If the surface location provided in the accompanying 7520-6 form does not adequately describe the well location (i.e., due to deviation, directional, or horizontal drilling), please describe the well's orientation and provide the top- and bottom-hole coordinates, as appropriate. If any monitoring wells are proposed as part of this permit application, provide coordinates for all monitoring wells.

<u>For Area Permits (40 CFR § 144.33)</u>: Provide information similar to what is outlined above for individual permits for each well (existing or proposed) to be covered by this permit. In addition, provide a description of the proposed permitted area. At a minimum, this area should include all the proposed or existing wells known at the time of permit application submittal. For circular areas, this description should consist of a defined-radius from a singular point whose coordinates have been given. For polygonal areas, use a series of coordinates describing the vertices or corners of the area. Submit a Geographic Information System (GIS) file, if available.

#### Part II. Area of Review Size Determination (40 CFR § 146.6)

<u>For All Permits.</u> Give the method (fixed radius or equation) and, if appropriate, all calculations used to determine the size of the area of review (AOR). If you are uncertain as to which method to use, consult with your regional EPA office.

The AOR must be a minimum radius of one-fourth (1/4) mile from the well bore, including a well's lateral, or the proposed area permit boundary for area permits, unless the use of an equation is approved by the Director.

<u>In addition, for Class II enhanced oil recovery well(s)</u>. The AOR will be at a minimum the larger of the following: one-fourth (1/4) mile radius or the distance to the nearest active producer in the production formation.

#### Part III. Map(s) (40 CFR §§ 144.31 & 146.24)

Submit a topographic map (or other map if a topographic map is unavailable) extending one mile beyond the facility property boundary showing:

- project injection well(s), well pad(s) and/or project area,
- · applicable area of review,
- all outcrops of injection and confining formations,
- all surface water intake and discharge structures, and
- all hazardous waste treatment, storage, or disposal facilities.

Consult with your EPA regional office for the definition of the facility property boundary.

The information below does not apply to existing rule authorized Class II well(s).

Within the one-fourth (1/4) mile beyond the facility property boundary or the AOR, whichever is larger, the map will also show the:

• name and location of all production wells, injection wells, abandoned wells, dry holes, and all water wells, noting their types (public water system, domestic drinking water, stock, etc.),

- springs and surface bodies of water,
- · mines (surface and subsurface) and quarries, and
- other pertinent surface features, including residences, schools, hospitals, and roads.

Only information of public record and pertinent information known to the applicant is required to be included on this map. Multiple maps may be needed to display this information clearly. If a certain feature is not present in the area covered, please state so definitively (e.g., "There are no known outcrops of the confining formation in the mapped area.").

Part IV, below does not apply to existing rule authorized Class II well(s).

#### Part IV. Area of Review Wells and Corrective Action Plans (40 CFR §§ 144.55 & 146.24)

Submit a tabulation of data and wellbore diagrams reasonably available from public records or otherwise known to the applicant on all wells within the AOR included on the map, which penetrate the proposed confining zone(s). Such information will include:

- · well name, location and depth,
- well type,
- date well was drilled.
- well construction that includes casing and cement details, including demonstrated or calculated top of cement,
- · cement bond logs (if available), and
- record of well completion and plugging (if applicable).

For such wells which are improperly sealed, completed, or abandoned, also submit a plan consisting of such steps or modifications as are necessary to prevent movement of fluid into USDWs.

#### Part V. Landowners Information (40 CFR § 144.31 and part 147)

Identify and submit a list with the names and addresses of all owners of record of land within one-fourth (1/4) mile of the facility property boundary. This requirement may be waived by the Regional Administrator if the site is in a populous area and the Regional Administrator determines that the requirement would be impracticable.

Consult with your regional EPA office, as additional state landowner notification requirements may apply (40 CFR part 147).

#### Attachment B. Geological and Geophysical Information

#### Part I. Geological Data (40 CFR § 146.24)

Provide the following information:

- geological data on all formations from the surface to the base of the injection well, identifying all USDWs and confining and injection zone(s). This data includes the lithologic description, geological name, thickness, depth, and total dissolved solids (TDS) concentrations from these formations (if known),
- source of information for the geologic data and formation TDS,
- porosity and permeability of injection formation (if available),
- geological cross-sections (if available) proximate to the injection well that includes the confining and injection zones.
   The cross-sections should illustrate the regional geologic setting and show the thickness and lateral continuity of the confining zone(s) through the area of review,
- within the AOR, identify known or suspected faults and fracture systems. If identified, provide proximity to the
  injection zone and the effect the fault/fracture system may have on the injection activities, and
- a history of seismic activity in the area and proximity to crystalline (i.e., granitic) basement.

#### Part II. Proposed Formation Testing Program (40 CFR § 146.22)

Provide a formation testing program to obtain data on:

- fluid pressure,
- estimated fracture pressure, and
- physical and chemical characteristics of the injection zone.

#### Attachment C. Well Construction/Conversion Information

#### Part I. Well Schematic Diagram (40 CFR § 146.24)

Provide a detailed proposed well schematic diagram that includes:

- identification of USDWs and confining and injection zones,
- casing and cementing details, including demonstrated or calculated top of cement,
- tubing and packer (if applicable),
- · open hole or perforated intervals, and

surface trace (if horizontal or deviated well).

For wells that are drilled and to be converted to an injection well, also provide the current well schematic diagram.

#### Part II. Well Construction or Conversion Procedures (40 CFR §§ 144.52, 146.22, & 146.24)

Provide detailed description of well construction or conversion procedures, that includes:

- proposed logs and other tests conducted during the drilling and construction of new well(s),
- proposed stimulation plan(s), if planned, and
- · description of alarms and shut-down systems at the well (if applicable).

For wells that are drilled and to be converted to an injection well, also provide:

- well completion and cementing records, and
- previously run logs/tests.

#### Attachment D. Injection Operation and Monitoring Program (40 CFR §§ 146.23 & 146.24)

Submit the following information:

- flow diagram of fluid flow through the facility,
- contingency plan(s) to cope with well failure, so as to prevent migration of contaminating fluids into a USDW,
- drawing of the surface construction,
- locations of all monitoring devices (show on the map(s) referenced in section A.III. above), and
- description of sampling and monitoring devices to monitor the nature of the injected fluids, injection pressure, annulus pressure (if applicable), flowrate, and cumulative volume.

Hydrocarbon storage and enhanced recovery may be monitored on a field or project basis rather than on an individual well basis by manifold monitoring. If a manifold monitoring program is utilized, describe details of the monitoring program and how the program is comparable to individual well monitoring. Also, include on the map in section A.III.B, the distribution manifold applying injection fluid to all wells in the area, including location of all system monitoring locations.

Additionally, submit the following proposed operating data for each well in the individual or area permit:

- average and maximum daily rate and volume of fluids to be injected,
- · average and maximum injection pressure,
- source(s) of injection fluids (including field and formation names),
- · proposed annular fluid, and
- analysis of the chemical and physical characteristics of the injection fluid. At a minimum, this should include pH, specific gravity, TDS, and conductivity. Consult with the regional EPA office for additional guidance.

#### Attachment E. Plugging and Abandonment Plan (40 CFR §§ 144.31, 144.51 & 146.24)

Submit a plugging and abandonment (P&A) plan of the well on EPA Form 7520-19 along with a P&A diagram. The plan should include:

- type, and number of plugs to be used,
- placement of each plug including the elevation of top and bottom,
- · type, grade, and quantity of cement to be used, and
- method of placement of the plugs.

Provide one or more cost estimates from an independent firm in the business of plugging and abandoning wells to conduct the work proposed in the P&A plan for EPA to contract plugging of the well. This is to ensure that EPA has adequate funding to plug the well(s) if the operator is unable to plug the well(s).

Consult with the regional EPA office for additional guidance on developing the P&A plan and cost estimate calculations.

#### Attachment F. Financial Assurance (40 CFR § 144.52)

Submit evidence of financial resources, such as a surety bond or financial statement, necessary for a third party to close, plug, or abandon the well in the event an owner or operator is unable to do so. The monetary amount is based on the P&A plan cost estimate provided in Attachment E.

#### Attachment G. Site Security and Manifest Requirements (Commercial Wells Only)

Provide a proposed site security plan. This could include fencing around the perimeter of the facility. Consult with the regional EPA office for additional guidance on manifest requirements.

#### Attachment H. Aquifer Exemptions (40 CFR §§ 144.7 & 146.4)

If an aquifer exemption (AE) is requested, submit the information required at 40 CFR § 144.7 and to demonstrate that the criteria found at 40 CFR § 146.4 are met. Consult with your regional EPA office for additional guidance.

#### Attachment I. Existing EPA Permits (40 CFR § 144.31)

Submit a listing of all permits or construction approvals received or applied for under any of the following programs:

- Hazardous Waste Management program under RCRA,
- UIC program under SDWA,
- NPDES program under CWA,
- Prevention of Significant Deterioration (PSD) program under the Clean Air Act,
- Nonattainment program under the Clean Air Act,
- National Emission Standards for Hazardous Pollutants (NESHAPS) preconstruction approval under the Clean Air Act.
- Ocean dumping permits under the Marine Protection Research and Sanctuaries Act,
- Dredge and fill permits under section 404 of CWA, and
- Other relevant environmental permits, including State permits.

#### Attachment J. Description of Business (40 CFR § 144.31)

Provide a brief description of the nature of the business.

#### Attachment K. Optional Additional Project Information (40 CFR § 144.4)

The following is a list of Federal laws that may apply prior to the issuance of permits. When any of these laws are applicable, EPA must ensure that they are followed. The optional additional information requested below will assist EPA in its analyses to satisfy these laws.

The Wild and Scenic Rivers Act, 16 U.S.C. 1273 et seg.

Identify any national wild and scenic river that may be impacted by the activities associated with the proposed project.

The National Historic Preservation Act of 1966, 16 U.S.C. 470 et seq.

Identify properties listed or eligible for listing in the National Register of Historic Places that may be affected by the activities associated with the proposed project. If previous historic and cultural resource survey(s) have been conducted, provide the results of the survey(s).

The Endangered Species Act, 16 U.S.C. 1531 et seg.

Identify any endangered or threatened species that may be affected by the activities associated with the proposed project. If a previous endangered or threatened species survey has been conducted, provide the results of the survey.

The Coastal Zone Management Act, 16 U.S.C. 1451 et seq.

Identify any coastal zones that may be affected by the activities associated with the proposed project.

ATTACHMENT

# A

#### 1.0 Introduction

The fixed radius of  $\frac{1}{4}$ -mile from proposed UIC Well 900146 was used for the area of review. All information presented and mapping provided are based upon the  $\frac{1}{4}$ -mile radius using Well 900146 as the center.

On some selective mapping, a radius of one mile, using proposed UIC well 900146 as the center, will be the area of review as required by this permit application.

# Α

#### 1.0 AREA OF REVIEW MAP

ENERVEST used ¼-mile as the Area of Review for proposed UIC well 900146. Drawing 1 is a topographic map that identifies the area within a one mile and ¼-mile radius of proposed UIC well 900146. This drawing provides the following information:

- □ Location of proposed UIC well 900146 This well is located on an existing CBM well site. The proposed injection zone is the Weir formation at a projected depth of 4,400'. The existing CBM well, Haysi 26, was drilled to a total depth ("TD") of 2,330' into the Pocahontas Formation, which is approximately 2,000' above the proposed injection zone.
- □ **Existing Well Information** All wells within one mile are identified by operator's well number, state file number and well type for all known producing, abandoned, dry holes, and injection. This information was gathered from well and map records on file with the Virginia Division of Gas and Oil and from Range Pine Mountains' company files.
- □ Surface and Subsurface Features The map identifies all surface bodies of water, springs, underground sources of drinking water ("USDW"), mines (surface and deep), quarries, roads, and other pertinent surface and subsurface features. Structures were identified using aerial photography.
- ☐ **Geologic Features** The map also identifies the inactive Little Pawpaw fault, the only fault within one mile of proposed UIC well 900146.

Environmental Data Resources, Inc. conducted a state and federal records review within a one mile radius. There were no intake and discharge structures or hazardous waste facilities identified (attached as Appendix B).

#### 2.0 PROPOSED UIC WELL 900146

Proposed UIC Class IID Well 900146 will be located in the Prater District of Buchanan County, Virginia and is approximately 4,350' to the south of existing UIC Permit

#### **ATTACHMENT**



Number VAS2D950BBUC (Class IID Injection Well), which is also permitted to inject into the Weir Formation and is owned and operated by ENERVEST OPERATING.

The 900146 is projected to be drilled to an approximate depth of 4,650', with the target injection zone (Weir Formation) being approximately 4,400' deep. The geologic prognosis is included in Attachment G.

#### 3.0 SURFACE OWNERS

The surface owners within the ¼-mile radius of proposed UIC well 900146 are listed below. Addresses and tax map identification information are listed for each owner. A certified plat is also attached.

#### **One Quarter Mile Radius Surface Ownership**

#### Proposed UIC well 900146 Location

Owner Name and Address	Tax Map ID

CF Highlands, LLC
 The Nature Conservancy
 19045 Stone Mountain Road
 Abingdon, VA 24210

2HH-272-003

#### 1/4-Mile Surface Owners

#### **Owner Name and Address**

- CF Highlands, LLC –
   The Nature Conservancy
   19045 Stone Mountain Road
   Abingdon, VA 24210
- Samuel J. Breeding Jr.
   4322 Louita Avenue

Kingsport, TN 37660

- Edgar Mae O'Quinn
   1052 Sawbriar Road
   Vansant, VA 24656
- Kimberly Nicole O'Quinn
   1442 O'Quinn Hollow Road
   Vansant, VA 24656





#### Tax Map ID

2HH-271-027

2HH-271-032 2HH-271-034

2HH-271-033

2HH-271-034A

2HH-271-027A

2HH-272-012

# 1/4-Mile Surface Owners (continued)

#### **Owner Name and Address**

 Berenice O'Quinn and Alice Jane O'Quinn 1423 O'Quinn Hollow Road Vansant, VA 24656

7. Jimmy Jerry O'Quinn 1404 O'Quinn Hollow Road PO Box 461 Vansant, VA 24656

Jimmy Adam O'Quinn
 1404 O'Quinn Hollow Road
 Vansant, VA 24656

Natasha Lyn O'Quinn
 1404 O'Quinn Hollow Road
 Vansant, VA 24656

10. Jeffery Lyn Yates andDiana Kay Yates2169 Cranesnest RoadVansant, VA 24656





- 11. Michael Yates andHeather Yates2169 Cranesnest RoadVansant, VA 24656
- 12. Lenda Owens andSammie Ray OwensRt. 1 Box 465Vansant, VA 24656
- 13. Dempsey Stanley andCathy Sue Stanley1280 Cranesnest RoadVansant, VA 24656

¼ -Mile Surface Owners (continued)

**ATTACHMENT** 

#### **Owner Name and Address**

- 14. Roy Dee Stanley and Brenda Joyce Stanley Rt. 1 Box 442 Vansant, VA 24656
- 15. Roger Lee Stanley andSarah Mabeline Stanley3118 Belchers Fork RoadGrundy, VA 24614
- 16. Winford Stanley andJudy Ilene Stanley5306 Helen Henderson HighwayHonaker, VA 24260
- 17. Jerry L. Coleman andBarbara Ann Coleman2613 Cranesnest RoadVansant, VA 24656
- 18. Tollie Fleming2056 Rose RidgeClintwood, VA 24228
- 19. Kyle Fleming2056 Rose RidgeClintwood, VA 24288
- 20. Melissa Fleming Deel2056 Rose RidgeClintwood, VA 24228

**ATTACHMENT** 

### 4.0 SURROUNDING NATURAL GAS WELLS

Within a one mile radius of proposed UIC well 900146, a total of 65 natural gas wells exist and 1 UIC wells existing based on Virginia Division of Gas and Oil and EnerVest's records as of November 2024. The existing wells consist of:

- □ **Vertical Natural Gas Wells** There are 15 vertical wells within one mile that penetrate the Weir formation, with only one falling within the ¼-mile area of review. Drilling and completion reports are attached as Appendix C.
- □ Coalbed Methane Wells There are 50 drilled CBM wells within one mile. Of those, two fall within ¼-mile. Information on these wells, such as TD and formation at TD, is presented as Appendix C. The intended injection zone in the proposed well is the Weir formation. The deepest CBM well within the ¼-mile radius is 2,610′, which provides for a minimum separation of approximately 1,700 feet from the top of the Weir to the bottom of the deepest CBM well within the area of review. Many low permeability formations such as tight sands, shales and limestones form the layers separating the coals and the injection zone. These include the Mauch Chunk Formation (Ravencliff sand and Maxton sands) and the Greenbrier Limestone (Big Lime). More detailed information on these formations is included in Attachment G.
- □ Horizontal Wells There are no existing horizontal wells within one mile of the proposed UIC well. Five permitted horizontal wells have been identified within one mile; none fall within ¼-mile. The target formation for these wells is the Huron, a Devonian aged shale part of the Ohio Shale Formation, which is approximately 1,500' below the Weir. One horizontal lateral leg is planned to pass within 750' of the proposed well location, but will be over 1,500' below the injection zone. The numerous tight gas sands and shales lying between the formations will act as a barrier for any fluid migration. These formations include the lower section of the Price Formation, the Sunbury shale, the Berea sand, and the upper shales and siltstones of the Ohio Shale.
- □ **Existing UIC Disposal Wells** There is one UIC Class II-D injection well within one mile (Permit #VAS2D950BBUC) and is located 4,350' to the north of

Α

proposed UIC well 900146. The injection formation for this well is also the Weir and it is owned and operated by ENERVEST.

Appendix C is a listing of all the wells, their total depths and the geologic formation at total depth. Additionally, all wells penetrating the Weir formation have been noted and the drilling and completion reports have been attached. These reports were obtained from the Virginia Division of Gas and Oil.

#### 5.0 WATER SOURCES

A survey of the area within a one mile radius of proposed UIC well 900146 was conducted to identify water wells, springs, and other drinking water sources. This survey was performed by Environmental Monitoring, Inc. and included a compilation of groundwater monitoring results conducted as part of Virginia Division of Gas and Oil permitting requirements for existing natural gas and coal bed methane wells. The results of the survey indicated there are no water wells within ¼-mile of the proposed well. The survey identified 19 water wells and six springs between ¼-mile and one mile of proposed UIC well 900146. All water wells and springs are shown on the attached Drawing-1. The results are outlined in Attachment E.

#### 6.0 MINING ACTIVITIES

Data obtained from the Virginia Department of Mines, Minerals and Energy indicate there are no active deep or surface mining operations within one mile of the proposed injection well. There is an inactive surface mine within ¼-mile, and one additional inactive surface mine within the one mile radius of the proposed well. There are three inactive deep mines within one mile of the proposed site. These deep mines targeted the Hagy and Clintwood seams located several thousand feet above the intended injection zone.

Associated with these inactive mines, are several surface and ground water monitoring points and National Pollutant Discharge Elimination System ("NPDES") points that have been identified. Figure B-1 identifies these points, but no data was obtained given the current inactive status of the mines.

**ATTACHMENT** 




Figure B-1. Mining Activity

#### 7.0 REGIONAL STRUCTURE AND FAULTS

The proposed UIC well will be properly separated from all USDW's by thousands of feet of confining strata and there are no active faults in the region.

The proposed UIC wellsite falls within the Appalachian Plateau geologic province, dominated by relatively flat-lying strata typically dipping one to two degrees. (Nolde, et.al.,1984). This region consists of an extensive, thick sedimentary sequence with numerous confining strata between all USDW's and the proposed injection zone. The proposed injection zone is the Weir formation, which has confining strata above and below of sufficient thickness and low enough permeability to confine the injection

CHMENT A

interval and isolate injected fluids to that zone. The Weir is thousands of feet below any known underground source of drinking water, thereby allowing adequate separation from potable water zones.

There are no faults identified within the Area of Review. The region is considered geologically stable with no active faults. The currently inactive faults in this region originated during the Acadian and Alleghanian Orogenies approximately 375 million to 260 million years ago. The Little Pawpaw fault, a tear fault associated with the Russell Fork Fault, is a high-angle, right-lateral strike-slip fault located within one mile of the proposed disposal well. Figures B-2 and B-3 identify these inactive faults. Maps depicting all recorded seismic activity (see Attachment G) show there is no activity associated with these faults. A cross-section is attached as Figure G-9. The cross-section highlights the Weir formation in four wells and transects the Little Pawpaw fault. This cross-section demonstrates there is little variability and no measurable offset resulting from the fault.




Figure B-2. Regional Faults adapted from Grimm, et.al., 2012





Figure B-3. Faults within one mile of proposed well

#### **REFERENCES**

Grimm, Ryan P., et al, 2012, Seal evaluation and confinement screening criteria for beneficial carbon dioxide storage with enhanced coal bed methane recovery in the Pocahontas Basin, Virginia, *International Journal of Coal Geology*, V. 90-91, p. 110-125.

Nolde, Jack, et.al., 1984, Geology of the Prater and Vansant Quadrangles, Virginia, Virginia Division of Mineral Resources Publication 52.



#### Wells within 1/4 mile of Proposed 900146 SWD

STATE FILE	WELL TYPE	STATUS	API	ALT NAME	OPERATOR	LATITUDE	LONGITUDE	SPUD DATE	COMP DATE	TD
BU-3236	CBM	Drilled	450270323600	HAYSI 26	EnerVest Operating LLC	37.193837	-82.204044	11/20/2006	1/4/2007	2400
BU-3244	CBM	Drilled	450270324400	HAYSI 24	EnerVest Operating LLC	37.196935	-82.206725	12/28/2006	2/8/2007	2460
BU-4949	GAS	Drilled	450270494900	V-900109	EnerVest Operating LLC	37.195917	-82.205287	8/31/2012	9/17/2012	5162

BB-2799 CBM Drilled 480270736900 HAYSI 2 Enewhyst Operating LLC 31,197045 92,217485 71,152005 37312000 2480 BB-2570 CBM Drilled 48027035000 HAYSI 1 Enewhyst Operating LLC 31,19856 52,212602 71,172005 33022000 2480 BB-2570 CBM Drilled 4802703500400 HAYSI 4 Enewhyst Operating LLC 37,198056 52,212602 71,172005 3702000 2480 BB-2570 CBM Drilled 4802703500400 HAYSI 4 Enewhyst Operating LLC 37,200200 42,208402 47,70006 55,62006 2480 BB-2570 CBM Drilled 4802703500400 HAYSI 4 Enewhyst Operating LLC 37,200200 42,208402 47,70006 55,62006 2480 BB-2570 CBM Drilled 4802703500400 HAYSI 4 Enewhyst Operating LLC 37,200200 42,208402 47,70006 55,62006 2480 BB-2570 CBM Drilled 4802703500400 HAYSI 4 Enewhyst Operating LLC 37,200200 42,208402 51,02006 51,02006 2480 BB-2570 CBM Drilled 4802703500900 HAYSI 6 Enewhyst Operating LLC 37,200200 82,207006 51,02006 52,000 BB-2570 CBM Drilled 4802703500900 HAYSI 6 Enewhyst Operating LLC 37,200200 82,207006 51,02006 52,000 BB-2570 CBM Drilled 480270350000 HAYSI 6 Enewhyst Operating LLC 37,207133 82,189731 11,147000 11,167000 44,000 BB-2570 CBM Drilled 480270351000 HAYSI 6 Enewhyst Operating LLC 37,207133 82,189731 11,147000 11,167000 44,000 BB-2570 CBM Drilled 480270351000 HAYSI 12 Enewhyst Operating LLC 37,209726 82,207738 11,147000 11,167000 44,000 BB-2570 CBM Drilled 480270351000 HAYSI 25 Enewhyst Operating LLC 37,189040 82,2010 11,167000 44,000 CBM Drilled 480270351000 HAYSI 25 Enewhyst Operating LLC 37,189040 82,224602 11,147000 2460 BB-2570 CBM Drilled 480270351000 HAYSI 25 Enewhyst Operating LLC 37,189040 82,224602 11,147000 2460 BB-2570 CBM Drilled 480270351000 HAYSI 25 Enewhyst Operating LLC 37,189040 82,224602 12,147000 2460 BB-2570 CBM Drilled 480270351000 HAYSI 25 Enewhyst Operating LLC 37,189040 82,224602 12,147000 24,147000		1-mile ofPro	•	API	ALT NAME	OPERATOR	LATITUDE	LONGITUDE	SPUD DATE	COMP DATE	TD
Bul-2790   CBM											
BU-2970   CBM						1 0					
Bit   Start   CBM					1						
Bit   396    CBM					1	1 0					
BB-3666 CBM Drilled 450270305600 HAYS1 Den/vest Operating LLC 37.21090 82.202338 51/2006 82.00 BB-3666 CBM Drilled 450270305600 HAYS1 To Enervied Operating LLC 37.210374 82.202107 51/2006 72.2006 82.00 BB-3666 CBM Drilled 450270305600 HAYS1 Enervied Operating LLC 37.206252 82.207366 42/260206 200 BB-3606 CBM Drilled 450270305600 HAYS1 Enervied Operating LLC 37.206252 82.207366 42/26006 82.00 BB-3606 CBM Drilled 450270305000 HAYS1 Enervied Operating LLC 37.206252 82.207366 42/26006 82.00 BB-3606 CBM Drilled 450270305000 HAYS1 Enervied Operating LLC 37.206359 82.00 BB-3606 CBM Drilled 450270315600 HAYS1 Enervied Operating LLC 37.008597 82.109531 11/14/2006 12/12/006 82.00 BB-3166 CBM Drilled 450270315600 HAYS1 Enervied Operating LLC 37.008643 82.210317 11/14/2006 12/12/006 82.00 BB-3166 CBM Drilled 450270315600 HAYS1 Enervied Operating LLC 37.008643 82.211876 11/14/2006 12/12/006 12/12/006 BB-3166 CBM Drilled 450270315600 HAYS1 Enervied Operating LLC 37.008643 82.211876 11/14/2006 12/12/007 24.00 BB-3239 CBM Drilled 450270331500 HAYS1 Enervied Operating LLC 37.008643 82.211876 11/14/2007 22/12/007 24.00 BB-3310 CBM Drilled 450270331500 HAYS1 Enervied Operating LLC 37.008643 82.211876 11/14/2007 22/12/007 24.00 BB-3310 CBM Drilled 450270331500 HAYS1 Enervied Operating LLC 37.00860 82.211876 11/14/2007 22/12/007 24.00 BB-3310 CBM Drilled 4502703357500 HAYS1 Enervied Operating LLC 37.108006 82.212477 37/10/2007 24.00 BB-3350 CBM Drilled 4502703357500 HAYS1 Enervied Operating LLC 37.108606 82.212477 37/10/2007 24.00 BB-3350 CBM Drilled 450270335500 HAYS1 Enervied Operating LLC 37.108606 82.212477 37/10/2007 24.00 BB-3350 CBM Drilled 450270335500 HAYS1 Enervied Operating LLC 37.108606 82.212477 37/10/2007 24.00 BB-3350 CBM Drilled 450270335500 HAYS1 Enervied Operating LLC 37.108606 82.212477 37/10/2007 24.00 BB-3350 CBM Drilled 450270345500 HAYS1 Enervied Operating LLC 37.108606 82.212477 37/10/2007 24.00 BB-3350 CBM Drilled 450270345500 HAYS1 Enervied Operating LLC 37.108606 82.212477 37/10/2007 24.00 BB-3350 CBM Dri											
Bill-3066   CBM					1						
BU-396   CBM											
BU-9080   CBM					1						
Bu-3999   CBM					1						
BU-3142	BU-3086	CBM	Drilled	450270308600	HAYSI 5	EnerVest Operating LLC		-82.202107	5/18/2006	7/21/2006	2460
Bu-3356   CBM	BU-3090	CBM	Drilled	450270309000	HAYSI 6	EnerVest Operating LLC	37.207153	-82.198731	11/1/2006		2310
BB-3365 CBM Drilled 450270335900 HAYSI 5 EnerVest Operating LLC 37.20643 82.217367 127267000 1/18/2007 2260 BB-3297 CBM Drilled 450270323700 HAYSI 5 EnerVest Operating LLC 37.206034 82.21737 1/19/2007 2272007 2840 BB-3292 CBM Drilled 45027032900 HAYSI 6 EnerVest Operating LLC 37.206034 82.217376 1/19/2007 2272007 2840 BB-3292 CBM Drilled 45027033900 HAYSI 8 EnerVest Operating LLC 37.206034 82.217376 1/19/2007 2272007 2840 BB-3293 CBM Drilled 450270335000 HAYSI 8 EnerVest Operating LLC 37.206034 82.211376 1/19/2007 1272007 2870 BB-3351 CBM Drilled 450270335000 HAYSI 9 EnerVest Operating LLC 37.201657 82.19543 1/19/2007 1272007 2870 BB-3350 CBM Drilled 450270335000 HAYSI 9 EnerVest Operating LLC 37.201635 82.215477 3/72007 3/23/2007 2870 BB-3355 CBM Drilled 450270345500 HAYSI 9 EnerVest Operating LLC 37.196096 82.218258 5/24/2007 6/14/2007 2280 BB-3455 CBM Drilled 450270345500 HAYSI 25 EnerVest Operating LLC 37.196096 82.218258 5/24/2007 6/14/2007 2280 BB-3456 CBM Drilled 450270345500 HAYSI 25 EnerVest Operating LLC 37.196096 82.218258 5/18/2007 6/14/2007 2280 BB-3456 CBM Drilled 450270345500 HAYSI 25 EnerVest Operating LLC 37.196096 82.218258 5/18/2007 6/14/2007 2800 BB-3456 CBM Drilled 450270345500 HAYSI 25 EnerVest Operating LLC 37.196094 82.20234 9/20/2007 10/10/2007 2400 BB-3456 CBM Drilled 450270355300 HAYSI 25 EnerVest Operating LLC 37.196094 82.20234 9/20/2007 10/10/2007 2400 BB-3456 CBM Drilled 450270355900 HAYSI 35 EnerVest Operating LLC 37.196094 82.19139 10/24/2007 11/13/2007 2400 BB-3456 CBM Drilled 450270355900 HAYSI 35 EnerVest Operating LLC 37.196094 82.19139 10/24/2007 11/13/2007 2400 BB-3456 CBM Drilled 450270356900 HAYSI 35 EnerVest Operating LLC 37.196094 82.19139 10/24/2007 11/13/2007 2400 BB-3456 CBM Drilled 450270356900 HAYSI 35 EnerVest Operating LLC 37.196094 82.19139 10/24/2007 11/13/2007 2400 BB-3456 CBM Drilled 450270366000 HAYSI 35 EnerVest Operating LLC 37.196094 82.19609 11/24/2007 12/24/2007 2400 BB-3456 CBM Drilled 450270366000 HAYSI 35 EnerVest Operating LLC 37.196394 82.19696 12	BU-3142	CBM	Drilled	450270314200	HAYSI 11	EnerVest Operating LLC	37.198897	-82.196351	11/14/2006	12/1/2006	2460
Bu-3237   CBM   Drilled   450270323700   HAYS1 5   EnerVest Operating LLC   37.203729   82.211783   12/12/2005   7/13/2007   2310	BU-3158	CBM	Drilled	450270315800	HAYSI 12	EnerVest Operating LLC	37.199143	-82.201301	11/6/2006	4/4/2007	2490
Bu-3391   CBM   Drilled   450270339200   HAYS121   EnerVest Operating LC   37.19006   48.2.21437   1/16/2007   2/2/2007   2/460	BU-3165	CBM	Drilled	450270316500	HAYSI 17	EnerVest Operating LLC	37.206843	-82.219167	12/29/2006	1/18/2007	2460
Bu-3292   CBM   Drilled   45027033100   HAYS1 18   EnerVest Operating LLC   37.199006   -82.224942   12/1/2006   21.6/2007   22.60	BU-3237	CBM	Drilled	450270323700	HAYSI 15	EnerVest Operating LLC	37.203729	-82.217783	12/12/2006	7/13/2007	2610
BU-3311 CBM Drilled 45027033100 HAYSI Enervest Operating LLC 37.201567 82.19543 1/9/2007 1/27/2007 2370 BU-3350 CBM Drilled 450270337500 HAYSI Penervest Operating LLC 37.201635 82.215477 3/70207 3/23/2007 2438 BU-3455 CBM Drilled 450270345500 HAYSI Penervest Operating LLC 37.18606 82.218258 5/48/2007 3/30/2007 2280 BU-3455 CBM Drilled 450270345800 HAYSI Penervest Operating LLC 37.18606 82.218258 5/48/2007 6/16/2007 2280 BU-3456 CBM Drilled 450270345800 HAYSI Penervest Operating LLC 37.18606 82.218258 5/48/2007 6/16/2007 2280 BU-3456 CBM Drilled 450270345800 HAYSI Penervest Operating LLC 37.18606 82.218258 5/48/2007 6/16/2007 2280 BU-3458 CBM Drilled 450270345800 HAYSI Penervest Operating LLC 37.189402 82.218958 5/18/2007 6/16/2007 2310 BU-3458 CBM Drilled 450270355800 HAYSI Penervest Operating LLC 37.189404 82.202234 9/02/2007 10/16/2007 2460 BU-3557 CBM Drilled 450270355800 HAYSI Penervest Operating LLC 37.189416 82.189389 9/26/2007 10/16/2007 2460 BU-3557 CBM Drilled 450270358900 HAYSI Penervest Operating LLC 37.189416 82.189389 9/26/2007 10/16/2007 2460 BU-3557 CBM Drilled 450270358080 HAYSI Penervest Operating LLC 37.189404 82.202234 9/26/2007 11/6/2007 2460 BU-3557 CBM Drilled 450270368080 HAYSI Penervest Operating LLC 37.189408 82.191367 10/12/2007 11/6/2007 2450 BU-3758 CBM Drilled 450270375200 HAYSI Penervest Operating LLC 37.189508 82.191367 10/12/2007 10/2/2007 2550 BU-3725 CBM Drilled 450270372500 HAYSI Penervest Operating LLC 37.189508 82.1933 10/2/2007 10/2/2007 2550 BU-3725 CBM Drilled 450270372500 HAYSI Penervest Operating LLC 37.189508 82.1933 10/2/2007 10/2/2007 2550 BU-3725 CBM Drilled 450270372500 HAYSI Penervest Operating LLC 37.189508 82.19350 12/2/2007 10/2/2007 2550 BU-3725 CBM Drilled 450270405800 HAYSI Penervest Operating LLC 37.189508 82.19350 12/2/2007 10/2/2007 2550 BU-3725 CBM Drilled 450270405800 HAYSI Penervest Operating LLC 37.189508 82.19350 12/2/2007 10/2/2007 2550 BU-3725 CBM Drilled 450270405800 HAYSI Penervest Operating LLC 37.189508 82.218957 12/2/2007 12/2/2008 2550 BU-372	BU-3291	CBM	Drilled	450270329100	HAYSI 23	EnerVest Operating LLC	37.206034	-82.211876	1/16/2007	2/2/2007	2340
BU-3350 CBM Drilled 450270335900 HAYSI 22 EnerVest Operating LLC 37.201635 82.215477 3/7/2007 3/23/2007 2280 BU-3456 CBM Drilled 450270345500 HAYSI 59 EnerVest Operating LLC 37.394912 82.223383 3/7/2007 616/2/2007 2280 BU-3456 CBM Drilled 450270345600 HAYSI 20 EnerVest Operating LLC 37.39402 82.219285 5/24/2007 616/2/2007 2310 BU-3456 CBM Drilled 450270345800 HAYSI 20 EnerVest Operating LLC 37.39402 82.219285 5/24/2007 6/14/2007 2310 BU-3553 CBM Drilled 450270355300 HAYSI 27 EnerVest Operating LLC 37.39402 82.219395 5/18/2007 6/14/2007 2310 BU-3556 CBM Drilled 450270355300 HAYSI 27 EnerVest Operating LLC 37.39404 82.219395 5/18/2007 10/16/2007 2400 BU-3556 CBM Drilled 450270355900 HAYSI 27 EnerVest Operating LLC 37.39416 82.19389 9/26/2007 10/16/2007 2400 BU-3556 CBM Drilled 450270359700 HAYSI 27 EnerVest Operating LLC 37.39416 82.19389 9/26/2007 10/16/2007 2400 BU-3556 CBM Drilled 450270359900 HAYSI 27 EnerVest Operating LLC 37.39416 82.19389 10/24/2007 11/13/2007 2400 BU-3556 CBM Drilled 450270359900 HAYSI 28 EnerVest Operating LLC 37.39438 82.19157 10/11/2007 11/13/2007 2400 BU-3556 CBM Drilled 450270359900 HAYSI 28 EnerVest Operating LLC 37.39438 82.19157 10/11/2007 11/13/2007 2400 BU-3556 CBM Drilled 450270369800 HAYSI 28 EnerVest Operating LLC 37.39438 82.19157 10/11/2007 11/13/2007 2400 BU-3656 CBM Drilled 450270368500 HAYSI 28 EnerVest Operating LLC 37.39504 82.19275 10/11/2007 11/13/2007 2400 BU-3656 CBM Drilled 450270378500 HAYSI 28 EnerVest Operating LLC 37.39504 82.19275 10/11/2007 11/13/2007 2400 BU-3656 CBM Drilled 45027038650 HAYSI 28 EnerVest Operating LLC 37.39504 82.19380 10/11/2007 11/13/2007 2400 BU-3656 CBM Drilled 45027038650 HAYSI 28 EnerVest Operating LLC 37.38569 82.19380 10/11/2008 24056 BU-3656 CBM Drilled 450270405600 HAYSI 31 EnerVest Operating LLC 37.38569 82.29568 9/11/2008 24056 BU-3656 CBM Drilled 45027046500 HAYSI 48 EnerVest Operating LLC 37.38569 82.29568 9/11/2008 11/11/2008 11/11/2008 11/11/2008 11/11/2008 11/11/2008 11/11/2008 11/11/2008 11/11/2008 11/11/2008 11/11/2008 11	BU-3292	CBM	Drilled	450270329200	HAYSI 18	EnerVest Operating LLC	37.199006	-82.224942	12/1/2006	2/16/2007	2460
BU-3375   CBM   Drilled   450270337500   HAYSI 19   EnerVest Operating LLC   37.184912   82.22383   3/16/2007   3/30/2007   2280   BU-3455   CBM   Drilled   450270345600   HAYSI 20   EnerVest Operating LLC   37.184916   8-2.18288   5/18/2007   6/14/2007   2310   BU-3458   CBM   Drilled   450270345600   HAYSI 20   EnerVest Operating LLC   37.184978   82.214547   5/9/2007   6/12/2007   2310   BU-3458   CBM   Drilled   450270345800   HAYSI 21   EnerVest Operating LLC   37.183759   82.214547   5/9/2007   6/12/2007   2310   BU-3458   CBM   Drilled   450270355600   HAYSI 27   EnerVest Operating LLC   37.183759   82.214547   5/9/2007   6/12/2007   2460   BU-3556   CBM   Drilled   450270355600   HAYSI 27   EnerVest Operating LLC   37.183744   82.202234   9/2/2007   10/16/2007   2460   BU-3597   CBM   Drilled   450270359800   HAYSI 27   EnerVest Operating LLC   37.203425   82.191359   10/2/2007   10/16/2007   2460   BU-3598   CBM   Drilled   450270356800   HAYSI 27   EnerVest Operating LLC   37.203425   82.191359   10/2/2007   11/3/2007   2460   BU-3615   CBM   Drilled   450270366800   HAYSI 28   EnerVest Operating LLC   37.195048   82.19135   10/18/2007   11/6/2007   2460   BU-3615   CBM   Drilled   450270366800   HAYSI 28   EnerVest Operating LLC   37.195048   82.1938   10/3/2007   10/3/2007   2560   BU-3825   CBM   Drilled   450270372800   HAYSI 28   EnerVest Operating LLC   37.195048   82.1938   12/3/2007   10/3/2007   2560   BU-3825   CBM   Drilled   450270386500   HAYSI 28   EnerVest Operating LLC   37.18547   82.19657   7/18/2008   87.12/2008   2350   BU-3894   CBM   Drilled   450270368600   HAYSI 24   EnerVest Operating LLC   37.18547   82.19696   12/4/2008   12/17/2008   2350   BU-4055   CBM   Drilled   450270405500   HAYSI 24   EnerVest Operating LLC   37.18547   82.19696   12/4/2008   12/17/2008   2350   BU-4055   CBM   Drilled   450270405600   HAYSI 34   EnerVest Operating LLC   37.18549   82.220789   1/1/2008   1/1/2009   2350   BU-4056   CBM   Drilled   450270405000   HAYSI 35   EnerVest Operating LLC	BU-3311	CBM	Drilled	450270331100	HAYSI 31	EnerVest Operating LLC	37.201567	-82.19543	1/9/2007	1/27/2007	2370
BU-3455 CBM Drilled 450270345500 HAYS159 EnerVest Operating LLC 37.186096 e.82.218256 5/24/2007 6/16/2007 2310 BU-3456 CBM Drilled 450270345600 HAYS120 EnerVest Operating LLC 37.190402 e82.21847 59/2007 6/12/2007 2310 BU-3553 CBM Drilled 450270345800 HAYS157 EnerVest Operating LLC 37.193769 82.214547 59/2007 6/12/2007 2310 BU-3553 CBM Drilled 450270355300 HAYS157 EnerVest Operating LLC 37.193769 82.214547 59/2007 10/10/2007 2400 BU-3559 CBM Drilled 450270355900 HAYS157 EnerVest Operating LLC 37.194126 e82.196389 9/26/2007 10/10/2007 2400 BU-3597 CBM Drilled 450270359700 HAYS129 EnerVest Operating LLC 37.203425 82.191359 10/24/2007 11/13/2007 2480 BU-3598 CBM Drilled 450270359700 HAYS129 EnerVest Operating LLC 37.195938 e82.191359 10/24/2007 11/13/2007 2480 BU-3598 CBM Drilled 450270359800 HAYS129 EnerVest Operating LLC 37.195938 e82.191359 10/11/2007 12/4/2007 2560 BU-3615 CBM Drilled 450270361500 HAYS131 EnerVest Operating LLC 37.195048 e82.19335 10/11/2007 10/23/2007 2550 BU-3728 CBM Drilled 450270372500 HAYS138 EnerVest Operating LLC 37.195048 e82.1933 10/3/2007 10/23/2007 2550 BU-3728 CBM Drilled 450270372500 HAYS137 EnerVest Operating LLC 37.195048 e82.1933 10/3/2007 21/3/2008 2550 BU-3728 CBM Drilled 4502703786500 HAYS137 EnerVest Operating LLC 37.195048 e82.19357 17/3/2007 21/3/2008 2550 BU-3728 CBM Drilled 450270386500 HAYS137 EnerVest Operating LLC 37.195048 e82.19357 7/3/20/2008 2550 BU-3656 CBM Drilled 450270366500 HAYS137 EnerVest Operating LLC 37.195048 e82.19577 7/3/20/2008 81/2/2008 BU-3656 CBM Drilled 450270405600 HAYS151 EnerVest Operating LLC 37.185047 e82.19677 7/3/20/2008 2350 BU-4056 CBM Drilled 450270405600 HAYS140 EnerVest Operating LLC 37.185047 e82.201689 12/11/2008 12/11/2008 12/11/2008 BU-4056 CBM Drilled 450270405600 HAYS140 EnerVest Operating LLC 37.185047 e82.201689 12/11/2008 12/12/2008 25000 BU-4056 CBM Drilled 450270456000 HAYS145 EnerVest Operating LLC 37.185047 e82.201689 11/11/2018 12/2/2001 22/2012 24/11/2012 E0000000000000000000000000000000000	BU-3350	CBM	Drilled	450270335000	HAYSI 22	EnerVest Operating LLC	37.201635	-82.215477	3/7/2007	3/23/2007	2430
BU-3455 CBM Drilled 450270345500 HAYS120 EnerVest Operating LLC 37.186096 8.2.218258 5/24/2007 6/12/2007 2280 BU-3456 CBM Drilled 450270345600 HAYS121 EnerVest Operating LLC 37.193759 8.2.214547 5/9/2007 6/12/2007 2310 BU-3553 CBM Drilled 450270345600 HAYS157 EnerVest Operating LLC 37.193759 8.2.214547 5/9/2007 6/12/2007 2310 BU-3556 CBM Drilled 450270355900 HAYS157 EnerVest Operating LLC 37.19416 8.2.196389 9/26/2007 10/10/2007 2400 BU-3557 CBM Drilled 450270359700 HAYS157 EnerVest Operating LLC 37.19416 8.2.196389 9/26/2007 10/10/2007 2400 BU-3559 CBM Drilled 450270359900 HAYS120 EnerVest Operating LLC 37.19416 8.2.196389 9/26/2007 10/10/2007 2400 BU-3559 CBM Drilled 450270359900 HAYS129 EnerVest Operating LLC 37.194508 82.191359 10/24/2007 11/13/2007 2460 BU-3558 CBM Drilled 450270359900 HAYS129 EnerVest Operating LLC 37.195788 82.191359 10/11/2007 12/4/2007 2560 BU-3615 CBM Drilled 450270361500 HAYS128 EnerVest Operating LLC 37.195048 82.191359 10/11/2007 10/23/2007 2560 BU-3728 CBM Drilled 450270372500 HAYS138 EnerVest Operating LLC 37.195048 82.1933 10/3/2007 10/23/2007 2550 BU-3725 CBM Drilled 450270372500 HAYS138 EnerVest Operating LLC 37.195048 82.1933 10/3/2007 10/23/2007 2550 BU-3726 CBM Drilled 4502703786500 HAYS137 EnerVest Operating LLC 37.195048 82.1933 10/3/2007 21/3/2008 2550 BU-3865 CBM Drilled 450270386500 HAYS137 EnerVest Operating LLC 37.20552 82.18677 7/3/0/2008 81/2/2008 BU-3894 CBM Drilled 450270386500 HAYS153 EnerVest Operating LLC 37.20552 82.18677 7/3/0/2008 81/2/2008 BU-3894 CBM Drilled 45027036600 HAYS154 EnerVest Operating LC 37.185047 82.196090 12/11/2008 18/2/2008 2350 BU-4056 CBM Drilled 450270405600 HAYS154 EnerVest Operating LC 37.18547 82.201689 12/11/2008 18/2/2008 2350 BU-4056 CBM Drilled 45027045600 HAYS154 EnerVest Operating LC 37.18547 82.201689 12/11/2008 12/11/200	BU-3375	CBM	Drilled	450270337500	HAYSI 19	EnerVest Operating LLC	37.194912	-82.223383	3/16/2007	3/30/2007	2280
BU-3456   CBM   Drilled   450270345600   HAYSI 20   EnerVest Operating LLC   37.190402   82.219885   57.18/2007   67.14/2007   23.10		СВМ				EnerVest Operating LLC					2280
BU-3458   CBM											
BU-3553   CBM   Drilled   450270355300   HAYS157   EnerVest Operating LLC   37.189944   -82.20234   9/20/2007   10/10/2007   2400   BU-3556   CBM   Drilled   450270355800   HAYS127   EnerVest Operating LLC   37.194126   -82.195939   9/26/2007   10/16/2007   2460   BU-3598   CBM   Drilled   45027035900   HAYS130   EnerVest Operating LLC   37.03425   -82.191359   10/24/2007   11/3/2007   2480   BU-3598   CBM   Drilled   450270359800   HAYS127   EnerVest Operating LLC   37.194326   -82.191359   10/24/2007   11/3/2007   2480   BU-3598   CBM   Drilled   450270350800   HAYS128   EnerVest Operating LLC   37.195936   -82.191572   10/11/2007   12/4/2007   2556   BU-3616   CBM   Drilled   450270351500   HAYS128   EnerVest Operating LLC   37.195044   -82.19335   10/3/2007   10/3/2007   2556   BU-3725   CBM   Drilled   450270372500   HAYS138   EnerVest Operating LLC   37.195043   -82.19385   12/3/2007   4/23/2008   2550   BU-3728   CBM   Drilled   450270372800   HAYS138   EnerVest Operating LLC   37.195043   -82.195857   12/20/2007   2/13/2008   2550   BU-3865   CBM   Drilled   45027038500   HAYS152   EnerVest Operating LLC   37.205529   32.18677   7/30/2008   8/12/2008   2350   BU-3984   CBM   Drilled   45027038500   HAYS153   EnerVest Operating LLC   37.205529   32.18677   7/30/2008   8/12/2008   2350   BU-4056   CBM   Drilled   450270405500   HAYS140   EnerVest Operating LLC   37.186247   82.19696   12/4/2008   12/17/2008   2/10/2008   2/10/2009   2/10/											
BU-3556   CBM   Drilled   450270355600   HAYS127   EnerVest Operating LLC   37.194126   82.196389   9/26/2007   10/16/2007   2460   BU-3597   CBM   Drilled   45027035900   HAYS130   EnerVest Operating LLC   37.203425   82.191359   10/24/2007   11/13/2007   2480   BU-3598   CBM   Drilled   450270359800   HAYS151   EnerVest Operating LLC   37.206354   82.192757   10/112/007   11/6/2007   2460   BU-3608   CBM   Drilled   450270361500   HAYS151   EnerVest Operating LLC   37.195048   82.192757   10/18/2007   11/6/2007   2400   BU-3615   CBM   Drilled   450270372500   HAYS1138   EnerVest Operating LLC   37.195048   82.1933   10/3/2007   10/23/2007   2550   BU-3728   CBM   Drilled   450270372500   HAYS1137   EnerVest Operating LLC   37.195048   82.19355   12/20/2007   2/3/2008   2550   BU-3855   CBM   Drilled   450270372500   HAYS1137   EnerVest Operating LLC   37.195048   82.19557   12/20/2007   2/3/2008   2550   BU-3856   CBM   Drilled   450270386500   HAYS152   EnerVest Operating LLC   37.205592   82.18677   7/39/2008   8/12/2008   2350   BU-3894   CBM   Drilled   450270405600   HAYS141   EnerVest Operating LLC   37.205592   82.18677   7/39/2008   8/6/2008   2350   BU-4056   CBM   Drilled   450270407400   HAYS141   EnerVest Operating LLC   37.18547   82.196096   12/4/2008   12/17/2008   2/10/2009   2460   2/10/2008   2/10/2009   2					1						
BU-3597         CBM         Drilled         450270359700         HAYSI 30         EnerVest Operating LLC         37.203425         -82.191359         10/24/2007         11/13/2007         2480           BU-3598         CBM         Drilled         450270359800         HAYSI 51         EnerVest Operating LLC         37.203548         -82.191572         10/11/2007         12/4/2007         2556           BU-3615         CBM         Drilled         450270360800         HAYSI 28         EnerVest Operating LLC         37.206354         82.192757         10/13/2007         11/6/2007         2550           BU-3725         CBM         Drilled         450270372500         HAYSI 138         EnerVest Operating LLC         37.19043         82.191849         12/13/2007         14/23/2008         2550           BU-3725         CBM         Drilled         450270386500         HAYSI 137         EnerVest Operating LLC         37.190403         82.191849         12/13/2007         2/13/2008         2550           BU-3895         CBM         Drilled         450270405500         HAYSI 52         EnerVest Operating LLC         37.05554         82.186278         7/18/2008         8/6/2008         2328           BU-4056         CBM         Drilled         450270405000         HAYSI 142						1 0					
BU-3598         CBM         Drilled         450270359800         HAYSI 29         EnerVest Operating LLC         37.197938         -82.191672         10/11/2007         12/4/2007         2556           BU-3608         CBM         Drilled         450270361800         HAYSI 51         EnerVest Operating LLC         37.206354         -82.192757         10/18/2007         11/6/2007         2400           BU-3725         CBM         Drilled         450270372800         HAYSI 38         EnerVest Operating LLC         37.195048         -82.1933         10/3/2007         10/23/2007         2550           BU-3725         CBM         Drilled         450270372800         HAYSI 33         EnerVest Operating LC         37.189591         -82.198857         12/02/2007         21/3/2008         266           BU-3865         CBM         Drilled         450270386500         HAYSI 32         EnerVest Operating LC         37.20582         -82.18677         7/18/2008         8/12/2008         2358           BU-3655         CBM         Drilled         450270405600         HAYSI 41         EnerVest Operating LC         37.186247         -82.196906         12/17/2008         24/52           BU-4074         CBM         Drilled         450270407400         HAYSI 42         EnerVest Operating LC </td <td></td>											
BU-3608         CBM         Drilled         450270360800         HAYS151         EnerVest Operating LLC         37.206354         -82.192757         10/18/2007         11/6/2007         2400           BU-3615         CBM         Drilled         450270361500         HAYS128         EnerVest Operating LLC         37.195048         82.1933         10/3/2007         10/23/2007         2550           BU-3725         CBM         Drilled         450270372800         HAYS1138         EnerVest Operating LLC         37.195043         -82.191849         12/13/2007         4/23/2008         2550           BU-3865         CBM         Drilled         450270386500         HAYS152         EnerVest Operating LLC         37.205582         -82.18677         7/30/2008         8/12/2008         2350           BU-3855         CBM         Drilled         450270405500         HAYS154         EnerVest Operating LLC         37.205121         82.186277         7/30/2008         8/12/2008         2350           BU-4056         CBM         Drilled         450270405500         HAYS1141         EnerVest Operating LLC         37.185476         -82.201689         12/11/2008         12/17/2008         2/10/2009         2465           BU-4074         CBM         Drilled         450510179100         <											
BU-3615 CBM Drilled 450270361500 HAYSI 28 EnerVest Operating LLC 37.195048 -82.1933 10/3/2007 10/23/2007 2550 BU-3725 CBM Drilled 450270372800 HAYSI 3138 EnerVest Operating LLC 37.190043 -82.191849 12/13/2007 2/13/2008 2550 BU-3728 CBM Drilled 450270372800 HAYSI 37 EnerVest Operating LLC 37.19591 -82.19657 12/20/2007 2/13/2008 2460 BU-3865 CBM Drilled 450270368500 HAYSI 53 EnerVest Operating LLC 37.20552 -82.18677 7/30/2008 8/12/2008 2350 BU-3894 CBM Drilled 450270389400 HAYSI 53 EnerVest Operating LLC 37.20512 -82.186278 7/18/2008 8/6/2008 2328 BU-3605 CBM Drilled 450270405500 HAYSI 141 EnerVest Operating LLC 37.186247 -82.196806 12/4/2008 12/17/2008 2345 BU-4056 CBM Drilled 450270407400 HAYSI 142 EnerVest Operating LLC 37.18547 -82.196806 12/4/2008 12/17/2008 2310 BU-4074 CBM Drilled 450270407400 HAYSI 142 EnerVest Operating LLC 37.18547 -82.19606 12/17/2008 2/10/2009 2465 DI-1791 CBM Drilled 450510179100 HAYSI 54 EnerVest Operating LLC 37.18540 -82.206768 9/10/2007 9/25/2007 2115 DI-1797 CBM Drilled 450510179700 HAYSI 58 EnerVest Operating LLC 37.189429 -82.226768 9/10/2007 9/25/2007 2150 DI-2064 CBM Drilled 450510206400 HAYSI 154 EnerVest Operating LLC 37.18969 -82.217692 11/13/2008 12/3/2008 2494 BU-4800 CBMIF Drilled 450270482000 HAYSI 155 EnerVest Operating LLC 37.201664 -82.192112 11/5/2011 2/27/2012 2402 BU-4830 CBMIF Drilled 450270483000 HAYSI 155 EnerVest Operating LLC 37.19869 -82.193516 11/3/2011 2/22/2012 2308 BU-4860 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.198199 -82.198492 11/18/2011 2/22/2012 2453 BU-4860 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.198199 -82.198492 11/18/2011 2/22/2012 2453 BU-4860 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.198199 -82.198492 11/18/2011 2/24/2012 2453 BU-4860 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.198199 -82.198492 11/18/2011 2/24/2012 2453 BU-4860 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.198199 -82.198531 11/19/2011 1/26/2012 2453 BU-1360 CBMIF Drilled 4											
BU-3725 CBM Drilled 450270372500 HAYSI 138 EnerVest Operating LLC 37.190043 -82.191849 12/13/2007 4/23/2008 2550 BU-3728 CBM Drilled 450270386500 HAYSI 137 EnerVest Operating LLC 37.189591 -82.195857 12/20/2007 2/13/2008 2460 BU-3865 CBM Drilled 450270386500 HAYSI 52 EnerVest Operating LLC 37.20582 -82.18677 7/30/2008 8/12/2008 2350 BU-3894 CBM Drilled 450270405500 HAYSI 141 EnerVest Operating LLC 37.202121 -82.186278 7/18/2008 8/6/2008 2328 BU-4055 CBM Drilled 450270405500 HAYSI 141 EnerVest Operating LLC 37.186247 -82.196906 12/4/2008 12/17/2008 2345 BU-4056 CBM Drilled 450270405600 HAYSI 141 EnerVest Operating LLC 37.185476 -82.201689 12/11/2008 2/10/2009 2350 BU-4074 CBM Drilled 450270407400 HAYSI 142 EnerVest Operating LLC 37.185476 -82.201689 12/11/2008 12/10/2009 2465 DI-1791 CBM Drilled 450510179100 HAYSI 142 EnerVest Operating LLC 37.185476 -82.201689 12/11/2008 12/10/2009 2465 DI-1791 CBM Drilled 450510179100 HAYSI 145 EnerVest Operating LLC 37.185439 -82.20568 9/10/2007 9/25/2007 2115 DI-1797 CBM Drilled 450510179700 HAYSI 58 EnerVest Operating LLC 37.185633 -82.223021 9/13/2007 10/2/2007 2340 DI-2064 CBM Drilled 4505270480000 HAYSI 63 EnerVest Operating LLC 37.179869 -82.217692 11/13/2008 12/3/2008 2494 BU-4830 CBMIF Drilled 450270480000 HAYSI 145 EnerVest Operating LLC 37.19869 -82.201259 10/31/2011 2/27/2012 2602. BU-4830 CBMIF Drilled 450270483000 HAYSI 155 EnerVest Operating LLC 37.198784 -82.193516 11/3/2011 2/27/2012 2442 BU-4830 CBMIF Drilled 450270484000 HAYSI 155 EnerVest Operating LLC 37.19879 -82.20269 11/11/2011 2/22/2012 2453.4 BU-4866 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.19879 -82.198492 11/8/2011 2/24/2012 2453.4 BU-4866 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.19879 -82.20869 11/11/2011 2/24/2012 2453.4 BU-4866 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.19879 -82.20869 11/11/2011 2/24/2012 2571.5 BU-5078 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.19879 -82.198531 11/3/2011 1/25/2012 2414.6 BU-5078					1						
BU-3728 CBM Drilled 450270372800 HAYSI 37 EnerVest Operating LLC 37.189591 -82.195857 12/20/2007 2/13/2008 2460 BU-3896 CBM Drilled 4502703896500 HAYSI 52 EnerVest Operating LLC 37.205582 -82.18677 7/30/2008 8/12/2008 2350 BU-3894 CBM Drilled 450270405500 HAYSI 53 EnerVest Operating LLC 37.205121 -82.186278 7/18/2008 8/6/2008 2328 BU-4055 CBM Drilled 450270405500 HAYSI 141 EnerVest Operating LLC 37.186247 -82.196906 12/4/2008 12/17/2008 2/10/2009 2455 BU-4055 CBM Drilled 450270405500 HAYSI 141 EnerVest Operating LLC 37.185476 -82.201689 12/11/2008 12/10/2009 2455 BU-4074 CBM Drilled 450270407400 HAYSI 142 EnerVest Operating LLC 37.185476 -82.201689 12/11/2008 1/9/2009 2455 BU-4074 CBM Drilled 450510179100 HAYSI 54 EnerVest Operating LLC 37.18547 -82.190106 12/17/2008 1/9/2009 2455 BU-1797 CBM Drilled 450510179700 HAYSI 58 EnerVest Operating LLC 37.18949 82.226768 9/10/2007 9/25/2007 2145 BU-4800 CBMI Drilled 450510206400 HAYSI 58 EnerVest Operating LLC 37.179869 82.217692 11/13/2008 12/3/2008 2494 BU-4800 CBMIF Drilled 45027048000 HAYSI 55 EnerVest Operating LLC 37.179869 82.217692 11/13/2001 12/27/2012 2602. BU-4821 CBMIF Drilled 45027048300 HAYSI 55 EnerVest Operating LLC 37.198784 82.193516 11/3/2011 2/27/2012 2602. BU-4821 CBMIF Drilled 45027048300 HAYSI 55 EnerVest Operating LLC 37.198784 82.193516 11/3/2011 2/22/2012 2452. BU-4830 CBMIF Drilled 450270484000 HAYSI 55 EnerVest Operating LLC 37.198784 82.193516 11/3/2011 2/22/2012 2452. BU-4860 CBMIF Drilled 450270486400 HAYSI 55 EnerVest Operating LLC 37.198784 82.193516 11/3/2011 2/22/2012 2452. BU-4860 CBMIF Drilled 450270486400 HAYSI 55 EnerVest Operating LLC 37.198784 82.193516 11/3/2011 2/22/2012 2452. BU-4860 CBMIF Drilled 450270486400 HAYSI 55 EnerVest Operating LLC 37.198784 82.193510 11/3/2011 2/21/2012 2452. BU-4860 CBMIF Drilled 450270486400 HAYSI 55 EnerVest Operating LLC 37.19869 82.19464 11/3/2011 12/26/2012 2450. BU-5126 CBMIF Drilled 450270486400 HAYSI 55 EnerVest Operating LLC 37.19869 82.19464 11/3/2011 12/26/2012 2450. BU-5126 CBMIF Drill											
BU-3865 CBM Drilled 450270386500 HAYSI 52 EnerVest Operating LLC 37.205582 -82.18677 7/30/2008 8/12/2008 2350 BU-3894 CBM Drilled 450270389400 HAYSI 53 EnerVest Operating LLC 37.205121 -82.186278 7/18/2008 12/17/2008 2345 BU-4055 CBM Drilled 450270405500 HAYSI 140 EnerVest Operating LLC 37.186247 -82.196906 12/4/2008 12/17/2008 2345 BU-4056 CBM Drilled 450270405600 HAYSI 140 EnerVest Operating LLC 37.186247 -82.201689 12/11/2008 2/10/2009 2350 BU-4074 CBM Drilled 450270407400 HAYSI 140 EnerVest Operating LLC 37.185476 -82.201689 12/11/2008 1/9/2009 2456 DI-1791 CBM Drilled 450510179100 HAYSI 54 EnerVest Operating LLC 37.189429 -82.226768 9/10/2007 9/25/2007 2115 DI-1797 CBM Drilled 450510179700 HAYSI 58 EnerVest Operating LLC 37.185633 -82.223021 9/13/2007 10/2/2007 2340 BU-4806 CBMIF Drilled 450510206400 HAYSI 148 EnerVest Operating LLC 37.185633 -82.223021 9/13/2008 12/37/2008 12/37/2008 BU-4821 CBMIF Drilled 45027048000 HAYSI 148 EnerVest Operating LLC 37.203839 -82.202129 10/31/2011 2/27/2012 2602. BU-4821 CBMIF Drilled 450270483000 HAYSI 154 EnerVest Operating LLC 37.203839 -82.202129 10/31/2011 2/22/2012 2305 BU-4830 CBMIF Drilled 450270483000 HAYSI 155 EnerVest Operating LLC 37.198784 -82.19869 11/8/2011 2/22/2012 2452. BU-4837 CBMIF Drilled 450270483000 HAYSI 155 EnerVest Operating LLC 37.198798 -82.198492 11/8/2011 2/28/2012 2450. BU-4860 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.198199 -82.198492 11/8/2011 2/28/2012 2450. BU-4861 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.198199 -82.198492 11/8/2011 1/26/2012 2571.3 BU-4861 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.198199 -82.20869 11/11/2011 1/26/2012 2450. BU-5164 CBMIF Drilled 450270466000 HAYSI 155 EnerVest Operating LLC 37.198199 -82.20869 11/11/2011 1/26/2012 2450. BU-5164 CBMIF Drilled 450270512600 HAYSI 35 EnerVest Operating LLC 37.198199 -82.20869 11/11/2011 1/26/2012 2450. BU-5164 CBMIF Drilled 450270512600 HAYSI 35 EnerVest Operating LLC 37.188347 -82.20649 12/7/2014 1/03/2016 10											
BU-3894 CBM Drilled 450270389400 HAYSI 53 EnerVest Operating LLC 37.202121 -82.186278 7/18/2008 8/6/2008 2328 BU-4055 CBM Drilled 450270405500 HAYSI 141 EnerVest Operating LLC 37.186247 -82.196906 12/4/2008 12/17/2008 2345 BU-4056 CBM Drilled 450270405600 HAYSI 140 EnerVest Operating LLC 37.185476 -82.201689 12/11/2008 2/10/2009 2350 BU-4074 CBM Drilled 450270407400 HAYSI 140 EnerVest Operating LLC 37.185476 -82.201689 12/11/2008 12/10/2009 2465 DI-1791 CBM Drilled 450510179700 HAYSI 54 EnerVest Operating LLC 37.185472 -82.190106 12/17/2008 1/9/2009 2465 DI-1797 CBM Drilled 450510179700 HAYSI 58 EnerVest Operating LLC 37.185633 -82.223021 9/13/2007 10/2/2007 2340 DI-2064 CBM Drilled 450510206400 HAYSI 63 EnerVest Operating LLC 37.179869 -82.217692 11/13/2008 12/3/2008 2494 BU-4800 CBMIF Drilled 450270480000 HAYSI 148 EnerVest Operating LLC 37.203839 -82.202129 10/31/2011 2/27/2012 2602. BU-4821 CBMIF Drilled 450270482100 HAYSI 154 EnerVest Operating LLC 37.203839 -82.202129 10/31/2011 2/22/2012 2002. BU-4837 CBMIF Drilled 450270483000 HAYSI 155 EnerVest Operating LLC 37.19864 -82.192212 11/5/2011 2/22/2012 2402. BU-4830 CBMIF Drilled 450270484600 HAYSI 155 EnerVest Operating LLC 37.198794 -82.193516 11/3/2011 2/22/2012 2453.4 BU-4860 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.198791 -82.202699 11/11/2011 2/24/2012 2571.3 BU-4860 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.198791 -82.202869 11/11/2011 2/24/2012 2571.3 BU-4861 CBMIF Drilled 450270486000 HAYSI 155 EnerVest Operating LLC 37.198791 -82.202869 11/11/2011 1/26/2012 2430. BU-5078 CBMIF Drilled 450270486100 HAYSI 35 EnerVest Operating LC 37.20157 -82.20404 10/3/2016 10/12/2016 2501. BU-5126 CBMIF Drilled 450270514400 HAYSI 35 EnerVest Operating LC 37.20127 -82.220444 10/3/2016 10/12/2016 2501. BU-5126 CBMIF Drilled 450270137900 V-823605 EnerVest Operating LC 37.203729 -82.220349 17/19/2011 1/26/2012 230. BU-1337 GAS Drilled 450270138000 V-823605 EnerVest Operating LC 37.19859 -82.19953 7/16/1999 8/10/19/1998 6054 B					1						
BU-4055         CBM         Drilled         450270405500         HAYSI 14I         EnerVest Operating LLC         37.186247         -82.196906         12/4/2008         12/17/2008         2345           BU-4056         CBM         Drilled         450270405600         HAYSI 140         EnerVest Operating LLC         37.185476         -82.201689         12/11/2008         2/10/2009         2350           BU-4074         CBM         Drilled         450270407400         HAYSI 142         EnerVest Operating LLC         37.18547         -82.190106         12/17/2008         1/9/2007         2465           DI-1791         CBM         Drilled         450510179100         HAYSI 54         EnerVest Operating LLC         37.18543         -82.223021         9/13/2007         10/2/2007         20/2           DI-1797         CBM         Drilled         450510179700         HAYSI 63         EnerVest Operating LLC         37.185633         -82.223021         9/13/2007         10/2/2007         20/2           DI-1797         CBM         Drilled         450510266400         HAYSI 63         EnerVest Operating LC         37.179869         -82.17692         11/13/2001         2/27/2012         2602.           BU-4800         CBMIF         Drilled         450270483000         HAYSI 154											
BU-4056         CBM         Drilled         450270405600         HAYSI 140         EnerVest Operating LLC         37.185476         -82.201689         12/11/2008         2/10/2009         2350           BU-4074         CBM         Drilled         450270407400         HAYSI 142         EnerVest Operating LLC         37.18547         -82.190106         12/17/2008         1/9/2009         2465           DI-1791         CBM         Drilled         450510179700         HAYSI 58         EnerVest Operating LLC         37.189429         -82.226768         9/10/2007         9/25/2007         2115           DI-1797         CBM         Drilled         450510179700         HAYSI 58         EnerVest Operating LLC         37.18969         -82.227629         1/13/2007         10/2/2007         2340           DI-2064         CBMI         Drilled         450510206400         HAYSI 63         EnerVest Operating LC         37.179869         -82.20129         10/31/2011         12/27/2012         2602           BU-4821         CBMIF         Drilled         450270482100         HAYSI 148         EnerVest Operating LC         37.201564         -82.192212         11/5/2011         2/22/2012         2305           BU-4837         CBMIF         Drilled         450270483000         HAYSI 152				450270389400	1	EnerVest Operating LLC	37.202121	-82.186278			
BU-4074   CBM   Drilled   450270407400   HAYSI 142   EnerVest Operating LLC   37.18547   -82.190106   12/17/2008   1/9/2009   2465	BU-4055	CBM	Drilled	450270405500	HAYSI 141	EnerVest Operating LLC	37.186247	-82.196906	12/4/2008	12/17/2008	2345
DI-1791   CBM   Drilled   450510179100   HAYSI 54   EnerVest Operating LLC   37.189429   -82.226768   9/10/2007   9/25/2007   2115   DI-1797   CBM   Drilled   450510179700   HAYSI 58   EnerVest Operating LLC   37.185633   -82.223021   9/13/2007   10/2/2007   2340   DI-2064   CBM   Drilled   450510206400   HAYSI 63   EnerVest Operating LLC   37.179869   82.217692   11/13/2008   12/3/2008   2494   BU-4800   CBMIF   Drilled   450270480000   HAYSI 148   EnerVest Operating LLC   37.203839   -82.202129   10/31/2011   2/27/2012   2602.   BU-4821   CBMIF   Drilled   450270482100   HAYSI 154   EnerVest Operating LLC   37.201564   -82.192212   11/5/2011   2/22/2012   2305   BU-4830   CBMIF   Drilled   450270483000   HAYSI 155   EnerVest Operating LLC   37.198784   -82.193516   11/3/2011   2/221/2012   2452   BU-4830   CBMIF   Drilled   450270483700   HAYSI 155   EnerVest Operating LLC   37.198794   -82.193516   11/3/2011   2/28/2012   2452   BU-4860   CBMIF   Drilled   450270484600   HAYSI 155   EnerVest Operating LLC   37.198199   -82.202869   11/11/2011   2/28/2012   2571.3   BU-4860   CBMIF   Drilled   450270486000   HAYSI 155   EnerVest Operating LLC   37.197891   -82.202869   11/11/2011   2/28/2012   2571.3   BU-4861   CBMIF   Drilled   450270486000   HAYSI 155   EnerVest Operating LLC   37.198347   -82.197631   12/2/2011   1/26/2012   2430.   BU-4861   CBMIF   Drilled   450270486100   HAYSI 35   EnerVest Operating LLC   37.201247   -82.20649   12/7/2014   4/10/2015   2513.8   BU-5126   CBMIF   Drilled   45027057800   HAYSI 35   EnerVest Operating LLC   37.201247   -82.220649   12/7/2014   4/10/2015   2513.8   BU-5126   CBMIF   Drilled   450270512600   HAYSI 36   EnerVest Operating LLC   37.201247   -82.220444   10/3/2016   10/12/2016   2501   BU-5144   CBMIF   Drilled   450270514400   HAYSI 37   EnerVest Operating LLC   37.203729   -82.220444   10/3/2016   10/12/2016   2501   BU-5144   CBMIF   Drilled   45027051800   V-823309   EnerVest Operating LLC   37.195033   82.220308   87/1/1998   10/10/1998   6058   BU-13	BU-4056	CBM	Drilled	450270405600	HAYSI 140	EnerVest Operating LLC	37.185476	-82.201689	12/11/2008	2/10/2009	2350
DI-1797   CBM   Drilled   450510179700   HAYSI 58   EnerVest Operating LLC   37.185633   -82.223021   9/13/2007   10/2/2007   2340	BU-4074	CBM	Drilled	450270407400	HAYSI 142	EnerVest Operating LLC	37.18547	-82.190106	12/17/2008	1/9/2009	2465
DI-2064         CBM         Drilled         450510206400         HAYSI 63         EnerVest Operating LLC         37.179869         -82.217692         11/13/2008         12/3/2008         2494           BU-4800         CBMIF         Drilled         450270480000         HAYSI 148         EnerVest Operating LLC         37.203839         -82.202129         10/31/2011         2/27/2012         2602           BU-4821         CBMIF         Drilled         450270482100         HAYSI 154         EnerVest Operating LLC         37.201564         -82.192212         11/5/2011         2/22/2012         2305           BU-4830         CBMIF         Drilled         450270483000         HAYSI 155         EnerVest Operating LLC         37.198794         -82.193516         11/3/2011         2/21/2012         2442           BU-4837         CBMIF         Drilled         450270483700         HAYSI 152         EnerVest Operating LLC         37.198199         -82.198492         11/8/2011         2/21/2012         2453.4           BU-4860         CBMIF         Drilled         450270486000         HAYSI 153         EnerVest Operating LLC         37.192615         -82.197631         12/2/2011         1/26/2012         2430.           BU-5078         CBMIF         Drilled         450270486100 <t< td=""><td>DI-1791</td><td>CBM</td><td>Drilled</td><td>450510179100</td><td>HAYSI 54</td><td>EnerVest Operating LLC</td><td>37.189429</td><td>-82.226768</td><td>9/10/2007</td><td>9/25/2007</td><td>2115</td></t<>	DI-1791	CBM	Drilled	450510179100	HAYSI 54	EnerVest Operating LLC	37.189429	-82.226768	9/10/2007	9/25/2007	2115
BU-4800         CBMIF         Drilled         450270480000         HAYSI 148         EnerVest Operating LLC         37.203839         -82.202129         10/31/2011         2/27/2012         2602.           BU-4821         CBMIF         Drilled         450270482100         HAYSI 154         EnerVest Operating LLC         37.201564         -82.192212         11/5/2011         2/22/2012         2305           BU-4830         CBMIF         Drilled         450270483000         HAYSI 155         EnerVest Operating LLC         37.198784         -82.193516         11/3/2011         2/21/2012         2442           BU-4837         CBMIF         Drilled         450270483700         HAYSI 152         EnerVest Operating LLC         37.198199         -82.198492         11/8/2011         2/28/2012         2453.4           BU-4846         CBMIF         Drilled         450270486000         HAYSI 149         EnerVest Operating LLC         37.197891         -82.20869         11/11/2011         2/24/2012         2571.3           BU-4861         CBMIF         Drilled         450270486100         HAYSI 157         EnerVest Operating LLC         37.188347         -82.197571         12/5/2011         1/25/2012         2414.0           BU-5078         CBMIF         Drilled         450270512600	DI-1797	CBM	Drilled	450510179700	HAYSI 58	EnerVest Operating LLC	37.185633	-82.223021	9/13/2007	10/2/2007	2340
BU-4821         CBMIF         Drilled         450270482100         HAYSI 154         EnerVest Operating LLC         37.201564         -82.192212         11/5/2011         2/22/2012         2305           BU-4830         CBMIF         Drilled         450270483000         HAYSI 155         EnerVest Operating LLC         37.198784         -82.193516         11/3/2011         2/21/2012         2442           BU-4837         CBMIF         Drilled         450270483700         HAYSI 152         EnerVest Operating LLC         37.198199         -82.198492         11/8/2011         2/28/2012         2453.4           BU-4846         CBMIF         Drilled         450270486000         HAYSI 153         EnerVest Operating LLC         37.192615         -82.197631         12/2/2011         1/26/2012         2430.           BU-4861         CBMIF         Drilled         450270486100         HAYSI 157         EnerVest Operating LLC         37.193615         -82.197571         12/5/2011         1/26/2012         2430.           BU-5078         CBMIF         Drilled         450270507800         HAYSI 35         EnerVest Operating LLC         37.201247         -82.220649         12/7/2014         4/10/2015         2513.8           BU-5126         CBMIF         Drilled         450270514400	DI-2064	CBM	Drilled	450510206400	HAYSI 63	EnerVest Operating LLC	37.179869	-82.217692	11/13/2008	12/3/2008	2494
BU-4830         CBMIF         Drilled         450270483000         HAYSI 155         EnerVest Operating LLC         37.198784         -82.193516         11/3/2011         2/21/2012         2442           BU-4837         CBMIF         Drilled         450270483700         HAYSI 152         EnerVest Operating LLC         37.198199         -82.198492         11/8/2011         2/28/2012         2453.4           BU-4846         CBMIF         Drilled         450270486000         HAYSI 149         EnerVest Operating LLC         37.197891         -82.202869         11/11/2011         2/24/2012         2571.3           BU-4860         CBMIF         Drilled         450270486100         HAYSI 153         EnerVest Operating LLC         37.192615         -82.197631         12/2/2011         1/26/2012         2430.           BU-5078         CBMIF         Drilled         450270507800         HAYSI 35         EnerVest Operating LLC         37.201247         -82.220649         12/7/2014         4/10/2015         2513.8           BU-5126         CBMIF         Drilled         450270512600         HAYSI 36         EnerVest Operating LLC         37.201247         -82.224044         10/3/2016         10/12/2016         2501           BU-5144         CBMIF         Drilled         450270514400	BU-4800	CBMIF	Drilled	450270480000	HAYSI 148	EnerVest Operating LLC	37.203839	-82.202129	10/31/2011	2/27/2012	2602.4
BU-4830         CBMIF         Drilled         450270483000         HAYSI 155         EnerVest Operating LLC         37.198784         -82.193516         11/3/2011         2/21/2012         2442           BU-4837         CBMIF         Drilled         450270483700         HAYSI 152         EnerVest Operating LLC         37.198199         -82.198492         11/8/2011         2/28/2012         2453.4           BU-4846         CBMIF         Drilled         450270486000         HAYSI 149         EnerVest Operating LLC         37.197891         -82.202869         11/11/2011         2/24/2012         2571.3           BU-4860         CBMIF         Drilled         450270486100         HAYSI 157         EnerVest Operating LLC         37.192615         -82.197631         12/2/2011         1/26/2012         2430.           BU-5078         CBMIF         Drilled         45027057800         HAYSI 35         EnerVest Operating LLC         37.188347         -82.197571         12/5/2011         1/25/2012         2414.0           BU-5126         CBMIF         Drilled         45027057800         HAYSI 35         EnerVest Operating LLC         37.201227         -82.220649         12/7/2014         4/10/2015         2513.8           BU-5126         CBMIF         Drilled         450270514400	BU-4821	CBMIF	Drilled	450270482100	HAYSI 154	EnerVest Operating LLC	37.201564	-82.192212	11/5/2011	2/22/2012	2305
BU-4837         CBMIF         Drilled         450270483700         HAYSI 152         EnerVest Operating LLC         37.198199         -82.198492         11/8/2011         2/28/2012         2453.4           BU-4846         CBMIF         Drilled         450270484600         HAYSI 149         EnerVest Operating LLC         37.197891         -82.202869         11/11/2011         2/24/2012         2571.3           BU-4860         CBMIF         Drilled         450270486000         HAYSI 153         EnerVest Operating LLC         37.192615         -82.197631         12/2/2011         1/26/2012         2430.           BU-4861         CBMIF         Drilled         450270486100         HAYSI 35         EnerVest Operating LLC         37.188347         -82.197571         12/5/2011         1/25/2012         2414.0           BU-5078         CBMIF         Drilled         450270507800         HAYSI 35         EnerVest Operating LLC         37.201247         -82.220649         12/7/2014         4/10/2015         2513.8           BU-5126         CBMIF         Drilled         450270514400         HAYSI 37         EnerVest Operating LLC         37.201227         -82.220649         12/7/2014         4/10/2015         2513.8           BU-5144         CBMIF         Drilled         4502700900	BU-4830		Drilled	450270483000							2442
BU-4846         CBMIF         Drilled         450270484600         HAYSI 149         EnerVest Operating LLC         37.197891         -82.202869         11/11/2011         2/24/2012         2571.3           BU-4860         CBMIF         Drilled         450270486000         HAYSI 153         EnerVest Operating LLC         37.192615         -82.197631         12/2/2011         1/26/2012         2430.           BU-4861         CBMIF         Drilled         450270486100         HAYSI 35         EnerVest Operating LLC         37.188347         -82.197571         12/5/2011         1/25/2012         2414.0           BU-5078         CBMIF         Drilled         450270517800         HAYSI 35         EnerVest Operating LLC         37.201247         -82.220649         12/7/2014         4/10/2015         2513.8           BU-5126         CBMIF         Drilled         450270512600         HAYSI 36         EnerVest Operating LLC         37.201227         -82.2204044         10/3/2016         10/12/2016         2501           BU-5144         CBMIF         Drilled         450270514400         HAYSI 37         EnerVest Operating LLC         37.203729         -82.2209228         6/3/2017         6/27/2017         2377           BU-092         GAS         Drilled         450270137900         <	BU-4837	CBMIF	Drilled	450270483700			37.198199	-82.198492	11/8/2011	2/28/2012	2453.47
BU-4860         CBMIF         Drilled         450270486000         HAYSI 153         EnerVest Operating LLC         37.192615         -82.197631         12/2/2011         1/26/2012         2430.           BU-4861         CBMIF         Drilled         450270486100         HAYSI 157         EnerVest Operating LLC         37.188347         -82.197571         12/5/2011         1/25/2012         2414.0           BU-5078         CBMIF         Drilled         450270507800         HAYSI 35         EnerVest Operating LLC         37.201247         -82.220649         12/7/2014         4/10/2015         2513.8           BU-5126         CBMIF         Drilled         450270512600         HAYSI 36         EnerVest Operating LLC         37.201227         -82.224044         10/3/2016         10/12/2016         2501           BU-5144         CBMIF         Drilled         450270514400         HAYSI 37         EnerVest Operating LLC         37.203729         -82.209228         6/3/2017         6/27/2017         2377           BU-092         GAS         Drilled         45027009200         V-809587         EnerVest Operating LLC         37.208666         -82.214012         9/10/1970         10/27/1970         5860           BU-1379         GAS         Drilled         450270137900         V-82											2571.36
BU-4861         CBMIF         Drilled         450270486100         HAYSI 157         EnerVest Operating LLC         37.188347         -82.197571         12/5/2011         1/25/2012         2414.0           BU-5078         CBMIF         Drilled         450270507800         HAYSI 35         EnerVest Operating LLC         37.201247         -82.220649         12/7/2014         4/10/2015         2513.8           BU-5126         CBMIF         Drilled         450270512600         HAYSI 36         EnerVest Operating LLC         37.201227         -82.224044         10/3/2016         10/12/2016         2501           BU-5144         CBMIF         Drilled         450270514400         HAYSI 37         EnerVest Operating LLC         37.203729         -82.209228         6/3/2017         6/27/2017         2377           BU-0992         GAS         Drilled         45027009200         V-809587         EnerVest Operating LLC         37.208666         -82.214012         9/10/1970         10/27/1970         5860           BU-1379         GAS         Drilled         450270137900         V-823309         EnerVest Operating LLC         37.195033         -82.220339         8/7/1998         10/10/1998         6054           BU-1380         GAS         Drilled         450270143700         V-82161					t						
BU-5078         CBMIF         Drilled         450270507800         HAYSI 35         EnerVest Operating LLC         37.201247         -82.220649         12/7/2014         4/10/2015         2513.8           BU-5126         CBMIF         Drilled         450270512600         HAYSI 36         EnerVest Operating LLC         37.201227         -82.224044         10/3/2016         10/12/2016         2501           BU-5144         CBMIF         Drilled         450270514400         HAYSI 37         EnerVest Operating LLC         37.203729         -82.209228         6/3/2017         6/27/2017         2377           BU-092         GAS         Drilled         450270009200         V-809587         EnerVest Operating LLC         37.208666         -82.214012         9/10/1970         10/27/1970         5860           BU-1379         GAS         Drilled         450270137900         V-823309         EnerVest Operating LLC         37.195033         -82.220339         8/7/1998         10/10/1998         6054           BU-1380         GAS         Drilled         450270138000         V-821619         EnerVest Operating LLC         37.19837         -82.223087         7/27/1998         10/10/1998         6118           BU-1437         GAS         Drilled         450270161300         V-823605 <td></td>											
BU-5126         CBMIF         Drilled         450270512600         HAYSI 36         EnerVest Operating LLC         37.201227         -82.224044         10/3/2016         10/12/2016         2501           BU-5144         CBMIF         Drilled         450270514400         HAYSI 37         EnerVest Operating LLC         37.203729         -82.209228         6/3/2017         6/27/2017         2377           BU-0092         GAS         Drilled         450270009200         V-809587         EnerVest Operating LLC         37.208666         -82.214012         9/10/1970         10/27/1970         5860           BU-1379         GAS         Drilled         450270137900         V-823309         EnerVest Operating LLC         37.195033         -82.220339         8/7/1998         10/10/1998         6054           BU-1380         GAS         Drilled         450270138000         V-821619         EnerVest Operating LLC         37.20288         -82.223087         7/27/1998         10/10/1998         6118           BU-1437         GAS         Drilled         450270143700         V-823605         EnerVest Operating LLC         37.198837         -82.212861         9/2/1998         10/12/1998         6102           BU-1613         GAS         Drilled         450270162600         V-823310											
BU-5144         CBMIF         Drilled         450270514400         HAYSI 37         EnerVest Operating LLC         37.203729         -82.209228         6/3/2017         6/27/2017         2377           BU-0092         GAS         Drilled         45027009200         V-809587         EnerVest Operating LLC         37.208666         -82.214012         9/10/1970         10/27/1970         5860           BU-1379         GAS         Drilled         450270137900         V-823309         EnerVest Operating LLC         37.195033         -82.220339         8/7/1998         10/10/1998         6054           BU-1380         GAS         Drilled         450270138000         V-821619         EnerVest Operating LLC         37.20288         -82.223087         7/27/1998         10/10/1998         6118           BU-1437         GAS         Drilled         450270143700         V-821617         EnerVest Operating LLC         37.198837         -82.212861         9/2/1998         10/12/1998         6102           BU-1613         GAS         Drilled         450270161300         V-823605         EnerVest Operating LLC         37.19502         -82.210016         6/15/1999         8/23/1999         6176           BU-1626         GAS         Drilled         450270162600         V-823310											
BU-092 GAS Drilled 45027009200 V-809587 EnerVest Operating LLC 37.208666 -82.214012 9/10/1970 10/27/1970 5860 BU-1379 GAS Drilled 450270137900 V-823309 EnerVest Operating LLC 37.195033 -82.220339 8/7/1998 10/10/1998 6054 BU-1380 GAS Drilled 450270138000 V-821619 EnerVest Operating LLC 37.20288 -82.223087 7/27/1998 10/10/1998 6118 BU-1437 GAS Drilled 450270143700 V-821617 EnerVest Operating LLC 37.198837 -82.212861 9/2/1998 10/12/1998 6102 BU-1613 GAS Drilled 450270161300 V-823605 EnerVest Operating LLC 37.198797 -82.199533 7/16/1999 8/23/1999 6176 BU-1626 GAS Drilled 450270162600 V-823310 EnerVest Operating LLC 37.191502 -82.210016 6/15/1999 8/16/1999 6099											
BU-1379         GAS         Drilled         450270137900         V-823309         EnerVest Operating LLC         37.195033         -82.220339         8/7/1998         10/10/1998         6054           BU-1380         GAS         Drilled         450270138000         V-821619         EnerVest Operating LLC         37.20288         -82.223087         7/27/1998         10/10/1998         6118           BU-1437         GAS         Drilled         450270143700         V-821617         EnerVest Operating LLC         37.198837         -82.212861         9/2/1998         10/12/1998         6102           BU-1613         GAS         Drilled         450270161300         V-823605         EnerVest Operating LLC         37.198797         -82.199533         7/16/1999         8/23/1999         6176           BU-1626         GAS         Drilled         450270162600         V-823310         EnerVest Operating LLC         37.191502         -82.210016         6/15/1999         8/16/1999         6099											
BU-1380         GAS         Drilled         450270138000         V-821619         EnerVest Operating LLC         37.20288         -82.223087         7/27/1998         10/10/1998         6118           BU-1437         GAS         Drilled         450270143700         V-821617         EnerVest Operating LLC         37.198837         -82.212861         9/2/1998         10/12/1998         6102           BU-1613         GAS         Drilled         450270161300         V-823605         EnerVest Operating LLC         37.198797         -82.199533         7/16/1999         8/23/1999         6176           BU-1626         GAS         Drilled         450270162600         V-823310         EnerVest Operating LLC         37.191502         -82.210016         6/15/1999         8/16/1999         6099						1 0					
BU-1437         GAS         Drilled         450270143700         V-821617         EnerVest Operating LLC         37.198837         -82.212861         9/2/1998         10/12/1998         6102           BU-1613         GAS         Drilled         450270161300         V-823605         EnerVest Operating LLC         37.198797         -82.199533         7/16/1999         8/23/1999         6176           BU-1626         GAS         Drilled         450270162600         V-823310         EnerVest Operating LLC         37.191502         -82.210016         6/15/1999         8/16/1999         6099	BU-1379										6054
BU-1613         GAS         Drilled         450270161300         V-823605         EnerVest Operating LLC         37.198797         -82.199533         7/16/1999         8/23/1999         6176           BU-1626         GAS         Drilled         450270162600         V-823310         EnerVest Operating LLC         37.191502         -82.210016         6/15/1999         8/16/1999         6099	BU-1380										6118
BU-1626 GAS Drilled 450270162600 V-823310 EnerVest Operating LLC 37.191502 -82.210016 6/15/1999 8/16/1999 6099	BU-1437	GAS	Drilled		V-821617		37.198837	-82.212861	9/2/1998		6102
	BU-1613	GAS	Drilled	450270161300	V-823605	EnerVest Operating LLC	37.198797	-82.199533	7/16/1999	8/23/1999	6176
BU-1806 GAS Drilled 450270180600 V-824073 EnerVest Operating LLC 37.210112 -82.19864 5/2/2000 6/21/2000 6060	BU-1626	GAS	Drilled	450270162600	V-823310	EnerVest Operating LLC	37.191502	-82.210016	6/15/1999	8/16/1999	6099
	BU-1806	GAS	Drilled	450270180600	V-824073	EnerVest Operating LLC	37.210112	-82.19864	5/2/2000	6/21/2000	6060

BU-1864	GAS	Drilled	450270186400	V-824153	EnerVest Operating LLC	37.188137	-82.218126	6/17/2000	7/18/2000	5895
BU-2549	GAS	Drilled	450270254900	V-824545	EnerVest Operating LLC	37.180422	-82.215757	10/21/2003	11/19/2003	5974
BU-3349	GAS	Drilled	450270334900	V-824155	EnerVest Operating LLC	37.190939	-82.200111	5/30/2007	7/3/2007	6625
BU-3391	GAS	Drilled	450270339100	V-826204	EnerVest Operating LLC	37.20163	-82.190586	7/19/2007	8/14/2007	6707
BU-3396	GAS	Drilled	450270339600	V-826203	EnerVest Operating LLC	37.194625	-82.191409	8/3/2007	8/27/2007	6728
BU-4554	GAS	Drilled	450270455400	V-900005	EnerVest Operating LLC	37.188138	-82.193572	11/30/2010	12/22/2010	5202
BU-4608	GAS	Drilled	450270460800	V-900004	EnerVest Operating LLC	37.183969	-82.199634	12/21/2010	1/20/2011	4936

#### UIC within 1-mile of Proposed 900146 SWD

STATE FILE	WELL TYPE	STATUS	API	ALT NAME	OPERATOR	LATITUDE	LONGITUDE	SPUD DATE	COMP DATE	TD
BU-1614	SWD	Drilled	450270161400	VS-823606	EnerVest Operating LLC	37.205985	-82.204358	7/6/1999	8/23/1999	6165



#### 1.0 INTRODUCTION

The proposed injection well is in the Appalachian Basin in an area with an extensive, thick sedimentary sequence with an adequate injection interval and numerous confining strata. The injection zone, the Weir Formation, is a siltstone that is relatively homogeneous with no highly permeable streaks or major lithologic differences across its vast lateral extent. The lateral extent, which covers most of southwest Virginia, into Kentucky, West Virginia and beyond, is large enough to minimize injection pressure variations. The Weir has confining strata above and below of sufficient thickness and low enough permeability to confine the injection interval and isolate injected fluids to that zone. The Weir is thousands of feet below any known underground source of drinking water, thereby allowing adequate separation from potable water zones.

The overall geology in the area is structurally simple with flat-lying strata and no active fault systems. There are no identified faults within the Area of Review. Faults in the region were active hundreds of millions of years ago with no current tectonic forces on fault planes resulting in movement. Since the forces that caused faulting in the area occurred hundreds of millions of years ago, the fault zones are considered inactive and the triggering of seismic activity by fluid injection is unlikely.

The Weir is the primary injection zone targeted by Class II-D wells in Virginia. Rock characteristics allow for it to be an effective injection zone with lithology above and below for adequate confinement.

#### 2.0 INJECTION ZONE

The target formation for the injection of produced fluid is a zone within the Mississippian Price Formation, known as the Weir. The Weir is a hydrocarbon reservoir rock across the Basin. As such, it has sufficient porosity and permeability to permit the storage and accumulation of hydrocarbons under adequate confining conditions. This formation is the target zone in many existing injection wells throughout southwest Virginia including ENERVEST's existing UIC Class II-D injection well located approximately 4,350' to the north of the proposed well (UIC Permit VAS2D950BBUC).

In the area of the proposed well, the Weir formation consists of a very fine-grained siltstone. The lower portion of the Weir, locally referred to as the Weir Shale, is finer grained with slightly higher organic content. The target interval within the Weir is in the upper siltstone section with an average offset porosity of approximately six percent. Water saturation in the Weir is around 35% and is mainly associated with bound water found in its clay constituents.

A local geologic stratigraphic column is included in this section as Figure G-1. The Weir lies below the Greenbrier Group (Big Lime) and above the Pocono Formation (Berea). The Weir is expected to be at a depth of about 4,250' and the Weir Shale at a depth of about 4,500'. The target zone is projected to be at a depth of 4,400' with an approximate thickness of 60-80'. Exact depths will be determined once the well is drilled and geophysical logs are run. Figure G-6 is an isopach map of the Weir.

#### 3.0 CONFINING ZONES

The sedimentary sequence in the southern Appalachian Basin contains several confining zones above and below the Weir siltstone. Since the Weir is a hydrocarbon reservoir rock across the Basin, there are adequate confining zones above the formation that act as barriers to the upward movement of hydrocarbons. These confining rock layers are stratigraphic traps for the accumulating hydrocarbons as a result of lithologic changes in reduced porosity and permeability.

Figure G-1 is a geologic column indicating the formations above and below the proposed injection zone. The following is a brief description of these formations.




Figure G-1. Virginia Geologic Column

The confining zone directly above the Weir formation is the Mississippian Greenbrier Group, locally referred to as the Big Lime. This is a dense carbonate approximately 350' thick. The porosity zones in the Big Lime consist of thin oolitic channel deposits. Overall porosity within this formation, based on offset data, is around two percent. Water saturation for the Big Lime is typically near zero.

The Big Lime is projected to be at a depth of approximately 3,900' to 4,250'. A structure map for the base of the Big Lime is attached as Figure G-7.

Above the Big Lime is the Mauch Chunk Formation consisting of over 1,000' of tight sands, siltstones and limestones that act as further barriers to the upward migration of fluids.

Above the Mauch Chunk are several thousand feet of siltstone, tight sands and coal beds that also inhibit the migration of injected fluid.

There are also several confining zones below the Weir, such as the Weir shale and below that the Sunbury shale. The very low permeability of shale will inhibit the downward migration of produced fluids.

Additionally the Pocono Formation, locally known as the Berea Sandstone, consists of a fine-grained, dirty siltstone. Offset data indicate the Berea has an average porosity of about four percent. In this area, the Berea is approximately 50-60' thick. As mentioned, directly above the Berea is the Sunbury Shale. This shale is also about 60-70' thick and acts as a further barrier for downward migration of fluid. The top of the Sunbury is projected at approximately 4,850' and the top of the Berea at 4,920'. A structure map of the top of the Berea is attached at the end of this section as Figure G-8.

Based on offset well data, an approximate geologic prognosis for the proposed UIC well 900146 is:

Formation:	Depth	Interval
Formation.	KB	Ft
Base Lee Sand	2139	
Bluestone	2543	
Ravencliff	2847	551
Maxton	3398	273
Little Lime	3671	206
Big Lime	3877	370
Weir (proposed injection zone)	4247	244
Weir Shale	4491	366
Sunbury	4857	61
Berea	4918	60

Figure G-2. Geologic Prognosis for proposed UIC well 900146

#### 4.0 STRUCTURAL GEOLOGY

As stated, the site falls with the Appalachian Plateau geologic province. This region is dominated by relatively flat-lying strata typically dipping one to two degrees. There are no active tectonic forces in the region with Virginia being on a passive continental margin. There are no faults identified within the Area of Review. The few faults closest to the proposed well have minimal surficial movement. The attached cross-

section (Figure G-9) indicates no measureable offset through the proposed injection zone.

One of the main structural features in the region is the Pine Mountain Thrust Block (Figure G-3). Movement along this block occurred several hundred million years ago and was due to regional compression oriented northwest-southeast causing the block to move in a northwest direction. Crustal rupturing occurred along the eastern most extent of this block resulting in the Russell Fork Fault. This fault is a high angle, right-lateral strike-slip fault with the fault plane dipping 75° to 90° to the southwest. Overall vertical movement is slight, with numerous slickensides existing along the fault trace (Giles, 1921). There are several tear faults to the northeast of the Russell Fork Fault that occurred as the block rotated counterclockwise (Molinda and Ingram, 1989). The Little Pawpaw Fault, located about one mile west of the proposed well, is an example of a surficial tear fault. The strike of the Little Pawpaw Fault is generally N35°W (Byington, 2007). There is minimal offset associated with the fault (20' max). The Little Pawpaw Fault is located to the west of the proposed UIC well 900146 as indicated on the attached map.




Figure G-3. Regional Geology. (Adapted from Grimm, et al, 2012)
The Little Pawpaw Fault lies almost 1 mile to the west of proposed 900146.

A cross-section is attached as Figure G-9 at the end of this section. The cross-section highlights the Weir formation in four wells and transects the Little Pawpaw fault. This cross-section demonstrates there is little variability and no measurable offset

В

resulting from the fault. Figure G-10 is a cross-section of the same wells showing all formations.

#### **Local Seismic Activity**

Historically, seismic activity in Virginia has been minor. The proposed well is in a region that is not susceptible to earthquakes since there are no active forces causing crustal movement. There are no recorded earthquakes within the area of review (Figure G-5). The faults that exist were active during the Acadian and Alleghanian Orogenies approximately 375 million to 260 million years ago.

Two main concentrations of earthquakes in the state are the central Virginia seismic zone and the Giles County/New River seismic zone.




Figure G-4. Seismic Zones in Virginia (http://www.dmme.virginia.gov/dgmr/earthquakes.shtml)

The mechanism for Virginia's earthquakes has been attributed to residual stresses from the formation of the Appalachian Mountain range and the Piedmont province hundreds of millions of years ago. Most of the earthquake hypocenters are located miles below the target injection zone at depths between 3-15 miles and are not associated with faults mapped at the surface (VADMME, 2007). Figure G-5 shows the location of earthquakes in southwest Virginia. There have been no earthquakes recorded in the vicinity of proposed UIC well 900146 or along the Little Pawpaw Fault system. Also of note is that the Weir formation is the injection zone for EnerVest's existing UIC well, which is approximately one mile to the north of the proposed well and has been in operation since 2007 with no associated seismic activity.




Figure G-5. Location of seismic activity (http://www.dmme.virginia.gov/DGMR/earthquake2011.shtml)

#### 5.0 FRACTURE PRESSURES

**Target Zone:** Table G-1 summarizes the fracture pressures for the Weir formation in several offset wells within one mile of the proposed well. The average fracture gradient for these wells was 0.53 psi/ft. This results in an estimated fracture pressure of 2,332 psi at 4,400', the approximate depth of the Weir zone in the proposed well.

			Frac				
			Pressure-	Frac	ISIP-		
	State File	Company	Bottomhole	Gradient	Surface		Mid Perf
WEIR:	Number	Well#	(psi)	(psi/ft)	(psi)	ISIP fluid	Depth (ft)
Existing UIC Class IID	BU-1614	823606	2431	0.55	1890	90% foam	4410
Well within 1 mi	BU-1437	821617	2087	0.48	1304	65% foam	4332
Well within 1 mi	BU-3391	826204	2803	0.62	2425	nitrogen	4541
Well within 1 mi	BU-4608	900004	2245	0.52	1245	65% foam	4303
Well within 1 mi	BU-4554	900005	2263	0.50	296	freshwater	4540
		Average	2366	0.53			

Table G-1. Offset Fracture Pressures - Weir Formation

**Upper Confining Zone**: There are seven wells within one mile of the proposed UIC well 900146 that were completed in the overlying Big Lime zone and have fracture

pressures available. The average fracture gradient for these wells was 0.79 psi/ft. This results in an estimated fracture pressure of 3,358 psi at approximately 4,250', the base of the Big Lime, in the proposed well. The offset well data is shown in Table G-2.

								_
			Frac					
			Pressure-	Frac	ISIP-			
	State File	Company	Bottomhole	Gradient	Surface		Mid Perf	
BIG LIME:	Number	Well#	(psi)	(psi/ft)	(psi)	ISIP fluid	Depth (ft)	
Well within 1/4 mi	BU-4959	900109	2318	0.54	470	freshwater	4266	(2-stage Big Lime
		n n	2963	0.74	1217	freshwater	4030	completion)
Well within 1 mi	BU-1613	823605	3634	0.89	2717	60% foam	4100	
Well within 1 mi	BU-3349	824155	3090	0.73	2688	nitrogen	4234	
Well within 1 mi	BU-3396	826203	3267	0.78	2872	nitrogen	4222	
Well within 1 mi	BU-3391	826204	3846	0.92	3411	nitrogen	4186	
Well within 1 mi	BU-4608	900004	2895	0.75	1230	freshwater	3844	
Well within 1 mi	BU-4554	900005	4061	0.95	2219	freshwater	4253	
		Average:	3259	0.79				•

Table G-2. Offset Fracture Pressures – Big Lime

**Lower Confining Zone:** There are eight wells within one mile of the proposed UIC well 900146 well that have fracture pressures available and were completed in the underlying Berea zone. The average fracture gradient for these wells was 0.48 psi/ft. This results in an estimated fracture pressure of 2,361 psi at 4,920', the approximate top of the Berea formation, in the proposed well. The offset well data is shown in Table G-3.

			Frac				
			Pressure-	Frac	ISIP-		
	State File	Company	Bottomhole	Gradient	Surface		Mid Perf
BEREA:	Number	Well #	(psi)	(psi/ft)	(psi)	ISIP fluid	Depth (ft)
Existing UIC Class IID	BU-1614	823606	2453	0.48	2083	nitrogen	5085
Well within 1/4 mi	BU-4959	900109	2215	0.44	1880	nitrogen	4969
Well within 1 mi	BU-1437	821617	2578	0.52	1911	80% foam	4935
Well within 1 mi	BU-1379	823309	2012	0.41	1347	80% foam	4915
Well within 1 mi	BU-1626	823310	2557	0.52	2198	nitrogen	4936
Well within 1 mi	BU-1613	823605	2520	0.50	2150	nitrogen	5080
Well within 1 mi	BU-1864	824153	2211	0.45	1884	nitrogen	4844
Well within 1 mi	BU-4554	900005	2559	0.51	365	freshwater	5066
	_	Average:	2388	0.48			

Table G-3. Offset Fracture Pressures - Berea




Figure G-6. Isopach – Weir Formation




Figure G-7. Structure Map - Base of Big Lime / Top of Weir




Figure G-8. Structure Map - Top of Berea sand



#### **REFERENCES**

Byington, Craig B., 2007, The Tectonic History and Characteristics of Fracture Systems Affecting Coal Mine Roof Stability in Southwest Virginia, Virginia Division of Mineral Resources Open0File Report 07-01.

Giles, Albert W., 1921, *The Geology and Coal Resources of Dickenson County, Virginia*, Virginia Geological Survey, Bulletin No. XXI.

Grimm, Ryan P., et al, 2012, Seal evaluation and confinement screening criteria for beneficial carbon dioxide storage with enhanced coal bed methane recovery in the Pocahontas Basin, Virginia, *International Journal of Coal Geology*, V. 90-91, p. 110-125.

Molinda, M. and D.K. Ingram, 1989, Effects of structural faults on ground control in selected coal mines in southwest Virginia, *International Journal of Mining and Geological Engineering*, V. 1990, 8, p. 332-347.

Virginia Department of Mines, Minerals and Energy, Division of Geology and Mineral Resources, 2007, Earthquake Factsheet

(http://www.dmme.virginia.gov/dgmr/earthquakes.shtml), and Major Earthquake 2011 (http://www.dmme.virginia.gov/DGMR/earthquake2011.shtml).

#### 1.0 FORMATION TESTING PROGRAM

The intended injection zone in proposed UIC well 900146 is the Weir Formation. A typical suite of geophysical logs will be run after the well is drilled to establish porosity and reservoir parameters. The formation will then be stimulated and tested.

#### 2.0 MECHANICAL INTEGRITY TESTING

Proposed UIC well 900146 will be mechanically tested following the procedures as outlined below:

☐ A 2 %-inch injection tubing will be installed on a packer set just above the

- perforated interval which will be determined after the geophysical logging operations are completed.

  The annulus between the 4½-inch casing and the 2 ¾-inch injection tubing will be filled from the top of the packer to the surface with a mixture of fresh water and Nabors Completion and Production Services Packer Fluid Inhibitor at a concentration of 0.2% for fresh water. A copy of the Material Safety Data Sheet is included at the end of this attachment.
- ☐ The annulus between the 4 ½ -inch casing and the 2 ¾-inch injection tubing will be pressured to a minimum pressure of 110% of the maximum injection pressure (yet to be determined) for the minimum mechanical integrity test pressure.
- □ The pressure placed on the annulus area between the 4½ -inch casing and the 2¾-inch injection tubing will be monitored for thirty (30) minutes, minimum, and with no loss of pressure greater than 5% of the set test pressure during this time period, the test will be terminated.
- ☐ The pressure within the 2 %-inch injection tubing will be monitored for the same thirty (30) minutes as the annulus pressure noted above and with no change in the initial pressure in the 2 %-inch injection tubing during this time period, the test will be terminated.

- Should a loss of pressure or the inability to establish the desired minimum test pressure of the annulus area between the 4½-inch casing and the 2¾-inch injection tubing occur, all testing will cease. At the same time, should the pressure within the 2¾-inch injection tubing have a rapid pressure change coinciding with the annulus pressure changes between the 4½-inch casing and the 2¾-inch tubing, all testing will cease. The problem will be corrected and the testing resumed based upon the concurrence of Virginia's Division of Gas and Oil representative and the U.S. EPA Region III's representative present during the testing.
- The pressuring up and the monitoring of the annulus between  $4 \frac{1}{2}$  -inch casing and the  $2 \frac{3}{8}$ -inch injection tubing, the  $2 \frac{3}{8}$ -inch injection tubing pressure, and the duration of the test will be recorded by a pressure chart, with these pressures verified by a calibrated digital test pressure gauge.
- ☐ The mechanical integrity testing will be witnessed by representatives of the Virginia Division of Gas and Oil, the U.S. EPA Region III, and EnerVest. With the successful completion of the mechanical integrity test, the pressure chart will be signed and dated by those witnessing the test.
- $\Box$  At the conclusion of the testing, pressure will be vented from the annulus of the 4 ½ -inch casing and the 2 %-inch injection tubing.

## 3.0 NOTIFICATIONS


ENERVEST will request the presence of representatives from the Virginia Division of Gas and Oil and U.S. EPA Region III to observe and witness the mechanical integrity testing program. EnerVest will notify the respective state and federal agencies ten working days prior to commencing the testing programs.

# В

## 4.0 STIMULATION PROGRAM

The proposed hydraulic fracture stimulation on the Weir formation for proposed UIC Well 900146 is placing approximately 80,000 lbs of proppant in a carrier fluid. Only one hydraulic fracture stimulation treatment in the Weir interval is planned for proposed UIC well 900146 with no other formations being stimulated. Actual perforation depths and hydraulic fracture stimulation design with results will be provided once proposed UIC Well 900146 has been drilled and logged.

Additionally, completion information will also be submitted to "**FracFocus.org**" which is managed by the Ground Water Protection Council and Interstate Oil and Gas Compact Commission.



## WELL LOCATION PLAT NORA GRID AF-70

COMPANY Range Resources-Pine Mountain, Inc. WELL NAME AND NUMBER 900146 TRACT NO. W. C. Owens ELEVATION 1.999.97' QUADRANGLE Prater
COUNTY <u>Buchanan</u> DISTRICT <u>Prater</u> SCALE $1" = 400'$ DATE $7-30-2013$
This Plat is a new plat <u>*</u> ; an updated plat; or a final location plat
+ Denotes the location of a well on United States topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown.
' 24,000, latitude and longitude lines being represented by border lines as shown.
PRELIMINARY PLAT

Licensed Professional Engineer or Licensed Land Surveyor

# C

## 1.0 CONSTRUCTION DETAILS

Figure M-1 at the end of this attachment provides an illustration of proposed UIC well 900146's construction details. Figure M-2 shows a more detailed illustration from the bottom of the tubing to the casing TD. A review of these schematics will provide the following information:

□ The estimated total depth of the 4 ½-inch casing will be about 4,600 feet. A latch-in float insert will be run 10 feet above the casing shoe on which to land the cement wiper plug. This will leave in place a 10 foot cement plug between the wiper plug and the casing shoe in this air drilled hole and effectively seal off the wellbore.
 □ The injection string will be 2 ¾-inch, 4.7 lb/ft tubing with a 4 ½-inch x 2 ¾-inch Baker Mechanical Set Retrievable Packer (or equivalent). The packer will be set approximately 50 feet above the perforations in the Weir (depths yet to be

determined). The packer will be set on the 2 %-inch injection tubing with a joint

□ The annulus area between the 2 %-inch injection tubing and the 4 ½-inch casing from the top of the packer to the surface will be filled with a mixture of fresh water and Nabors Completion and Production Services Packer Fluid Corrosion Inhibitor at a concentration of 0.2%. A copy of the Material Safety Data Sheet is included at the end of Attachment I.

of tail pipe extending below the bottom of the packer.

- □ The annulus area between the 4½-inch casing and the 7 inch casing from the top of the cement will be filled to surface with a mixture of fresh water and Champion Technologies corrosion inhibitor Cortron RN-211 at a concentration of 0.2%.
- ☐ A casing head will be installed to seal the 2 3/8 inch injection tubing, 4 ½-inch casing, and the 7 inch casing. The casing head will have pressure monitoring connections for the pressure recorders and the pressure switches.

Drawing-2 provides a schematic layout of the proposed surface facilities, which outlines fluid handling, storage, treatment, and fail-safe controls.

## 1.0 WELL CONSTRUCTION PROCEDURE

Proposed UIC well 900146 will be a new well drilled through the Weir Formation. The well construction procedures used when this well is drilled and completed are illustrated in Figure L-1 at the end of this attachment. A review of this schematic diagram will provide the following information:

	The total estimated depth of proposed UIC well 900146 will be about 4,650 feet, as measured from the ground surface of the well.
	Approximately 44 feet of 13 %-inch conductor casing will be installed through unconsolidated sediment until solid bedrock is reached.
	Approximately 400 feet of 9 %-inch of groundwater protection casing will be installed, with this casing cemented along its entire length to the ground surface, thus sealing and protecting groundwater aquifers.
	Approximately 2,350 feet of 7-inch coal protection casing will be installed, with this casing cemented along its entire length to the ground surface protecting the coal and groundwater aquifers.
	Approximately 4,600 feet of 4 $\frac{1}{2}$ -inch production casing will be installed, with the production casing cemented from casing TD to a minimum of 100 feet up inside the 7" coal protection string, thus isolating any formation.
	The Weir Formation is estimated to be confined within the interval from approximately 4,250 feet to approximately 4,500 feet. The depleted gas zone anticipated to be perforated and stimulated for fluid injection within this interval will be determined from continuous geophysical measurements ("Logging").
П	The Weir formation will be the only zone perforated and open to the well bore.

The well's Drilling and Completion reports will be filed with the Virginia Division of Gas and Oil.

## 2.0 **DRILLING AND LOGGING**

WELL CONSTRUCTION PROCEDURES


The following logging, deviation and testing procedures will be conducted upon proposed UIC well 900146:


<b>Logging</b> – The well will be logged with the following log types:
Compensated Formation Density -Temperature - Gamma Ray – Neutron – PE Log and Dual Induction. A Cement Bond Log will be run after the production casing is set and cemented. Copies of these logs will be provided in Appendix C once the well is drilled.
<b>Deviation Checks</b> –A deviation survey will be performed from 200 feet to the lowest minable coal seam penetrated at intervals no greater than 200 feet. Results of the deviation survey will be provided in the well Drilling Report for proposed UIC well 900146 and will be submitted once the well is drilled.
<b>Drilling</b> - Drilling reports will be provided once the proposed UIC well 900146 is drilled.
<b>Pressure Testing</b> - A casing pressure test will be performed on the $4\%$ -inch production casing to a surface pressure of 2,200 psi prior to the stimulation of the Weir.
Coring Program – No formation coring is anticipated.
<b>Annulus Fluid</b> – The well will be drilled using air drilling methods. No formation fluids are anticipated to be encountered once the intermediate 7 inch coal protection casing is set.


## 3.0 CEMENT BOND

Cement fill up will be calculated from the well TD to a minimum of 100 feet up inside the 7" intermediate coal protection casing with 20% excess cement.

After 72 hours, a Cement Bond Log will be run from the 4½-inch production casing total depth to a minimum of 300 feet above the observed top of cement to verify the isolation of the formation.







**ATTACHMENT** 



## 1.0 OPERATIONAL INFORMATION

Proposed UIC well 900146 will only accept treated produced fluids from EnerVest operations in Virginia. The proposed well will utilize existing treatment facilities associated with EnerVest existing permitted UIC VAS2D950BBUC as outlined in approved original permit.

## 2.0 FLOW RATES

The maximum injection fluid volume is 56,000 barrels per month for EnerVest existing UIC Permit VAS2D950BBUC. The maximum monthly injection fluid volume in the proposed UIC well 900146 will be determined after the well has been completed and tested.

## 3.0 INJECTION PRESSURES

The maximum injection pressure is 1,512 psig (80% of 1890 psig) for EnerVest's existing UIC Permit VAS2D950BBUC, which is located less than one mile from the proposed well. The maximum injection pressure for proposed UIC well 900146 will be determined once the well is completed. However, until such time that the well is completed and a maximum surface pressure can be calculated, any post completion injection work will not exceed 1,512 psig. The actual Pmax for fluid injection will be based on site specific completion data after the well is completed.

## 4.0 INJECTION FLUID

Produced fluids will be properly stored at EnerVest operated facilities in Virginia. At frequent intervals, an enclosed tank truck will remove and transport the collected fluids to the existing UIC well's treatment and injection system located at EnerVest UIC Permit VAS2D950BBUC. The treatment and well injection system is outlined in original approved permit. After the fluid is treated, it will then be pumped from the UIC Permit VAS2D950BBUC treatment facilities for injection into the planned UIC well 900146.

The proposed UIC well 900146 will only accept fluids produced from EnerVest operations located in Virginia. Since the fluids to be injected in the proposed well will utilize the same treatment facility as EnerVest's existing UIC well, the physical and chemical characteristics will be similar to what is currently being injected.

## OPERATION INFORMATION

**ATTACHMENT** 

D

Sampling results for the existing UIC Permit VAS2D950BBUC over the past three years is summarized in Table 1.

All samples were collected and tested following set EPA standards:

- □ Sample was collected in first-use, certified clean sample containers with the required preservants.
- ☐ The collected sample containers were labeled, chain-of-custody completed, placed in a cooler, maintained at 5°C, and hand-carried to the lab.



EMI No. 51776

## ENVIRONMENTAL MONITORING, INCORPORATED

ENVIRONMENTAL CONSULTANTS ▲ ANALYTICAL LABORATORIES 5730 INDUSTRIAL PARK RD. ▲ NORTON, VIRGINIA 24273 ▲ 276/679-6544

## **Certificate of Analysis**

Page: 1 of 2

Client Name: ENERVEST OPERATING, LLC

Address: 408 W MAIN STREET

Site Description: INJECTION WELL MONITORING

Sample Identification: 3096.160 HAYSI 23606

ABINGDON, VA

24210

Report Date: 02/16/2023

Lab Sample No.: 1933461

Client No.: 3096

EMI Project No.: 160
Date Received: 01/30/2023

Date Collected: 01/30/2023 Time Collected: 1142

Sample Matrix: AQ

Collected By: BAKER, BRANDON

Flow if Available (GPM): Depth if Available (Ft): Temp. if Available (C): 7.0 Analysis Package Code: BF4 Type of Sample: Grab

**Case Narrative:** 

The analysis of EMI sample number 1933461 was obtained under standard operating conditions unless otherwise indicated. For QA Flag descriptions see attachment.

## **Summary of Analytical Results**

Method Parameter	Sample Result	Units	MDL	RL	Date Analyzed	Time Analyzed	Analyst
EPA 200.7 Rev 4.4 1994							
Barium, Total	1479	mg/l	0.100	3.00	2/2/2023	1358	AWM
Iron, Total	29.0	mg/l	0.800	5.00	2/2/2023	1358	AWM
Magnesium, Total	1480	mg/l	5.00	50.0	2/2/2023	1358	AWM
Manganese, Total	1.66 J	mg/l	0.500	5.00	2/2/2023	1358	AWM
Sodium, Total	28780	mg/l	7.40	50.0	2/2/2023	1358	AWM
SM 2320B-4c-2011							
Alkalinity	78.1	mg/l CaCO3	4.00	4.00	1/31/2023	855	THR
SM 2340 B-2011							
Hardness, Total (by Calculation)	26250	mg/l CaCO3	0.363	1.00	2/2/2023	1726	PGM
SM 2510B-2011							
Conductivity	212100	umhos/cm	1000	1000	1/31/2023	1007	KLM
SM 2540 C-2015							
Total Dissolved Solids	109765 DC SV	mg/l	25.0	25.0	1/31/2023	706	KLM
SM 2710 F-2011							
Specific Gravity (Not NELAP) (Not WV)	1.07				1/31/2023	1400	KBL
SM 4500 CI B-2011							
Chloride	69978	mg/l	796	1000	2/2/2023	1156	KBL
SM 4500 S2-F-2011							
Sulfide	BDL	mg/l	1.37	2.00	2/2/2023	1435	THR
SM 4500-H+B-2011							
pH (Not NELAP) (Not WV)	6.30	STD			1/30/2023	1145	FLD



## ENVIRONMENTAL MONITORING, INCORPORATED

ENVIRONMENTAL CONSULTANTS ▲ ANALYTICAL LABORATORIES 5730 INDUSTRIAL PARK RD. ▲ NORTON, VIRGINIA 24273 ▲ 276/679-6544

## **Certificate of Analysis**

02/16/2023

Page: 2 of 2

EMI No. 51776 Sample Identification: 3096.160 HAYSI 23606

Lab Sample No.: 1933461

## **Summary of Analytical Results Summary of Analytical Results - Continued**

Method Parameter	Sample Result	Units	MDL	RL	Date Analyzed	Time Analyzed	Analyst
SM 4500-O G-2011 Dissolved Oxygen (Not NELAP) (Not WV)	2.46	mg/l			1/30/2023	1142	FLD

**END OF EMI SAMPLE NUMBER 1933461 CERTIFICATE** 

To the best of our knowledge and belief, the collection, preservation, and analysis of all parameters represented by this report have been determined to comply the requirements as specified in 40 CFR, Part 136 unless indicated otherwise. This report may not be reproduced except in full, without the written approval of the laboratory.



VA Laboratory ID#: 460038 WV Laboratory ID#: 105 KY Laboratory ID#: 98012 EPA Laboratory ID#: VA00010

The release of this report is authorized by:

R. J. Porter **Technical Director** 



2790 Whitten Road, Memphis, TN 38133 Main 901.213.2400 ° Fax 901.213.2440 www.waypointanalytical.com

25447

Environmental Monitoring Inc. Ms. Missy Collins 5730 Industrial Park Road Norton , VA 24273 Project #:3096.160

 Report Date : 02/13/2023

 Information :
 Received : 02/03/2023

Comio Cook

Report Number: 23-034-0157 REPORT OF ANALYSIS

Connie Cook Project Manager

Lab No : 82666 Matrix: Aqueous

Sample ID : 1933461- Haysi Sampled: 1/30/2023 11:42

Test	Results	Units	MQL	DF	Date / Time Analyzed	Ву	Analytical Method
TOC	11.2	mg/L	10.0	10	02/11/23 09:18	CJD	5310C-2014

Qualifiers/ Definitions

DF Dilution Factor

MQL

Method Quantitation Limit



## QA\_FLAGS and Definitions

QA_FLAGS	and Definitions
CODE	DESCRIPTION
AB	Analyte found in Method Blank
BDL	Below detection limit
BQ	Batch QC is outside acceptable range
DC	Duplicate did not meet method criteria; method process in control
EV	Estimated value; outside of calibration range
FC	Failure to comply with current SOP
FLD	Field Technician
HE	Parameter holding time has been exceeded
IV	Insufficient sample volume
J	Estimated value below Report Limit
MI	Matrix Interference - Final result may not be representative
MR	Multiple runs were used to determine the result (an Average)
MSF	Matrix Spike Failure - analyte concentration is disproportionate to spike level; method in control
NA	Result for this analyte is not available
Р	Sample container not properly preserved
QR	Additional quality evaluation performed
R	Sample results rejected due to deficiencies in QC or method performance
SV	Volume indicated by method not used
T	Possible toxicity which is expected to influence reported value
XI	Matrix required alternate internal reference standard

# SAMPLE LOG SHEET AND CHAIN OF CUSTODY ENVIRONMENTAL MONITORING, INC 5730 INDUSTRIAL PARK RD \* NORTON VA 24273 \* 276-679-6544

PROJECT: Enervest Injection Well Project

-30-23 ROUTE #: 3096.160 DATE SAMPLED: SAMPLED BY: Brandon Baker EMP. ID# 3397

				9	
COMMENTS				P.O. DUP : 2.10	
ANAL CODE	BF4) ND	(BF4/ND	(BF4) ND	(BF4) ND	
COFOR CODE	В	B	82	80	
APP CODE	1	_	7	~	
D.O.	4.04	2.46	1 46	2.12	
FIELD	0.9 -	6.3	<u>ج</u> ف	5.8	
7.0 RB	1	7.1	١	11	
dmoT\Hq quQ	,	13	į,	1.8	
PH	10:48	1:45	09:39	64:80	
3 PT pH CAL	ľ	ļ	1	7	
TEMP °C	\$	1		8	
E)	7	42	30	7	
TIME	h 01	11:42	8	98:4	
LONA FINE	V 10.4	=	1 09 30	V 08:44	
	6 10.4	= \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	° / 8	φ:80 / °	
BINO	CANE CREEK 6 / 10: 4	HAYSI 23606 6 / 11:	P-143-T 6 7 09:	>	
BIAO <sup>2</sup>	120. CANE CREEK 6 V   0. 4	ر ر	° /	<u>&gt;</u>	124
HIAO' 'AO' COAL 'SWALE TD' 'SWALE	CAN	HAYSI 23606 6	P-143-T 6	<b>&gt;</b> 171 6	124

preservation were verified to be All samples requiring pH

as indicated on COC by ML Time: /833 Date: 1/36/23

\* D.O. Meter #1336 calibrated 1/30/23 by DWP

Ō
ž
I
₾_
2
V.
片
45
9
=
K.
2
$\geq$
$\mathbf{\alpha}$
Ш
TETER MORING OF SAMPLING
₹
111
Ξ
⋖
2
<u>m</u>
Į
Ϋ́
O
0
<b>-</b>
Щ
۳
VILL NEED
$\exists$
₹
>
O
လ
ź
YGEN,
C
$\succeq$
×
SSOLVED OXYGEN, SO WILL NEED TO CALIBRATE ME'
Ω
_VED
ō
Ś
<u> </u>
S
⋖
I
LSO H
Ś
ᆛ
4
THIS AL
I
$\vdash$

1277	
EMI pH Meter #_	
23	•
BIN#	

(1) 32 oz. NAOH / ZN ACE (3) 40 ML VOA'S H3PO4

(1) 1/2 gallon plain (1) 16 oz. HNO3

Bottle list:

CHECKED BY: BEB Number of Containers this COC#\_

COOLER TEMP Relinquished by:\_

S. CR

130, 23 Time: 13:31 Received by 6 Time: 1831 Received Art. 130127 Date: Relinquished by. 146 Cocert

COLOR CODES A. Natural APPEARANCE CODES

Clear
 Slighlly Turbid
 Moderately Turbid
 Very Turbid
 Very Turbid
 Visible Suspended Matter

B. Brown to Red C. Gray D. Black E. Other

Page 1 of 1 Updated 08/05/21



## ENVIRONMENTAL MONITORING, INCORPORATED

ENVIRONMENTAL CONSULTANTS ▲ ANALYTICAL LABORATORIES 5730 INDUSTRIAL PARK RD. ▲ NORTON, VIRGINIA 24273 ▲ 276/679-6544

## **Certificate of Analysis**

Page: 1 of 1

Client Name: ENERVEST OPERATING, LLC

Site Description: INJECTION WELL MONITORING

Address: 408 W MAIN STREET

Sample Identification: HAYSI 23606

ABINGDON, VA

24210

Report Date: 02/23/21 Lab Sample No.: 1855572

Client No.:

EMI Project No.:

Date Collected: 01/25/21

Time Collected:

Sample Matrix: AO

Collected By: BAKER, BRANDON

Parameter	Sample Result	Units	MDL	RL	Method	Date Analyzed	Time Analyzed	Analyst
Alkalinity	87.4	mg/l CaCO3	4.00	4.00	SM 2320B-4c-2011	1/28/2021	819	THR
Chloride	62980	mg/l	1000	1000	SM 4500 Cl B-2011	1/29/2021	1522	AWM
Conductivity	199700	umhos/cm	1000	1000	SM 2510B-2011	2/7/2021	1209	RSV
Dissolved Oxygen (Not NELAP)	1.21	mg/l			SM 4500-O G-2011	1/25/2021	910	FLD
Hardness, Total	23000	mg/l CaCO3	200	200	SM 2340 C-2011	1/27/2021	1308	AWM
pH (Not NELAP)	6.00	STD			SM 4500-H+B-2011	1/25/2021	910	FLD
Specific Gravity (Not NELAP)	1.06				SM 2710 F-2011	2/1/2021	1151	JLW
Sulfide	BDL	mg/l	1.00	1.00	SM 4500 S2-F-2011	1/28/2021	1457	THR
Total Dissolved Solids	89025 SV	mg/l	1.00	1.00	SM 2540 C-2011	1/27/2021	1515	THR
Barium, Total	1218	mg/l	0.100	3.00	EPA 200.7	2/3/2021	1255	AWM
Iron, Total	42.0	mg/l	0.080	0.500	EPA 200.7	1/26/2021	1813	AWM
Magnesium, Total	1260	mg/l	5.00	50.0	EPA 200.7	1/27/2021	1419	AWM
Manganese, Total	1.77	mg/l	0.050	0.500	EPA 200.7	1/26/2021	1813	AWM
Sodium, Total	26230	mg/l	7.40	50.0	EPA 200.7	1/27/2021	1419	AWM

To the best of our knowledge and belief, the collection, preservation, and analysis of all parameters represented by this report have been determined to comply the requirements as specified in 40 CFR, Part 136. This report may not be reproduced except in full, without the written approval of the laboratory.



VA Laboratory ID#: 460038 WV Laboratory ID#: 105 KY Laboratory ID#: 98012 EPA Laboratory ID#: VA00010

The release of this report is authorized by

R. J. Porter **Technical Director** 

Flow if Avaliable (GPM): Temp. if Available (C): 11.0 Depth if Available (Ft): Analysis Package Code: BF3

Rev-06-02-17p

Type of Sample: Grab BDL = Below Detection Limit

FLD = Field Technician MR = Multiple analytical runs were used for this result IV = Flag indicates Insufficient Sample Volume

SV = Sample volume indicated by method not used AB = Analyte found in Method Blank

MSF = Matirx Spike Failure - Method in Control EV = Estimated Value: Outside of calibration range J = Flag indicates estimated value below Report Limit

T = Results indicate possible toxicity which is expected to influence reported value.

NA = A result for this analyte is not available

MI = Matrix Interference - Final result may not be representative.


BQ = Batch QC Outside Acceptable Range

HE = Parameter Hold Time Exceeded

FC = Failure to Comply Current SOP R = Sample results rejected because of gross deficiencies in QC or method performance

DC = Duplicate did not meet method criteria, method process in control

P = Sample was not properly preserved for this parameter.



# SAMPLE LOG SHEET & CHAIN OF CUSTODY



CLIENT:

OR RETURNED TO CLIENT OR months SAMPLES WILL BE DISPOSED EMI's TERMS & CONDITIONS DUP D.0 = 1.20 OF IN ACCORDANCE WITH if No, Anomaly Report DUP OH/TEMP = 6.0/ ON EMI# 51776 Sample Acceptance / Condition Checklist Report to be sent (if different than customer information): (SOP61) followed Purchase Order No. REMARKS Yes or No Required. Archive for STATE/ZIP PHONE ( FAX ( Preservation Checked By Date: 个 BILLING ADDRESS: <del>ر</del>ة. 238 0 1,27 1 141 Wal \* PARAMETER (ANALYSIS REQUESTED) 7 'n NAME: <u>ට</u> ල 5.9 5.9 HO Ś Other Suifide 304 NZ Lawson × X X Received By (sign, 'os'h ENErVes+ ЮН Unknown M etals °ОNН X Son 125/E 863 1803 2,9 > 9 Х COC DV: N Regular (15 Working Days) \*CONTACT:\_ Ali|samples|requiling Poison B 1111 B B AB Special Instructions / QC Requirements & Comments UB GO(ER Relinquished by (sign) 'DATE 'TIME COLLECTED COLLECTED 1-25-21 10:02 1-25-21 10:59 SECURIT WA 51776/18 SSS72/Hays; 23606 11-25-21/09:10 1-25-21/11:32 15/1 2 Day 3 Day 5 Day 10 Day (Working Days) (Working Days) Skin Irritant MON HOLLY 9 Baker ENVIRONMENTAL MONITORING, INCORPORATED ENVIRONMENTAL CONSULTANTS ▲ ANALYTICAL LABORATORIES 5730 Industrial Park Rd. ▲ Norton, Virginia 24273 ▲ 276-679-6594 Dat brese Lab Cooler Flammable Additional Cost May Apply – Any TAT Not Specified Will Be Regular Lane Creek 535517 Brandon Received By (sign) EMI PROJECT MANAGER CUSTOMER SAMPLE IDENTIFICATION DWP 7. 202 Non Hazard -25-21 14:19 Date/Time Œ INjection COLLECTOR(S) SIGNATURE(S)\_ 3096 573 514 575 Hazard Information: (circle) TURN-AROUND (circle): COLLECTED BY (print) EMI PROJECT NO.: Relinquished by (sign) CLIENT PROJ. NO. 51778 61779 5177 SITE ID:

1277 Additional Hamarks PH Meter #

FAX (

STATE/ZIP

ADDRESS:

CITY

Temperature of Cooler upon Receipt by Lab

Ł

B

No. of Containers\_

OTHER

PERSONAL DELIVERY

EMI PICKUP

"METHOD OF SHIPMENT TO LAB (GLONE)
US MAIL UPS FED. EX. EMI-DIRECT

# NB

**ATTACHMENT** 

# D

## 1.0 INJECTION PROCEDURES

The production fluid treatment facility located at the UIC Class II-D well, Permit VAS2D950BBUC is designed to serve as a central produced fluid treatment facility, having the capacity to furnish treated produced fluids for injection in UIC Permit VAS2D950BBUC and proposed UIC Well 900146. The produced fluids to be injected into the wells will be transported to the treatment facility by both tank truck and fluid pipeline.

The injection procedures are graphically illustrated by Drawing-2. A review of the drawing will identify the following (minimum) injection procedures:

- □ Starting with the arrival of the tank truck and/or pipeline pumped fluids at the planned treatment facilities at UIC Permit VAS2D950BBUC, the collected produced fluids will be pumped from the tank truck or from the fluid pipeline to the primary holding/settling tanks. From the primary holding/settling tanks, the fluids will flow into two secondary settling/holding tanks. These four tanks will have a minimum capacity of 250 barrels ("bbl") per tank. Should water volumes increase, two future secondary holding/settling tanks are proposed.
- □ By gravity, the fluid will flow from the primary settling/holding tanks to the secondary holding/settling tanks. From the secondary holding/settling tanks, the fluid is pumped through the treatment system and stored in the treated fluid storage tank.
- ☐ The treatment system will consist of in-line filters to remove suspended materials. After filtering, the fluids will be injected with an oxygen scavenger chemical, a biocide and a scale inhibitor before flowing to the treated fluid storage tank(s). MSDS sheets are located at the end of this section.
- $\hfill \Box$  A second treated fluid storage tank will be installed if necessary.
- ☐ From the treated fluid storage tank, the fluids will be pumped (proposed Pump B) into a suction fluid manifold and from the proposed suction manifold the fluid will be pumped in UIC Permit VAS2D950BBUC and/or proposed UIC well

D

900146 through the 2 %-inch injection tubing by positive displacement pumps. The discharge of the injection pumps will be metered

to record the injection volumes. In addition, the fluid volume injected into proposed UIC well 900146 will be metered at the well site. Simultaneously, at the injection wellheads, the injection pressures on the 2 %-inch injection tubing will be measured and recorded, the annulus pressures between the 2 %-inch injection tubing and 4 ½-inch casing will be measured and recorded, and the annulus pressures between the 4 ½-inch and 7-inch casing will also be measured and recorded.

## 2.0 INJECTION FACILITIES

Drawing-2 provides a schematic which indicates equipment, pumps, storage tank capacities, pressure and volume monitoring, safety shut-down, and data recorders. Further, this drawing defines the interaction and connections between these various components of the treatment facility at UIC Permit VAS2D950BBUC.

The UIC Permit VAS2D950BBUC well site & injection facility is fenced in with a locked chain link security fence for site security. In addition a facility camera system is also installed and monitors the site continuously. The truck transfer valve is locked at all times except during authorized fluid transfer to the site. Warning lights are also located at the main gate and transfer site so that the transfer truck driver(s) and site operator know when the system is in an alarm condition and not available for operation without supervisory authorization.

The proposed pipeline to 900146 will have an automatic shut off valve also entirely within the UIC Permit VAS2D950BBUC well site and injection facility secure area. The 900146 well site and associated equipment will also be enclosed within a locked chain link security fence. An additional automatic pipeline shut off valve will also be located in the 900146 security site as an additional safety feature.

ATTACHMENT

## 1.0 MONITORING PROGRAM

Drawing-2 provides a schematic layout of the proposed monitoring program for the receipt, treatment and injection of the produced fluid. A review of this monitoring program will, at a minimum, provide the following:

Pump controls (low and high pressures) at treatment facility and proposed UIC well 900146 well head
Flow metering
Well casing and injection tubing pressure controls (low and high pressures) at proposed UIC well 900146
Continuous recording at all pressure and flow monitoring points at proposed UIC well 900146 and UIC permit VAS2D950BBUC
At a minimum, the pipeline will be visually inspected annually

## 2.0 MONITORING WELLS

No monitoring wells are proposed or planned in conjunction with this application for proposed UIC well 900146. However, the pressures between the 7-inch and 4 1/2-inch casings and 4 1/2-inch casing and 2 3/8-inch injection tubing at proposed UIC well 900146 will be continuously monitored, with pressure and injection flow recorded. Should a problem exist, these two areas should show an immediate pressure fluctuation, thus alerting ENERVEST OPERATING, LLC that a problem exists and corrective action is needed.



### 1.0 **WELL FAILURES**

The operation of the proposed UIC well 900146 will be continuously monitored by recording charts. This monitoring will consist of:

Continuous pressure recordings of the area between the 7-inch and 4 ½-inch
casings (fresh water and inhibitor area).
Continuous pressure recordings of the area between the 4 $\frac{1}{2}$ -inch casing and 2
%-inch tubing (fresh water and inhibitor area).
Continuous recordings of the injection pressure and flow

Continuous recordings of the injection pressure and flow.

This monitoring data will provide historical operation records for the well and should allow for detection of variances or failures within the well. Further, the well and the injection facilities will be equipped with fail-safe devices that will shutdown the operations for the lack of fluid, high pressure, and high flow.

Should failures or shut-ins happen, all injection operations will be stopped immediately. No additional fluid will be trucked and/or pumped to UIC well permit VAS2D950BBUC and the proposed UIC well 900146 sites. If the problem cannot be readily corrected or immediate danger exists that migration will occur, the following will be undertaken:

Reduce and stabilize the fluid pressure in the well. Fluid may be returned to
surface tanks for proper disposal at other permitted locations.

With the fluid pressure stabilized, the well will be plugged as outlined by
Attachment E.

### 2.0 MONITORING

The proposed UIC well 900146 pressures will be continuously monitored at three points and the injection fluid flows will be continuously monitored at two points. The pressures and flow rates will also be recorded.

The	10 K 0 0 0 1 1 K 0		
rne	pressure	points	are:

- □ Injection pressure measured at the 2 %-inch injection tubing at the wellhead.
- $\Box$  The area (annulus) between the outside of the 2 %-inch injection tubing and the inside of the 4 ½-inch casing. The pressure measurement point will be at the wellhead.
- $\Box$  The area (annulus) between the outside of the 4½-inch casing and inside of the 7-inch casing. The pressure measurement point will be at the wellhead.

## The injection fluid flow points are:

- ☐ The injection flow will be measured as the fluid is pumped from the treated fluid suction manifold through the pump and into the proposed pipeline. The measurement point is on the discharge side of the pump.
- $\Box$  The injection flow will also be measured as the fluid flows from the pipeline to the well's 2 %-inch injection tubing. The measurement point is at the wellhead.

As shown by Drawing-2, no relief valves will be used to control the well's operations. Pressure switches and flow meters will be used to control the injection at the well head and to monitor the well's injection activities and operations.

## The following will occur at proposed UIC well 900146:

- ☐ If any abnormal pressure is recorded by pressure switch PC-6 (7-inch and 4 ½-inch annulus), the control valve on the injection fluid pipeline will close and alarm. The injections will not re-start automatically but must be manually restarted after the problem is corrected.
- ☐ If any abnormal pressure is recorded by pressure switch PC-(7-inch and 4 ½-inch annulus), the pipeline control valves will close and alarm. The system will not re-start automatically, but must be manually re-started after the problem is corrected.

D

Pressure switch PC-6 monitors the pressures between the annulus of the 4 $\frac{1}{2}$ -inch casing and the 7-inch casing. This pressure switch will be set at 2 psig high pressure shutdown and -2 psig (vacuum) low pressure shutdown.
Pressure switch PC-5 monitors the pressure between the annulus of the 2 $\%$ -inch injection tubing and the 4 $\%$ -inch casing. This pressure switch will be set at 2 psig high pressure shutdown and for -2 psig (vacuum) low pressure shutdown.
Pressure switch PC-4 and flow control switches FC-2 and FC-3 control the treated injection fluid pump (C-2) and the suction manifold pump (B-1). Pressure switch PC-4 will be set at the maximum allowable operating pressure (high pressure setting) to be determined.
Pressure switch PC-4 and flow control switches (flow meter contacts) FC-2 & FC-3 will control the injection into proposed UIC Well 900146. Pressure switch PC-4 will be set at the maximum allowable operating pressure to be determined and flow control switch FC-2 & FC-3 will be set at the maximum daily injection flow.
If the maximum allowable injection pressure is reached and recorded by pressure switch PC-4, the control valves on the injection pumps will close and alarm. A one-hour period will be programmed into pressure switch PC-4. If the maximum pressure has subsided to below the maximum allowable injection pressure, then the control valves will open and injection resumed. If the pressure has not subsided then the control valves will remain closed and no injection will occur. At this point, the problem will be corrected before injection resumes.
If the maximum allowable daily injection volume or flow has occurred, flow switch FC-2 and FC-3 will close the control valves and alarm, with no further injection. Upon closing of the control valve, the system will be manually checked before pumping/injection is resumed.

## MONITORING PROGRAM - WELL FAILURES

**ATTACHMENT** 

D

If the injection fluid pressure reaches the maximum allowable injection pressure at the wellhead of proposed UIC well 900146, the high pressure shutdown will close the control valves and alarm. After one hour, if the wellhead pressure is less than maximum allowable injection pressure, the control valves will re-open and injection will resume. If after one hour, the wellhead pressure is still at the maximum allowable injection pressure, the system will not re-start automatically, but must be manually re-started after the problem is corrected. If at any time the injection flow reaches the maximum allowable injection rate, the proposed UIC well 900146 meters and the flow control switches (FC-2, or FC-3, or PC-4) will shut down the injection pump and alarm. The system will not re-start automatically, but must be manually re-started after the problem is corrected.

**≎EPA** 

United States Environmental Protection Agency

# WELL REWORK RECORD, PLUGGING AND ABANDONMENT PLAN,

B 111 1 1 1			ING A	NU ABA	MDONME	NI AF	FIDAVII	
EnerVest Operation 809 Happy Valley Clintwood, VA 24:	<sup>r</sup> Drive	Email						
Dameit on EDA ID Nov		48111						
Permit or EPA ID Nui		API Numbe	er			Full Well 900146		
VAS2D955BBUC						900146	3000	
State Virginia				Buchanan				
Locate well in two di	irections from nearest lines of	quarter sect	ion and dri	lling unit	Latitude 37	11 38 N		
Surface Location								
1/4 of	1/4 of Section	Township	Ra	nge	Longitude 82	12 15 W		
	ft. from (N/S) Line of quarter section ft. from (E/W) Line of quarter section.							
Well Class	Timing of Action (pick one)						Type of Action	pick one)
Class I	✓ Notice Prior to Work						Well Rewor	k
✓ Class II	Date Expected to Comme	nce					. A Blugging a	nd Abandonment
Class III	_					l l	✓ Plugging a	iu Abandonnient
Class V	Report After Work			7			Conversion	to a Non-Injection Well
	Date Work Ended							
	escription of the work planned as necessary. <u>Please see the i</u>						ort that meets th	e requirements.
See Original (atta	ached)							
See Original (atta	acrieu)							
			Cert	ification				
	the penalty of law that I have p							
	ed that, based on my inquiry of true, accurate, and complete.							
the possibility	of fine and imprisonment. (Re	f. 40 CFR § 1	44.32)	·		-		
Authorized Signatory	y and Official Title <i>(Please typ</i>	e or print)	Signature	)				Date Signed
Kevin Miller, VP-	Land		4.:	$\sim$	` MQ			12/04/2024
			reut	ny.m.	LUBER)			
			l					

## **INSTRUCTIONS FOR FORM 7520-19**

This form replaces forms 7520-12 and 7520-14. Use this form only when work is planned or has occurred that affects the well's construction or operation as an injection well, including work on the casing, tubing or packer (or for shallow Class V wells, the subsurface fluid emplacement network). Use one form per injection well. Note: operators closing Class V wells should use Form 7520-17.

**PERMITTEE NAME, ADDRESS, PHONE AND/OR EMAIL**: Enter the name and street address, city/town, state, and ZIP code of the permittee. Also provide an email address (if available) and/or a phone number.

PERMIT OR EPA ID NUMBER: Enter the well identification number or permit number assigned to the well by the EPA or the permitting authority.

**API NUMBER**: Enter the number assigned by the local jurisdiction (usually a State Oil and Gas Agency) using the American Petroleum Institute standard numbering system.

**FULL WELL NAME:** Enter the full name of the well or project.

Enter the **STATE** and **COUNTY** where the well is located. For States that do not have counties, use the name of that State's equivalent jurisdiction at a more local level.

**WELL LOCATION:** Fill in the complete township, range, and section to the nearest quarter-quarter section. A township is north or south of the baseline, and a range is east or west of the principal meridian (e.g., T12N, R34W). Also include the distance, in feet, from the nearest north or south line and nearest east or west line of the quarter-section. Also, enter the **latitude** and **longitude** of the well in decimal degrees, to five or six places if possible; be sure to include a negative sign for the longitude of a well in the Western Hemisphere and a negative sign for the latitude of a well in the Southern Hemisphere.

Enter the WELL CLASS, i.e., the class of injection well as defined in 40 CFR 144.6.

**TIMING OF THE ACTION:** Check *Notice prior to work* if the activity has not yet occurred (i.e., is planned). Check *Report after work* if the activity described has already occurred. As appropriate, include the date the activity is expected to start or the date the activity was completed. (Note this may not be available, e.g., for a plugging plan submitted with a permit application.)

**TYPE OF ACTION:** Check the appropriate box to describe the kind of activity being reported. Check *Well Rework* for work that was/will be performed on the well after it has already been in operation as an injection well. Check *Plugging and Abandonment* to report on plans for or descriptions of final closure/plugging after use as an injection well. Check *Conversion to a Non-Injection Well* if the well is to be converted to something other than an injection well.

Provide a **NARRATIVE DESCRIPTION** of the work planned to be performed, or that was performed. The narrative should include a description of the main procedures planned or that occurred during the work activity. A service company report, daily report, or similar document may be attached if it includes all the requested information and is clear and legible.

For well reworks, include the following information: The reason for the well rework; depths of activity; type of activity; changes to injection well configuration, well casing, or cement behind casing; any plug added to the well and its depth; any newly drilled interval and its depth; method(s) to demonstrate that the well has mechanical integrity (as applicable); and any deviations from the approved rework plan (as applicable).

For a well plugging plan, include the following information: Reason for the well plugging; number of plugs placed, and their depths; materials used as plugs (e.g., cast iron bridge plug, cement, cement retainer); method to set plugs; and wait-on-cement times, if any. Also provide one or more cost estimates from an independent firm in the business of plugging and abandoning wells to plug the well as described in the plan.

For well plugging affidavit, include the following information: Reason for the well plugging; the method of plug emplacement; a tabular description of casing and tubing after plugging (i.e., size, weight, depth to be put in the well/left in the well, and hole size); a tabular description of plugs placed (i.e., depth of each plug, hole size, amount of cement, slurry weight and volume, calculated and measured top of the plug, materials used as plugs (e.g., cast iron bridge plug, cement, cement retainer)); a tabular description of all open hole and/or perforated intervals and intervals where casing will be varied (if any); wait-on-cement times, if any; and any deviations from the approved plugging plan (if applicable).

For conversion to a non-injection well, include the following information: Depths of activity; type of activity; changes to injection well configuration, well casing, or cement behind casing; any plug added to the well and its depth; any newly drilled interval and its depth; depths of new perforations; and method(s) to demonstrate that the well has mechanical integrity (as applicable).

For all of the above activities, also include the following: a well sketch depicting the work, results of well tests/logging performed, service company tickets, and any other available information demonstrating how the work was/is to be performed. Also, specify whether depths are below ground surface, relative to Kelly bushing, etc.

**CERTIFICATION:** This form must be signed and dated by either: a responsible corporate officer for a corporation, by a general partner for a partnership, by the proprietor of a sole proprietorship, or by a principal executive or ranking elected official for a public agency. While reports or other information developed by contractors or service companies may be attached, this form must be signed by a responsible entity as described at 40 CFR 144.32.

PAPERWORK REDUCTION ACT NOTICE: The public reporting and recordkeeping burden for this collection of information is estimated to average between 6.0 and 7.9 hours per response, depending on the injection well class. Burden means the total time, effort, or financial resource expended by persons to generate, maintain, retain, or disclose or provide information to or for a Federal Agency. This includes the time needed to review instructions; develop, acquire, install, and utilize technology and systems for the purposes of collecting, validating, and verifying information, processing and maintaining information, and disclosing and providing information; adjust the existing ways to comply with any previously applicable instructions and requirements; train personnel to be able to respond to the collection of information; search data sources; complete and review the collection of information; and, transmit or otherwise disclose the information. An agency may not conduct or sponsor, and a person is not required to respond to, a collection of information unless it displays a currently valid OMB control number. Send comments on the Agency's need for this information, the accuracy of the provided burden estimates, and any suggested methods for minimizing respondent burden, including the use of automated collection techniques to Director, Collection Strategies Division, U.S. Environmental Protection Agency (2822), 1200 Pennsylvania Ave., NW., Washington, D.C. 20460. Include the OMB control number in any correspondence. Do not send the completed forms to this address.



## 1.0 PLUGGING AND ABANDONMENT PLAN

The plugging and abandonment plan to be used to abandon proposed UIC well 900146 is illustrated by Figure Q-1 at the end of this attachment. A review of this schematic along with the following procedure outlines the plugging plan:

Move in service rig and cement service company.
Rig up cement service company and pump Class A cement down the injection tubing for Plug #1. Mix and pump enough cement to cover from injection perforations back to the bottom of tubing plus 100% excess to squeeze and shut off the formation perforations.
Displace cement out the bottom of the injection tubing.
Let cement set until adequate compressive strength has been obtained to allow completion of Plug #1.
Release the packer and pull tubing and packer out of the hole. If injection tubing cannot be pulled, cut the tubing off just above the packer and pull the tubing. Run back in hole with tubing only.
Using the tubing, finish Plug #1 by spotting 100 foot of Class A cement on top of the existing cement that was used to shut off the perforations.
Using the tubing, fill the 4 $\frac{1}{2}$ -inch production casing with bentonite gel from top of Plug #1 to 100 foot below the top of the cement in the 4 $\frac{1}{2}$ inch x 7 inch annulus as verified by the cement bond log. Pull the tubing out of the hole.
Run in the hole with wireline tools and cut off the 4 $\frac{1}{2}$ -inch casing just above the top of the cement in the 4 $\frac{1}{2}$ -inch x 7 inch annulus. Pull the 4 $\frac{1}{2}$ -inch casing out of the hole.
Run back in the hole with the 2 %-inch tubing to the top of the bentonite gel. Pump Class A cement for Plug #2 to fill the 4 ½-inch

E

casing from the top of the bentonite gel to the top of the cutoff  $4 \frac{1}{2}$  inch casing and then from the top of the cutoff  $4 \frac{1}{2}$  inch casing to 100 feet above the cutoff  $4\frac{1}{2}$ -inch casing for a total minimum plug length of 200 feet.

- □ Pull the 2 %-inch tubing above the top of Plug #2 and fill the 7 inch casing with bentonite gel from the top of the cement plug to 120 feet below surface.
- □ Pull the tubing above the bentonite gel at 120 feet and fill the 7 inch casing from 120 feet to the surface with Class A cement for Plug #3.
- ☐ Install monument as per Virginia Division of Gas and Oil requirements on the top of the 7-inch casing.
- ☐ The cement to be used will be Class A or Type 1 cement. The fluid between the cement plugs will be 6% bentonite gel slurry.

## 2.0 PLUGGING AND ABANDONMENT FORM

The completed and signed Plugging and Abandonment Plan Form is presented at the end of this section. Following the Plugging and Abandonment Plan Form is Figure Q-1, a schematic of the proposed UIC well 900146 Plugging and Abandonment Plan.

OMB No. 2040-0042 Approval Expires 11/30/2014 United States Environmental Protection Agency **SEPA** Washington, DC 20460 PLUGGING AND ABANDONMENT PLAN Name and Address of Facility Name and Address of Owner/Operator Class II-D Injection Well 900146 EnerVest Opearting, LLC Prater District, Buchanan County, VA 300 Capitol Street, Suite 200, Charleston, WV 25301 County Permit Number Locate Well and Outline Unit on V۸ Buchanan Section Plat - 640 Acres Surface Location Description 1/4 of \_\_\_\_ 1/4 of \_\_\_\_ 1/4 of \_\_\_ 1/4 of \_\_\_ Section \_ \_\_ Township\_ Locate well in two directions from nearest lines of quarter section and drilling unit Location\_ \_\_ ft. frm (N/S) \_\_\_\_ Line of quarter section ft. from (E/W) \_\_\_\_ Line of quarter section. TYPE OF AUTHORIZATION WELL ACTIVITY W ✓ Individual Permit CLASSI Area Permit CLASS II Rule Brine Disposal Enhanced Recovery Number of Wells 1 Hydrocarbon Storage CLASS III Lease Name W.C. Owens (Tr. 377.12ac) Well Number 900146 CASING AND TUBING RECORD AFTER PLUGGING METHOD OF EMPLACEMENT OF CEMENT PLUGS SIZE WT (LB/FT) TO BE PUT IN WELL (FT) TO BE LEFT IN WELL (FT) HOLE SIZE The Balance Method 13.38 37 44 17 1/2 The Dump Baller Method 9.625 | 26 400 400 12 3/8 The Two-Plug Method 7.00 19 2350 2350 8 3/4 Other 4.50 9.5 4600 6 1/4 CEMENTING TO PLUG AND ABANDON DATA: PLUG #1 PLUG #2 PLUG #3 PLUG #4 PLUG #5 PLUG #6 PLUG #7 Size of Hole or Pipe in which Plug Will Be Placed (inche 4.5 4.5/7 7.0 Depth to Bottom of Tubing or Drill Pipe (ft 4300 2300 120 Sacks of Cement To Be Used (each plug) 23 27 23 Slurry Volume To Be Pumped (cu. ft.) 27 32 27 Calculated Top of Plug (ft.) 4200 2100 Surface Measured Top of Plug (if tagged ft.) ----Slurry Wt. (Lb./Gal.) 15.6 15.6 15.6 Type Cement or Other Material (Class III) Class A Class A Class A LIST ALL OPEN HOLE AND/OR PERFORATED INTERVALS AND INTERVALS WHERE CASING WILL BE VARIED (If any) From To 4300 4400 Projected Weir Perforated Interval Estimated Cost to Plug Wells \$35,000 Certification I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the

Signature

D MAK-

Date Signed

EPA Form 7520-14 (Rev. 12-11)

Name and Official Title (Please type or print)

James McKinney, Senior VP & General Manager

possibility of fine and imprisonment. (Ref. 40 CFR 144.32)



## 1.0 PLUGGING AND ABANDONMENT PLAN

The plugging and abandonment plan to be used to abandon proposed UIC well 900146 is illustrated by Figure Q-1 at the end of this attachment. A review of this schematic along with the following procedure outlines the plugging plan:


Move in service rig and cement service company.
Rig up cement service company and pump Class A cement down the injection tubing for Plug #1. Mix and pump enough cement to cover from injection perforations back to the bottom of tubing plus 100% excess to squeeze and shut off the formation perforations.
Displace cement out the bottom of the injection tubing.
Let cement set until adequate compressive strength has been obtained to allow completion of Plug #1.
Release the packer and pull tubing and packer out of the hole. If injection tubing cannot be pulled, cut the tubing off just above the packer and pull the tubing. Run back in hole with tubing only.
Using the tubing, finish Plug #1 by spotting 100 foot of Class A cement on top of the existing cement that was used to shut off the perforations.
Using the tubing, fill the $4 \frac{1}{2}$ -inch production casing with bentonite gel from top of Plug #1 to 100 foot below the top of the cement in the $4 \frac{1}{2}$ inch x 7 inch annulus as verified by the cement bond log. Pull the tubing out of the hole.
Run in the hole with wireline tools and cut off the $4\frac{1}{2}$ -inch casing just above the top of the cement in the $4\frac{1}{2}$ -inch x 7 inch annulus. Pull the $4\frac{1}{2}$ -inch casing out of the hole.
Run back in the hole with the 2 $\%$ -inch tubing to the top of the bentonite gel. Pump Class A cement for Plug #2 to fill the 4 $\%$ -inch

casing from the top of the bentonite gel to the top of the cutoff  $4\frac{1}{2}$  inch casing and then from the top of the cutoff  $4\frac{1}{2}$  inch casing to 100 feet above the cutoff  $4\frac{1}{2}$ -inch casing for a total minimum plug length of 200 feet.

- □ Pull the 2 %-inch tubing above the top of Plug #2 and fill the 7 inch casing with bentonite gel from the top of the cement plug to 120 feet below surface.
- □ Pull the tubing above the bentonite gel at 120 feet and fill the 7 inch casing from 120 feet to the surface with Class A cement for Plug #3.
- ☐ Install monument as per Virginia Division of Gas and Oil requirements on the top of the 7-inch casing.
- ☐ The cement to be used will be Class A or Type 1 cement. The fluid between the cement plugs will be 6% bentonite gel slurry.

## 2.0 PLUGGING AND ABANDONMENT FORM

The completed and signed Plugging and Abandonment Plan Form is presented at the end of this section. Following the Plugging and Abandonment Plan Form is Figure Q-1, a schematic of the proposed UIC well 900146 Plugging and Abandonment Plan.





## **EAGLE WELL SERVICE INC**

**SALYERSVILLE, KY** 

## CONTACT

Eagle Well Service Inc PO Box 1666 Salyersville, KY 41465 (606) 349-4141

August 24, 2023

Mr. Landon.

Eagle Well Service Inc, would like to submit the following bid to plug Enervest Operating's salt water disposal well in VA for a turnkey price of \$96,500.00

This turnkey bid will include:

Rig time and labor

- Up to 8 days total to include rig time and labor along with power swivel, mills, and mud pump

Cementing services - cement mixing and pumping equipment

Cement – Class A (Class L) with 2% gel and 2% CaCl

Wireline services – including Cast Iron Bridge plug, perforating and casing cutting as listed in plugging procedure.

All hauling to and from location and well fluid disposal

All labor per deim and lodging

If changes to the plugging procedure are made, this bid will be adjusted accordingly. If you should have any questions, please do not hesitate to call. Thank you for this opportunity to quote this job for you!

Sincerely, Brent Wright Eagle Well Service Inc. Cell: (740) 502-6171

ATTACHMENT

# F

## 1.0 SURETY BOND

EnerVest has provided information to EPA Region 3 on the current surety bond for previous injection wells.

The surety is active and renewed annually with the third party insurer

# **EXISTING U.S. EPA PERMITS**

## 1.0 EXISTING U.S. EPA PERMITS

EnerVest operates six existing UIC wells, recently plugging VAS2D927BDIC, and has permits for two undrilled UIC wells (Table I-1) in Dickenson County and Buchanan County, Virginia.

**Table I-1. Existing EPA Permits** 

Table	1-1. Existing EPA Po	emms
UIC		
Wells		
NORA		
State File #	Operation Name	EPA#
DI-0192	P-750132 WD	VAS2D947BDIC
DI-0203	P-143 (750143)	VAS2D907BDIC
DI-0220	P-148 (PLUGGED)	VAS2D927BDIC
DI-0230	P-750171 WD	VAS2D937BDIC
DI-0249	P-750205 WD	VAS2D957BDIC
DI-1144	VWD-535517	VAS2D932BDIC
not drilled	VWD-539572	VAS2D697BDIC
HAYSI		
BU-1614	23606 w/PL	VAS2D950BBUC
not drilled	900146	VAS2D955BBUC

#### 1.0 DESCRIPTION OF BUSINESS

EnerVest (<a href="www.EnerVest.net">www.EnerVest.net</a>) is a private oil and gas company with 10,000 wells across 4 states, 1.5 million acres under lease and \$3 billion in assets under management. Operational Fund XIV owns proved reserves of 6.5 TCF and operations in Appalachia and the Southwestern United States. The December 2015 purchase of Range Resources – Pine Mountain included the operations in the southern Appalachian Basin. EnerVest now owns or has leased the oil, gas and coal bed methane on approximately 350,000 acres in Virginia and produces gas from Pennsylvania age coal seams, as well as deeper formations, including the Devonian Shale, Berea, Weir and Mississippian Big Lime. EnerVest currently operates approximately 3,500 wells in Virginia and plans to drill several hundred additional wells in the next 5 years. Along with coal bed methane and the deeper formation gas production, produced fluid is also extracted. It is these produced fluids that EnerVest will dispose of in the renewed Class II-D disposal well.



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

Tracking Number:	2997
------------------	------

**Company:** Range Resources-Pine Mountain

File Number: BU-1380

Completion Report Type: Drill Deeper Recompletion

## **COMPLETION REPORT (DGO-GO-15)**

Well Type:	Gas/Pipeline	Date Well Completed:	3/15/2011
Driller's Total Depth:		Log's Total Depth:	

#### 1. Changes In Casing/Tubing from Approved Drilling Report

Description	FileName		
821619 casing	Casing.xls		

## 2. Stimulation Record

Stimulation Status: RStimulated & GOB & Not Stimulated & Service Well

Description	FileName	
821619 stimulation	Frac Report 821619.pdf	

#### 3. Final Production

Description	FileName		
821619 final production	Final_Prod.xls		

#### 4. Comments

Form DGO-GO-15-E

Rev. 04/2009

Page 1 of 2

Notes:		

# 5. Signature

Permittee: Range Resources-Pine Date: 7/26/2011 (Company)

Mountain

By: Jonathan Horne Title: Engineering Tech (Signature)

# INTERNAL USE ONLY

Submit Date: 7/26/2011

Status: Approved Date: 3/5/2012

Final PDF Date: 3/6/2012

**Casing Program** 

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented
Conductor	13%"	0-45'	15"			
Water Protection	95/8"	0-406'	121/4"			
Coal Protection	7"	0-2443'	8%"			
Production Casing	41/2"	0-6126'	6¼"	250 ft <sup>3</sup>	No	08/17/10
Other Casing And						
Tubing Left In Well	23/8"	0-6118'				
Liners						

Packers Or Bridge Plugs Kind/Size/Set	Cement Baskets (ft)
11110, 3120, 301	(11)
-	

## **Completion Report**

105000089	2	821619					***
Stage 1			Service Co	Baker Hughes	Avg DH Rate	10.5	
Stage Date	3,	/15/2011	Fluid Type	60Q Foam	Max DH Rate	11.5	
Perf Date	3/	/15/2011	BD	2774	Total Slurry Volume	298	BBLs
Logging Co.	G	ray Wireline	ISIP	0	Total Fluid Volume	240	BBLs
Formation	M	laxton	Avg Press	3441	Avg N2 Rate	6,700	
Top Perf	33	323	Max Treat Pressure	3499	Max N2 Rate	6,900	scfm
Bottom Perf	33	365	Final ISIP	1639	Total N2 Volume	340,214	scf
#Shots	23	3	2 Min SIP	1496	Max DH PPA	3.0	
Perf Size	0.	52	5 Min SIP	1466	Total Proppant Sks	248	sks
Perf Comment	ts		10 Min SIP	0	Total Acid	750	Gal
					Acid Type	15% HCL	
			Comments	formation, could only o		60Q foam, Ra	an extra a

## Summary Total for All Stages

Number of Stages	Total Slurry	Total Fluid Volume	Total N2 Volume	Total Proppant	Total Acid
1	298	240	340.214	248	750

Final Production After Stimulation				
	BOD	MCFD	<b>Hours Tested</b>	<b>Rock Pressure</b>
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		133	3	



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

Tracking Number: 4282

**Company:** Range Resources-Pine Mountain

File Number: BU-1380

Completion Report Type: Original

## **COMPLETION REPORT (DGO-GO-15)**

Well Type: Gas/Pipeline Date Well Completed: 1/11/2002

**Driller's Total Depth:** 6118.00 **Log's Total Depth:** 0.00

## 1. Changes In Casing/Tubing from Approved Drilling Report

Description	FileName

#### 2. Stimulation Record

Stimulation Status:  $\bigcirc$  Stimulated  $\bigcirc$  GOB  $\bigcirc$  Not Stimulated  $\bigcirc$  Service Well

Description	FileName
STIM	BU-1380 stim.pdf
STIM	BU-1380 stim_0830201308103700.pdf

#### 3. Final Production

Description	FileName
FINAL	BU-1380 stim.pdf
FINAL	BU-1380 stim_0830201308103700.pdf

## Notes: Inserted by DGO [8/29/2013, jhh] 5. Signature Range Resources-Pine Permittee: 8/30/2013 (Company) Date: Mountain \*\*\*\*\* By: **CNR** Title: (Signature) INTERNAL USE ONLY Submit Date: 8/30/2013 Status: Approved 11/18/2013 Date: Final PDF Date: 11/18/2013

4. Comments



Commonwealth of Virginia Department of Mines, Minerals and Energy Division of Gas and Oil

P.O. Box 1416; Abingdon, VA 24212

Telephone: (540) 676-5423

AU) 5/6/02 BU-1380

	Operations Name: Colu Permit Number: #380		Well #21619
	COMPLETION REI		
Well type:	Coalbed Methane	njection Well	
Date Well Completed: 1/11/02	Total Depth:	LTD – 6118' KB	
STIMULATION RECORD (Use addition	nal sheets with this format,	if more than three zones	are stimulated.)
Perforated 4290' to 4374' Formation Broke down at: 1328	Perforated4290'to4374'No. of Perforations27Perforation Size0.38"Formation Broke down at:1328PSIG Average Injection Rate:30BPMISIP 1140 (PSIG) 5 MIN SIP.1057 (PSIG)Average Injection Pressure1350 (PSIG)		
ZONE 2:Big LimeFormation Stimulated With: Foam and AcidPerforated 3988'to 3993'No. of Perforations 11Perforation Size 0.38"Formation Broke down at: 2367PSIG Average Injection Rate: 7.5BPMISIP 1451(PSIG) 5 MIN SIP. 1382(PSIG)Average Injection Pressure 1470(PSIG)Stimulated:YesNoDate Stimulated: 11/3/2001			
Well was worked over and all plugs drilled out following completion of workover operations. Shale and berea production were maintained.			
FINAL PRODUCTION:	Natural X	_ After Stimulation	
BOD	MCFD HOUR TESTE	D PRESSURE	HOURS TESTED
ZONE 1, 2 0 353	6	550	72
Permittee: Columbia Natural Resources By:	(Company) (Signature) I  (NAY  RECEIVED DIVISION GAS &	ED LOF	/02

## ENTERED

Operations Name: CNR-21619

Permit # 3807

Department of Mines, Minerals and Energy
Division of Gas and Oil
P. O. Box 1416
Abingdon, Virginia 24210
703/676-5423

#### COMPLETION REPORT

WELL TYPE: Oil Gas _X_ Co	albed Methane o	or Injection well.	Telsis.	stroregres,
Date Well Completed:10/10/98	Total Depth of We	ll:6118 (LTI	0)	ZILLON.
Attach the Drilling Report, if not previous After the Drilling Report was submitted		ldition, submit any chang	ges in casing or tubing that	were appr.
STIMULATION RECORD	F	Cr. 1 1 1 1 1 1 2 2 2 2 2 2 2 2 2 2 2 2 2	1 7/0/ F TTG: 1 511	000 GGB GAV
Zone 1: Devonian Shale				
Perforated:         5560         to         583           Formation Broke down at:         2585           ISIP         2156         PSIG         5           Date Stimulated:         08/31/98         .	8 No. of Perfora PSIG Average I MIN SIP 2128	tions: F njection Rate: 7 B PSIG Avera	Perforation Size:0.44° 70,525 SCF/M age Injection Pressure:36	BPM 10 PSIG
Zone 2: <u>Berea</u> Clean Fluid; 43,400 lbs 20/40 sand; 342	2.400 scf nitrogen			
Perforated: 4840' to 512	26' No. of Perfora	tions: 19 Perfora	ntion Size: 0.44"	•
Formation Broke Down at: 2100 ISIP 1695 PSIG 5 MI	PSIG Aver	age Injection Rate:3	5 BPM Foam Rate	BPM
ISIP <u>1695</u> PSIG <u>5</u> MI	N SIP <u>1433</u> I	PSIG Average Injection	on Pressure: 2365	PSIG
Date stimulated: 10/05/98.				
Zone 3:N/A	Formation	Stimulated With:		
Perforated:to	No. of Perforations	:	Perforation Size:	
Formation Broke Down at:	PS	SIG Average Injection R	ate:	BPM
ISIPPSIG1	MIN SIP	PSIG Av	erage Injection Pressure: _	PSIG
Date stimulated:				
FINAL PRODUCTION: Natura	1 X After Stim	ulation		
			ROCK PRESSURE	HOURS TESTED
Zone (1) _Devonian Shale				120
Zone (2) Berea	110	48	605	72
Zone (3)				
Final Production if Gas Zones are Comi	ngled <u>286</u> MCF	D 48 Hours Test	ed 605 PSIG 72	Hours Tested
Use additional sheets with this format,	if more than three (3)	zones were stimulated.		
Permittee: C	olumbia Natural Reso	urces, Inc. (Company)		
By: Journ	E. Stidhon	(Signa	ature)	

Form DGO-GO-15 Rev. 9/91



Commonwealth of Virginia Department of Mines, Minerals and Energy Division of Gas and Oil P.O. Box 1416; Abingdon, VA 24212

Telephone: (540) 676-5423

5/6/02 BU-1380

Operations Name: Columbia Natural Resources Well #21619 Permit Number: #3808 COMPLETION REPORT X Gas Well type: | Oil Coalbed Methane Injection Well Date Well Completed: 1/11/02 Total Depth: LTD – 6118' KB STIMULATION RECORD (Use additional sheets with this format, if more than three zones are stimulated.) ZONE 1:Weir Sand Formation Stimulated With: Foam and Sand No. of Perforations 27 Perforation Size 0.38" Perforated 4290' to 4374' PSIG Average Injection Rate: 30 Formation Broke down at: 1328 ISIP 1140 (PSIG) 5 MIN SIP. 1057 (PSIG) Average Injection Pressure 1350 (PSIG) Stimulated: X Yes No Date Stimulated: 11/3/2001 Formation Stimulated With: ZONE 2:Big Lime Foam and Acid to 3993' Perforated 3988' No. of Perforations 11 Perforation Size 0.38" Formation Broke down at: 2367 PSIG Average Injection Rate: 7.5 (PSIG) ISIP 1451 (PSIG) 5 MIN SIP. 1382 Average Injection Pressure 1470 (PSIG) Date Stimulated: 11/3/2001 Stimulated: X Yes No Well was worked over and all plugs drilled out following completion of workover operations. Shale and berea production were maintained. After Stimulation FINAL PRODUCTION: Natural ROCK HOURS BOD MCFD HOURS PRESSURE TESTED **TESTED** ZONE 1, 2 353 6 550 Permittee: Columbia Natural Resources, Inc. (Company) (Signature) Date: By:

> RECEIVED DIVISION OF GAS & OIL

Form DGO-GO-15 Rev. 1/98

## ENTERED

Operations Name: CNR-21619

Permit # 3807

Department of Mines, Minerals and Energy
Division of Gas and Oil
P. O. Box 1416
Abingdon, Virginia 24210
703/676-5423

#### COMPLETION REPORT

WELL TYPE: Oil Gas _X_ Co	albed Methane o	or Injection well.	Telsis.	stroregres,
Date Well Completed:10/10/98	Total Depth of We	ll:6118 (LTI	0)	ZILLON.
Attach the Drilling Report, if not previous After the Drilling Report was submitted		ldition, submit any chang	ges in casing or tubing that	were appr.
STIMULATION RECORD	F	Cr. 1 1 1 1 1 1 2 2 2 2 2 2 2 2 2 2 2 2 2	1 7/0/ F TTG: 1 511	000 GGB GAV
Zone 1: Devonian Shale				
Perforated:         5560         to         583           Formation Broke down at:         2585           ISIP         2156         PSIG         5           Date Stimulated:         08/31/98         .	8         No. of Perfora           PSIG         Average I           MIN SIP         2128	tions: F njection Rate: 7 B PSIG Avera	Perforation Size:0.44° 70,525 SCF/M age Injection Pressure:36	BPM 10 PSIG
Zone 2: <u>Berea</u> Clean Fluid; 43,400 lbs 20/40 sand; 342	2.400 scf nitrogen			
Perforated: 4840' to 512	26' No. of Perfora	tions: 19 Perfora	ntion Size: 0.44"	•
Formation Broke Down at: 2100 ISIP 1695 PSIG 5 MI	PSIG Aver	age Injection Rate:3	5 BPM Foam Rate	BPM
ISIP <u>1695</u> PSIG <u>5</u> MI	N SIP <u>1433</u> I	PSIG Average Injection	on Pressure: 2365	PSIG
Date stimulated: 10/05/98.				
Zone 3:N/A	Formation	Stimulated With:		
Perforated:to	No. of Perforations	:	Perforation Size:	
Formation Broke Down at:	PS	SIG Average Injection R	ate:	BPM
ISIPPSIG1	MIN SIP	PSIG Av	erage Injection Pressure: _	PSIG
Date stimulated:				
FINAL PRODUCTION: Natura	1 X After Stim	ulation		
			ROCK PRESSURE	HOURS TESTED
Zone (1) _Devonian Shale				120
Zone (2) Berea	110	48	605	72
Zone (3)				
Final Production if Gas Zones are Comi	ngled <u>286</u> MCF	D 48 Hours Test	ed 605 PSIG 72	Hours Tested
Use additional sheets with this format,	if more than three (3)	zones were stimulated.		
Permittee: C	olumbia Natural Reso	urces, Inc. (Company)		
By: Journ	E. Stidhon	(Signa	ature)	

Form DGO-GO-15 Rev. 9/91



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

**Tracking Number:** 4276

Range Resources-Pine Mountain Company:

File Number: BU-1380

**Operations Name:** 21619 W/PL

**Operation Type:** Gas/Pipeline

**Drilling Report Type:** Original

# **DRILLING REPORT (DGO-GO-14)**

#### 1. Drilling Data

Date drilling commenced: Drilling Contractor: S W Jack Drilling 7/27/1998

Co.

Date drilling completed: Rig Type: Rotary & Cable 8/7/1998

Driller's Total Depth (feet): 6118.00

Log Total Depth (feet): 0.00 Formation At Total Depth Weir

## 2. Final Location Plat (as required by 4 VAC25-150-360.C.)

Permitted State Plane X: Final Plat State Plane X: 10398885.8650 10398886.0000

Permitted State Plane Y: 3618804.7100 Final Plat State Plane Y: 3618804.7190

Plat Previously Submitted Or...

List of Attached Items:

Form DGO-GO-14-E

Page 1 of 4

Rev. 04/2009

Description	FileName
PLAT	BU-1380 plat.pdf

# 3. Geological Data

#### Fresh Water At:

Depth (in feet)	Rate	Unit of Measure
68	1	GPM

#### Salt Water At:

Depth (in feet)	Rate	Unit of Measure
1530	1	GPM

#### Coal Seams:

List of Attached Items:

Description	FileName
COAL	BU-1380 coal-gs.pdf

#### Gas and Oil Shows:

List of Attached Items:

Description	FileName
GAS	BU-1380 coal-gs.pdf
GAS	BU-1380 gs.pdf

# 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run: GR/IND/DEN/NEU/PHOTO/TEMP/AUDIO

 $\operatorname{\mathsf{Did}}\nolimits \operatorname{\mathsf{logs}}\nolimits \operatorname{\mathsf{disclose}}\nolimits \operatorname{\mathsf{vertical}}\nolimits \operatorname{\mathsf{locations}}\nolimits \operatorname{\mathsf{of}}\nolimits \operatorname{\mathsf{a}}\nolimits \operatorname{\mathsf{coal}}\nolimits$ 

seam?

R

# 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Form DGO-GO-14-E

Page 2 of 4

Rev. 04/2009

Description	FileName
SURVEY	BU-1380 casing-survey.pdf

# 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
CASING	BU-1380 casing-survey.pdf
CASING	BU-1380 casing.pdf

#### 7. Remarks


Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

8. Drillers Log	
Compiled By:	
List of Attached Items:	
Description	FileName
Description	I licivallic
LOG	BU-1380 log.pdf

Inserted by DGO [8/29/2013, jhh]

10. Signature			
Permitee:	Range Resources-Pine Mountain	Date:	8/30/2013
Signed By:	CNR	Title:	******

INTERNAL USE	ONLY			
Submit Date:	8/30/2013			
Status:	<u>A</u>	Date:	11/18/2013	_



-2,026,-

NUMBER21619
SLE Prater
400' DATE 08-31-98
plat X
s, scale 1 to
lines as shown.
& Mullens
GREGORY LEE MULLINS D
No. 002066
8-31-98
THE WAY OF THE PERSON OF THE P
RESPONDED TO SURVEY OF THE PARTY OF THE PART

For

Operations Name: CNR-21619

Permit # 3808

BU-1380

Department of Mines, Minerals and Energy
Division of Gas and Oil
P. O. Box 1416
Abingdon, Virginia 24210
703/676-5423

**ENTERED** 

#### DRILLING REPORT

Pursuant to VR-480-05-22.1, Section 1.36, the undersigned Permittee submits this report on Well 21619 in the Prater District of the Buchanan City/County, Virginia on the 22nd day of December, 1998.

LOCATION							
Ft. S. of	: <u>1880.57</u> Ele Latitude <u>37</u>	strict: <u>Prater</u> evation of Kelly Bu deg 12' 30" and 337,926 and <u>E-915</u>	ushing: 1890.57 Qua 4339 Ft. V 5,901.	drangle: <u>Prater</u> V. of Longitude <u>8</u>	2 deg 12'3	30"	
Attach a final loca	ation plat as re	equired by VR 480-	-05-22.1, Section 1.3	6.			
DRILLING DATA	<u>A</u>						
Date Drilling Com Date Drilling Com Total Depth of We GEOLOGICAL D	npleted: 08/ell: 6118'		ling Contractor: SV:  X Rotary	/ Jack Drilling Cor Cable Tool	npany Rig		
	Feet	1 GPM GPM GPM	Feet Feet Feet	GF GP	PM		
	Feet		FeetFeetFeet				
COAL SEAMS: NAME: Unknown	TOP 802'	BOTTO 804'	OM THICKNI 2'	the state of the s	INING IN . NO X	AREA MINED X	OUT
GAS AND OIL SE FORMATION Big Lime	HOWS: TOP 3716'	BOTTOM 4190'	THICKNESS 474	IPF (MCFD/BOF		RESSURE .tmosphere	HOURS TESTED N/A
DIS DIMO	3/10	7170	77/7	210		шиозриеге	IV/A

Operations Name: CNR-21619

Permit # 3808

BU-1380

Department of Mines, Minerals and Energy
Division of Gas and Oil
P. O. Box 1416
Abingdon, Virginia 24210
703/676-5423

**ENTERED** 

#### DRILLING REPORT

Pursuant to VR-480-05-22.1, Section 1.36, the undersigned Permittee submits this report on Well 21619 in the Prater District of the Buchanan City/County, Virginia on the 22nd day of December, 1998.

LOCATION							
Ft. S. of	: <u>1880.57</u> Ele Latitude <u>37</u>	strict: <u>Prater</u> evation of Kelly Bu deg 12' 30" and 337,926 and <u>E-915</u>	ushing: 1890.57 Qua 4339 Ft. V 5,901.	drangle: <u>Prater</u> V. of Longitude <u>8</u>	2 deg 12'3	30"	
Attach a final loca	ation plat as re	equired by VR 480-	-05-22.1, Section 1.3	6.			
DRILLING DATA	<u>A</u>						
Date Drilling Com Date Drilling Com Total Depth of We GEOLOGICAL D	npleted: 08/ell: 6118'		ling Contractor: SV:  X Rotary	/ Jack Drilling Cor Cable Tool	npany Rig		
	Feet	1 GPM GPM GPM	Feet Feet Feet	GF GP	PM		
	Feet		FeetFeetFeet				
COAL SEAMS: NAME: Unknown	TOP 802'	BOTTO 804'	OM THICKNI 2'	the state of the s	INING IN . NO X	AREA MINED X	OUT
GAS AND OIL SE FORMATION Big Lime	HOWS: TOP 3716'	BOTTOM 4190'	THICKNESS 474	IPF (MCFD/BOF		RESSURE .tmosphere	HOURS TESTED N/A
DIS DIMO	3/10	7170	77/7	210		шиозриеге	IV/A

Shale Perfs:		OPEN HOLE	TOTAL DEPTH	BIT SIZE	PACKER	"	2 3/8"	, ,	4 1/2"	7"	9 5/8"	PIPE SIZE		OBTAINED FROM:	TWP/DIST County Co		
Beren Perfs: 5560-5838 (17 Holes); 5124-5126 (2holes) TD-6	Que C		6118	61/4"	,	,	,	,	6048	2432	358	TEET		WELL LOG SUMMARY (V), O	TWP/DIST County Common / Proter CO. Buchanan	and the state of t	
5124-5126 (2holes) TO-6118	1/2/02	a a			8.47	#	#	#	10.5 #	20 #	32.3 #	WEIGHT		OTHER	anan ST. Vicqinia	COMPLET	
8		Sh	ale	. d [	Ber	ea	Ga	S					_			COMPLETED/WORKED OVER_	
143 CS4 Set @ 6050 Kb			7" cy set @ 1441' kg				9 8 czy szł @ 3/8 ' K			7.				Ť		Completed	

Department of Mine Division of Gas and		nergy				perations Name: C	NR-21619
Cuttings or samples Cuttings or samples	are X are no have have	t available notX been	for examination furnished to the	on by a member of ne Virginia Divisi	f the Virginia D on of Mineral R	Division of Mineral Resources	Resources
ELECTRIC LOGS A	AND SURVEYS:						
List logs ran on well	lbore: <u>Gamma F</u>	lay, Dual Induct	ion, Litho Der	sity, Compensate	d Neutron, Pho	toelectric, Temper	rature & Audio
Did log disclose vert	tical location of a	coal seam? Ye	es X 1	No N/A	<i>Y</i>		
SURVEY RESULTS DEPTH OF SURVEY	DIRECTION	DISTANCE/DE RUE VERTICA		DEPTH OF SURVEY		CTION/DISTANC ROM TRUE VER	
400 600 1000 1200 1400 2000 *Use additional she	3/4DE 1/2 DE 3/4 DE	GREE GREE GREE GREE		<u>2200</u> <u>2400</u>		1 DEGREE 1/4 DEGREE	
		<u>(</u>	CASING ANI	TUBING			
1	SIZE TOP	BOTTOM	<u>LENGTH</u>	CEMENT USEI IN CU/FT	DATE CEMENTED	PACKERS OR BI KIND SIZE	RIDGE PI SET
Conductor 13	3/8" Surface	45'KB	35'	Driven			
Surface 9	5/8" Surface	368'KB	358'	142 cu.ft.	07/28/98		
Water Protection 7	7" Surface	2442'KB	2432'	461 cu.ft.	07/31/98		
Coal Protection							
Other Casing and Tubing Left in W	4 ½" Surface Vell	6058'KB	6048'	184 cu.ft.	08/07/98		
Liners							
REMARKS: Shut do	own, fishing jobs,	depths and dates	, caving, lost	circulation, etc.			

Department of Mine Division of Gas and		nergy				perations Name: C	NR-21619
Cuttings or samples Cuttings or samples	are X are no have have	t available notX been	for examination furnished to the	on by a member of ne Virginia Divisi	f the Virginia D on of Mineral R	Division of Mineral Resources	Resources
ELECTRIC LOGS A	AND SURVEYS:						
List logs ran on well	lbore: <u>Gamma F</u>	lay, Dual Induct	ion, Litho Der	sity, Compensate	d Neutron, Pho	toelectric, Temper	rature & Audio
Did log disclose vert	tical location of a	coal seam? Ye	es X 1	No N/A	<i>Y</i>		
SURVEY RESULTS DEPTH OF SURVEY	DIRECTION	DISTANCE/DE RUE VERTICA		DEPTH OF SURVEY		CTION/DISTANC ROM TRUE VER	
400 600 1000 1200 1400 2000 *Use additional she	3/4DE 1/2 DE 3/4 DE	GREE GREE GREE GREE		<u>2200</u> <u>2400</u>		1 DEGREE 1/4 DEGREE	
		<u>(</u>	CASING ANI	TUBING			
1	SIZE TOP	BOTTOM	<u>LENGTH</u>	CEMENT USEI IN CU/FT	DATE CEMENTED	PACKERS OR BI KIND SIZE	RIDGE PI SET
Conductor 13	3/8" Surface	45'KB	35'	Driven			
Surface 9	5/8" Surface	368'KB	358'	142 cu.ft.	07/28/98		
Water Protection 7	7" Surface	2442'KB	2432'	461 cu.ft.	07/31/98		
Coal Protection							
Other Casing and Tubing Left in W	4 ½" Surface Vell	6058'KB	6048'	184 cu.ft.	08/07/98		
Liners							
REMARKS: Shut do	own, fishing jobs,	depths and dates	, caving, lost	circulation, etc.			



Commonwealth of Virginia
Department of Mines, Minerals and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212

Telephone: (540) 676-5423

Ope	rations	Name:	Columbia	Natural	Resources	Well #21619
-		2				

Permit Number:

3808

## DRILLING REPORT

Well was squeeze cemented with 80 Sax Class A w/ 2% gel, 2% CaCl2 (108 cuft). TOC – 3440'. No other alterations were made to the wellbore, and all production from the Huron Shale, Berea Sand, Weir Sand and Big Lime is through the  $4\frac{1}{2}$ " production casing.

Permittee:	Columbia Natural Resources, Inc.	(Company)
By:	27/1/2	(Signature)

Department of Mines, Minerals and Energy Division of Gas and Oil

Operations Name: CNR-21619

Permit # 3808

#### DRILLER'S LOG

Compiled by Geologist

GEOLOGICAL		GENERAL			DEPTH		
<u>AGE</u>	<b>FORMATION</b>	LITHOLOGY	COLOR	TOP	BOTTOM	THICKNESS	REMARKS
DED DIGINAL VILLAGE	. T	0 1 0 0 0 1				anazana n	
PENNSYLVANIAN	- 1775 - 717 / L	Sandstone & Shale		0	1310	1310	
	Salt Sand	Sandstone		1310	2100	790	
MISSISSIPPIAN	Bluestone	Sandstone & Shale		2100	2577	477	
	Bluestone	Shale		2577	2782	205	
	Bluefield	Sandstone		2782	2953	171	
	Bluefield	Sandstone & Shale					
	Maxon			2953	3100	147	
		Sandstone		3100	3132	32	
	Bluefield	Siltstone & Shale		3132	3310	178	
	Maxon	Sandstone		3310	3372	62	
	Bluefield	Sandstone & Shale		3372	3590	218	
	Little Lime	Argillaceous Ls		3590	3716	126	
	Big Lime	Limestone		3716	4190	474	
	Pocono	Shale		4190	4288	98	
	Weir	Siltstone		4288	4410	122	
	Pocono	Shale		4410	4808	398	
	Sunbury	Shale		4808	4832	24	
	Berea	Sandstone		4832	4888	56	
DEVONIAN	Devonian Shale	Shale		4888	5650	762	
	Lower Huron	Shale		5650	5854	204	
	Java	Shale		5854	TD (6118)	264	

Permittee: Columbia Natural Resources (Company)

By: Auson E. Stickom (Signature)

Form DGO-GO-14 Rev. 9/91



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

Tracking Number:	2988
------------------	------

**Company:** Range Resources-Pine Mountain

File Number: BU-1806

Completion Report Type: Drill Deeper Recompletion

## **COMPLETION REPORT (DGO-GO-15)**

Well Type:	Gas/Pipeline	Date Well Completed:	11/16/2010
Driller's Total Depth:		Log's Total Depth:	

#### 1. Changes In Casing/Tubing from Approved Drilling Report

Description	FileName
824073 casing	Casing.xls

## 2. Stimulation Record

Stimulation Status: RStimulated & GOB & Not Stimulated & Service Well

Description	FileName		
824073 stimulation	824073 stimulation.rtf		

#### 3. Final Production

Description	FileName		
824073 final production	Final_Prod.xls		

#### 4. Comments

Form DGO-GO-15-E

Rev. 04/2009

Page 1 of 2

Approved [4/18/2012, cbl]

Need to include cementing information on casing changes. If there were no changes to the casing, please indicate. [3/5/2012, cbl]

Need to describe how was stimulated including water, nitrogen, sand, acid, etc., volumes. [3/5/2012, cbl]

5.	C	ia	n	ot:	ıır	_
J.	-	ш	ш	- 14		u

By:

(Company) Range Resources-Pine Permittee: Date: 4/10/2012 Mountain Jonathan Horne Title: **Engineering Tech** (Signature)

# INTERNAL USE ONLY

Submit Date: 4/10/2012

> 4/18/2012 Status: Approved Date:

Final PDF Date: 5/14/2012 Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs	Cement Baskets
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set	(ft)
Conductor	13%"	0-45'	15"					
Water Protection	95/8"	0-407'	121/4"					
Coal Protection	7"	0-2130'	81/8"					
Production Casing	41/2"	0-6006'	61/4"					
Other Casing And								
Tubing Left In Well	23/8"	0-5920'						
Liners								

<sup>\*</sup>Tubing was ran on 4/11/11, no other changes were made to the casing program.

105000111 2 824073

Stage 1	
Stage Date	11/16/2010
Perf Date	11/15/2010
Logging Co.	Universal
Formation	Big Lime
Top Perf	3903
Bottom Perf	4084
#Shots	26
Perf Size	0.52
Perf Comments	

Service Co Fluid Type	Baker Hughes Bullhead Acid	Avg DH Rate Max DH Rate	2.5 3	
BD	613	Total Slurry Volume	105	BBLs
ISIP	0	Total Fluid Volume	105	BBLs
Avg Press	451	Avg N2 Rate	0	
Max Treat Pressure	509	Max N2 Rate	0	scfm
Final ISIP	134	Total N2 Volume	0	scf
2 Min SIP	129	Max DH PPA	0	
5 Min SIP	118	Total Proppant Sks	0	sks
10 Min SIP	0	Total Acid	2700	Gal
Sand Mesh:	n/a	Acid Type		
Frac Gradient:	0.4			

Packer Depth - 3710'

# Summary Total for All

Number of Stages	Total Slurry	Total Fluid Volume	Total N2 Volume	Total Proppant	Total Acid
1	105	105	0	0	2700

Final Production After Stimulation				
	BOD	MCFD	<b>Hours Tested</b>	<b>Rock Pressure</b>
Final/Commingled Zones		14	in-line	



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

Tracking Number: 4889

**Company:** Range Resources-Pine Mountain

File Number: BU-1806

Completion Report Type: Original

## **COMPLETION REPORT (DGO-GO-15)**

Well Type: Gas/Pipeline Date Well Completed: 6/21/2000

**Driller's Total Depth:** 6060.00 **Log's Total Depth:** 6060.00

## 1. Changes In Casing/Tubing from Approved Drilling Report

Dosori	ntion	FileName
Descri	ption	riiename

#### 2. Stimulation Record

Stimulation Status: RStimulated EGOB ENot Stimulated EService Well

Description	FileName		
STIM	BU-1806 stim-final.pdf		

#### 3. Final Production

Description	FileName		
FINAL	BU-1806 stim-final.pdf		

#### 4. Comments

Form DGO-GO-15-E

Rev. 04/2009

Notes:							
Material ins	serted by I	DGO [3/10/2014, jhh]					
5. Signature							
Permittee:	Range R Mountair	esources-Pine	Date:	3/28/2014			(Company)
Ву:	Jason E.	Stidham	Title:	*****			(Signature)
INTERNA	AL USE	ONLY					
Subr	nit Date:	3/28/2014					
	Status:	Approved		D	ate:	3/31/2014	

Final PDF Date:

3/31/2014





Commonwealth of Virginia Department of Mines, Minerals and Energy Division of Gas and Oil P.O. Box 1416 Abingdon, VA 24212 Telephone: (540) 676-5423

	Oper	ations Name(	CNR Well # 24073		
	Perm	it Number 4	510		
	COMPLETIC	ON REPORT			
WELL TYPE: OIL Gas X	Coalbed Methane	Injection			
Date Well CompletedJune 21, 200	0	Tota	d Depth DTD: 6060 I	LTD: 6060	
Attach the Drilling Report, if not p approved after the Drilling Report v		addition, submi	t any changes in casin	ng or tubing that were	
STIMULATION RECORD*  * Use additional sheets with this form	nat, if more than three zon	nes are stimulate	ed .		
ZONE 1: Devonian Shale	Formation S	timulated with_	250 gal 7 1/2% HCl, 1,	013,700 SCF N2	
Perforated 5680 To	5926 No. of Perfo	rations 15	Perforation Size	0.38"	
	MIN. SIP 2417 (PSIG)	Average Down	hole Injection Pressure	3959 (PSIG)	
ZONE 2: Berea	Formation S	timulated with_	250 gal 7 ½% HCl, 1,	017,500 SCF N2	
Perforated 4832 To	4864 No. of Perfo	rations 17	Perforation Size	0.38"	
			hole Injection Pressure		
Stimulated X Yes N		May 30, 2000	등 전 기업 경기 등 등 전 등 등 등 등 등 등 등 등 등 등 등 등 등 등 등 등	(1010)	
ZONE 3: <u>Maxon</u> 525,000 SCF N2, 21,000 Lbs 20/40	Mesh Sand	======================================	250 gal 15 % HCl, 15		
Perforated 3468 To			Perforation Size	0.38"	
ISIP			hole Injection Pressure	3138 (PSIG)	
FINAL PRODUCTIONNatu	ral After Stimula	tion			
В	OD MC	FD I	HOURS TESTED	ROCK PRESSURE	HOURS TESTED
ZONE (1)					
ZONE (2)					
ZONE (3)	103	5	48	750	96
Final production if gas zones are com Tested *These values here represent co	ningled <u>169</u> MCFD mmingled values for the	72 Hours Berea and Devo	s Tested 950 l	PSIG 72 Hours	
Permittee Columbia Natural Resou	irces, Inc.	(Company)			
By Juson E Stictham		(Signature)			
Date 6/22/2000					

Form DGO-GO-15 Rev. 10/96







Commonwealth of Virginia Department of Mines, Minerals and Energy Division of Gas and Oil P.O. Box 1416 Abingdon, VA 24212 Telephone: (540) 676-5423

	Operations Name	CNR Well # 24073		
	Permit Number_	4510		
	COMPLETION REPORT	r		
WELL TYPE: OIL Gas X Co	oalbed Methane Injection			
Date Well CompletedJune 21, 2000		Total Depth DTD: 6060	LTD: 6060	
Attach the Drilling Report, if not previous approved after the Drilling Report was s		bmit any changes in cas	sing or tubing that were	
STIMULATION RECORD*  * Use additional sheets with this format, i	f more than three zones are stimu	lated		
ZONE 1: Devonian Shale	Formation Stimulated w		1,013,700 SCF N2	
Perforated 5680 To 592	No. of Perforations 15	Perforation Size	0.38"	
ISIP 3039 (PSIG) 5 MIN.				
Stimulated X Yes No	Date Stimulated May 30, 20			
ZONE 2: Berea	Formation Stimulated w	th 250 gal 7 ½% HCl,	1,017,500 SCF N2	
Perforated 4832 To 486	No. of Perforations 17	Perforation Size	0.38"	
	SIP 2046 (PSIG) Average De			
Stimulated X Yes No	Date Stimulated May 30, 2			
ZONE 3: <u>Maxon</u> 525,000 SCF N2, 21,000 Lbs 20/40 Mes		ith 250 gal 15 % HCl,	153 Bbls of Water	
Perforated 3468 To 348		Perforation Size	0.38"	
ISIP 2939 (PSIG) 5 MIN.				
Stimulated X Yes No	Date Stimulated June 15, 2		471040000	
FINAL PRODUCTIONNatural	After Stimulation			
BOD	MCFD	HOURS TESTED	ROCK PRESSURE	HOURS TESTED
ZONE (1)				
ZONE (2)				
ZONE (3)	103	48	750	96
Final production if gas zones are comingle Tested *These values here represent commi			PSIG 72 Hours	
Permittee Columbia Natural Resources	, Inc. (Compar	y)		
By Joson E Stitlam	(Signatur	re)		
Date 6/22/2000				

Form DGO-GO-15 Rev. 10/96

ENLEGED



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

**Tracking Number:** 4887

Range Resources-Pine Mountain Company:

File Number: BU-1806

**Operations Name:** 24073 W/PL

Gas/Pipeline **Operation Type:** 

**Drilling Report Type:** Original

## **DRILLING REPORT (DGO-GO-14)**

### 1. Drilling Data

Date drilling commenced: Drilling Contractor: S.W. Jack Drilling 5/2/2000

Co.Rig # 18

Date drilling completed: Rig Type: Rotary & Cable 5/13/2000

Driller's Total Depth (feet): 6060.00

Log Total Depth (feet): 6060.00 Formation At Total Depth Java Shale

### 2. Final Location Plat (as required by 4 VAC25-150-360.C.)

Permitted State Plane X: Final Plat State Plane X: 10406103.4350 10406103.4350

Permitted State Plane Y: 3621155.0490 Final Plat State Plane Y: 3621155.0490

Plat Previously Submitted Or...

List of Attached Items:

Form DGO-GO-14-E

Page 1 of 3

Description	FileName		
PLAT	BU-1806 plat.pdf		

## 3. Geological Data

Fresh Water At:

Depth (in feet)	Rate	Unit of Measure
120	damp	

Salt Water At:

Depth (in feet) Rate Unit of Measure
--------------------------------------

Coal Seams:

List of Attached Items:

Description	FileName
-------------	----------

Gas and Oil Shows:

List of Attached Items:

Description	FileName		
GAS	BU-1806 gs.pdf		

### 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run: GR/DEN/COMP NUETRON/INDUCT/AUDIO/TEMP

 $\operatorname{\mathsf{Did}}\nolimits \operatorname{\mathsf{logs}}\nolimits \operatorname{\mathsf{disclose}}\nolimits \operatorname{\mathsf{vertical}}\nolimits \operatorname{\mathsf{locations}}\nolimits \operatorname{\mathsf{of}}\nolimits \operatorname{\mathsf{a}}\nolimits \operatorname{\mathsf{coal}}\nolimits$ 

seam?

£

## 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName			
SURVEY	BU-1806 casing-survey.pdf			

Form DGO-GO-14-E

Page 2 of 3

## 6. Casing and Tubing Program

List of Attached Items:

Description	FileName			
CASING	BU-1806 casing-survey.pdf			


### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

8. Drillers Log						
Compiled By	:					
List of Attach	ed Items	s:				
	De	scription		FileName		
		LOG		BU-1806 log.pdf		
9. Comments						
Material inse	rted by [	OGO [3/10/2014, jhh]				
10. Signature						
Permitee:	Range	Resources-Pine Mountain	Date:	3/28/2014		
Signed By:	Jason E. Stidham		Title:	********		
INTERNAL	USE	ONLY				
Submit	t Date:	3/28/2014		_		
\$	Status:	<u>A</u>		Date: 3/31/2014		
Final PDF	Date:	3/31/2014		_		

Form DGO-GO-14-E

Page 3 of 3



NO SURVE



Telephone: (540) 676-5423 Operations Name CNR Well # 24073 Permit Number 4510 DRILLING REPORT ATTACH A FINAL LOCATION PLAT AS REQUIRED BY 4 VAC 25-150-360.C. DRILLING DATA Date drilling commenced May 2, 2000 Drilling Contractor S. W. Jack Drilling Co. Rig #18 Date drilling completed Rig Type X Rotary May 13, 2000 Total Depth of Well DTD: 6060 LTD: 6060 GEOLOGICAL DATA Fresh water at 120 Feet Damp GPM/Inch Stream 700 Feet Damp GPM/Inch Stream Feet GPM/Inch Stream Feet GPM/Inch Stream Salt water at Feet GPM/Inch Stream \_ Feet \_ GPM/Inch Stream Feet \_\_ Feet \_ GPM/Inch Stream GPM/Inch Stream Coal Seams NAME TOP BOTTOM THICKNESS MINING IN AREA MINED OUT YES Gas and Oil Shows FORMATION TOP BOTTOM THICKNESS IPF PRESSURE HOURS TESTED (MCFD/BOPD) Ravencliff 2217 2221 103 Atmosphere Cuttings or samples \_\_\_\_ are \_X are not available for examination by a member of the Virginia Division of Mineral Resources Cuttings or samples have \_\_\_\_ have not X been furnished to the Virginia Division of Mineral Resources ELECTRIC LOGS AND SURVEYS List logs ran on wellbore Gamma Ray, Litho-Density, Compensated Nuetron, Dual Induction, Audio, and Temperature Did logs disclose vertical location of a coal seam? Yes \_\_\_\_ No \_X

Operations Name	CNR Well # 24073	
Permit Number	4510	

SURVEY RESULTS

	DIRECTION/DISTANCE/ DEGREES FROM TRUE		DIRECTION/DISTANCE DEGREES FROM TRUE
DEPTH OF SURVEY	VERTICAL	DEPTH OF SURVEY	VERTICAL
200	½ Degree	1200	3/4 Degree
400	¾ Degree	1400	3/4 Degree
600	3/4 Degree	1600	3/4 Degree
800	¾ Degree	1800	3/4 Degree
1000	¾ Dgree	2000	3/4 Degree

Use additional sheets as necessary

CASING AND TUBING PROGRAM

		CASH O AND I	DING I ROULE				
CONDUCTOR	CASING 13 3/8"	CASING INTERVAL 45' KB	HOLE SIZE 17 ½"	CEMENT USED IN CU/FT N/A	TO SURFACE YES NO No	DATE CEMENTED	PACKERS OF BRIDGE PLUC KIND/SIZE/SF
SURFACE							
WATER PROTECTION	9 5/8"	407' KB	12 3/8"	177	Yes	May 3, 2000	
COAL PROTECTION	7"	2130' KB	8 3/4"	409	Yes	May 6, 2000	
OTHER CASING AND TUBING LEFT IN	4 1/2"	6006' KB	6 1/4"	189	No	May 12, 2000	
WELL							
LINERS							

Operations Name	CNR Well # 24073	
Permit Number	4510	

SURVEY RESULTS

	DIRECTION/DISTANCE/ DEGREES FROM TRUE		DIRECTION/DISTANCE DEGREES FROM TRUE
DEPTH OF SURVEY	VERTICAL	DEPTH OF SURVEY	VERTICAL
200	½ Degree	1200	3/4 Degree
400	¾ Degree	1400	3/4 Degree
600	3/4 Degree	1600	3/4 Degree
800	¾ Degree	1800	3/4 Degree
1000	¾ Dgree	2000	3/4 Degree

Use additional sheets as necessary

CASING AND TUBING PROGRAM

		CASH O AND I	DING I ROULE				
CONDUCTOR	CASING 13 3/8"	CASING INTERVAL 45' KB	HOLE SIZE 17 ½"	CEMENT USED IN CU/FT N/A	TO SURFACE YES NO No	DATE CEMENTED	PACKERS OF BRIDGE PLUC KIND/SIZE/SF
SURFACE							
WATER PROTECTION	9 5/8"	407' KB	12 3/8"	177	Yes	May 3, 2000	
COAL PROTECTION	7"	2130' KB	8 3/4"	409	Yes	May 6, 2000	
OTHER CASING AND TUBING LEFT IN	4 1/2"	6006' KB	6 1/4"	189	No	May 12, 2000	
WELL							
LINERS							

Operations Name	CNR Well # 24073	
Permit Number	4510	

#### DRILLER'S LOG

Compiled by Jason E. Stidham

		GENERAL		1	DEPTH		
GEOLOGIC AGE	FORMATION	LITHOLOGY	COLOR	TOP	BOTTOM	THICKNESS	REMARK
Penn	Lee	Siltstone & Shale		0	1254	1254	
Penn	Salt Sand (Lee)	Sandstone		1254	1396	142	
Penn	Lee	Siltstone & Shale		1396	1504	108	
Penn	Salt Sand (Lee)	Sandstone		1504	1556	52	
Penn	Lee	Siltstone & Shale		1556	1670	114	
Penn	Salt Sand (Lee)	Sandstone		1670	1744	74	
Penn	Lee	Siltstone & Shale		1744	1922	178	
Penn	Salt Sand (Lee)	Sanstone		1922	2058	136	
Miss	Pennington	Siltstone & Shale		2058	2140	82	
Miss	Ravecliff	Sandstone		2140	2220	80	
Miss	Pennington	Siltstone & Shale		2220	2708	488	
Miss	Maxon	Sandstone		2708	2766	58	
Miss	Pennington	Siltstone & Shale		2766	3060	294	
Miss	Maxon	Sandstone		3060	3164	104	
Miss	Pennington	Siltstone & Shale		3164	3266	102	
Miss	Maxon	Sandstone		3266	3300	34	
Miss	Pennington	Siltstone & Shale		3300	3458	158	
Miss	Maxon	Sandstone		3458	3496	38	
Miss	Pennignton	Siltstone & Shale		3496	3546	50	
Miss	Little Lime	Limestone		3546	3664	118	
Miss	Big Lime	Limestone		3664	4102	438	
Miss	Pocono	Shale		4102	4282	180	
Miss	Weir	Siltstone		4282	4374	92	
Miss	Pocono	Shale		4374	4808	434	
Miss	Sunbury	Shale		4808	4830	22	
Miss	Berea	Sandstone		4830	4876	68	
Dev	Devonian Shale	Shale		4876	5716	840	
Dev	Lower Huron	Shale		5716	5936	220	
Dev	Java	Shale		5936	6060	124	

Permittee: Columbia Natural Resources, Inc.	(Company)
By: Joseph & Stickham	(Signature)
Form DGO-GO-14	
Rev. 10/96	



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

	Tracking N	umber:	7758	
	Company:		Range Resources-Pine Mountain,	
	File Numbe	er:	BU-2549	
	Completion	n Report Type:	Original	
COMPLETION REPORT (DGO-GO-15)				
Well Type:	Gas	Date Well C	Completed: 11/19/2003	
Driller's Total Depth:	Driller's Total Depth: 5983.00		otal Depth: 5974.00	
Changes In Casing/Tubing		Timing Report	FileName	
0.1 1.1 5				
Stimulation Record				
	ulated GOB	Not Stimulated	d Service Well	
		Not Stimulated	d Service Well  FileName	
Stimulation Status: X Stimu			Ш	
Description			FileName	
Stimulation Status: X Stimu  Description  STIM			FileName	
Stimulation Status: X Stimu  Description  STIM  Final Production		5BU2549_24	FileName 4545 WPL_RR_BUCHANAN.pdf	
Stimulation Status: X Stimu  Description  STIM  Final Production  Description		5BU2549_24	FileName  4545 WPL_RR_BUCHANAN.pdf  FileName	

Notes:	
MATERIAL INSERTED BY DGO [10/26/2015, jhh]	

W/ (12/()/ (2 // () // (

 INTERNAL USE ONLY

 Submit Date:
 10/26/2015

 Status:
 Approved

 Date:
 10/27/2015

 Final PDF Date:
 3/11/2016



BU2549

Telephone: (540) 676-5423

		Permit Nur	nber: <u>3912 (Col</u>	umbia Naturai Reso	urces 24545)
		COMPL	ETION REPORT		
Well type:	Oil 🛭 Gas	Coalbed Meth	ane 🗌 Injectio	on Well	
Date Well Com	pleted: 11/19/200	)3	Total Depth: _DT	D - 5983, LTD - 59°	74
	ing Report if not pre he Drilling Report w		In addition, submi	t any changes in cas	ing or tubing that we
STIMULATIO	N RECORD (Use ad	ditional sheets with	this format, if mor	re than three zones a	re stimulated.)
Stimulated:  ZONE 2:Berea Perforated 47 Formation Brok ISIP 2394 Stimulated:  ZONE 3:Weir Perforated 42 Formation Brok ISIP 1968 Stimulated:	to 58  te down at: 3658  (PSIG) MIN SIP.  Yes	Formation Stimula  Formation Stimula  Formation Stimula  (PSIG) A  PSIG A	verage Downhole 1 ted: 11/4/2003  nulated With: F o. of Perforations PSIG Average Injury verage Downhole 1 ted: 11/11/200  ulated With: Fo o. of Perforations PSIG Average Inj	48 Perforate   ection Rate: 7770 Injection Pressure    oam and sand   50 Perforate   ection Rate: 40 B Injection Pressure   3  oam and sand   24 Perforate   ection Rate: 30 B Injection Pressure	(PSIG)   (
FINAL RODU	CTION:	Natural _x	Aft	er Stimulation	
	BOD	MCFD	HOURS TESTED	ROCK PRESSURE	HOURS TESTED
ZONE (1)					
ZONE (2)					
ZONE (3)					
Final production	n if gas zones are cor		MCF	D <u>48</u>	Iours Tested
Permittee: Cø	Ambia Natural Day	_550	PS16	<u>144</u> H	Iours Tested
Permittee: Co	Jumbia Natural Reso	ources, ELC	(Company) (Signature) Date:	1/6/1- 2	
Form DGO-GØ-15 Rev. 1/98	Sign ( JALLELIA)	<u> </u>	(Signature) Date:	ENTER	ED



Telephone: (540) 676-5423

Aw) 2/5/04 GWJ

Permit Number: 5912 Columbia Natural Resources 24545 **COMPLETION REPORT** Well type: Oil ⊠ Gas Coalbed Methane Injection Well Date Well Completed: 11/19/2003 Total Depth: <u>DTD - 5983, LTD - 5974</u> Attach the Drilling Report if not previously submitted. In addition, submit any changes in casing or tubing that were approved after the Drilling Report was submitted. STIMULATION RECORD (Use additional sheets with this format, if more than three zones are stimulated.) ZONE 1:Zone 4 Maxon sand Formation Stimulated With: Natural Perforated to No. of Perforation Stimulated With: Natural Perforated To No. of Perforations Perforation Size

Formation Broke down at: PSIG Average Injection Rate: (PSIG)

ISIP (PSIG) MIN SIP. (PSIG) Average Downhole Injection Pressure (PSIG) Date Stimulated: Stimulated: Yes No Formation Stimulated With: ZONE 2: Perforated to No. of Perforation Stimulated With:

Perforated to No. of Perforations Perforation Size

Formation Broke down at: PSIG Average Injection Rate: (PSIG)

ISIP (PSIG) MIN SIP. (PSIG) Average Downhole Injection Pressure (PSIG) Stimulated: Yes No Date Stimulated: ZONE 3:\_\_\_\_ Formation Stimulated With: to \_\_\_\_\_\_ No. of Perforations \_\_\_\_\_ Perforation Size \_\_\_\_ Perforated Formation Broke down at:

PSIG Average Injection Rate:

(PSIG)

ISIP

(PSIG) MIN SIP.

(PSIG) Average Downhole Injection Pressure

(PSIG)

Stimulated:

Yes

No

Date Stimulated: FINAL RODUCTION: x Natural After Stimulation BOD MCFD HOURS ROCK HOURS TESTED PRESSURE **TESTED** 637 72 ZONE (1) Zone 4 650 288 ZONE (2) ZONE (3) Final production if gas zones are commingled MCFD Hours Tested PS16 By: Form DGO-GG/15 Rev. 1/98



BU2549

Telephone: (540) 676-5423

		Permit Nun	nber: <u>5912 (Colu</u>	ımbia Natural Reso	urces 24545)
		COMPL	ETION REPORT		
Well type:	Oil 🛭 Gas	Coalbed Meth	ane	n Well	
Date Well Comp	leted: 11/19/200	)3	Total Depth: DTI	O - 5983, LTD - 597	74
	ng Report if not pre e Drilling Report w		In addition, submit	any changes in cas	ing or tubing that were
STIMULATION	RECORD (Use add	ditional sheets with	this format, if mor	e than three zones a	re stimulated.)
ZONE 1:Lower I Perforated 552 Formation Broke ISIP 2599 ( Stimulated:	0 to <u>58</u> down at: <u>3658</u> PSIG) MIN <u>SIP</u> 2	54 N	verage Downhole I		6 scfm (PSIG)
ZONE 2: <u>Berea</u> Perforated <u>474</u> Formation Broke ISIP <u>2394</u> ( Stimulated:	down at: 2486 PSIG) MIN SIP.		o. of Perforations  PSIG Average Injury  verage Downhole I	njection Pressure	PM (PSIG)
ZONE 3: Weir Perforated 423 Formation Broke ISIP 1968 (Stimulated:	down at: 2330	1863 (PSIG) A	o. of Perforations PSIG Average Injury Verage Downhole In	ection Rate: 30 B	PM (PSIG)
FINAL RODUC	TION:	Natural <u>x</u>	Afte	er Stimulation	
	BOD	MCFD	HOURS TESTED	ROCK PRESSURE	HOURS TESTED
ZONE (1)					
ZONE (2)					
ZONE (3)					
Final production	if gas zones are con	nmingled 765	MCFI	O 48 H	Iours Tested
Permittee: College By: College	umbia Natural Reso	ources, $\alpha = \frac{550}{100}$	PS16 (Company) (Signature) Date:	144 H	Iours Tested
Rev. 1/98					



Telephone: (540) 676-5423

Aw) 2/5/04 GWJ

Permit Number: 5912 Columbia Natural Resources 24545 **COMPLETION REPORT** Well type: Oil ⊠ Gas Coalbed Methane Injection Well Date Well Completed: 11/19/2003 Total Depth: <u>DTD - 5983, LTD - 5974</u> Attach the Drilling Report if not previously submitted. In addition, submit any changes in casing or tubing that were approved after the Drilling Report was submitted. STIMULATION RECORD (Use additional sheets with this format, if more than three zones are stimulated.) ZONE 1:Zone 4 Maxon sand Formation Stimulated With: Natural Perforated to No. of Perforation Stimulated With: Natural Perforated To No. of Perforations Perforation Size

Formation Broke down at: PSIG Average Injection Rate: (PSIG)

ISIP (PSIG) MIN SIP. (PSIG) Average Downhole Injection Pressure (PSIG) Date Stimulated: Stimulated: Yes No Formation Stimulated With: ZONE 2: Perforated to No. of Perforation Stimulated With:

Perforated to No. of Perforations Perforation Size

Formation Broke down at: PSIG Average Injection Rate: (PSIG)

ISIP (PSIG) MIN SIP. (PSIG) Average Downhole Injection Pressure (PSIG) Stimulated: Yes No Date Stimulated: ZONE 3:\_\_\_\_ Formation Stimulated With: to \_\_\_\_\_\_ No. of Perforations \_\_\_\_\_ Perforation Size \_\_\_\_ Perforated Formation Broke down at:

PSIG Average Injection Rate:

(PSIG)

ISIP

(PSIG) MIN SIP.

(PSIG) Average Downhole Injection Pressure

(PSIG)

Stimulated:

Yes

No

Date Stimulated: FINAL RODUCTION: x Natural After Stimulation BOD MCFD HOURS ROCK HOURS TESTED PRESSURE **TESTED** 637 72 ZONE (1) Zone 4 650 288 ZONE (2) ZONE (3) Final production if gas zones are commingled MCFD Hours Tested PS16 By: Form DGO-GG/15 Rev. 1/98



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

Tracking Number:	7807
Company:	Range Resources-Pine Mountain,
File Number:	BU-2549
<b>Operations Name:</b>	24545 W/PL
Operation Type:	Gas
<b>Drilling Report Type:</b>	Original
	l-

# **DRILLING REPORT (DGO-GO-14)**

1. Drilling Data						
Date drilling commenced:	10/21/2003	Drilling Contract	or: GASCO			
Date drilling completed: 10/30/2003		Rig Type: X Ro	otary Cable			
Driller's Total Depth (feet):	5983.00					
Log Total Depth (feet):	5974.00	Formation At Total Dep	oth Java Shale			
2. Final Location Plat (as require	ed by 4 VAC25-	150-360.C.)				
Permitted State Plane X: 104	100698.0000	Final Plat State Plane X:	10400697.0000			
Permitted State Plane Y: 3610548.9700		Final Plat State Plane Y:	3610549.0000			
Plat Previously Submitted Or						
List of Attached Items:						
Description		FileNan	пе			
PLAT		1BU2549_24545 WPL_RR_BUCHANAN.pdf				

Form DGO-GO-14-E

Page 1 of 3

# 3. Geological Data

Fresh Water At:

Depth (in feet)	Rate	Unit of Measure

Salt Water At:

Depth (in feet)	Rate	Unit of Measure

Coal Seams:

List of Attached Items:

Description	FileName		
COAL	2BU2549_24545 WPL_RR_BUCHANAN.pdf		

Gas and Oil Shows:

List of Attached Items:

Description	FileName		
GAS	3BU2549_24545 WPL_RR_BUCHANAN.pdf		

## 4. Geophysical Logs (As required by 4VAC25-150-280.A)

List all logs run: GR/DEN/NEU/IND/NOISE/TEMP/CALIPER/CEMENT BOND/CCL

Did logs disclose vertical locations of a coal seam?

X

### 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName		
SURVEY	3BU2549_24545 WPL_RR_BUCHANAN.pdf		

### 6. Casing and Tubing Program

Form DGO-GO-14-E

Page 2 of 3

List of Attached Items:

Description	FileName		
CASING	4BU2549_24545 WPL_RR_BUCHANAN.pdf		

#### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

8. Drillers Log	
Compiled By:	
List of Attached Items:	
Description	FileName

4BU2549\_24545 WPL\_RR\_BUCHANAN.pdf


### 9. Comments

MATERIAL INSERTED BY DGO [10/26/2015, jhh]

LOG

10. Signature			
Permitee:	Range Resources-Pine Mountain,	Date:	10/26/2015
Signed By:	JASON STDHAM	Title:	******

INTERNAL USE	ONLY		
Submit Date:	10/26/2015		
Status:	<u>A</u>	Date:	10/27/2015
Final PDF Date:	3/7/2016		





Commonwealth of Virginia Department of Mines, Minerals and Energy Division of Gas and Oil P.O. Box 1416; Abingdon, VA 24212 Telephone: (540) 676-5423

	(	Columbia Natural Resources Well # 24545				
	Permit Number: 5912					
		DRILLIN	G REPORT			
ATTACH A FINAL I	LOCATION PLA	T AS REQUIRE	D BY 4 VAC 25-1	50-360.C.		
DRILLING DATA						
Date drilling comment Date drilling complete Total Depth of Well:	ed: 10/30/2003	3	Drilling Contract Rig Type:			lling Cable Tool
GEOLOGICAL DAT  Fresh Water atnc	one Feet damp	GPM/Inch	Stream	_ Feet	GPM/I	Inch Stream
Feet GPM/Inch Salt Water at none Feet GPM/Inch Feet GPM/Inch GPM/Inch				Feet GPM/Inch Stre		
Coal Seams						
NAME	ТОР	воттом	THICKNESS	MINING IN YES	AREA NO	MINED OUT
Unknown	1000	1003	3			

Gas and Oil Shows

FORMATION	TOP	DOTTO! (	THOWNESS	IPF	DDECCIDE	HOURS
FORMATION	TOP	BOTTOM_	THICKNESS	(MCFD/BOPD)	PRESSURE	TESTED
Maxon Sand	2675	2770	95	637 mcfd	650	288
		_				
Cuttings or samples:  are  are not available for examination by a member of the Virginia Division of Mineral Resources  Cuttings or samples:  have  have  not been furnished to the Virginia Division of Mineral Resources						
ELECTRIC LOGS AND SURVEYS						
List logs ran on wellbore: GR, Density, Neutron, Induction, Noise, Temp., Caliper, Cement Bond, CCL						
Did logs disclose vertical location of a coal seam?						

# **SURVEY RESULTS**

	Direction/Distance/		Direction/Distance Degrees From True
Depth Of Survey	Degrees From True Vertical	Depth Of Survey	Vertical
200	1/4		
400	1/4		
600	1/4		
800	1/4		
1007	1/4		
1225	1/4		
1411	1/2		
1600	1/2		
1819	1/2		
2006	1/2		

Use additional sheets as necessary

**CASING AND TUBING PROGRAM** 

FORMATION TOP BOTTOM THICKNESS (MCFD/BOPD) PRESSURE TESTED									
Maxon Sand 2675 2770 95 637 mcfd 650 288									
Cuttings or samples:  are  are not available for examination by a member of the Virginia Division of Mineral Resources  Cuttings or samples:  have  have not been furnished to the Virginia Division of Mineral Resources									
ELECTRIC LOGS AND SURVEYS									
List logs ran on wellbore: GR, Density, Neutron, Induction, Noise, Temp., Caliper, Cement Bond, CCL									
Did logs disclose ve	Did logs disclose vertical location of a coal seam?  Yes No								

# **SURVEY RESULTS**

	Direction/Distance/		Direction/Distance Degrees From True
Depth Of Survey	Degrees From True Vertical	Depth Of Survey	Vertical
200	1/4		
400	1/4		
600	1/4		
800	1/4		
1007	1/4		
1225	1/4		
1411	1/2		
1600	1/2		
1819	1/2		
2006	1/2		

Use additional sheets as necessary

**CASING AND TUBING PROGRAM** 

				Cement	ı	ented		Packers Or
		Casing	Hole	Used In	To Si	ırface	Date	Bridge Plugs
	Casing	Interval	Size	Cu/Ft	Yes	No	Cemented	Kind/Size/Set
Conductor	12 3/4	14	15	driven		$\boxtimes$		
Surface	9 5/8	326	12 1/4	177	$\boxtimes$		10/22/2003	
Water Protection								
Coal Protection	7	2123	8 7/8	393	$  \boxtimes $		10/24/2003	
Other Casing And	4 1/2	5934	6 3/8	270		$\boxtimes$	10/30/2003	
Tubing Left In								
Well								
Liners								

	REMARKS:	Shut down	fishing jobs,	depths and dates,	caving, lost	t circulation,	etc.:	
--	----------	-----------	---------------	-------------------	--------------	----------------	-------	--

Operations Name: Columbia Natural Resources
Permit Number 5912

DRILLER'S LOG

Compiled by: Jason Stidham

		General		D	epth		
Geologic Age	Formation	Lithology	Color	Тор	Bottom	Thickness	Remarks
Pennsylvanian	Various	sand and shale		0	1090	1090	
Pennsylvanian	salt sand	sand and shale		1090	1990	900	
Mississippian	unknown	sand and shale		1990	2675	685	
Mississippian	Maxon	sand		2675	2770	95	
Mississippian	unknown	sand and shale		2770	3530	760	
Mississippian	little lime	limestone		3530	3570	40	
Mississippian	big lime	limestone		3570	4120	550	
Mississippian	Borden	sand and shale	·	4120	4250	130	
Mississippian	Weir	sand		4250	4370	120	
Mississippian	Pocono,coffee	dark shale		4370	4745	375	
Mississippian	berea	sand		4745	4800	55	
Devonian	shale	various shale		4800	5575	775	
Devonian	lower huron	brown shale		5575	5860	285	
Devonian	java	shale		5860	5983	123	

Permittee:	Columbia Natural Resources LLC	(Company)
By:	Ben E Mithe	(Signature)
	<del>/</del>	

				Cement	ı	ented		Packers Or
		Casing	Hole	Used In	To Si	ırface	Date	Bridge Plugs
	Casing	Interval	Size	Cu/Ft	Yes	No	Cemented	Kind/Size/Set
Conductor	12 3/4	14	15	driven		$\boxtimes$		
Surface	9 5/8	326	12 1/4	177	$\boxtimes$		10/22/2003	
Water Protection								
Coal Protection	7	2123	8 7/8	393	$  \boxtimes $		10/24/2003	
Other Casing And	4 1/2	5934	6 3/8	270		$\boxtimes$	10/30/2003	
Tubing Left In								
Well								
Liners								

	REMARKS:	Shut down	fishing jobs,	depths and dates,	caving, lost	t circulation,	etc.:	
--	----------	-----------	---------------	-------------------	--------------	----------------	-------	--

Operations Name: Columbia Natural Resources
Permit Number 5912

DRILLER'S LOG

Compiled by: Jason Stidham

		General		D	epth		
Geologic Age	Formation	Lithology	Color	Тор	Bottom	Thickness	Remarks
Pennsylvanian	Various	sand and shale		0	1090	1090	
Pennsylvanian	salt sand	sand and shale		1090	1990	900	
Mississippian	unknown	sand and shale		1990	2675	685	
Mississippian	Maxon	sand		2675	2770	95	
Mississippian	unknown	sand and shale		2770	3530	760	
Mississippian	little lime	limestone		3530	3570	40	
Mississippian	big lime	limestone		3570	4120	550	
Mississippian	Borden	sand and shale	·	4120	4250	130	
Mississippian	Weir	sand		4250	4370	120	
Mississippian	Pocono,coffee	dark shale		4370	4745	375	
Mississippian	berea	sand		4745	4800	55	
Devonian	shale	various shale		4800	5575	775	
Devonian	lower huron	brown shale		5575	5860	285	
Devonian	java	shale		5860	5983	123	

Permittee:	Columbia Natural Resources LLC	(Company)
By:	Ben E Mithe	(Signature)
	<del>/</del>	



Telephone: (276) 676-5423

	Tracking N	Number:	78	
	Company:	:	Pine Mountain Oil	& Gas
	File Numb	er:	BU-3066	
	Operation	s Name:	Haysi #7 W/PL	
	Operation	Type:	Coalbed/Pipeline	
	Completio	n Report Type:	Original	
	COMPLETION RE	PORT (DGO-	-GO-15)	
Well Type:	Coalbed/Pipeline	Date Well Con	npleted: 8/4/2006	
Driller's Total Depth:	2,160	Log's Total De	epth: 0	_
1. Changes In Casing/Tu	ubing from Approved Drill	ling Report		
Des	scription		FileName	
2. Stimulation Record				
✓ Stimulated	Not Stimulated	Gob		
	scription		FileName	
Н	IAYSI 7	HA	AYSI 7 COMPLETION	ON.pdf
3. Final Production				
	scription		FileName	
Н	IAYSI 7	H.	AYSI 7 FINAL PRO	DD.jpg
4. Comments				
Notes:				
5. Signature				
Permittee: Pine Mount	ain Oil & Gas	ate: 2/1/2007 2	2:53:05 PM	(Company)

Form DGO-GO-15-E

Rev. 1/2007

Page 1 Of 2

Bv:	CHRISTIAN MOORE	Title: MANAGER	(Signature)

INTERNAL USE ONLY

Submit Date: 2/1/2007

Status: Inspr Approved Date: 2/2/2007

Final PDF Date: 2/2/2007

Form DGO-GO-15-E Rev. 1/2007 Page 2 Of 2



Commonwealth of Virginia Department of Mines, Minerals and Energy Division of Gas and Oil P.O. Box 1416; Abingdon, VA 24212 Telephone: (276) 676-5423 BU-3066

			Permit N	lumber: _	7233- Haysi	7	
			COMP	LETION	REPORT		
Well type:	Oil	Gas	Coalbed Me	ethane [	Injection	Well	
Date Well	Completed	8/4/06		_ Total D	epth: 2160		
			eviously submitted was submitted.	d. In addit	ion, submit a	any changes in o	casing or tubing that wer
STIMULA	TION REC	ORD (Use a	dditional sheets wi	ith this for	mat, if more	than three zone	s are stimulated.)
ZONE 1:	Poca 1				Formation	n Stimulated W	ith: 70Q N2 Foam
Perforated	2004	to 2008	feet	No. of Per			ration Size 0.49
Formation :						ction Rate: 6.	
ISIP <u>1775</u>	_ PSIG	5 Min SI	P N/A PSIG	Averag	ge Downhole	Injection Press	ure 3066 PSIG
Stimulated:	⊠ Yes	š	No Date Stimu	ılated:	8/4/06		
ZONE 2:	Poca 3				Formation	Stimulated W	ith: 70Q N2 Foam
Perforated	1877.5	to 1882	feet	No. of Per	rforations	18 Perfor	ration Size 0.33
Formation 1	Broke down	n at: 3191	PSIG		Average Inje	ction Rate: 9.	1 BPM
ISIP _1650	_ PSIG	5 Min SI	P N/A PSIG	Averag	e Downhole	Injection Press	ure 3327 PSIG
Stimulated:	Yes	3 🔲 ]	No Date Stimu	ılated:	8/4/06		
70NF 3	War Creek	Rockley &	Lower Horsepen		Formation	Stimulated W	ith: 70Q N2 Foam
Perforated	1406.5	to 1560		No. of Per			ration Size 0.33
Formation 1		_				ction Rate: 13	-
ISIP 1892			P 1890 PSIG				
Stimulated:			No Date Stimu		8/4/06		
				_			
FINAL PRO	DUCTION	:	Natural		After	Stimulation	
		BOD	MCFD	Н	OURS	ROCK	HOURS
					STED	PRESSURE	TESTED
ZONE (1)							
ZONE (2)							
ZONE (3)							
Final produ	ction if gas	zones are co	mmingled	37	MCFD	In-line	Hours Tested
				150	PSIG	24	Hours Tested
Permittee:	Pine Mon	untain Oil &	Gas, Inc.	(Compa	nny)		CEIVED
By:	U	uetri [	)h_	_ ,	ure) Date: _	16 No	V 06
Form DGO-GO	-15						( MON 50 SONE)

ZONE 4:	Upper Seaboa	ard, Greasy	Creek & Uppe	r Horsepen	Formatic	on Stimul	lated With:	70Q N	2 Foam
Perforated	983.5 to	1276	feet	No. of Perfo	rations	19	Perforation	Size	0.33
Formation 1	Broke down at	: 2421	PSIG	Av	erage Inj	ection Ra	ate:	BPM	
ISIP	PSIG	5 Min SIP	1127 PSIG	Average I	Downhol	e Injectio	n Pressure	3881	PSIG
Stimulated:	Yes Yes	☐ No	Date Stim	nulated: 8/	4/06				

37	MCFD _	In-line	_ Hours Tested
150	PSIG _	24	_ Hours Tested
	37 150	A Section Contraction	



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil

P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

Tracking Number:	100
Company:	Pine Mountain Oil & Gas
File Number:	BU-3066
Operations Name:	Haysi #7 W/PL
Operation Type:	Coalbed/Pipeline
<b>Drilling Report Type:</b>	Original

# **DRILLING REPORT (DGO-GO-14)**

1. Drilling Data					
Date drilling commenced:	5/14/2006	<ul> <li>Drilling Contractor:</li> </ul>	NOAH HORN		
Date drilling completed:	5/18/2006	-	Rotary ☐ Cable Tool		
Driller's Total Depth (feet):	2,160	- Tag Typo.	Color Cable 1001		
Log Total Depth (feet):	0	Coal Seam At Total [	Depth POCAHONTAS #1		
		-			
2. Final Location Plat (as req	uired by 4 VAC2	5-150-360.C.)			
Permitted State Plane X 923	3,168	Final Plat State Plane	e X: <u>923,174</u>		
Permitted State Plane Y: 340	0,730	Final Plat State Plane	e Y: <u>340,736</u>		
☐ Plat Previously Submitted Or					
List of Attached Items:					
Description FileName					
Descrip	tion		i licitallic		
Descrip HAYS		HAYSI 7 WELI	LOCATION PLAT (FINAL).pdf		
		HAYSI 7 WELI			
HAYS		HAYSI 7 WELI			
HAYS  3. Geological Data  Fresh Water At:	17		LOCATION PLAT (FINAL).pdf		
HAYS  3. Geological Data  Fresh Water At:		HAYSI 7 WELI			
HAYS  3. Geological Data  Fresh Water At:	(in feet)	Rate	LOCATION PLAT (FINAL).pdf Unit of Measure		
HAYS  3. Geological Data  Fresh Water At:  Depth  Salt Water At:	(in feet)	<b>Rate</b> 1/4	Unit of Measure INCH		
HAYS  3. Geological Data  Fresh Water At:  Depth  Salt Water At:	(in feet)	Rate	LOCATION PLAT (FINAL).pdf Unit of Measure		

#### Coal Seams

List of Attached Items:

Description	FileName
HAYSI 7	HAYSI 7 COAL SEAMS.jpg

#### Gas and Oil Shows

List of Attached Items:

Description	FileName
HAYSI 7	HAYSI 7 GAS AND OIL SHOW.JPG

#### **4. Electric Logs** (As required by 4VAC25-150-280.A.)

List all logs run: HI RES GR/DENS/TEMP/AUDIO/PE/CALIPER (DATA PACK)

Did logs disclose vertical locations of a coal seam? ✓ Yes □ No

### **5. Survey Results** (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName

### 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
HAYSI 7	HAYSI 7 CASING AND TUBING.jpg

#### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

10 1/2" HOLE,BASKET@44',CIRC 9BBL SLURRY. 6 1/2" HOLE,BASKET @JOINTS 9,18,&27,CIRC 6 BBLS SLURRY TO SURF.

#### 8. Drillers Log

Compiled By: DENNY JOHNSON

List of Attached Items:

Description	FileName
HAYSI 7	HAYSI 7 DRILLERS LOG.jpg

Form DGO-GO-14-E

### 9. Comments

DEVIATION LOG DELAYED INDEFINITELY.

10. Signature

Permitee: Pine Mountain Oil & Gas Date: 2/1/2007 (Company)

Signed By: CHRISTIAN MOORE Title: MANAGER (Signature)

INTERNAL USE ONLY

Submit Date: 2/1/2007


Status: Inspr Approved Date: 2/2/2007

Final PDF Date: 2/13/2007

Form DGO-GO-14-E

Page 3 of 3

CU-301de



WELL LOCATION PLAT

COMPANY Pine Mountain Oil & Gas, Inc. WELL NAME AND NUMBER Haysi-7 TRACT NO. Carl Raines ELEVATION 1.702.22' QUADRANGLE Prater COUNTY Buchanan DISTRICT Prater SCALE 1'' = 400' DATE 5-26-2006 This Plat is a new plat \_\_\_; an updated plat \_\_\_; or a final location plat \_\_x \_\_\_ Denotes the location of a well on United States topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown.

# Coal Seams

TOP	BOTTOM	Saffered William Trailings			<b>MINED</b>
	DOLLOM	THICKNESS	YES	NO	OUT
763	766			X	
804	805			X	
870	871			X	
982	984			X	
1132	1135			X	
1272	1273			X	
1405	1405			X	
1503	1504			X	
1567	1568			X	
1878	1881			X	
2004	2007			X	
	804 870 982 1132 1272 1405 1503 1567 1878	804     805       870     871       982     984       1132     1135       1272     1273       1405     1405       1503     1504       1567     1568       1878     1881	804     805       870     871       982     984       1132     1135       1272     1273       1405     1405       1503     1504       1567     1568       1878     1881	804     805       870     871       982     984       1132     1135       1272     1273       1405     1405       1503     1504       1567     1568       1878     1881	804       805       X         870       871       X         982       984       X         1132       1135       X         1272       1273       X         1405       1405       X         1503       1504       X         1567       1568       X         1878       1881       X

# Gas and Oil Shows

FORMATION	ТОР	воттом	THICKNESS	IPF (MCFD/BOPD)	PRESSURE	HOURS TESTED
TD				70M w/ CSG		

# CASING AND TUBING PROGRAM

		Casing	Hole	Cement Used In	Cemented To Surface		Date	Packers Or Bridge Plugs
	Casing	Interval	Size	Cu/Ft	Yes	No	Cemented	Kind/Size/Set
Conductor	113/4"	0-18'	15"					
Surface	85/8"	0-393'	101/2"	173	Yes		5/15/06	
Water Protection								
Coal Protection	41/2"	0-2106'	61/2"	421	Yes		5/18/06	
Other Casing And								
Tubing Left In Well								
Liners								

DRILLER'S LOG

Compiled by: Denny Johnson

		General		Depth			
Geologic Age	Formation	Lithology	Color	Top	Bottom	Thickness	Remarks
	Jawbone Rider			763	766		
	Jawbone			804	805		
	Tiller			870	871		
	Upper Seaboard			982	984		
	Greasy Creek			1132	1135		
	Upper Horsepen			1272	1273		
	Warcreek			1405	1405		
	Beckley			1503	1504		
	Lower Horsepen			1567	1568		
	Poco 3			1878	1881		
	Poco 1			2004	2007		



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

Tracking	Number:	7846
		7010

Company: Range Resources-Pine

Mountain,

File Number: BU-3065

**Completion Report Type:** Original

## **COMPLETION REPORT (DGO-GO-15)**

Well Type: Coalbed/Pipeline Date Well Completed: 5/18/2006

**Driller's Total Depth:** 2400.00 **Log's Total Depth:** 2400.00

## 1. Changes In Casing/Tubing from Approved Drilling Report

Description	FileName
,	

#### 2. Stimulation Record

Stimulation Status: 

Stimulated GOB Not Stimulated Service Well

Description	FileName		
STIM	5BU3065_Haysi9_WPL_RR_BUCHANAN.pdf		

## 3. Final Production

Description	FileName
FINAL	5BU3065_Haysi9_WPL_RR_BUCHANAN.pdf

#### 4. Comments

Form DGO-GO-15-E

Rev. 04/2009

Notes:				
MATERIAL	INSERTED BY DGO [11/19/2	2015, jhh]		
i. Signature				
Permittee:	Range Resources-Pine Mountain,	Date:	11/19/2015	(Company)

Title:

(Signature)

**DENNY JOHNSON** 

Ву:





Commonwealth of Virginia
Department of Mines, Minerals and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212
Telephone: (276) 676-5423

(AUG 3.1 2006)	] ]				Form DGO-GO-15 Rev. 1/98
RECEIVED	28 Ave	(Company) (Signature) Date:	Gas, Inc.	Pine Mountain Oil &	Permittee: By:
Hours Tested	120 H	PSIG	92		
Hours Tested	Vent H	MCFD	mmingled 64	Final production if gas zones are commingled	Final product
					ZONE (3)
					ZONE (1)
HOURS TESTED	ROCK PRESSURE	HOURS TESTED	MCFD	BOD	
	After Stimulation	After	Natural	DUCTION:	FINAL PRODUCTION:
0Q N2 Foam ion Size 0.33 (BPM) 3216 (PSIG)	.7 m 2	ge IG	L. Horsepen, Poco 9 1844.5 No. o. 95 1877 (PSIG) Avera No Date Stimulated:	ZONE 3 Warcreek, Beckley, L. Horsepen, Poco 9 Perforated 1616.5 to 1844.5 1 Formation Broke down at: 2685 ISIP 2390 (PSIG) MIN SIP. 1877 (PSIG) / Stimulated: Yes  No Date Stimul	ZONE 3 Perforated Formation By ISIP 2390 Stimulated:
With 70Q N2 Foam Perforation Size 0.33 : 13.7 (BPM) essure 3877 (PSIG)	Formation Stimulated With 70Q N2 Foam erforations 22 Perforation Size 0.3 Average Injection Rate: 13.7 (B) Downhole Injection Pressure 3877 (1) 5/18/06	ege FD FD	5.5 712 Da	ZONE 2 Poco 4, Poco 4 & Poco 3 Perforated 1997.5 to 2095 Formation Broke down at: 3494 ISIP 2687 (PSIG) MIN SIP. 17 Stimulated: X Yes No	ZONE 2 Perforated Formation By ISIP 2687 Stimulated:
0Q N2 Foam ion Size 0.49 (BPM) 2596 (PSIG)	2 # 7	88 G F	2219.5 No. o. ps. ps. 1953 (PSIG) Avera No Date Stimulated:	ZONE 1 Poco 1 Perforated 2215 to 2: Formation Broke down at: 2043 ISIP 2307 (PSIG) MIN SIP. Stimulated: Yes	ZONE 1 Perforated Formation By ISIP 2307 Stimulated:
e stimulated.)	than three zones ar	n this format, if more	lditional sheets with	STIMULATION RECORD (Use additional sheets with this format, if more than three zones are stimulated.)	STIMULATI
In addition, submit any changes in casing or tubing that were	any changes in casi		eviously submitted.	Attach the Drilling Report if not previously submitted. approved after the Drilling Report was submitted.	Attach the Di approved after
		Total Depth: 2400		ompleted: 5/18/06	Date Well Completed:
	Well	hane 🔲 Injection Well		Oil Gas	Well type:
		COMPLETION REPORT	COMPL		
		mber:	Permit Number:		

ZONE 4	Upper Seaboar	d, Greas	sy Crk., U	U. Hpen		Formation S	Stimulated	With	70Q N2 Fo	am
Perforated .	1195.5	to 14	85.5	-	No. of P	erforations	18	Perfora	ation Size	0.33
Formation B	roke down at:	1650			PSIG	Average Inj	ection Rat	e: 21.	.4	(BPM)
ISIP 2780	_(PSIG) MIN	SIP.	2527	(PSIG)	Average	Downhole l	Injection P	ressure	3749	(PSIG)
Stimulated:	Yes		lo Da	ate Stimu	ılated:	5/18/06				
ZONE 5	Aily, Raven, Jl	B Rider,	Jawbone	e, Tiller		Formation S	Stimulated	With	70Q N2 Fo	am
Perforated	786.5	to 10	87		No. of P	erforations	32	Perfora	ation Size	0.33
	roke down at:									(BPM)
	_(PSIG) MIN						Injection P	ressure	2616	(PSIG)
Stimulated:	⊠ Yes	$\square$ N	lo Da	ate Stimu	ılated:	5/18/06				





Commonwealth of Virginia
Department of Mines, Minerals and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212
Telephone: (276) 676-5423

(AUG 3.1 2006)	] ]				Form DGO-GO-15 Rev. 1/98
RECEIVED	28 Ave	(Company) (Signature) Date:	Gas, Inc.	Pine Mountain Oil &	Permittee: By:
Hours Tested	120 H	PSIG	92		
Hours Tested	Vent H	MCFD	mmingled 64	Final production if gas zones are commingled	Final product
					ZONE (3)
					ZONE (1)
HOURS TESTED	ROCK PRESSURE	HOURS TESTED	MCFD	BOD	
	After Stimulation	After	Natural	DUCTION:	FINAL PRODUCTION:
0Q N2 Foam ion Size 0.33 (BPM) 3216 (PSIG)	.7 m 2	ge IG	L. Horsepen, Poco 9 1844.5 No. o. 95 1877 (PSIG) Avera No Date Stimulated:	ZONE 3 Warcreek, Beckley, L. Horsepen, Poco 9 Perforated 1616.5 to 1844.5 1 Formation Broke down at: 2685 ISIP 2390 (PSIG) MIN SIP. 1877 (PSIG) / Stimulated: Yes  No Date Stimul	ZONE 3 Perforated Formation By ISIP 2390 Stimulated:
With 70Q N2 Foam Perforation Size 0.33 : 13.7 (BPM) essure 3877 (PSIG)	Formation Stimulated With 70Q N2 Foam erforations 22 Perforation Size 0.3 Average Injection Rate: 13.7 (B) Downhole Injection Pressure 3877 (1) 5/18/06	ege FD FD	5.5 712 Da	ZONE 2 Poco 4, Poco 4 & Poco 3 Perforated 1997.5 to 2095 Formation Broke down at: 3494 ISIP 2687 (PSIG) MIN SIP. 17 Stimulated: X Yes No	ZONE 2 Perforated Formation By ISIP 2687 Stimulated:
0Q N2 Foam ion Size 0.49 (BPM) 2596 (PSIG)	2 # 7	88 G F	2219.5 No. o. ps. ps. 1953 (PSIG) Avera No Date Stimulated:	ZONE 1 Poco 1 Perforated 2215 to 2: Formation Broke down at: 2043 ISIP 2307 (PSIG) MIN SIP. Stimulated: Yes	ZONE 1 Perforated Formation By ISIP 2307 Stimulated:
e stimulated.)	than three zones ar	n this format, if more	lditional sheets with	STIMULATION RECORD (Use additional sheets with this format, if more than three zones are stimulated.)	STIMULATI
In addition, submit any changes in casing or tubing that were	any changes in casi		eviously submitted.	Attach the Drilling Report if not previously submitted. approved after the Drilling Report was submitted.	Attach the Di approved after
		Total Depth: 2400		ompleted: 5/18/06	Date Well Completed:
	Well	hane 🔲 Injection Well		Oil Gas	Well type:
		COMPLETION REPORT	COMPL		
		mber:	Permit Number:		

ZONE 4	Upper Seaboar	d, Greas	sy Crk., U	U. Hpen		Formation S	Stimulated	With	70Q N2 Fo	am
Perforated .	1195.5	to 14	85.5	-	No. of P	erforations	18	Perfora	ation Size	0.33
Formation B	roke down at:	1650			PSIG	Average Inj	ection Rat	e: 21.	.4	(BPM)
ISIP 2780	_(PSIG) MIN	SIP.	2527	(PSIG)	Average	Downhole 1	Injection P	ressure	3749	(PSIG)
Stimulated:	Yes		lo Da	ate Stimu	ılated:	5/18/06				
ZONE 5	Aily, Raven, Jl	B Rider,	Jawbone	e, Tiller		Formation S	Stimulated	With	70Q N2 Fo	am
Perforated	786.5	to 10	87		No. of P	erforations	32	Perfora	ation Size	0.33
	roke down at:									(BPM)
	_(PSIG) MIN						Injection P	ressure	2616	(PSIG)
Stimulated:	⊠ Yes	$\square$ N	lo Da	ate Stimu	ılated:	5/18/06				



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

Tracking Number: 7900

Company: Range Resources-Pine

Mountain,

File Number: BU-3065

Operations Name: Haysi #9 W/PL

Operation Type: Coalbed/Pipeline

**Drilling Report Type:** Original

## **DRILLING REPORT (DGO-GO-14)**

## 1. Drilling Data

Date drilling commenced: 5/4/2006 Drilling Contractor: NOAH HORN

Date drilling completed: 5/13/2006 Rig Type: 

Rotary 

Cable

Driller's Total Depth (feet): 2400.00

Log Total Depth (feet): 2400.00 Coal Seam at Total POCAHONTAS

Depth: #1

## 2. Final Location Plat (as required by 4 VAC25-150-360.C.)

Permitted State Plane X: 10405025.0100 Final Plat State Plane X: 10405025.0000

Permitted State Plane Y: 3621223.8800 Final Plat State Plane Y: 3621223.0000

Plat Previously Submitted Or...

List of Attached Items:

Form DGO-GO-14-E

Page 1 of 4

Rev. 04/2009

Description	FileName
PLAT	1BU3065_Haysi9_WPL_RR_BUCHANAN.pdf

## 3. Geological Data

Fresh Water At:

Depth (in feet)	Rate	Unit of Measure

## Salt Water At:

Depth (in feet)	Rate	Unit of Measure
1290	DAMP	

## Coal Seams:

List of Attached Items:

Description	FileName
COAL	2BU3065_Haysi9_WPL_RR_BUCHANAN.pdf

## Gas and Oil Shows:

List of Attached Items:

Description	FileName
GAS	3BU3065_Haysi9_WPL_RR_BUCHANAN.pdf

## 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run: GR/DEN/TEMP/AUDIO/PE/CAL

Did logs disclose vertical locations of a coal

seam?

 $\overline{\checkmark}$ 

## 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName
SURVEY	3BU3065_Haysi9_WPL_RR_BUCHANAN.pdf

## 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
CASING	4BU3065_Haysi9_WPL_RR_BUCHANAN.pdf

## 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

8. Drillers Log			
Compiled By:			

List of Attached Items:

Description	FileName
LOG	4BU3065_Haysi9_WPL_RR_BUCHANAN.pdf

## 9. Comments

MATERIAL INSERTED BY DGO [11/19/2015, jhh]

10. Signature			
Permitee:	Range Resources-Pine Mountain,	Date:	11/19/2015
Signed By:	DENNY JOHNSON	Title:	******

INTERNAL USE	ONLY		
Submit Date:	11/19/2015	_	
Status:	A	Date:	11/19/2015
0.0.00.		-	


Form DGO-GO-14-E

Page 3 of 4

Rev. 04/2009

Final PDF Date: 11/19/2015

BU-3065



WELL LOCATION PLAT

COMPANY Pine Mountain Oil & Gas, Inc. WELL NAME AND NUMBER Haysi-9	
TRACT NO. Big Sandy Fuel Corp. ELEVATION 1,895.52' QUADRANGLE Prater	
COUNTY <u>Buchanan</u> DISTRICT <u>Prater</u> SCALE $1" = 400'$ DATE $5-17-200$	6
This Plat is a new plat; an updated plat; or a final location plat _x	
+ Denotes the location of a well on United States topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown.	
and the	

Licensed Professional Engineer or Licensed Land Surveyor





Commonwealth of Virginia
Department of Mines, Minerals and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212

	٠.	
	Operations Name: Haysi 9	I
	Haysi	elephone:
The second secon	9	(276) 676-5423
		23
-		1

# DRILLING REPORT

Permit Number:

7232

ATTACH A FINAL LOCATION PLAT AS REQUIRED BY 4 VAC 25-150-360.C.

I	t			į
١	Ė	•	Ę	_
l	ĺ			
ĺ	Į			
ı	Į			
ļ	٠	2	7	
l	(			
١	t			
Į	ŀ	j		,
l	-	•		
I	۰	Ì		•
•	•			

	いんパー	\ \				
	A CELLY	<b>\</b>				
	X			2218	2216	Poco 1
	×			2095	2091	Poco 3
	X			2027	2025	Poco 4
	×			1998	1998	Poco 4
	×			1843	1843	Poco 9
-	X			1754	1753	Lower Horsepen
	X			1713	1713	Beckley
	X			1617	1617	Warcreek
	×			1485	1485	Upper Horsepen
	×			1346	1345	Greasy Creek
	X			1197	1196	Upper Seaboard
	×			1086	1085	Tiller
	X			1022	1021	Jawbone
	×			983	981	Jawbone Rider
	X			861	860	Raven
	X			788	787	Aily
OUT	NO NO	YES	THICKNESS	воттом	TOP	NAME
MNED	NADEA	MINIMUC INI ADEA				Coar Seams
PM/Inch Stream	GPM/I	Feet	Stream	GPM/Inch Stream	Feet	
PM/Inch Stream	GPM/I	Feet	Stream	GPM/Inch Stream	Feet Damp	Salt Water at 1290
GPM/Inch Stream	GPM/I	Feet	Stream	GPM/Inch Stream	Feet	
PM/Inch Stream	GPM/I	Feet	Stream	GPM/Inch Stream	Feet	Fresh Water at
						GEOLOGICAL DATA
		-			2400	Total Depth of Well: 2
Cable Tool		Rotar	Rig Type: [		5/13/06	Date drilling completed:
	Noah Horn		<b>Drilling Contractor:</b>		d: 5/04/06	Date drilling commenced:

# Gas and Oil Shows

				<del>,</del>	<del>,                                      </del>			
		}		IPF		HOURS		
FORMATION	TOP	воттом	THICKNESS	(MCFD/BOPD)	PRESSURE	TESTED		
TD				70 M w/ Csg	:			
		:						
Cuttings or samples: are are not available for examination by a member of the Virginia Division of Mineral Resources  Cuttings or samples: have have not been furnished to the Virginia Division of Mineral Resources								
ELECTRIC LOGS AND SURVEYS								
List logs ran on wellbore: Hi Res GR/Dens/Temp/Audio/Pe/Caliper (Data Pack)								
Did logs disclose vertical location of a coal seam?								
SURVEY RESULTS								
<del></del>		<del></del>						

D. 4. OCC	Direction/Distance/	D 41 000	Direction/Distance Degrees From True
Depth Of Survey	Degrees From True Vertical	Depth Of Survey	Vertical

Use additional sheets as necessary

# Gas and Oil Shows

				<del>,</del>	<del>,                                      </del>			
		}		IPF		HOURS		
FORMATION	TOP	воттом	THICKNESS	(MCFD/BOPD)	PRESSURE	TESTED		
TD				70 M w/ Csg	:			
		:						
Cuttings or samples: are are not available for examination by a member of the Virginia Division of Mineral Resources  Cuttings or samples: have have not been furnished to the Virginia Division of Mineral Resources								
ELECTRIC LOGS AND SURVEYS								
List logs ran on wellbore: Hi Res GR/Dens/Temp/Audio/Pe/Caliper (Data Pack)								
Did logs disclose vertical location of a coal seam?								
SURVEY RESULTS								
<del></del>		<del></del>						

D. 4. OCC	Direction/Distance/	D 41 000	Direction/Distance Degrees From True
Depth Of Survey	Degrees From True Vertical	Depth Of Survey	Vertical

Use additional sheets as necessary

CASING AND TUBING PROGRAM

				Cement	Cemented			Packers Or	
		Casing	Hole	Used In	To Su	ırface	Date	Bridge Plugs	
	Casing	Interval	Size	Cu/Ft	Yes	No	Cemented	Kind/Size/Set	
Conductor	113/4"	0-17'	15"						
Surface	85/8"	0-309'	10½"	107	Yes		5/04/06		
Water Protection									
Coal Protection	41/2"	0-2325'	61/2"	472	Yes		4/23/06		
Other Casing And									
Tubing Left In Well									
Liners									

REMARKS: 10½" Hole, basket@30', circ 1 bbls to surf. 6½ hole, baskets@ Jts 9,17&27, circ 6 bbls slurry to surf.

Operations Name: Haysi 9
Permit Number 7232

# **DRILLER'S LOG**

Compiled by: Denny Johnson

		General			Depth		
Geologic Age	Formation	Lithology	Color	Тор	Bottom	Thickness	Remarks
	Aily			787	788		
	Raven			860	861		
	Jawbone Rider			981	983		-
	Jawbone			1021	1022		
	Tiller			1085	1086		
	Upper Seaboard			1196	1197		
	Greasy Creek			1345	1346		
	Upper Horsepen	·		1485	1485		
	Warcreek			1617	1617		
	Beckley			1713	1713		
	Lower Horsepen			1753	1754		
	Poco 9			1843	1843		
	Poco 4			1998	1998		
	Poco 4			2025	2027		
	Poco 3			2091	2095		
	Poco 1			2216	2218		

Permittee:	Pine Mountain Oil & Gas	(Company)
By:	CutaDh	(Signature)

CASING AND TUBING PROGRAM

				Cement	Cemented			Packers Or	
		Casing	Hole	Used In	To Su	ırface	Date	Bridge Plugs	
	Casing	Interval	Size	Cu/Ft	Yes	No	Cemented	Kind/Size/Set	
Conductor	113/4"	0-17'	15"						
Surface	85/8"	0-309'	10½"	107	Yes		5/04/06		
Water Protection									
Coal Protection	41/2"	0-2325'	61/2"	472	Yes		4/23/06		
Other Casing And									
Tubing Left In Well									
Liners									

REMARKS: 10½" Hole, basket@30', circ 1 bbls to surf. 6½ hole, baskets@ Jts 9,17&27, circ 6 bbls slurry to surf.

Operations Name: Haysi 9
Permit Number 7232

# **DRILLER'S LOG**

Compiled by: Denny Johnson

		General			Depth		
Geologic Age	Formation	Lithology	Color	Тор	Bottom	Thickness	Remarks
	Aily			787	788		
	Raven			860	861		
	Jawbone Rider			981	983		-
	Jawbone			1021	1022		
	Tiller			1085	1086		
	Upper Seaboard			1196	1197		
	Greasy Creek			1345	1346		
	Upper Horsepen	·		1485	1485		
	Warcreek			1617	1617		
	Beckley			1713	1713		
	Lower Horsepen			1753	1754		
	Poco 9			1843	1843		
	Poco 4			1998	1998		
	Poco 4			2025	2027		
	Poco 3			2091	2095		
	Poco 1			2216	2218		

Permittee:	Pine Mountain Oil & Gas	(Company)
By:	CutaDh	(Signature)



Commonwealth of Virginia
Department of Mines, Minerals, and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

	Tracking I	Number:	594			
	Company		Pine Mountain Oil	& Gas		
	File Numb	er:	BU-3165			
	Operation	Operations Name:		Haysi #17 W/PL		
	Operation	Type:	Coalbed/Pipeline			
	Completio	n Report Type:	Original			
	COMPLETION RE	PORT (DGO	-GO-15)			
Well Type:	Coalbed/Pipeline	Date Well Cor	npleted: 1/18/2007	7		
Driller's Total Depth:	2,454	Log's Total De	epth: 2,438			
l. Changes In Casing/Tub	oing from Approved Dril	ling Report				
Desc	ription		FileName			
Haysi 17 C	Comp. Casing	Ha	aysi 17 Comp Casi	ng.doc		
2. Stimulation Record						
☐ Stimulated ☐ I	Not Stimulated	Gob				
	ription		FileName			
Haysi 17	Stimulation	Haysi 17 Stimulation.doc				
3. Final Production						
Desc	ription		FileName			
Haysi 17	Final Prod.		Haysi 17 Final Prod	d.xls		
I. Comments						
Notes:						
110100.						
5. Signature						
Permittee: Pine Mountai	n Oil & Gas D	oate: 8/16/2007	2:21:06 PM	(Company)		

Form DGO-GO-15-E

Rev. 1/2007

By:	Christian D. Moore	Title: Permit/GIS Specialist	(Signature)
-----	--------------------	------------------------------	-------------

INTERNAL USE ONLY

Submit Date: 8/16/2007

Status: Inspr Approved Date: 8/30/2007

Final PDF Date: 8/30/2007

Form DGO-GO-15-E

Rev. 1/2007

# CASING AND TUBING PROGRAM

				Cement	Ceme	ented		Packers Or
		Casing	Hole	Used In	To Su	ırface	Date	Bridge Plugs
	Casing	Interval	Size	Cu/Ft	Yes	No	Cemented	Kind/Size/Set
Conductor	113/4"	15'	15"					
Surface	85/8"	395'	11"	155	Yes		1/2/07	
Water Protection	41/2"	2405'	61/2/61/4"	488	Yes		1/8/07	
Coal Protection								
Other Casing And	23/8"	2349'						
Tubing Left In Well								
Liners								

# STIMULATION RECORD

ZONE 1: Poco 2 & 1	Formation Stimulated With:	Gel
	erforations 5 Perforation	
Formation Broke down at: 2533 PSIG	Average Injection Rate: 14	BPM
ISIP 1643 PSIG 5 Min SIP 1555 PSIG Avera	ige Downhole Injection Pressure	3300 PSIG
Stimulated:  Yes	1/18/07	
ZONE 2: Poco 4 & 3	Formation Stimulated With:	Gel
	erforations 13 Perforation	
Formation Broke down at: 3480 PSIG		
ISIP 1959 PSIG 5 Min SIP 1777 PSIG Avera	ige Downhole Injection Pressure	3600 PSIG
Stimulated: Yes	1/18/07	
		G 1
ZONE 3: Lower Horsepen x2, War Creek & Beckley		Gel
Perforated 1742 to 1855.5 feet No. of P	erforations 26 Perforation	n Size <u>0.33</u>
Formation Broke down at: 2282 PSIG	Average Injection Rate: 20	BPM
ISIP 1465 PSIG 5 Min SIP 1348 PSIG Avera	•	2400 PSIG
Stimulated: No Date Stimulated:	1/18/07	
ZONE 4: Greasy Creek, Upper & Middle Horsepen		~ .
	Formation Stimulated With:	Gel
Perforated 1442 to 1661.5 feet No of P	Formation Stimulated With: erforations 27 Perforation	Gel n Size 0.33
Perforated 1442 to 1661.5 feet No. of P	erforations 27 Perforation	n Size 0.33
Perforated 1442 to 1661.5 feet No. of P	erforations 27 Perforation	n Size 0.33
Perforated 1442 to 1661.5 feet No. of Promation Broke down at: 2249 PSIG ISIP 1482 PSIG 5 Min SIP 1383 PSIG Average	erforations 27 Perforation Average Injection Rate: 20 age Downhole Injection Pressure	n Size 0.33
Perforated 1442 to 1661.5 feet No. of P	erforations 27 Perforation Average Injection Rate: 20 age Downhole Injection Pressure	n Size 0.33
Perforated 1442 to 1661.5 feet No. of Promation Broke down at: 2249 PSIG ISIP 1482 PSIG 5 Min SIP 1383 PSIG Average	erforations 27 Perforation Average Injection Rate: 20 age Downhole Injection Pressure 1/18/07	n Size 0.33
Perforated 1442 to 1661.5 feet No. of Perforation Broke down at: 2249 PSIG  ISIP 1482 PSIG 5 Min SIP 1383 PSIG Avera  Stimulated: Yes No Date Stimulated:  ZONE 5: JB Rider, Jawbone, Tiller & Upper Seaboard  Perforated 1082.5 to 1310 feet No. of P	erforations 27 Perforation Average Injection Rate: 20 age Downhole Injection Pressure 1/18/07  Formation Stimulated With: erforations 29 Perforation	n Size 0.33 BPM 2843 PSIG  Gel n Size 0.33
Perforated 1442 to 1661.5 feet No. of Perforation Broke down at: 2249 PSIG  ISIP 1482 PSIG 5 Min SIP 1383 PSIG Avera Stimulated: Yes No Date Stimulated:  ZONE 5: JB Rider, Jawbone, Tiller & Upper Seaboard	erforations 27 Perforation Average Injection Rate: 20 age Downhole Injection Pressure 1/18/07  Formation Stimulated With: erforations 29 Perforation	n Size 0.33 BPM 2843 PSIG  Gel n Size 0.33
Perforated 1442 to 1661.5 feet No. of Perforation Broke down at: 2249 PSIG  ISIP 1482 PSIG 5 Min SIP 1383 PSIG Avera  Stimulated: Yes No Date Stimulated:  ZONE 5: JB Rider, Jawbone, Tiller & Upper Seaboard  Perforated 1082.5 to 1310 feet No. of P	erforations 27 Perforation Average Injection Rate: 20 age Downhole Injection Pressure 1/18/07  Formation Stimulated With: Perforations 29 Perforation Average Injection Rate: 17	Size   0.33   BPM   2843   PSIG
Perforated 1442 to 1661.5 feet No. of Promation Broke down at: 2249 PSIG  ISIP 1482 PSIG 5 Min SIP 1383 PSIG Avera Stimulated: No. of Promation Broke down at: 1310 feet No. of Promation Broke down at: 1338 PSIG	Average Injection Rate: 20 age Downhole Injection Pressure 1/18/07  Formation Stimulated With: erforations 29 Perforation Average Injection Rate: 17 age Downhole Injection Pressure	Size   0.33   BPM   2843   PSIG
Perforated 1442 to 1661.5 feet No. of Promation Broke down at: 2249 PSIG  ISIP 1482 PSIG 5 Min SIP 1383 PSIG Avera Stimulated: No. of Promation Broke down at: 2100 No. of Promation Broke down at: 1310 feet No. of Promation Broke down at: 1338 PSIG  ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1338 PSIG  ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1417 PSIG 5 Min SIP 1416 PSIG Avera Stimulated: No. of P	reforations 27 Perforation Average Injection Rate: 20 rege Downhole Injection Pressure 1/18/07  Formation Stimulated With: Perforations 29 Perforation Average Injection Rate: 17 rege Downhole Injection Pressure 1/18/07	Size   0.33   BPM   2843   PSIG
Perforated 1442 to 1661.5 feet No. of Promation Broke down at: 2249 PSIG  ISIP 1482 PSIG 5 Min SIP 1383 PSIG Avera Stimulated: No. of Promation Broke down at: 1380 PSIG Avera Stimulated: No. of Promation Broke down at: 1310 feet No. of Promation Broke down at: 1338 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1380 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1338 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1338 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1338 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1338 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1340 PSIG Avera Stimulated: No. of Promation Broke down at: 1340 PSIG Avera Stimulated: No. of Promation Broke down at: 1340 PSIG Avera Stimulated: No. of PSIG Avera	erforations 27 Perforation Average Injection Rate: 20 age Downhole Injection Pressure 1/18/07  Formation Stimulated With: erforations 29 Perforation Average Injection Rate: 17 age Downhole Injection Pressure 1/18/07  Formation Stimulated With:	Gel n Size 0.33 BPM 2843 PSIG  Gel n Size 0.33 BPM 2492 PSIG  Gel/H2O
Perforated 1442 to 1661.5 feet No. of Promation Broke down at: 2249 PSIG  ISIP 1482 PSIG 5 Min SIP 1383 PSIG Avera Stimulated: No. of Promation Broke down at: 1383 PSIG Avera Stimulated: No. of Promation Broke down at: 1310 feet No. of Promation Broke down at: 1338 PSIG  ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG  ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of PSIG ISIP 1417 PSIG ISIP 141	reforations 27 Perforation Average Injection Rate: 20 rage Downhole Injection Pressure 1/18/07  Formation Stimulated With: Perforations 29 Perforation Average Injection Rate: 17 rage Downhole Injection Pressure 1/18/07  Formation Stimulated With: Perforations 24 Perforation	Size   0.33   BPM   2843   PSIG
Perforated 1442 to 1661.5 feet No. of Promation Broke down at: 2249 PSIG  ISIP 1482 PSIG 5 Min SIP 1383 PSIG Avera Stimulated: No. of Promation Broke down at: 1380 PSIG Avera Stimulated: No. of Promation Broke down at: 1310 feet No. of Promation Broke down at: 1338 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: No. of Promation Broke down at: 1380 PSIG Avera Stimulated: No. of Promation Broke down at: No. of Promation Broke down at: 1925 PSIG	Average Injection Rate: 20 age Downhole Injection Pressure  1/18/07  Formation Stimulated With: erforations 29 Perforation Average Injection Rate: 17 age Downhole Injection Pressure  1/18/07  Formation Stimulated With: erforations 24 Perforation Average Injection Rate: 16	Gel
Perforated 1442 to 1661.5 feet No. of Promation Broke down at: 2249 PSIG  ISIP 1482 PSIG 5 Min SIP 1383 PSIG Avera Stimulated: No. of Promation Broke down at: 1383 PSIG Avera Stimulated: No. of Promation Broke down at: 1310 feet No. of Promation Broke down at: 1338 PSIG  ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG  ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of Promation Broke down at: 1384 PSIG ISIP 1417 PSIG 5 Min SIP 1236 PSIG Avera Stimulated: No. of PSIG ISIP 1417 PSIG ISIP 141	Average Injection Rate: 20 age Downhole Injection Pressure  1/18/07  Formation Stimulated With: erforations 29 Perforation Average Injection Rate: 17 age Downhole Injection Pressure  1/18/07  Formation Stimulated With: erforations 24 Perforation Average Injection Rate: 16	Gel

Final Production After Stimulation				
	BOD	MCFD	<b>Hours Tested</b>	<b>Rock Pressure</b>
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		32	In-Line	120



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil

P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

Tracking Number:	576
Company:	Pine Mountain Oil & Gas
File Number:	BU-3165
Operations Name:	Haysi #17 W/PL
Operation Type:	Coalbed/Pipeline
<b>Drilling Report Type:</b>	Original

## **DRILLING REPORT (DGO-GO-14)**

	DIVILLING	IVE! (	טט-טטט) ואכ	/- 1 <del>-1</del> /			
1. Drilling Data							
Date drilling commenced: 12/29/2006		D	Drilling Contractor: Noah Horn  Rig Type: ✓ Rotary ☐ Cable Tool				
Date drilling completed: 1/8/2007							
Driller's Total Depth (feet):	2,454			•			
Log Total Depth (feet):	2,438	Co	al Seam At Total	Depth POCAHONTAS #1			
2. Final Location Plat (as red	quired by 4 VAC	25-150	-360.C.)				
Permitted State Plane X 91	7,103	Fir	inal Plat State Plane X: 917,098				
Permitted State Plane Y: 33	9,319	Fir	Final Plat State Plane Y: 339,323				
☐ Plat Previously Submitted	Plat Previously Submitted Or						
List of Attached Items:							
Descrip	otion			FileName			
Haysi 17 Plat			Haysi 17 Plat.pdf				
3. Geological Data							
Fresh Water At:							
Depth	(in feet)		Rate	Unit of Measure			
Salt Water At:							
Depth	(in feet)		Rate	Unit of Measure			
	1,414		Damp	GPM			

Form DGO-GO-14-E

Rev. 1/2007

#### Coal Seams

List of Attached Items:

Description	FileName			
Haysi 17 Coals	Haysi 17 Coal.xls			

#### Gas and Oil Shows

List of Attached Items:

Description	FileName			
Haysi 17 Shows	Haysi 17 Shows.xls			

#### **4. Electric Logs** (As required by 4VAC25-150-280.A.)

List all logs run: Hi Res GR/Dens/Temp/Audio/Pe/Caliper (Data Pack)

Did logs disclose vertical locations of a coal seam? ✓ Yes □ No

## **5. Survey Results** (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName			
Haysi 17 Surveys	Haysi 17 Survey.xls			

#### 6. Casing and Tubing Program

List of Attached Items:

Description	FileName		
Haysi 17 Casing	Haysi 17 Casing.xls		

#### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

Circ 3 bbls to surf on 8?" csng. Circ 1 bbl to surf on 41/2" csng.

#### 8. Drillers Log

Compiled By: Noah Horn

List of Attached Items:

Description	FileName			
Haysi 17 Log	Haysi 17 Log.xls			

## 9. Comments

10. Signature

Permitee: Pine Mountain Oil & Gas Date: 7/31/2007 (Company)

Signed By: Christian D. Moore Title: Permit/GIS Specialist (Signature)

INTERNAL USE ONLY


Submit Date: 7/31/2007

Status: Inspr Approved Date: 8/21/2007

Final PDF Date: 8/21/2007

Form DGO-GO-14-E

Rev. 1/2007



#### WELL LOCATION PLAT

COMPANY <u>Pine Mountain Oil &amp; Gas, Inc.</u> WELL NAME AND NUMBER <u>Haysi-17</u> TRACT NO. <u>C.P. Self &amp; M.E. Deel</u> ELEVATION <u>1,911.00</u> ' QUADRANGLE <u>Prater</u>
COUNTY <u>Buchanan</u> DISTRICT <u>Prater</u> SCALE $1" = 400'$ DATE $1-16-2007$
This Plat is a new plat; an updated plat; or a final location platx
Denotes the location of a well on United States topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown.
<sup>1</sup> 24,000, latitude and longitude lines being represented by border lines as shown.
Cham E. Halan

Licensed Professional Engineer or Licensed Land Surveyor

# Coal Seams

					MINING IN AREA			
NAME	TOP	BOTTOM	THICKNESS	YES	NO	MINED OUT		
Kennedy	784	785	1		NO			
Aily Rider	867	868	1		NO			
Aily	896	897	1		NO			
Raven	970	971	1		NO			
Jawbone Rider	1083	1085	2		NO			
Jawbone	1130	1131	1		NO			
Tiller	1189	1190	1		NO			
Upper Seaboard	1307	1309	2		NO			
Greasy Creek	1443	1445	2		NO			
Upper Horsepen	1602	1603	1		NO			
Middle Horsepen	1659	1661	2		NO			
War Creek	1743	1744	1		NO			
Beckley	1812	1813	1		NO			
Lower Horsepen	1846	1847	1		NO			
Lower Horsepen	1854	1855	1		NO			
Poco 4	2113	2114	1		NO			
Poco 3	2196	2199	3		NO			
Poco 2	2264	2265	1		NO			
Poco 1	2301	2302	1		NO			

Gas and Oil Shows

FORMATION	TOP	BOTTOM	THICKNESS	IPF	(MCFD/BOPD)	PRESSURE	HOURS TESTED
Open Hole TD				14M			

Survey Results

Depth of Survey	Direction/Distance/Degree From True Vertical	
210'	0.5°	
420'	0.5	
600'	0.25°	
810'	0.25°	
1020'	0.25°	
1230'	0.25°	
1440'	0.25°	
1650'	0.75°	
1860'	0.75°	
2070'	0.5°	
2310'	0.25°	

Casing Program

	Casing	Casing	Hole	<b>Cement Used</b>	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented
Conductor	11.75	0-15	15			_
Surface	8.625	0-395	11	155	Yes	1/2/2007
Water Protection	4.5	0-2405	6.5/6.25	488	Yes	1/8/2007

Packers Or Bridge Plugs Kind/Size/Set

# Driller's Log

		General		Depth	Depth	
Geologic Age	Formation	Lithology	Color	Тор	Bottom	Thickness
PENN	Lee	SS, SH, Thin Coals		0	784	784
PENN	Lee	Coal		784	785	1
PENN	Lee	SS, SH, Thin Coals		785	867	82
PENN	Lee	Coal		867	868	1
PENN	Lee	SS, SH, Thin Coals		868	896	28
PENN	Lee	Coal		896	897	1
PENN	Lee	SS, SH, Thin Coals		897	970	73
PENN	Lee	Coal		970	971	1
PENN	Lee	SS, SH, Thin Coals		971	1083	112
PENN	Lee	Coal		1083	1085	2
PENN	Lee	SS, SH, Thin Coals		1085	1130	45
PENN	Lee	Coal		1130	1131	1
PENN	Lee	SS, SH, Thin Coals		1131	1189	58
PENN	Lee	Coal		1189	1190	1
PENN	Lee	SS, SH, Thin Coals		1190	1307	117
PENN	Lee	Coal		1307	1309	2
PENN	Lee	SS, SH, Thin Coals		1309	1443	134
PENN	Lee	Coal		1443	1445	2
PENN	Lee	SS, SH, Thin Coals		1445	1602	157
PENN	Lee	Coal		1602	1603	1
PENN	Lee	SS, SH, Thin Coals		1603	1659	56
PENN	Lee	Coal		1659	1661	2
PENN	Lee	SS, SH, Thin Coals		1661	1743	82
PENN	Lee	Coal		1743	1744	1
PENN	Lee	SS, SH, Thin Coals		1744	1812	68
PENN	Lee	Coal		1812	1813	1
PENN	Lee	SS, SH, Thin Coals		1813	1846	33
PENN	Lee	Coal		1846	1847	1
PENN	Lee	SS, SH, Thin Coals		1847	1854	7
PENN	Lee	Coal		1854	1855	1
PENN	Pocahontas	SS, SH, Thin Coals		1855	2113	258
PENN	Pocahontas	Coal		2113	2114	1
PENN	Pocahontas	SS, SH, Thin Coals		2114	2196	82
PENN	Pocahontas	Coal		2196	2199	3
PENN	Pocahontas	SS, SH, Thin Coals		2199	2264	
PENN	Pocahontas	Coal		2264	2265	1
PENN	Pocahontas	SS, SH, Thin Coals		2265		36
PENN	Pocahontas	Coal	1	2301	2302	

Remarks	
Remarks	
	_
	_
	_
	_
	٦



Commonwealth of Virginia
Department of Mines, Minerals, and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

		Tracking No	umber:	596			
		Company:		Pine Mountain Oil	& Gas		
		File Numbe	r:	BU-3292 Haysi #18 W/PL Coalbed/Pipeline			
		Operations	Name:				
		Operation 1	Гуре:				
		Completion	Report Type:	· Original			
COMPLETION REPORT (DGO-GO-15)							
Well Type:	Coalbed/Pipe	line	Date Well Con	npleted: 2/16/2007	,		
Driller's Total Depth:	2,460		Log's Total De	epth: 2,460			
I. Changes In Casing/Τι	ıbing from App	proved Drilli	ng Report				
Des	cription			FileName			
Haysi 18	Comp Casing		Haysi 18 Comp Casing.doc				
2. Stimulation Record							
Stimulated	Not Stimulated	d 🗆 G	Sob				
	cription			FileName			
Haysi 1	8 Stimulation		F	laysi 18 Stimulation	n.doc		
3. Final Production							
Des	cription			FileName			
Haysi 1	8 Final Prod.		Haysi 18 Final Prod.xls				
I. Comments							
Notes:							
i. Signature							
Permittee: Pine Mounta	ain Oil & Gas	Da	te: <u>8/16/2007</u>	2:25:28 PM	(Company)		

Form DGO-GO-15-E

Rev. 1/2007

By:	Christian D. Moore	Title: Permit/GIS Specialist	(Signature)
-----	--------------------	------------------------------	-------------

INTERNAL USE ONLY

Submit Date: 8/16/2007

Status: Inspr Approved Date: 8/30/2007

Final PDF Date: 8/30/2007

Form DGO-GO-15-E

Rev. 1/2007

# HAYSI 18 CASING AND TUBING PROGRAM

				Cement	Ceme	ented		Packers Or
		Casing	Hole	Used In	To Su	ırface	Date	Bridge Plugs
	Casing	Interval	Size	Cu/Ft	Yes	No	Cemented	Kind/Size/Set
Conductor	113/4"	0-28'	15"					
Surface	85/8"	0-309'	11"	149	Yes		12/2/06	
Water Protection	41/2"	0-2408'	61/2"	488	Yes		12/5/06	
Coal Protection								
Other Casing And	23/8"	0-2308						
Tubing Left In Well								
Liners								

# STIMULATION RECORD

ZONE 1: Poco 4, 3 Rider, 3 & 2	Formation Stimulated With: N <sub>2</sub> Foam
	Formation Stimulated With: $N_2$ Foam erforations $15$ Perforation Size $0.34$
Formation Broke down at: 2400 PSIG ISIP 2395 PSIG 5 Min SIP 2148 PSIG Avera	Average Injection Rate: 9.5 BPM ge Downhole Injection Pressure 2888 PSIG
Stimulated: Yes No Date Stimulated:	
Stimulated. Tes 10 Date Stimulated.	2/10/07
ZONE 2: Upper, Middle & Lower Horsepen	Formation Stimulated With: N <sub>2</sub> Foam
	erforations 21 Perforation Size 0.33
Formation Broke down at: 2078 PSIG	Average Injection Rate: 7.2 BPM
ISIP 2034 PSIG 5 Min SIP 1884 PSIG Avera	ge Downhole Injection Pressure 2951 PSIG
Stimulated: Yes	2/16/07
70NF 2 H C 1 10 C C 1	E ' G' 1 1W'1 NE
	Formation Stimulated With: N <sub>2</sub> Foam erforations 21 Perforation Size 0.33
Formation Broke down at: 2917 PSIG	Average Injection Rate: 6.4 BPM
	ge Downhole Injection Pressure 3404 PSIG
Stimulated: No Date Stimulated:	2/16/07
ZONE 4: JB Rider, Jawbone & Tiller	Formation Stimulated With: N <sub>2</sub> Foam
	erforations 25 Perforation Size 0.33
Formation Broke down at: 1976 PSIG	Average Injection Rate: 7.9 BPM
ISIP 1824 PSIG 5 Min SIP N/A PSIG Avera	ge Downhole Injection Pressure 2991 PSIG
Stimulated: Yes	2/16/07
70VF 7 4 11 0 P	F
ZONE 5: Aily & Raven x3	Formation Stimulated With: N <sub>2</sub> Foam
Perforated 907.5 to 1019.5 feet No. of Performation Broke down at: 1963 PSIG	erforations 26 Perforation Size 0.33  Average Injection Rate: 8.0 BPM
	ge Downhole Injection Pressure 2783 PSIG
Stimulated: Yes No Date Stimulated:	
Simulated.   168   NO Date Stimulated.	Z/10/U/

Final Production After Stimulation				
	BOD	MCFD	<b>Hours Tested</b>	<b>Rock Pressure</b>
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		36	In-Line	75



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil

P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

Tracking Number:	577
Company:	Pine Mountain Oil & Gas
File Number:	BU-3292
Operations Name:	Haysi #18 W/PL
Operation Type:	Coalbed/Pipeline
<b>Drilling Report Type:</b>	Original

### **DRILLING REPORT (DGO-GO-14)**

DRILLING REPORT (DGO-GO-14)					
1. Drilling Data					
Date drilling commenced: 12/1/2006  Date drilling completed: 12/5/2006		D	Drilling Contractor: Noah Horn  Rig Type: ✓ Rotary ☐ Cable Tool		
Driller's Total Depth (feet): Log Total Depth (feet):	2,460 2,460	Со	al Seam At Total	Depth <sub>.</sub>	POCAHONTAS #2
2. Final Location Plat (as rec	quired by 4 VAC25	-150	-360.C.)		
Permitted State Plane X 915	5,303	Fin	al Plat State Plan	ie X: <u>915</u>	5,305
Permitted State Plane Y: 336,542 Final Plat State Plane Y: 336,538					5,538
☐ Plat Previously Submitted	Or				
List of Attached Items:					
Description FileName					
Haysi 18 Plat				Haysi 18	3 Plat.pdf
3. Geological Data					
Fresh Water At:					
Depth	(in feet)		Rate	U	Jnit of Measure
Salt Water At:					
Depth	(in feet)		Rate	L L	Jnit of Measure
	1,210		Damp		GPM

Form DGO-GO-14-E Rev. 1/2007

### Coal Seams

List of Attached Items:

Description	FileName	
Haysi 18 Coals	Haysi 18 Coal.xls	

### Gas and Oil Shows

List of Attached Items:

Description	FileName	
Haysi 18 Shows	Haysi 18 Shows.xls	

### **4. Electric Logs** (As required by 4VAC25-150-280.A.)

List all logs run: Hi Res GR/Dens/Temp/Audio/Pe/Caliper (Data Pack)

Did logs disclose vertical locations of a coal seam? ✓ Yes □ No

### **5. Survey Results** (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName	
Haysi 18 Shows	Haysi 18 Shows.xls	

### 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
Haysi 18 Casing	Haysi 18 Casing.xls

#### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

Circ 1 bbl to surf on 8 5/8" csng. Circ 12 bbl to surf on 41/2" csng.

### 8. Drillers Log

Compiled By: Noah Horn

List of Attached Items:

Description	FileName	
Haysi 18 Log	Haysi 18 Log.xls	

### 9. Comments

10. Signature

Permitee: Pine Mountain Oil & Gas Date: 7/31/2007 (Company)

Signed By: Christian D. Moore Title: Permit/GIS Specialist (Signature)


INTERNAL USE ONLY


Submit Date: 7/31/2007

Status: Inspr Approved Date: 8/21/2007

Final PDF Date: 8/21/2007

Form DGO-GO-14-E





### WELL LOCATION PLAT

COMPANY Pine Mountain Oil & Gas, Inc. WELL NAME AND NUMBER Haysi-18	
TRACT NO. <u>Henry Deel</u> <u>ELEVATION 1.913.36'</u> QUADRANGLE <u>Prater</u>	- 12
COUNTY <u>Buchanan</u> DISTRICT <u>Prater</u> SCALE <u>1" = 400'</u> DATE <u>12-04-200</u>	6
This Plat is a new plat; an updated plat; or a final location platx	_
+ Denotes the location of a well on United States topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown.	
1 the	

# Coal Seams

				MINING IN AREA		
NAME	TOP	BOTTOM	THICKNESS	YES	NO	MINED OUT
Aily	908	909	1		NO	
Raven	989	990	1		NO	
Raven	1007	1008	1		NO	
Raven	1018	1019	1		NO	
Jawbone Rider	1105	1107	2		NO	
Jawbone	1143	1144	1		NO	
Tiller	1199	1200	1		NO	
Upper Seaboard	1307	1309	2		NO	
Greasy Creek	1457	1459	2		NO	
Upper Horsepen	1599	1600	1		NO	
Middle Horsepen	1658	1660	2		NO	
Lower Horsepen	1774	1775	1		NO	
Poco 4	2123	2124	1		NO	
Poco 3 rider	2182	2183	1		NO	
Poco 3	2198	2200	2		NO	
Poco 2	2260	2261	1		NO	

### Gas and Oil Shows

FORMATION	TOP BOTTOM THICKNESS   IPF (MCFD/BOPD)   PI	RESSURE HOURS TESTED
Open Hole TD	21.8M	
Cased Hole TD	22.2M	

### Gas and Oil Shows

FORMATION	TOP BOTTOM THICKNESS   IPF (MCFD/BOPD)   PI	RESSURE HOURS TESTED
Open Hole TD	21.8M	
Cased Hole TD	22.2M	

**Casing Program** 

	Casing	Casing	Hole	<b>Cement Used</b>	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented
Conductor	11.75	0-28	15			
Surface	8.625	0-309	11	149	Yes	12/2/2006
Water Protection	4.5	0-2408	6.5	488	Yes	12/5/2006

Packers Or Bridge Plugs Kind/Size/Set

### Driller's Log

		General		Depth	Depth	
Geologic Age	Formation	Lithology	Color	Тор	Bottom	Thickness
PENN	Lee	SS, SH, Thin Coals		0	908	908
PENN	Lee	Coal		908	909	1
PENN	Lee	SS, SH, Thin Coals		909	989	80
PENN	Lee	Coal		989	990	1
PENN	Lee	SS, SH, Thin Coals		990	1007	17
PENN	Lee	Coal		1007	1008	1
PENN	Lee	SS, SH, Thin Coals		1008	1018	10
PENN	Lee	Coal		1018	1019	1
PENN	Lee	SS, SH, Thin Coals		1019	1105	
PENN	Lee	Coal		1105	1107	
PENN	Lee	SS, SH, Thin Coals		1107	1143	36
PENN	Lee	Coal		1143	1144	1
PENN	Lee	SS, SH, Thin Coals		1144	1199	55
PENN	Lee	Coal		1199	1200	1
PENN	Lee	SS, SH, Thin Coals		1200	1307	107
PENN	Lee	Coal		1307	1309	2
PENN	Lee	SS, SH, Thin Coals		1309	1457	148
PENN	Lee	Coal		1457	1459	2
PENN	Lee	SS, SH, Thin Coals		1459	1599	140
PENN	Lee	Coal		1599	1600	1
PENN	Lee	SS, SH, Thin Coals		1600	1774	174
PENN	Lee	Coal		1774	1775	1
PENN	Pocahontas	SS, SH, Thin Coals		1775	2123	348
PENN	Pocahontas	Coal		2123	2124	1
PENN	Pocahontas	SS, SH, Thin Coals		2124	2182	58
PENN	Pocahontas	Coal		2182	2183	
PENN	Pocahontas	SS, SH, Thin Coals		2183	2198	15
PENN	Pocahontas	Coal		2198	2200	2
PENN	Pocahontas	SS, SH, Thin Coals		2200	2260	60
PENN	Pocahontas	Coal		2260	2261	1
PENN	Pocahontas	SS, SH, Thin Coals		2261	2460	199

Remarks	
	_
	_
	_
	_
· · · · · · · · · · · · · · · · · · ·	



Commonwealth of Virginia
Department of Mines, Minerals, and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

597

	Company:		Pine Mountain Oil	& Gas			
	File Numbe	er:	BU-3375				
	Operations	Name:	Haysi #19 W/PL				
	Operation <sup>-</sup>	Гуре:	Coalbed/Pipeline				
	Completion	Report Type:	Original				
СО	COMPLETION REPORT (DGO-GO-15)						
Well Type: Coalb	ed/Pipeline	Date Well Con	npleted: 3/30/2007				
Driller's Total Depth: 2,280		Log's Total De	epth: 2,271				
. Changes In Casing/Tubing fr	om Approved Drilli	ng Report					
Description	n		FileName				
Haysi 19 Comp	Casing	Ha	aysi 19 Comp Casi	ng.xls			
2. Stimulation Record							
✓ Stimulated	mulated 🔲 C	Gob					
Description			FileName				
Haysi 19 Stimu	lation	H	aysi 19 Stimulatior	n.doc			
3. Final Production							
B. Final Production  Description	n		FileName				
			<b>FileName</b> Haysi 19 Final Prod				
Description Haysi 19 Final							
Description Haysi 19 Final							
Description							
Description Haysi 19 Final  Comments							
Description Haysi 19 Final  Comments  Notes:							
Description Haysi 19 Final  I. Comments	Prod.		Haysi 19 Final Prod				

**Tracking Number:** 

Form DGO-GO-15-E

Rev. 1/2007

Page 1 Of 2

By: Christian D. Moore Title: Permit/GIS Specialist (Signa	Chr	Christian D. Moore	Title:	Permit/GIS Specialist	(Signatu	ıre)
--	-----	--------------------	--------	-----------------------	----------	------

INTERNAL USE ONLY

Submit Date: 8/16/2007

Status: Inspr Approved Date: 9/4/2007

Final PDF Date: 11/5/2007

Form DGO-GO-15-E Rev. 1/2007 Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented

Packers Or Bridge Plugs Kind/Size/Set STIMULATION RECORD (Use additional sheets with this format, if more than three zones are stimulated.)

ZONE 1: Poco 4, 3 & 2	Formation Stimulated With: N2 Foam
Perforated <u>2016.5</u> to <u>2124.8</u> feet No. 6	of Perforations 17 Perforation Size 0.33
Formation Broke down at: 3228 PSIG	Average Injection Rate: 16.9 BPM
ISIP <u>1856</u> PSIG 5 Min SIP <u>1770</u> PSIG Av	verage Downhole Injection Pressure 2713 PSIG
Stimulated: Yes	3/30/07
ZONE 2: U. Hpen, M. Hpen, L. Hpen & Poco 9	
	of Perforations 25 Perforation Size 0.33
Formation Broke down at: 2790 PSIG	<u></u>
ISIP <u>1480</u> PSIG 5 Min SIP <u>1433</u> PSIG Av	verage Downhole Injection Pressure 2435 PSIG
Stimulated: Xes No Date Stimulated:	3/30/07
ZONE 3: Upper Seaboard & Greasy Creek	Formation Stimulated With: N2 Foam
	of Perforations 23 Perforation Size 0.33
Formation Broke down at: 2047 PSIG	Average Injection Rate: 11.4 BPM
ISIP <u>1768</u> PSIG 5 Min SIP <u>1698</u> PSIG Av	verage Downhole Injection Pressure 2848 PSIG
Stimulated: Xes No Date Stimulated:	3/30/07
ZONE 4: _ Jb Rider, Jawbone x2, Tiller	Formation Stimulated With: N2 Foam
Perforated 971.5 to 1061.5 feet No. of	of Perforations 28 Perforation Size 0.33
Formation Broke down at: 2330 PSIG	Average Injection Rate: 16.0 BPM
ISIP N/A PSIG 5 Min SIP N/A PSIG AV	verage Downhole Injection Pressure 3186 PSIG
Stimulated: Xes No Date Stimulated:	3/30/07
ZONE 5:	Formation Stimulated With:
Perforated to feet No. of	of Perforations Perforation Size
	Average Injection Rate: BPM
	verage Downhole Injection Pressure PSIG
Stimulated: Yes	: :

Final Production After Stimulation				
	BOD	MCFD	<b>Hours Tested</b>	<b>Rock Pressure</b>
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		34	In-Line	60



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil

P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

Tracking Number:	592
Company:	Pine Mountain Oil & Gas
File Number:	BU-3375
<b>Operations Name:</b>	Haysi #19 W/PL
Operation Type:	Coalbed/Pipeline

**Drilling Report Type:** Original

DRILLING REPORT (DGO-GO-14)					
1. Drilling Data					
Date drilling commenced:	3/16/2007	D	rilling Contractor:	Noah Horn	
Date drilling completed:	3/22/2007		Rig Type	: ☑ Rotary ☐ Cable Tool	
Driller's Total Depth (feet):	2,280				
Log Total Depth (feet):	2,271	Co	al Seam At Total	Depth POCAHONTAS #2	
2. Final Location Plat (as red	quired by 4 VA	AC25-150	-360.C.)		
Permitted State Plane X 91	5,700	Fir	nal Plat State Plan	e X: 915,700	
Permitted State Plane Y: 33	5,025	Fir	Final Plat State Plane Y: 335,031		
☐ Plat Previously Submitted Or					
List of Attached Items:					
Description			FileName		
Haysi 19	9 Plat		Haysi 19 Plat.pdf		
3. Geological Data					
Fresh Water At:					
Depth	(in feet)		Rate	Unit of Measure	
	264		Damp		
Salt Water At:					
Depth	(in feet)		Rate	Unit of Measure	
	1,240		Damp		
	2,247		Log		
	2,260		Video		

Form DGO-GO-14-E Rev. 1/2007

### Coal Seams

List of Attached Items:

Description	FileName
Haysi 19 Coal	Haysi 19 Coal.xls

### Gas and Oil Shows

List of Attached Items:

Description	FileName
Haysi 19 Shows	Haysi 19 Shows.xls

### **4. Electric Logs** (As required by 4VAC25-150-280.A.)

List all logs run: Hi Res GR/Dens/Temp/Audio/Pe/Caliper (Data Pack)

Did logs disclose vertical locations of a coal seam? ✓ Yes □ No

### **5. Survey Results** (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName
Haysi 19 Survey	Haysi 19 Survey.xls

### 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
Haysi 19 Casing	Haysi 19 Casing.xls

### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

Circ 15 bbls to surf on 8?" csng. Circ 10 bbls to surf on 41/2" csng.

### 8. Drillers Log

Compiled By: Noah Horn

List of Attached Items:

Description	FileName
Haysi 19 Log	Haysi 19 Log.xls

### 9. Comments

10. Signature

Permitee: Pine Mountain Oil & Gas Date: 8/7/2007 (Company)

Signed By: Christian D. Moore Title: Permit/GIS Specialist (Signature)

INTERNAL USE ONLY

Submit Date: 8/7/2007


Status: Inspr Approved Date: 8/8/2007

Final PDF Date: 8/8/2007

Form DGO-GO-14-E

Page 3 of 3

Rev. 1/2007



WELL LOCATION PLAT

COMPANY <u>Pine Mountain Oil &amp; Gas. Inc.</u> WELL NAME AND NUMBER <u>Haysi-19</u> TRACT NO. <u>B.F. Deel</u> ELEVATION <u>1,799.75</u> QUADRANGLE <u>Prater</u>
COUNTY Buchanan DISTRICT Prater SCALE $1" = 400'$ DATE $3-22-2007$
This Plat is a new plat; an updated plat; or a final location platx
Denotes the location of a well on United States topographic Maps, scale 1 to
24,000, latitude and longitude lines being represented by border lines as shown.
O- E Hal

Licensed Professional Engineer or Licensed Land Surveyor

# Coal Seams

				MINING IN AREA		
NAME	ТОР	BOTTOM	THICKNESS	YES N	<b>VO</b>	MINED OUT
Jawbone Rider	973	975	2	١	<b>10</b>	
Jawbone	1010	1012	2	N	VO	
Jawbone	1025	1026	1	N	VO	
Tiller	1065	1067	2	N	VO	
Upper Seaboard	1181	1183	2	N	VO	
Greasy Creek	1319	1321	2	N	VO	
Upper Horsepen	1463	1465	2	N	VO	
Middle Horsepen	1511	1512	1	N	VO	
Lower Horsepen	1631	1632	1	N	VO	
Poco 9	1697	1698	1	N	VO	
Poco 4	2017	2019	2	N	VO	
Poco 3	2057	2060	3	N	VO	
Poco 2	2124	2125	1	N	VO	

Gas and Oil Shows

FORMATION	TOP BOTTOM	THICKNESS	IPF (	(MCFD/BOPD)	PRESSURE	HOURS TESTED
Open Hole TD			No S	Show		

Survey Results

Depth of Survey	Direction/Distance/Degree From True Vertical
210	0°
420	0°
600	1/4°
810	1/4°
1020	1/4°
1230	1/2°
1440	1/4°
1650	1/4°
1800	1/4°
2010	1/4°
2220	1/4°

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented
Conductor	113/4"	26'	15"			
Surface	85/8"	401'	11"	190	Yes	3/19/2007
Water Protection	41/2"	2229'	61/2"	671	Yes	3/22/2007

	_
Packers Or Bridge Plugs	
Kind/Size/Set	•

# Driller's Log

	General	
Formation	Lithology	Color
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
Lee	Coal	
Lee	Sand, shale, thin coals	
	Lee	Formation  Lee Sand, shale, thin coals Lee Coal Lee Sand, shale, thin coals

Depth	Depth		
Тор	Bottom	Thickness	Remarks
0	973	973	
973	975	2	Jawbone Rider
975	1010	35	
1010	1012	2	Jawbone
1012	1025	13	
1025	1026	1	Jawbone
1026	1065	39	
1065	1067		Tiller
1067	1181	114	
1181	1183	2	Upper Seaboard
1183	1319	136	
1319	1321	2	Greasy Creek
1321	1463	142	
1463	1465	2	Upper Horsepen
1465	1511	46	
1511	1512	1	Middle Horsepen
1512	1631	119	
1631	1632	1	Lower Horsepen
1632	1697	65	
1697	1698	1	Poco 9
1698	2017	319	
2017	2019	2	Poco 4
2019	2057	38	
2057	2060	3	Poco 3
2060	2124	64	
2124	2125	1	Poco 2
2125	2271	146	



Commonwealth of Virginia
Department of Mines, Minerals, and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

	Irackin	g Number:	598	
	Compar	ny:	Pine Mountain O	il & Gas
	File Nur	mber:	BU-3458	
	Operation	ons Name:	Haysi #21 W/PL	
	Operation	on Type:	Coalbed/Pipeline	<b>;</b>
	Comple	tion Report Type	: Original	
	COMPLETION F	REPORT (DGO	-GO-15)	
Well Type:	Coalbed/Pipeline	Date Well Co	mpleted: 6/13/200	7
Driller's Total Depth:	2,304	Log's Total D	epth: 2,295	
. Changes In Casing/T	ubing from Approved D	rilling Report		
Des	scription		FileName	
Haysi 2	1 Comp Casing	F	laysi 19 Comp Cas	sing.xls
2. Stimulation Record				
☐ Stimulated ☐	] Not Stimulated	☐ Gob		
	scription		FileName	
Haysi 2	21 Stimulation		Haysi 19 Stimulatio	on.doc
3. Final Production				
Des	scription		FileName	
Haysi	21 Final Prod		Haysi 19 Final Pro	od.xls
I. Comments				
Notes:				
Notes.				
5. Signature				
Permittee: Pine Mount	ain Oil & Gas	Date: 8/16/2007	7 2:34:50 PM	(Company)

Form DGO-GO-15-E

Page 1 Of 2

Rev. 1/2007

By: Christian D. Moore Title: Permit/GIS Specialist (Signa	Chi	Christian D. Moore	Title:	Permit/GIS Specialist	(Signatu	ıre)
--	-----	--------------------	--------	-----------------------	----------	------

INTERNAL USE ONLY

Submit Date: 8/16/2007

Status: Inspr Approved Date: 9/4/2007

Final PDF Date: 9/4/2007

Form DGO-GO-15-E

Rev. 1/2007

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented

Packers Or Bridge Plugs Kind/Size/Set STIMULATION RECORD (Use additional sheets with this format, if more than three zones are stimulated.)

ZONE 1: Poco 4, 3 & 2	Formation Stimulated With: N2 Foam
Perforated <u>2016.5</u> to <u>2124.8</u> feet No. 6	of Perforations 17 Perforation Size 0.33
Formation Broke down at: 3228 PSIG	Average Injection Rate: 16.9 BPM
ISIP <u>1856</u> PSIG 5 Min SIP <u>1770</u> PSIG Av	verage Downhole Injection Pressure 2713 PSIG
Stimulated: Yes	3/30/07
ZONE 2: U. Hpen, M. Hpen, L. Hpen & Poco 9	
	of Perforations 25 Perforation Size 0.33
Formation Broke down at: 2790 PSIG	<u></u>
ISIP <u>1480</u> PSIG 5 Min SIP <u>1433</u> PSIG Av	verage Downhole Injection Pressure 2435 PSIG
Stimulated: Xes No Date Stimulated:	3/30/07
ZONE 3: Upper Seaboard & Greasy Creek	Formation Stimulated With: N2 Foam
	of Perforations 23 Perforation Size 0.33
Formation Broke down at: 2047 PSIG	Average Injection Rate: 11.4 BPM
ISIP <u>1768</u> PSIG 5 Min SIP <u>1698</u> PSIG Av	verage Downhole Injection Pressure 2848 PSIG
Stimulated: Xes No Date Stimulated:	3/30/07
ZONE 4: _ Jb Rider, Jawbone x2, Tiller	Formation Stimulated With: N2 Foam
Perforated 971.5 to 1061.5 feet No. of	of Perforations 28 Perforation Size 0.33
Formation Broke down at: 2330 PSIG	Average Injection Rate: 16.0 BPM
ISIP N/A PSIG 5 Min SIP N/A PSIG AV	verage Downhole Injection Pressure 3186 PSIG
Stimulated: Xes No Date Stimulated:	3/30/07
ZONE 5:	Formation Stimulated With:
Perforated to feet No. of	of Perforations Perforation Size
	Average Injection Rate: BPM
	verage Downhole Injection Pressure PSIG
Stimulated: Yes	: :

Final Production After Stimulation				
	BOD	MCFD	<b>Hours Tested</b>	<b>Rock Pressure</b>
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		34	In-Line	60



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil

P.O. Box 1416; Abingdon, VA 24212

Pine Mountain Oil & Gas

Telephone: (276) 676-5423

601

BU-3458

		Operations Name:		Haysi #21 W/PL			
		Operation	Гуре:	Coalbed/Pipeline			
		Drilling Report Ty		Origi	inal		
DRILLING REPORT (DGO-GO-14)							
1. Drilling Data							
Date drilling commenced:	5/9/2007	Drilling Contractor: Noah Horn			Noah Horn		
Date drilling completed:	5/18/2007				e: 🗸 Rotary 🔲 Cable Tool		
Driller's Total Depth (feet):	2,304						
Log Total Depth (feet):	2,295	Co	al Seam At	Total	Depth POCAHONTAS #2		
2. Final Location Plat (as req	uired by 4 \	/AC25-150-	·360.C.)				
Permitted State Plane X 918,255 Final Plat State Plane X:					ne X: <u>918,255</u>		
Permitted State Plane Y: 334,506 Final Plat State Plane Y: 334,510					ne Y: <u>334,510</u>		
☐ Plat Previously Submitted Or							
List of Attached Items:							
Description				FileName			
Haysi 21 Plat			Haysi 21 Plat.pdf				
3. Geological Data							
Fresh Water At:							
Depth	(in feet)		i	Rate	Unit of Measure		
	960		D	amp			
Salt Water At:							
Depth	(in feet)		ı	Rate	Unit of Measure		

**Tracking Number:** 

Company:

File Number:

Form DGO-GO-14-E Rev. 1/2007

#### Coal Seams

List of Attached Items:

Description	FileName	
Haysi 21 Coal	Haysi 21 Coal.xls	

#### Gas and Oil Shows

List of Attached Items:

Description	FileName	
Haysi 21 Shows	Haysi 21 Shows.xls	

#### **4. Electric Logs** (As required by 4VAC25-150-280.A.)

List all logs run: Hi Res GR/Dens/Temp/Audio/Pe/Caliper (Data Pack)

Did logs disclose vertical locations of a coal seam?  $\square$  Yes  $\checkmark$  No

## **5. Survey Results** (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName	
Haysi 21 Survey	Haysi 21 Survey.xls	

#### 6. Casing and Tubing Program

List of Attached Items:

Description	FileName	
Haysi 21 Casing	Haysi 21 Casing.xls	

#### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

Basket @ 88' in 11" hole; Circ 10 bbl to surf. Circ 10 bbl to surf on 61/2 hole.

#### 8. Drillers Log

Compiled By: Noah Horn

List of Attached Items:

Description	FileName	
Haysi 21 Log	Haysi 21 Log.xls	

## 9. Comments

10. Signature

Permitee: Pine Mountain Oil & Gas Date: 8/10/2007 (Company)

Signed By: Christian D. Moore Title: Permit/GIS Specialist (Signature)

INTERNAL USE ONLY

Submit Date: 8/10/2007


Status: Inspr Approved Date: 8/21/2007

Final PDF Date: 8/22/2007

Form DGO-GO-14-E

Page 3 of 3

Rev. 1/2007



#### WELL LOCATION PLAT

COMPANY Pine Mountain Oil & Gas. Inc. WELL NAME AND NUMBER Haysi-21
TRACT NO. B. E. Arrington ELEVATION 1.844.53' QUADRANGLE Prater
COUNTY <u>Buchanan</u> DISTRICT <u>Prater</u> SCALE $1'' = 400'$ DATE $5-11-2007$
This Plat is a new plat; an updated plat; or a final location plat
+ Denotes the location of a well on United States topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown.
24,000, latitude and longitude lines being represented by border lines as shown.
Jam C. Helen

Licensed Professional Engineer or Licensed Land Surveyor

# Coal Seams

				N	IINING IN AREA
NAME	TOP	BOTTOM	THICKNESS	YES NO	MINED OUT
Kennedy	623	624	1	NO	
Aily Rider	713	714	1	NO	1
Aily	748	750	2	NO	1
Raven	830	831	1	NO	1
Jawbone Rider	951	953	2	NO	1
Jawbone	982	984	2	NO	1
Tiller	1043	1044	1	NO	1
Upper Seaboard	1160	1163	3	NO	1
Greasy Creek	1287	1289	2	NO	1
Upper Horsepen	1442	1443	1	NO	1
Middle Horsepen	1498	1499	1	NO	1
War Creek	1575	1576	1	NO	1
Lower Horsepen	1618	1620	2	NO	1
Poco 9	1696	1697	1	NO	1
Poco 4	1986	1987	1	NO	1
Poco 3	2066	2069	3	NO	1
Poco 2	2129	2130	1	NO	

Gas and Oil Shows

FORMATION TOP BOTTOM THICKNESS IPF (MCFD/BOPD) PRESSURE HOURS TESTED
Open Hole TD 6.2M

Survey Results

Depth of Survey	Direction/Distance/Degree From True Vertical
210	0°
420	1/4°
600	1/4°
810	1/4°
1020	1/4°
1200	1/4°
1410	1/4°
1620	1/4°
1800	1/4°
2101	1/4°
2220	1/4°

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented
Conductor	113/4"	0-20'	15"			
Surface	85/8"	0-345'	11"	169	Yes	5/10/2007
Water Protection	41/2"	0-2266'	6½"	417	Yes	5/18/2007
Tubing	23/8"	0-2167				

Packers Or Bridge Plugs
Kind/Size/Set

# Driller's Log

		General		
Geologic Age	Formation	Lithology	Color	
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		
Penn	Lee	Coal		
Penn	Lee	Sand, shale, thin coals		

Depth	Depth		
Тор	Bottom	Thickness	Remarks
0	623	623	
623	624		Kennedy
624	713		
713	714		Aily Rider
714	748		
748	750		Aily
750	830		
830	831		Raven
831	951	120	
951	953		Jawbone Rider
953	982	29	
982	984	2	Jawbone
984	1043	59	
1043	1044		Tiller
1044	1160	116	
1160	1163		Upper Seaboard
1163	1287	124	
1287	1289		Greasy Creek
1289	1442	153	
1442	1443		Upper Horsepen
1443	1498	55	
1498	1499		Middle Horsepen
1499	1575	76	
1575	1576		War Creek
1576	1618	42	
1618	1620	2	Lower Horsepen
1620	1696	76	
1696	1697		Poco 9
1697	1986	289	
1986	1987	1	Poco 4
1987	2066	79	
2066	2069		Poco 3
2069	2129	60	
2129	2130		Poco 3
2130	2301	171	



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

Tracking Number: 6548

**Company:** Range Resources-Pine

Mountain,

File Number: BU-5078

Completion Report Type: Original

**COMPLETION REPORT (DGO-GO-15)** 

Well Type: Coalbed/Pipeline Date Well Completed: 4/10/2015

Driller's Total Depth: 2520.00 Log's Total Depth: 2522.00

# 1. Changes In Casing/Tubing from Approved Drilling Report

Description	FileName	
Haysi 35 Casing/Tubing	Casing Haysi 35.xlsx	

#### 2. Stimulation Record

Stimulation Status: RStimulated & GOB & Not Stimulated & Service Well

Description	FileName
Haysi 35 Completion Report	Haysi 35 Completion Report.pdf

#### 3. Final Production

Description	FileName		
Haysi 35 Final Production	Final_Prod.xls		

## 4. Comments

Form DGO-GO-15-E

Rev. 04/2009

Page 1 of 2

Notes:			

5. Signature

By:

Permittee: Range Resources-Pine Date: 4/24/2015 (Company)

Mountain,

Laura Murray Title: Regulatory Compliance (Signature)

Specialist

INTERNAL USE ONLY

Submit Date: 4/24/2015

Status: Approved Date: 5/1/2015

Final PDF Date: 5/21/2015

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs	Cement Baskets
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set	(ft)
Conductor	13 3/8	0-92'	15		No			
Water Protection	9 5/8	0-344'	12 3/8	182	Yes	12/08/14		48' 92'
Coal Protection								
Production Casing	4½"	0-2475'	6 1/2	473	Yes	12/10/14		910'
Other Casing And								
Tubing Left In Well	23/8"	0-2403						
Liners								

Service Co.

# **Completion Report**

# 105010446 --Haysi 35

Stage:

Stage Date:	04/10/2015	Fluid Type:	70Q Foam	Max DH Rate:	63.0
Perf Date:	04/10/2015	BD:	1801	Total Slurry Volume:	682
Logging Co.	KLX (Blue Dot)	ISIP:	0	Total Fluid Volume:	658
Formation	Poco #4, #3, #2, #2	Avg Press:	3342	Avg N2 Rate:	43,000
Perf Top:	2200	Max Treat Pressure:	3447	Max N2 Rate:	45,200
Perf Bottom:	2375.7	Final ISIP:	1812	Total N2 Volume:	1,270,200
# Shots:	34	2 Min SIP:	0	Max DH PPA:	1.40
Perf Size:	0.52	5 Min SIP:	0	Total Proppant Sks:	288
Perf Comments:		10 Min SIP:	0	Total Acid:	250
		Sand Mesh:	20/40 Sand	Acid Type:	15% HCL
Comments:		Frac Gradient:	1.2		
				_	
Stage:	02	Service Co.	C&J Energy	Avg DH Rate:	58.0
Stage Date:	04/10/2015	Fluid Type:	70Q Foam	Max DH Rate:	60.0
Perf Date:	04/10/2015	BD:	2031	Total Slurry Volume:	229
Logging Co.	KLX (Blue Dot)	ISIP:	0	Total Fluid Volume:	215
Formation	Up Horsepen, Mid Horsepen,	Avg Press:	3409	Avg N2 Rate:	41,100
Perf Top:	1694.4	Max Treat Pressure:	3633	Max N2 Rate:	42,000
Perf Bottom:	1862.7	Final ISIP:	1406	Total N2 Volume:	432,400
# Shots:	28	2 Min SIP:	0	Max DH PPA:	1.80
Perf Size:	0.52	5 Min SIP:	0	Total Proppant Sks:	169
Perf Comments:	1	10 Min SIP:	0	Total Acid:	250
		Sand Mesh:	20/40 Sand	Acid Type:	15% HCL
Comments:		Frac Gradient:	1.3		
				_	
Stage:	03	Service Co.	C&J Energy	Avg DH Rate:	38.0
Stage Date:	04/10/2015	Fluid Type:	70Q Foam	Max DH Rate:	43.0
Perf Date:	04/10/2015	BD:	2803	Total Slurry Volume:	174
Logging Co.	KLX (Blue Dot)	ISIP:	0	Total Fluid Volume:	171
Formation	Upper Seaboard, Greasy Creek	Ava Press	4401	Avg N2 Rate:	37.900

C&J Energy

Avg DH Rate:

57.5

Perf Comments	:	10 Min SIP:	0	Total Acid:	250
		Sand Mesh:	20/40 Sand	Acid Type:	15% HCL
Comments:		Frac Gradient:	1.3		
Stage:	03	Service Co.	C&J Energy	Avg DH Rate:	38.0
Stage Date:	04/10/2015	Fluid Type:	70Q Foam	Max DH Rate:	43.0
Perf Date:	04/10/2015	BD:	2803	Total Slurry Volume:	174
Logging Co.	KLX (Blue Dot)	ISIP:	0	Total Fluid Volume:	171
Formation	Upper Seaboard, Greasy Creek	Avg Press:	4401	Avg N2 Rate:	37,900
Perf Top:	1395.6	Max Treat Pressure:	4634	Max N2 Rate:	38,200
Perf Bottom:	1551.7	Final ISIP:	1904	Total N2 Volume:	338,600
# Shots:	20	2 Min SIP:	0	Max DH PPA:	1.40
Perf Size:	0.52	5 Min SIP:	0	Total Proppant Sks:	49
Perf Comments	: '	10 Min SIP:	0	Total Acid:	250
		Sand Mesh:	20/40 Sand	Acid Type:	15% HCL
Comments:		Frac Gradient:	1.8		
Stage:	<u>04</u>	Service Co.	C&J Energy	Avg DH Rate:	61.5
Stage Date:	04/10/2015	Fluid Type:	70Q Foam	Max DH Rate:	63.5
Perf Date:	04/10/2015	BD:	1850	Total Slurry Volume:	463

# **Completion Report**

# 105010446 --Haysi 35

Logging Co.	KLX (Blue Dot)	ISIP:	0	Total Fluid Volume:	442
Formation	Jawbone Rider, Jawbone, Tiller	Avg Press:	3196	Avg N2 Rate:	40,200
Perf Top:	1192.7	Max Treat Pressure:	3535	Max N2 Rate:	42,300
Perf Bottom:	1291	Final ISIP:	1069	Total N2 Volume:	840,400
# Shots:	30	2 Min SIP:	0	Max DH PPA:	1.80
Perf Size:	0.52	5 Min SIP:	0	Total Proppant Sks:	266
Perf Comments:		10 Min SIP:	0	Total Acid:	750
		Sand Mesh:	20/40 Sand	Acid Type:	15% HCL
Comments:		Frac Gradient:	1.3		

Stage:	<u>05</u>	Service Co.	C&J Energy	Avg DH Rate:	59.0
Stage Date:	04/10/2015	Fluid Type:	70Q Foam	Max DH Rate:	61.0
Perf Date:	04/10/2015	BD:	3301	Total Slurry Volume:	273
Logging Co.	KLX (Blue Dot)	ISIP:	0	Total Fluid Volume:	260
Formation	Aily Rider, Aily, Raven, Raven	Avg Press:	3579	Avg N2 Rate:	43,400
Perf Top:	966.5	Max Treat Pressure:	3804	Max N2 Rate:	43,900
Perf Bottom:	1107.2	Final ISIP:	1948	Total N2 Volume:	647,800
# Shots:	23	2 Min SIP:	1234	Max DH PPA:	1.70
Perf Size:	0.52	5 Min SIP:	1172	Total Proppant Sks:	157
Perf Comments:		10 Min SIP:	1098	Total Acid:	1,000
		Sand Mesh:	20/40 Sand	Acid Type:	15% HCL
Comments:		Frac Gradient:	1.4		

Final Production After Stimula				
	MCFD	<b>Hours Tested</b>	Rock Pressure	
Final/Commingled Zones				
Commingled		52	in-line	



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

Tracking Number: 6120

**Company:** Range Resources-Pine

Mountain,

File Number: BU-5078

Operations Name: Haysi 35 w/PL

Operation Type: Coalbed/Pipeline

**Drilling Report Type:** Original

# **DRILLING REPORT (DGO-GO-14)**

## 1. Drilling Data

Date drilling commenced: 12/7/2014 Drilling Contractor: Gascp #2

Date drilling completed: 12/10/2014 Rig Type: Rotary ← Cable

Driller's Total Depth (feet): 2520.00

Log Total Depth (feet): 2522.00 Coal Seam at Total POCAHONTAS

Depth: #1

## 2. Final Location Plat (as required by 4 VAC25-150-360.C.)

Permitted State Plane X: 10399571.3100 Final Plat State Plane X: 10399572.2500

Permitted State Plane Y: 3618181.7600 Final Plat State Plane Y: 3618180.9100

Plat Previously Submitted Or...

List of Attached Items:

Form DGO-GO-14-E

Page 1 of 3

Rev. 04/2009

Description	FileName		
Haysi 35 Final Plat	Haysi-35 Final Plat.pdf		

# 3. Geological Data

Fresh Water At:

Depth (in feet)	Rate	Unit of Measure

Salt Water At:

Depth (in feet)	Rate	Unit of Measure
-----------------	------	-----------------

Coal Seams:

List of Attached Items:

Description	FileName		
Haysi 35 Coal	Coals Haysi 35.xlsx		

Gas and Oil Shows:

List of Attached Items:

Description	FileName	
Haysi 35 Gas Shows	Shows Haysi 35.xlsx	

## 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run: GR/CDL/PE/DIL/Neu/TEMP/Audio

 $\operatorname{\mathsf{Did}}\nolimits \operatorname{\mathsf{logs}}\nolimits \operatorname{\mathsf{disclose}}\nolimits \operatorname{\mathsf{vertical}}\nolimits \operatorname{\mathsf{locations}}\nolimits \operatorname{\mathsf{of}}\nolimits \operatorname{\mathsf{a}}\nolimits \operatorname{\mathsf{coal}}\nolimits$ 

seam?

£

# 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName	
Haysi 35 Survey	Survey Haysi 35.xlsx	

Form DGO-GO-14-E

Page 2 of 3

Rev. 04/2009

## 6. Casing and Tubing Program

List of Attached Items:

Description	FileName		
Haysi 35 Casing	Casing Haysi 35.xlsx		

## 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

8. Drillers Log	8.	Dril	lers	Log
-----------------	----	------	------	-----

Compiled By: Range Resources

List of Attached Items:

Description	FileName	
Haysi 35 Driller's Log	Drilling Haysi 35.xlsx	


## 9. Comments

0. Signature					
Permitee:	Range	Resources-Pine Mountain, Date		1/13/2015	
Signed By:	Laura I	Laura Murray		Regulatory Compliance Specialist	
			•		
INTERNAL	_ USE (	ONLY			
Submi	t Date:	1/13/2015			
5	Status:	A		Date:	1/13/2015
Final PDF	Date:	1/14/2015			

Form DGO-GO-14-E


Page 3 of 3

Rev. 04/2009



WELL LOCATION PLAT NORA GRID AD-67

COMPANY Range Resources-Pine Mountain, Inc. WELL NAME AND NUMBER Haysi-35
TRACT NO Noah Deel ELEVATION 2.019.75' QUADRANGLE Prater
COUNTY Buchanan DISTRICT Prater SCALE 1" = 400' DATE 12-8-2014
This Plat is a new plat; an updated plat; or a final location plat
Denotes the location of a well on United States topographic Maps, scale 1 to
+ 24,000, latitude and longitude lines being represented by border lines as shown.
L) if PJill
Licensed Professional Engineer or Licensed Land Surveyor



# WELL LOCATION PLAT NORA GRID AD-67

Area of Unit = 58.77 Ac.


Well Coordinates: (Clinchfield Coal Co.)

N 36,845.04 E 47,441.02

COMPANY Range Resources-Pin	e Mountain, Inc.	WELL NAME AND NUMBE	R _Havsi-35
TRACT NO. <u>Noah Deel</u>	ELEVATION _ <i>2.019.75</i>	QUADRANGLE Pra	ter
COUNTY Buchanan DIS	STRICT <u>Prater</u>	SCALE $1" = 400'$	_DATE _12-8-2014
This Plat is a new plat; an	updated plat; or	a final location plat	X
+ Denotes the location of a 1 24,000, latitude and longitu	de lines being represen	ted by border lines as	shown.
4	DiP Dill		
Licensed Profe	essional Engineer or Lic	ensed Land Surveyor	

Well elevation determined by GPS

survey from HARN Monument P-424



WELL LOCATION PLAT NORA GRID AD-67

COMPANY Range Resources-Pine Mountain, Inc. WELL NAME AND NUMBER Haysi-35
TRACT NO. Noah Deel ELEVATION 2.019.75' QUADRANGLE Prater
COUNTY Buchanan DISTRICT Prater SCALE 1" = 400' DATE 12-8-2014
This Plat is a new plat; an updated plat; or a final location plat
+ Denotes the location of a well on United States topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown.
24,000, latitude and longitude lines being represented by border lines as shown.
L) if PJill
Licensed Professional Engineer or Licensed Land Surveyor

Coal seams			Well # Haysi 35		01/09/15	
	Depth	Depth		Mining	in Area	
Names	Тор	Bottom	Thickness	Yes	No	Mined Out
Coal	198.00	199.00	1.00	. 55	No	No
Coal	229.00	230.00	1.00		No	No
Coal	580.00	581.00	1.00		No	No
Coal	640.00	641.00	1.00		No	No
Coal	860.00	861.00	1.00		No	No
Kennedy	874.40	875.5	1.10		No	No
Aily Rider	966.77	967.44	0.67		No	No
Aily	998.80	1000.22	1.42		No	No
Raven	1076.80	1078.4	1.60		No	No
Raven	1098.60	1098.8	0.20		No	No
Raven	1101.50	1101.6	0.10		No	No
Raven	1106.50	1106.7	0.20		No	No
Jawbone Rider	1192.70	1196.44	3.74		No	No
Jawbone	1227.10	1230.8	3.70		No	No
Tiller	1289.70	1290.7	1.00		No	No
Upper Seaboard	1395.90	1398.05	2.15		No	No
Greasy Creek	1548.90	1551.4	2.50		No	No
Upper Horsepen	1694.90	1695.57	0.67		No	No
Upper Horsepen	1702.90	1703.1	0.20		No	No
Middle Horsepen	1755.00	1756	1.00		No	No
Beckley	1836.10	1837.2	1.10		No	No
Beckley	1861.00	1862.2	1.20		No	No
Pocahontas #4	2200.70	2201.4	0.70		No	No
Pocahontas #3	2288.50	2291.9	3.40		No	No
Pocahontas #2	2352.50	2355	2.50		No	No
Pocahontas #2	2375.00	2375.2	0.20		No	No

# Gas and Oil Shows

FORMATION	DEPTH	THICKNESS	IPF (MCFD/BOPD)	PRESSURE	HOURS TESTED
	1263		Odor		
	1327		Odor		
	1579		Odor		
	1862		Odor		
	2306		Odor		
	2520		Odor		

**Survey Results** 

Depth of Survey	Direction/Distance/Degree From True Vertical
196	1/4
385	1/4
570	1/2
760	1/2
949	3/4
1137	3/4
1327	1/2
1516	1/2
1705	1/4
1894	1/4
2084	1/2
2275	3/4
2464	1/2
2510	1/2

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs	Cement Baskets
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set	(ft)
Conductor	13 3/8	0-92'	15		No			
Water Protection	9 5/8	0-344'	12 3/8	182	Yes	12/08/14		48' 92'
Coal Protection								
Production Casing	4½"	0-2475'	6 1/2	473	Yes	12/10/14		910'
Other Casing And								
Tubing Left In Well	23/8"							
Liners								

Drillers Log		Well # Haysi 35	1/9/2015		
			Depth	Depth	
Geologic Age	Formation	General Lithology	Тор	Bottom	Thickness
Pennsylvanian	Lee	КВ	0.00	8.00	8.00
Pennsylvanian	Lee	Overburden	8.00	120.00	112.00
Pennsylvanian	Lee	Sandyshale	120.00	150.00	30.00
Pennsylvanian	Lee	Sandstone	150.00	198.00	48.00
Pennsylvanian	Lee	Coal	198.00	199.00	1.00
Pennsylvanian	Lee	Sandstone	199.00	229.00	30.00
Pennsylvanian	Lee	Coal	229.00	230.00	1.00
Pennsylvanian	Lee	Sandstone	230.00	580.00	350.00
Pennsylvanian	Lee	Coal	580.00	581.00	1.00
Pennsylvanian	Lee	Sandyshale	581.00	640.00	59.00
Pennsylvanian	Lee	Coal	640.00	641.00	1.00
Pennsylvanian	Lee	Sandyshale	641.00	720.00	79.00
Pennsylvanian	Lee	Sandstone	720.00	860.00	140.00
Pennsylvanian	Lee	Coal	860.00	861.00	1.00
Pennsylvanian	Lee	Sandyshale	861.00	874.40	13.40
Pennsylvanian	Kennedy	Coal	874.40	875.50	1.10
Pennsylvanian	Lee	Sandyshale	875.50	966.77	91.27
Pennsylvanian	Aily Rider	Coal	966.77	967.44	0.67
Pennsylvanian	Lee	Sandyshale	967.44	998.80	31.36
Pennsylvanian	Aily	Coal	998.80	1000.22	1.42
Pennsylvanian	Lee	Sandyshale	1000.22	1076.80	76.58
Pennsylvanian	Raven	Coal	1076.80	1078.40	1.60
Pennsylvanian	Lee	Sandyshale	1078.40	1098.60	20.20
Pennsylvanian	Raven	Coal	1098.60	1098.80	0.20
Pennsylvanian	Lee	Sandyshale	1098.80	1101.50	2.70
Pennsylvanian	Raven	Coal	1101.50	1101.60	0.10
Pennsylvanian	Lee	Sandyshale	1101.60	1106.50	4.90
Pennsylvanian	Raven	Coal	1106.50	1106.70	
Pennsylvanian	Lee	Sandyshale	1106.70	1192.70	86.00
Pennsylvanian	Jawbone Rider	Coal	1192.70	1196.44	3.74
Pennsylvanian	Lee	Sandyshale	1196.44	1227.10	30.66
Pennsylvanian	Jawbone	Coal	1227.10	1230.80	3.70
Pennsylvanian	Lee Tiller	Sandyshale Coal	1230.80	1289.70 1290.70	58.90 1.00
Pennsylvanian			1289.70		
Pennsylvanian	Lee Upper Seaboard	Sandyshale	1290.70	1395.90	105.20
Pennsylvanian	1 1	Coal Sandyshale	1395.90	1398.05	2.15
Pennsylvanian Pennsylvanian	Lee Greasy Creek	Coal	1398.05 1548.90	1548.90	150.85 2.50
Pennsylvanian Pennsylvanian	Greasy Creek	Sandyshale	1548.90	1551.40 1694.90	143.50
Pennsylvanian Pennsylvanian	Lee Upper Horsepen	Coal	1694.90	1694.90	0.67
Pennsylvanian Pennsylvanian	<u> </u>	Sandyshale	1695.57	1702.90	7.33
Pennsylvanian	Lee	Coal	1702.90		0.20
Pennsylvanian	Upper Horsepen Lee	Sandyshale	1702.90	1703.10 1755.00	51.90
,		•			
Pennsylvanian	Middle Horsepen	Coal	1755.00	1756.00	1.00

Pennsylvanian	Lee	Sandyshale	1756.00	1836.10	80.10
Pennsylvanian	Beckley	Coal	1836.10	1837.20	1.10
Pennsylvanian	Lee	Sandyshale	1837.20	1861.00	23.80
Pennsylvanian	Beckley	Coal	1861.00	1862.20	1.20
Pennsylvanian	Lee	Sandyshale	1862.20	2200.70	338.50
Pennsylvanian	Pocahontas #4	Coal	2200.70	2201.40	0.70
Pennsylvanian	Lee	Sandyshale	2201.40	2288.50	87.10
Pennsylvanian	Pocahontas #3	Coal	2288.50	2291.90	3.40
Pennsylvanian	Lee	Sandyshale	2291.90	2352.50	60.60
Pennsylvanian	Pocahontas #2	Coal	2352.50	2355.00	2.50
Pennsylvanian	Lee	Sandyshale	2355.00	2375.00	20.00
Pennsylvanian	Pocahontas #2	Coal	2375.00	2375.2	0.20
Pennsylvanian	Lee	Sandyshale	2375.20	2513.87	138.67



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

	Tracking N	lumber:	9782					
	Company:		EnerVest Operating, LLC					
	File Numbe	er:	BU-5126					
	Completion	n Report Type:	Original					
(	COMPLETION RE	EPORT (DGO-	GO-15)					
Well Type:	Coalbed/Pipeline	Date Well C	ompleted:	10/12/2016				
Driller's Total Depth:	2501.00	Log's To	otal Depth:	2477.00				
. Changes In Casing/Tubing from Approved Drilling Report								
Descript	ion	FileName						
. Stimulation Record								
Stimulation Status: Sti	imulated GOB	Not Stimulated	Service	Well				
Descript	ion	FileName						
Perf Rep	ort	HAYSI-36 Perf Report.pdf						
Stimulation I	Report	HAYSI-36 Stimulation Report.pdf						
3. Final Production								
Descript	ion		FileNam	e				
<b>Descript</b> Final Produ		Ha	FileNam aysi 36 Final_					
		На						

Notes:							
5. Signature	<b>)</b>						
Permittee:	EnerVest	t Operating, LLC	Date:	12/15/2	016		(Company)
Ву:	Laura Mu	urray	Title:	Associate Landman			(Signature)
			,				
INTERN	AL USE (	ONLY					
	mit Date:	12/15/2016					
	Status:				Date:	12/15/2016	
Final P	DF Date:	12/27/2016			•		



## **HAYSI 036**

## Report date: 10/13/2016

# **Perforation Report**

Asset Name	APPALACHIAN
Project	APPALACHIA SOUTH
Site	HAYSI
Well Common Name	HAYSI 036
Operator	ENERVEST OPERATING, LLC
MD Top - MD Base	1,141.8 ft - 2,306.4 ft
Perf Length Gross	1,164.60 ft

## Intervals

Report Date	Stage	Formation	MD top (ft)	MD base (ft)	Shot density (shot/ft)	# of Shots	Charge Phasing (°)	Carr size (in)	Charge weight (gram)	Charge Manufacturer	Hole Diameter
10/12/2016	01	POCAHONTAS #02	2,304.7	2,306.4	3.00	6.000	60.00	2.500		Owens	0.32
10/12/2016	01	POCAHONTAS #03	2,245.8	2,250.0	3.00	14.000	60.00	2.250		Owens	0.32
10/12/2016	01	POCAHONTAS #04	2,218.0	2,219.0	3.00	4.000	60.00	2.500		Owens	0.32
10/12/2016	02	C SEAM	1,815.9	1,817.4	3.00	6.000	60.00	2.500		Owens	0.32
10/12/2016	02	C SEAM	1,790.4	1,791.6	3.00	5.000	60.00	2.500		Owens	0.32
10/12/2016	03	HORSEPEN MIDDLE	1,700.3	1,702.1	3.00	6.000	60.00	2.500		Owens	0.32
10/12/2016	03	HORSEPEN UPPER	1,646.8	1,648.4	3.00	6.000	60.00	2.500		Owens	0.32
10/12/2016	04	GREASY CREEK	1,490.7	1,493.7	3.00	10.000	60.00	2.750		Owens	0.42
10/12/2016	04	SEABOARD UPPER	1,340.8	1,343.8	3.00	10.000	60.00	2.500		Owens	0.42
10/12/2016	05	TILLER	1,232.1	1,233.6	3.00	6.000	60.00	2.750		Owens	0.42
10/12/2016	05	JAWBONE	1,182.6	1,184.0	3.00	5.000	60.00	2.750		Owens	0.42
10/12/2016	05	JAWBONE	1,178.8	1,180.8	3.00	7.000	60.00	2.750		Owens	0.42
10/12/2016	06	JAWBONE RIDER	1,141.8	1,144.5	3.00	9.000	60.00	2.750		Owens	0.42



## **APPALACHIAN**

# STIMULATION REPORT

Company / Asset	APPALACHIAN
Project / Basin	APPALACHIA SOUTH
Site / Field	HAYSI

Well common name:	HAYSI 036	API no.:	4502705126
Well legal name:	HAYSI 036	Bolo no.:	820000093
Wellbore name:	HAYSI 36	Wellbore No.:	00
Report No.:	1	Report date:	10/13/2016
Job Date:	10/12/2016	Event type:	COMPLETION
Spud date:	9/30/2016	Event end date:	
Contractor:	C&J ENERGY SERVICES	Active datum:	RKB @1,974.8ft (above Mean Sea Level)
Supervisor:	KEVIN DARBY		

Initial Wellhead Pressure (psi)	88.00
Water Source	FRESH

#### Summary for Stage No.: 1 - 10/12/2016

Summary for Stage 140 1 - 10/12/2010					
Fluid System: ENERGIZED - SW/N2 TREATMENT					
Interval Top: 2,218.0 ft	Frac Gradient: 1.1100 psi/ft				
Interval Base: 2,306.4 ft	Breakdown Press: 2,870.00 psi				
Stage Length: 88.4 ft	Breakdown Rate: 5.00 bbl/min				
CO2 Energized Quality (%):	Max Rate: 57.20 bbl/min				
N2 Energized Quality (%): 70.000	Avg Rate: 50.10 bbl/min				
No. of Perfs: 24	Max Treat. Press.: 3,994.00 psi				
No. of Clusters: 3	Avg Treat. Press.: 3,472.00 psi				
BP Removal Date:	Avg HHP:				
Screened out: No	ISIP: 1,523.00 psi				
Coil tubing used: No	10 Min ISIP:				
Tracer used: No	5 Min ISIP:				
	15 Min ISIP:				
	Total Proppant: 44,300 lbm				
	Total Propp. Format.: 44,300 lbm				
	Slurry Vol: 12,280.8 gal				
	Clean Vol: 10,277.4 gal				
	Treated Water Vol: 252.0 gal				

#### Fluids

Fluid name	Pumped (gal)	Energized Fluid total	Density (ppg)
ACID	252.0		
NITROGEN ENERGIZED		544100	

#### Proppants

Proppant name	Туре	Size	Used (Ibm)
WHITE	SAND	20/40	44,300

#### Summary for Stage No.: 2 - 10/12/2016

Summary for Stage No.: 2 - 10/12/2016					
Fluid System: ENERGIZED - SW/N2 TREATMENT					
Interval Top: 1,790.0 ft	Frac Gradient: 1.2400 psi/ft				
Interval Base: 1,817.4 ft	Breakdown Press: 2,646.00 psi				
Stage Length: 27.4 ft	Breakdown Rate: 5.00 bbl/min				
CO2 Energized Quality (%):	Max Rate: 40.10 bbl/min				
N2 Energized Quality (%): 70.000	Avg Rate: 34.70 bbl/min				
No. of Perfs: 11	Max Treat. Press.: 4,263.00 psi				
No. of Clusters: 2	Avg Treat. Press.: 4,081.00 psi				
BP Removal Date:	Avg HHP:				
Screened out: No	ISIP: 1,450.00 psi				
Coil tubing used: No	10 Min ISIP:				
Tracer used: No	5 Min ISIP:				
	15 Min ISIP:				
	Total Proppant: 15,800 lbm				
	Total Propp. Format.: 15,800 lbm				
	Slurry Vol: 11,806.2 gal				
	Clean Vol: 11,092.2 gal				
	Treated Water Vol: 252.0 gal				

#### Fluids

Fluid name	Pumped (gal)	Energized Fluid total	Density (ppg)
NITROGEN ENERGIZED		558700	
ACID	252.0		

#### Proppants

Proppant name	Туре	Size	Used (Ibm)
WHITE	SAND	20/40	15,800

#### Summary for Stage No.: 3 - 10/12/2016

Fluid System: ENERGIZED - SW/N2 TREATMENT					
Interval Top: 1,646.8 ft	Frac Gradient: 1.3900 psi/ft				
Interval Base: 1,702.1 ft	Breakdown Press: 2,114.00 psi				
Stage Length: 55.3 ft	Breakdown Rate: 5.20 bbl/min				
CO2 Energized Quality (%):	Max Rate: 53.20 bbl/min				
N2 Energized Quality (%): 70.000	Avg Rate: 48.20 bbl/min				
No. of Perfs: 12	Max Treat. Press.: 4,009.00 psi				
No. of Clusters: 2	Avg Treat. Press.: 3,552.00 psi				
BP Removal Date:	Avg HHP:				
Screened out: No	ISIP: 1,602.00 psi				
Coil tubing used: No	10 Min ISIP:				
Tracer used: No	5 Min ISIP:				
	15 Min ISIP:				

Total Proppant: 22,100 lbm

Total Propp. Format.: 22,100 lbm

Slurry Vol: 8,282.4 gal

Clean Vol: 7,282.8 gal

Treated Water Vol: 252.0 gal

#### Fluids

Fluid name	Pumped (gal)	Energized Fluid total	Density (ppg)
ACID	252.0		
NITROGEN ENERGIZED		345300	

#### Proppants

Proppant name	Туре	Size	Used (Ibm)
WHITE	SAND	20/40	22,100

#### Summary for Stage No.: 4 - 10/12/2016

Fluid System: ENERGIZED - SW/N2 TREATMENT					
Interval Top: 1,340.8 ft	Frac Gradient: 2.2300 psi/ft				
Interval Base: 1,493.7 ft	Breakdown Press: 2,073.00 psi				
Stage Length: 152.9 ft	Breakdown Rate: 5.10 bbl/min				
CO2 Energized Quality (%):	Max Rate: 51.30 bbl/min				
N2 Energized Quality (%): 70.000	Avg Rate: 37.90 bbl/min				
No. of Perfs: 20	Max Treat. Press.: 4,473.00 psi				
No. of Clusters: 2	Avg Treat. Press.: 4,054.00 psi				
BP Removal Date:	Avg HHP:				
Screened out: No	ISIP: 2,550.00 psi				
Coil tubing used: No	10 Min ISIP:				
Tracer used: No	5 Min ISIP:				
	15 Min ISIP:				
	Total Proppant: 33,600 lbm				
	Total Propp. Format.: 33,600 lbm				
	Slurry Vol: 15,615.6 gal				
	Clean Vol: 14,095.2 gal				
	Treated Water Vol: 252.0 gal				

#### Fluids

Fluid name	Pumped (gal)	Energized Fluid total	Density (ppg)
NITROGEN ENERGIZED		741400	
ACID	252.0		

#### Proppants

Proppant name	Туре	Size	Used (Ibm)
WHITE	SAND	20/40	33,600

#### Summary for Stage No.: 5 - 10/12/2016

Fluid System: ENERGIZED - SW/N2 TREATMENT			
Interval Top: 1,178.8 ft	Frac Gradient: 1,3800 psi/ft		
Interval Base: 1,233.6 ft	Breakdown Press: 2,217.00 psi		
Stage Length: 54.8 ft	Breakdown Rate: 5.00 bbl/min		
CO2 Energized Quality (%):	Max Rate: 65.10 bbl/min		
N2 Energized Quality (%): 70.000	Avg Rate: 54.70 bbl/min		
No. of Perfs: 18	Max Treat. Press.: 3,188.00 psi		
No. of Clusters: 3	Avg Treat. Press.: 2,860.00 psi		
BP Removal Date:	Avg HHP:		
Screened out: No	ISIP: 1,138.00 psi		
Coil tubing used: No	10 Min ISIP:		
Tracer used: No	5 Min ISIP:		
	15 Min ISIP:		
	Total Proppant: 29,700 lbm		
	Total Propp. Format.: 29,700 lbm		
	Slurry Vol: 8,341.2 gal		
	Clean Vol: 6,997.2 gal		
	Treated Water Vol: 252.0 gal		

## Fluids

Fluid name	Pumped (gal)	Energized Fluid total	Density (ppg)
ACID	252.0		
NITROGEN ENERGIZED		326300	

#### Proppants

Proppant name	Туре	Size	Used (Ibm)
WHITE	SAND	20/40	29,700

#### Summary for Stage No.: 6 - 10/12/2016

#### Fluids

# Fluid name Pumped (gal) Energized Fluid total Density (ppg) NITROGEN ENERGIZED 310000

#### Proppants

Proppant name	Туре	Size	Used (Ibm)
WHITE	SAND	20/40	19,300

Summary for Stage No.: 6 - 10/12/2	Summary for Stage No.: 6 - 10/12/2016			
Fluid System: ENERGIZED - SW/N2 TREATMENT				
Interval Top: 1,141.8 ft	Frac Gradient: 1.8900 psi/ft			
Interval Base: 1,144.5 ft	Breakdown Press: 1,411.00 psi			
Stage Length: 2.7 ft	Breakdown Rate: 5.00 bbl/min			
CO2 Energized Quality (%):	Max Rate: 36.20 bbl/min			
N2 Energized Quality (%): 70,000	Avg Rate: 31.50 bbl/min			
No. of Perfs: 9	Max Treat. Press.: 4,399.00 psi			
No. of Clusters: 1	Avg Treat. Press.: 4,012.00 psi			
BP Removal Date:	Avg HHP:			
Screened out: No	ISIP: 1,670.00 psi			
Coil tubing used: No	10 Min ISIP: 1,304.00 psi			
Tracer used: No	5 Min ISIP: 1,348.00			
	15 Min ISIP:			
	Total Proppant: 19,300 lbm			
	Total Propp. Format.: 19,300 lbm			
	Slurry Vol: 5,896.8 gal			
	Clean Vol: 5,023.2 gal			
	Treated Water Vol: 0.0 gal			

Final Production After Stimulation				
	BOD	MCFD	<b>Hours Tested</b>	Rock Pressure
Final/Commingled Zones				
Commingled		30	in-line	



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

Tracking Number:	9848
Company:	EnerVest Operating, LLC
File Number:	BU-5126
Operations Name:	Haysi 36 w/PL
Operation Type:	Coalbed/Pipeline
<b>Drilling Report Type:</b>	Original

## **DRILLING REPORT (DGO-GO-14)**

1. Drilling Data				
Date drilling commenced: 9/30/2016		Drilling Contractor: Gasco #5		
Date drilling completed:	10/4/2016	— Rig Type: X Ro	otary Cable	
Driller's Total Depth (feet):	2501.00			
Log Total Depth (feet):	2477.00	Coal Seam at Tot Dep		
2. Final Location Plat (as requir	ed by 4 VAC25-1	50-360.C.)		
Permitted State Plane X: 10398586.7300 Permitted State Plane Y: 3618212.9800  Plat Previously Submitted Or  List of Attached Items:		Final Plat State Plane X: Final Plat State Plane Y:	10398584.0900 3618212.4900	
Description		FileNam	ne	
Haysi 36 Final Plat		HAYSI-36 Final Plat.pdf		

Haysi 36 Final Plat	HAYSI-36 Final Plat.pdf

Form DGO-GO-14-E

Page 1 of 4

Haysi 36 Plat Attachment		Haysi-36_ plat Owner Info.pdf		
B. Geological Data				
Fresh Water At:				
Depth (in feet)		Rate	Unit of Measure	
Salt Water At:				
Depth (in feet)		Rate	Unit of Measure	
2150		2	INCH	
2233		wet		
Coal Seams:				
List of Attached Items:				
Description		FileName		
Coal		Haysi 36 Coals.xlsx		
Gas and Oil Shows:				
List of Attached Items:				
Description		FileN	lame	
Shows		Haysi 36 S	Shows.xlsx	
I. Geophysical Logs (As required by 4VAC25-150-280.A)				
List all logs run: GR/CDL/PE/DIL/Neu/TEMP/Audio				
Did logs disclose vertical locations of a coal seam?				
Survery Results (As required by 4VAC25-150-280.B.2)				
List of Attached Items:				
Description		FileN	lame	
Surveys		Haysi 36 Sı	urveys.xlsx	

Form DGO-GO-14-E

Page 2 of 4

## 6. Casing and Tubing Program

List of Attached Items:

Description	FileName	
Casing	Haysi 36 Casing.xlsx	

## 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

8. Drillers Lo	g
----------------	---

Compiled By: EnerVest Operating, LLC

List of Attached Items:

Description	FileName	
Driller's Log	Haysi 36 DrillersLog.xlsx	

### 9. Comments

10. Signatur	е
--------------	---

Permitee: EnerVest Operating, LLC Date: 12/14/2016

Signed By: Laura Murray Title: Associate Landman

## INTERNAL USE ONLY


Submit Date: 12/14/2016

Status: A Date: 12/15/2016

Form DGO-GO-14-E

Page 3 of 4

Final PDF Date: 12/15/2016



WELL LOCATION PLAT NORA GRID AD-66

COMPANY <u>EnerVest Operating</u> , <u>LLC</u>	WELL NAME AND NUMBER <u>Haysi-36</u>
TRACT NO. <u>Henry Deel</u> ELEVATION _1,	<i>964.46</i> QUADRANGLE <i>Prater</i>
COUNTY Buchanan DISTRICT Prater	SCALE <u>1" = 400'</u> DATE <u>10-01-2016</u>
This Plat is a new plat; an updated plat	
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
+ Denotes the location of a well on United St 24,000, latitude and longitude lines being re	epresented by border lines as shown.
010-101 10.	
Gl F) Mullips	

Licensed Professional Engineer or Licensed Land Surveyor

# HAYSI-36 PLAT TRACT OWNERSHIP INFORMATION SCHEDULE

10/1/2016

#### 1. Henry Deel

87.64 Acres

ACIN LLC - coal

Paramont Contura, LLC - coal lessee

WBRD LLC - coal

Dickenson-Russell Contura, LLC - coal lessee

EnerVest Energy Institutional Fund XIV-A, L.P., EnerVest Energy Institutional Fund XIV-A1, L.P., & EnerVest Energy Institutional Fund XIV-WIC, L.P. - oil, gas & CBM

Gas 22.05 Ac. 37.52%

#### 2. C. P. Self & M. E. Deel

106.63 Acres

ACIN LLC - coal

Paramont Contura, LLC - coal lessee

WBRD LLC - coal

Dickenson-Russell Contura, LLC - coal lessee

EnerVest Energy Institutional Fund XIV-A, L.P., EnerVest Energy Institutional Fund XIV-A1, L.P., & EnerVest Energy Institutional Fund XIV-WIC, L.P. - oil, gas & CBM

Gas 29.02 Ac. 49.38%

#### 3. Noah Deel

93.41 Acres

ACIN LLC - coal

Paramont Contura, LLC - coal lessee

WBRD LLC - coal

Dickenson-Russell Contura, LLC - coal lessee

EnerVest Energy Institutional Fund XIV-A, L.P., EnerVest Energy Institutional Fund XIV-A1, L.P., & EnerVest Energy Institutional Fund XIV-WIC, L.P. - oil, gas & CBM

Gas 7.70 Ac. 13.10%

Coal seams			Well #	Haysi 36		
	Depth	Depth		Mining	in Area	
Names	Тор	Bottom	Thickness	Yes	No	Mined Out
Aily	958.40	959.70	959.70		No	No
Raven	1016.50	1017.90	1017.90		No	No
Raven	1025.20	1026.90	1026.90		No	No
Jawbone Rider	1142.00	1144.30	1144.30		No	No
Jawbone	1179.00	1180.60	1180.60		No	No
Jawbone	1182.80	1183.80	1183.80		No	No
Tiller	1232.30	1233.40	1233.40		No	No
Upper Seaboard A	1306.00	1306.10	1306.10		No	No
Upper Seaboard	1341.00	1343.60	1343.60		No	No
Greasy Creek	1490.90	1493.50	1493.50		No	No
Middle Seaboard	1533.40	1533.50	1533.50		No	No
Lower Seaboard	1593.00	1593.10	1593.10		No	No
Unnamed A	1614.50	1614.60	1614.60		No	No
Unnamed B	1629.50	1629.60	1629.60		No	No
Upper Horsepen	1647.00	1648.20	1648.20		No	No
Middle Horsepen	1700.50	1701.90	1701.90		No	No
C Seam Rider	1790.60	1791.40	1791.40		No	No
C Seam	1816.10	1817.20	1817.20		No	No
War Creek	1851.00	1851.10	1851.10		No	No
Unnamed C	1877.00	1877.10	1877.10		No	No
Beckley	1903.50	1903.60	1903.60		No	No
Lower Horsepen	1911.50	1911.60	1911.60		No	No
Pocahontas #9	1944.60	1944.70	1944.70		No	No
Pocahontas #8	2014.00	2014.10	2014.10		No	No
Pocahontas #7	2090.00	2090.10	2090.10		No	No
Pocahontas #6	2145.70	2147.10	2147.10		No	No
Pocahontas #5	2187.40	2187.50	2187.50		No	No
Pocahontas #4	2218.20	2218.80	2218.80		No	No
Pocahontas #3	2246.00	2249.80	2249.80		No	No
Pocahontas #2	2304.90	2306.20	2306.20		No	No
Pocahontas #1	2397.50	2397.60	2397.60		No	No

Gas and Oil Shows

Haysi 36

FORMATION	DEPTH	THICKNESS	IPF (MCFD/BOPD)	PRESSURE	HOURS TESTED
	1103		N/S		
	1855		N/S		
	2248		N/S		

Survey Results Haysi 36

Depth of Survey	Direction/Distance/Degree From True Vertical
193	1/2
380	1/2
521	3/4
721	1/2
915.00	1/4
1,103.00	1/2
1,292.00	1/4
1,479.00	3/4
1,667.00	3/4
1,855.00	1
2,044.00	3/4
2,248.00	1/2
2,421.00	1/4

Casing Program

Haysi 36	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs	Cement Baskets (ft)
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set	
Conductor	18	0-42'	22	Sanded in	No			
Conductor	13 3/8	0-84'	13 3/8	Sanded in	No			
Water Protection	9 5/8	0-848'	12 3/8	151	Yes	10/04/16		382'
Coal Protection								
Production Casing	4½"	0-2378'	6 3/8	378	Yes	10/06/16		2378'
Other Casing And								
Tubing Left In Well	23/8"	0-2269'						
Liners								

Drillers Log		Well # Haysi 36	10/11/2016			
		,	De	pth	Depth	
Geologic Age	Formation	General Lithology		op	Bottom	Thickness
Pennsylvanian	Lee	Sand/Shale/Coal	0.	.00	958.40	958.40
Pennsylvanian	Lee	Aily	958	8.40	959.70	1.30
Pennsylvanian	Lee	Sand/Shale		9.70	1016.50	56.80
Pennsylvanian	Lee	Raven		6.50	1017.90	1.40
Pennsylvanian	Lee	Sand/Shale	101	7.90	1025.20	7.30
Pennsylvanian	Lee	Raven	102	5.20	1026.90	1.70
Pennsylvanian	Lee	Sand/Shale	102	6.90	1142.00	115.10
Pennsylvanian	Lee	Jawbone Rider	114	2.00	1144.30	2.30
Pennsylvanian	Lee	Sand/Shale		4.30	1179.00	34.70
Pennsylvanian	Lee	Jawbone	117	9.00	1180.60	1.60
Pennsylvanian	Lee	Sand/Shale	118	0.60	1182.80	2.20
Pennsylvanian	Lee	Jawbone		2.80	1183.80	1.00
Pennsylvanian	Lee	Sand/Shale		3.80	1232.30	48.50
Pennsylvanian	Lee	Tiller		2.30	1233.40	1.10
Pennsylvanian	Lee	Sand/Shale		3.40	1306.00	72.60
Pennsylvanian	Lee	Upper Seaboard A		6.00	1306.10	0.10
Pennsylvanian	Lee	Sand/Shale		6.10	1341.00	34.90
Pennsylvanian	Lee	Upper Seaboard		1.00	1343.60	2.60
Pennsylvanian	Lee	Sand/Shale		3.60	1490.90	147.30
Pennsylvanian	Lee	Greasy Creek		0.90	1493.50	2.60
Pennsylvanian	Lee	Sand/Shale	149	3.50	1533.40	39.90
Pennsylvanian	Lee	Middle Seaboard		3.40	1533.50	0.10
Pennsylvanian	Lee	Sand/Shale	153	3.50	1593.00	59.50
Pennsylvanian	Lee	Lower Seaboard	159	3.00	1593.10	0.10
Pennsylvanian	Lee	Sand/Shale	159	3.10	1614.50	21.40
Pennsylvanian	Lee	Unnamed A	161	4.50	1614.60	0.10
Pennsylvanian	Lee	Sand/Shale	161	4.60	1629.50	14.90
Pennsylvanian	Lee	Unnamed B	162	9.50	1629.60	0.10
Pennsylvanian	Lee	Sand/Shale	162	9.60	1647.00	17.40
Pennsylvanian	Lee	Upper Horsepen	164	7.00	1648.20	1.20
Pennsylvanian	Lee	Sand/Shale	164	8.20	1700.50	52.30
Pennsylvanian	Lee	Middle Horsepen	170	0.50	1701.90	1.40
Pennsylvanian	Lee	Sand/Shale	170	1.90	1790.60	88.70
Pennsylvanian	Lee	C Seam Rider	179	0.60	1791.40	0.80
Pennsylvanian	Lee	Sand/Shale	179	1.40	1816.10	24.70
Pennsylvanian	Lee	C Seam	181	6.10	1817.20	1.10
Pennsylvanian	Lee	Sand/Shale	181	7.20	1851.00	33.80
Pennsylvanian	Lee	War Creek	185	1.00	1851.10	0.10
Pennsylvanian	Lee	Sand/Shale	185	1.10	1877.00	25.90
Pennsylvanian	Lee	Unnamed C	187	7.00	1877.10	0.10
Pennsylvanian	Lee	Sand/Shale	187	7.10	1903.50	26.40
Pennsylvanian	Lee	Beckley	190	3.50	1903.60	0.10
Pennsylvanian	Lee	Sand/Shale	190	3.60	1911.50	7.90

Pennsylvanian	Lee	Lower Horsepen	1911.50	1911.60	0.10
Pennsylvanian	Lee	Sand/Shale	1911.60	1944.60	33.00
Pennsylvanian	Lee	Pocahontas #9	1944.60	1944.70	0.10
Pennsylvanian	Lee	Sand/Shale	1944.70	2014.00	69.30
Pennsylvanian	Lee	Pocahontas #8	2014.00	2014.10	0.10
Pennsylvanian	Lee	Sand/Shale	2014.10	2090.00	75.90
Pennsylvanian	Lee	Pocahontas #7	2090.00	2090.10	0.10
Pennsylvanian	Lee	Sand/Shale	2090.10	2145.70	55.60
Pennsylvanian	Lee	Pocahontas #6	2145.70	2147.10	1.40
Pennsylvanian	Lee	Sand/Shale	2147.10	2187.40	40.30
Pennsylvanian	Lee	Pocahontas #5	2187.40	2187.50	0.10
Pennsylvanian	Lee	Sand/Shale	2187.50	2218.20	30.70
Pennsylvanian	Lee	Pocahontas #4	2218.20	2218.80	0.60
Pennsylvanian	Lee	Sand/Shale	2218.80	2246.00	27.20
Pennsylvanian	Lee	Pocahontas #3	2246.00	2249.80	3.80
Pennsylvanian	Lee	Sand/Shale	2249.80	2304.90	55.10
Pennsylvanian	Lee	Pocahontas #2	2304.90	2306.20	1.30
Pennsylvanian	Lee	Sand/Shale	2306.20	2397.50	91.30
Pennsylvanian	Lee	Pocahontas #1	2397.50	2397.60	0.10
Pennsylvanian	Lee	Sand/Shale	2397.60	2501.00	103.40



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

•		Tracking N	umber:	9923		
		Company:		EnerVest 0	Operating, LLC	
		File Numbe	er:	BU-5144		
		Completion	n Report Type:	Original		
		COMPLETION RE	PORT (DGO-	GO-15)		
	Well Type:	Coalbed/Pipeline	Date Well C	ompleted:	6/27/2017	
	Driller's Total Depth:	2373.00	Log's To	otal Depth:	2377.00	
Ch	anges In Casing/Tubing f	om Approved Drilli	ng Report			
	Descripti	on		FileNam	пе	
Wa	nter Protection Casing Cer	ment Bond Log				
	Descripti	on	FileName			
	Cement Re	port	Haysi-37 Cement Chart.pdf			
Sti	mulation Record					
	Stimulation Status: X Stir Chemical Disclosure submits Final Fracturing Ingredient		Not Stimulated	Service	e Well	
	Descripti	on		FileNam	ne	
	Perf Rep	Haysi-37 Perforation Report.pdf				
	Stimulation F	Haysi-37 Stimulation Report.pdf				
Fin	nal Production					
[	Descripti	FileName				
ı	Final Produ	Haysi 37 Final_Prod.xls				
Co	mments					

Notes:	
OK. [11/8/2017, cwh]	

Signature

Permittee:EnerVest Operating, LLCDate:11/2/2017(Company)By:Laura MurrayTitle:Associate Landman(Signature)

 INTERNAL USE ONLY

 Submit Date:
 11/2/2017

 Status:
 Date:

 Final PDF Date:
 11/8/2017



## HAYSI 037

#### Report date: 6/28/2017

## **Perforation Report**

Asset Name	APPALACHIAN
Project	APPALACHIA SOUTH
Site	HAYSI
Well Common Name	HAYSI 037
Operator	ENERVEST OPERATING, LLC
MD Top - MD Base	981.4 ft - 2,254.6 ft
Perf Length Gross	1,273.20 ft

## Intervals

Report Date	Stage	Formation	MD top	MD base	Shot	# of	Charge	Carr	Charge	Charge Manufacturer	Hole
			(ft)	(ft)	density (shot/ft)	Shots	Phasing (°)	size (in)	weight (gram)		Diameter
06/27/2017	01	POCAHONTAS #02	2252	2255	3.00	8.000	60.00	2.500		Owens	0.32
06/27/2017	01	POCAHONTAS #03	2193	2197	3.00	15.000	60.00	2.500		Owens	0.32
06/27/2017	01	POCAHONTAS #04	2113	2116	3.00	9.000	60.00	2.500		Owens	0.32
06/27/2017	02	HORSEPEN LOWER	1853	1855	3.00	8.000	60.00	2.500		Owens	0.32
06/27/2017	02	HORSEPEN LOWER	1844	1846	3.00	6.000	60.00	2.500		Owens	0.32
06/27/2017	02	BECKLEY	1812	1815	3.00	9.000	60.00	2.500		Owens	0.32
06/27/2017	03	WAR CREEK	1723	1725	3.00	8.000	60.00	2.750		Owens	0.42
06/27/2017	03	HORSEPEN MIDDLE	1646	1648	3.00	9.000	60.00	2.750		Owens	0.42
06/27/2017	03	HORSEPEN UPPER	1583	1585	3.00	6.000	60.00	2.750		Owens	0.42
06/27/2017	04	GREASY CREEK	1448	1452	3.00	12.000	60.00	2.750		Owens	0.42
06/27/2017	04	SEABOARD UPPER	1303	1306	3.00	12.000	60.00	2.750		Owens	0.42
06/27/2017	05	TILLER	1194	1196	3.00	6.000	60.00	2.750		Owens	0.42
06/27/2017	05	JAWBONE	1144	1146	3.00	6.000	60.00	2.750		Owens	0.42
06/27/2017	05	JAWBONE	1134	1138	3.00	12.000	60.00	2.750		Owens	0.42
06/27/2017	06	JAWBONE RIDER	1090	1094	3.00	11.000	60.00	2.750		Owens	0.42
06/27/2017	06	RAVEN	981	985	3.00	11.000	60.00	2.750		Owens	0.42



## **APPALACHIAN**

## STIMULATION REPORT

Company / Asset	APPALACHIAN
Project / Basin	APPALACHIA SOUTH
Site / Field	HAYSI

Well common name:	HAYSI 037	API no.:	4502705144
Well legal name:	HAYSI 37	Bolo no.:	411116369
Wellbore name:	HAYSI 37	Wellbore No.:	00
Report No.:	1	Report date:	6/28/2017
Job Date:	6/27/2017	Event type:	COMPLETION
Spud date:	6/3/2017	Event end date:	
Contractor:	C&J ENERGY SERVICES	Active datum:	RKB @1,974.1ft (above Mean Sea Level)
Supervisor:	KEVIN DARBY	-	_

Initial Wellhead Pressure (psi)	48.00
Water Source	LITTLE GREENBRIER

Summary for Stage No.: 1 - 6/27/2017						
Fluid System: ENERGIZED - SW/N2 TF	REATMENT					
interval Top MD: 2,113.4 ft	Frac Gradient: 1.1900 psi/ft	ŀ				
nterval Base MD: 2,254.6 ft	Breakdown Press: 2,354.00 psi					
Stage Length: 141.2 ft	Breakdown Rate: 2.80 bbl/min					
CO2 Energized Quality (%):	Max Rate: 50.40 bbl/min	ı				
N2 Energized Quality (%): 65.000	Avg Rate: 47.20 bbl/min					
No. of Perfs: 32	Max Treat. Press.: 4,220.00 psi					
No. of Clusters: 3	Avg Treat. Press.: 3,524.00 psi					
BP Removal Date:	Avg HHP:					
Screened Out: No	ISIP: 1,646.00 psi					
Coil Tubing Used: No	10 Min ISIP:					
Fracer Used: No	5 Min ISIP:					
	15 Min ISIP:					
	Total Proppant: 45,200 lbm					
	Total Propp. Format.: 45,200 lbm					
	Slurry Vol: 13,343.4 gal					
	Clean Vol: 11,440.8 gal					
	Treated Water Vol: 252.0 gal					

## Fluids

Fluid name	Pumped (gal)	Energized Fluid total	Density (ppg)
ACID	252.0		
NITROGEN ENERGIZED		608200	

### Proppants

Proppant name	Туре	Size	Used (lbm)
WHITE	SAND	20/40	45,200

Summary for Stage No.: 2 - 6/27/2017					
Fluid System: ENERGIZED - SW/N2	Fluid System: ENERGIZED - SW/N2 TREATMENT				
Interval Top MD: 1,811.9 ft	Frac Gradient: 1.2200 psi/ft				
Interval Base MD: 1,855.4 ft	Breakdown Press: 3,013.00 psi				
Stage Length: 43.5 ft	Breakdown Rate: 6.00 bbl/min				
CO2 Energized Quality (%):	Max Rate: 55.70 bbl/min				
N2 Energized Quality (%): 70.000	Avg Rate: 52.50 bbl/min				
No. of Perfs: 23	Max Treat. Press.: 3,496.00 psi				
No. of Clusters: 3	Avg Treat. Press.: 3,302.00 psi				
BP Removal Date:	Avg HHP:				
Screened Out: No	ISIP: 1,450.00 psi				
Coil Tubing Used: No	10 Min ISIP:				
Tracer Used: No	5 Min ISIP:				
	15 Min ISIP:				
	Total Proppant: 29,700 lbm				
	Total Propp. Format.: 29,700 lbm				
	Slurry Vol: 8,857.8 gal				
	Clean Vol: 7,883.4 gal				
	Treated Water Vol: 252.0 gal				

252.0		
	392300	
		392300

### Proppants

Proppant name	Туре	Size	Used (lbm)
WHITE	SAND	20/40	29,700

August 07, 2017 at 10:22 am OpenWells

um	mary	for	Stag	e No	.: 3	- 6	/27/2	201
hiid	Sycto	m· I		CIZE	ח	C1/	V/NI2	TD

ouninary for orago from o cizinzi		
Fluid System: ENERGIZED - SW/N2	FREATMENT	7
Interval Top MD: 1,582.8 ft	Frac Gradient: 1.2600 psi/ft	٦,
Interval Base MD: 1,725.4 ft	Breakdown Press: 3,506.00 psi	٦Ľ
Stage Length: 142.6 ft	Breakdown Rate: 6.00 bbl/min	٦ ١
CO2 Energized Quality (%):	Max Rate: 56.20 bbl/min	76
N2 Energized Quality (%): 70.000	Avg Rate: 52.80 bbl/min	1
No. of Perfs: 23	Max Treat. Press.: 3,706.00 psi	1
No. of Clusters: 3	Avg Treat. Press.: 3,281.00 psi	7
BP Removal Date:	Avg HHP:	
Screened Out: No	ISIP: 1,367.00 psi	7
Coil Tubing Used: No	10 Min ISIP:	7
Tracer Used: No	5 Min ISIP:	7
	15 Min ISIP:	1
	Total Proppant: 28,400 lbm	7
	Total Propp. Format.: 28,400 lbm	7

Slurry Vol: 8,635.2 gal Clean Vol: 7,341.6 gal Treated Water Vol: 252.0 gal

#### Fluids

Fluid name	Pumped (gal)	Energized Fluid total	Density (ppg)
ACID	252.0		
NITROGEN ENERGIZED		396300	

#### Proppants

Proppant name	Туре	Size	Used (lbm)
WHITE	SAND	20/40	28,400

### Summary for Stage No.: 4 - 6/27/2017

Fluid System: ENERGIZED - SW/N2 TREATMENT				
Interval Top MD: 1,302.5 ft	Frac Gradient: 1.3900 psi/ft			
Interval Base MD: 1,451.5 ft	Breakdown Press: 2,779.00 psi			
Stage Length: 149.0 ft	Breakdown Rate: 6.10 bbl/min			
CO2 Energized Quality (%):	Max Rate: 44.80 bbl/min			
N2 Energized Quality (%): 70.000	Avg Rate: 41.30 bbl/min			
No. of Perfs: 24	Max Treat. Press.: 3,706.00 psi			
No. of Clusters: 2	Avg Treat. Press.: 2,654.00 psi			
BP Removal Date:	Avg HHP:			
Screened Out: No	ISIP: 1,313.00 psi			
Coil Tubing Used: No	10 Min ISIP:			
Tracer Used: No	5 Min ISIP:			
	15 Min ISIP:			
	Total Proppant: 38,600 lbm			
	Total Propp. Format.: 38,600 lbm			
	Slurry Vol: 9,219.0 gal			
	Clean Vol: 7,547.4 gal			
	Treated Water Vol: 252.0 gal			

#### Fluids

Fluid name	Pumped (gal)	Energized Fluid total	Density (ppg)
NITROGEN ENERGIZED		375600	
ACID	252.0		

### Proppants

Proppant name	Туре	Size	Used (lbm)
WHITE	SAND	20/40	38,600

#### Summary for Stage No.: 5 - 6/27/2017

Fluid System: ENERGIZED - SW/N2 TREATMENT			
Interval Top MD: 1,134.1 ft	Frac Gradient: 1.4000 psi/ft		
Interval Base MD: 1,195.7 ft	Breakdown Press: 2,646.00 psi		
Stage Length: 61.6 ft	Breakdown Rate: 6.10 bbl/min		
CO2 Energized Quality (%):	Max Rate: 44.60 bbl/min		
N2 Energized Quality (%): 70.000	Avg Rate: 41.10 bbl/min		
No. of Perfs: 24	Max Treat. Press.: 3,918.00 psi		
No. of Clusters: 3	Avg Treat. Press.: 3,312.00 psi		
BP Removal Date:	Avg HHP:		
Screened Out: No	ISIP: 1,123.00 psi		
Coil Tubing Used: No	10 Min ISIP:		
Tracer Used: No	5 Min ISIP:		
	15 Min ISIP:		
	Total Proppant: 27,700 lbm		
	Total Propp. Format.: 27,700 lbm		
	Slurry Vol: 7,274.4 gal		
	Clean Vol: 6,010.2 gal		
	Treated Water Vol: 252.0 gal		

## Fluids

Fluid name	Pumped (gal)	Energized Fluid total	Density (ppg)
NITROGEN ENERGIZED		315700	
ACID	252.0		

#### Proppants

Proppant name	Туре	Size	Used (lbm)
WHITE	SAND	20/40	27,700

#### Summary for Stage No.: 6 - 6/27/2017

#### Fluids

Fluid name

NITROGEN ENERGIZED

(gal)

#### Energized Fluid total Density Pumped (ppg)

313200

#### Proppants

Proppant name	Туре	Size	Used (lbm)
WHITE	SAND	20/40	37,300

Summary for Stage No.: 6 - 6/2//2017				
Fluid System: ENERGIZED - SW/N2 TREATMENT				
Interval Top MD: 981.4 ft	Frac Gradient: 2.3600 psi/ft			
Interval Base MD: 1,093.8 ft	Breakdown Press: 2,524.00 psi			
Stage Length: 112.4 ft	Breakdown Rate: 5.90 bbl/min			
CO2 Energized Quality (%):	Max Rate: 40.20 bbl/min			
N2 Energized Quality (%): 70.000	Avg Rate: 39.10 bbl/min			
No. of Perfs: 22	Max Treat. Press.: 3,823.00 psi			
No. of Clusters: 2	Avg Treat. Press.: 2,854.00 psi			
BP Removal Date:	Avg HHP:			
Screened Out: No	ISIP: 2,002.00 psi			
Coil Tubing Used: No	10 Min ISIP: 1,250.00 psi			
Tracer Used: No	5 Min ISIP: 1,309.00			
	15 Min ISIP:			
	Total Proppant: 37,300 lbm			
	Total Propp. Format.: 37,300 lbm			
	Slurry Vol: 7,429.8 gal			
	Clean Vol: 6,081.6 gal			
	Treated Water Vol: 0.0 gal			
	·			

Final Production After Stimulation			Haysi 37	
BOD		MCFD	<b>Hours Tested</b>	Rock Pressure
Final/Commingled Zones				
Commingled		50	in-line	



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

Tracking Number:	9981
Company:	EnerVest Operating, LLC
File Number:	BU-5144
Operations Name:	Haysi 37 w/PL
Operation Type:	Coalbed/Pipeline
Drilling Report Type:	Original

## **DRILLING REPORT (DGO-GO-14)**

1. Drilling Data				
Date drilling commenced:	6/3/2017	Drilling Contract	or: Gasco #5	
Date drilling completed:	6/4/2017		otary Cable	
Driller's Total Depth (feet):	2373.00		_	
Log Total Depth (feet):	2377.00	Coal Seam at Tot Dep		
2. Final Location Plat (as required by 4 VAC25-150-360.C.)				
	18953.1800	Final Plat State Plane X: Final Plat State Plane Y:	10402931.6600 3618952.9100	
Description		FileNam	пе	
Haysi 37 Final Plat		Haysi-37 Final plat.pdf		

Haysi 37 Plat attachment	Haysi-37_Plat Owner Info.pdf			
3. Geological Data				
Fresh Water At:				
Fresh water At:				
Depth (in feet)	Rate Unit of Measure			
Salt Water At:				
Depth (in feet)	Rate Unit of Measure			
Coal Seams:				
List of Attached Items:				
Description	FileName			
Haysi 37 Coals.xlsx				
Gas and Oil Shows:				
List of Attached Items:				
Description	FileName			
Haysi 37 Shows	Haysi 37 Shows.xlsx			
4. Geophysical Logs (As required by 4VAC25-1	50-280.A)			
List all logs run: GR/CDL/PE/DIL/Neu/TEMP	/Audio			
Did logs disclose vertical locations of a coal seam?				
5. Survery Results (As required by 4VAC25-150	-280.B.2)			
List of Attached Items:				
Description	FileName			
Haysi 37 Surveys Haysi 37 Survey.xlsx				
	Haysi 37 Survey.xisx			

Form DGO-GO-14-E

Page 2 of 3

Rev. 05/2017

### List of Attached Items:

Description	FileName	
Haysi 37 Casing, Centralizers and Tubing	Haysi 37 Casing.xlsx	

## 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

8. Dri	llers	Log
--------	-------	-----

Compiled By: EnerVest Operating, LLC

List of Attached Items:

Description	FileName
Haysi 37 Driller's Log	Haysi 37 DrillersLog.xlsx

### 9. Comments

Drilling Report OK. [8/30/2017, cwh]

1	0.	Sig	ına	ıtu	re

Permitee: EnerVest Operating, LLC Date: 8/18/2017

Signed By: Laura Murray Title: Associate Landman

## INTERNAL USE ONLY

Submit Date: 8/18/2017


Status: A Date: 8/30/2017

Final PDF Date: 8/31/2017

Form DGO-GO-14-E

Page 3 of 3

Rev. 05/2017



WELL LOCATION PLAT NORA GRID AD-69

COMPANY <u>EnerVest Operating, LLC</u> WELL NAME AND NUMBER <u>Haysi-37</u>
FRACT NO. Jas. M. Owens ELEVATION 1,963.79' QUADRANGLE Prater
COUNTY <u>Buchanan</u> DISTRICT <u>Prater</u> SCALE <u>1" = 400"</u> DATE <u>6-5-2017</u>
This Plat is a new plat; an updated plat; or a final location platx
Denotes the location of a well on United States topographic Maps, scale 1 to
24,000, latitude and longitude lines being represented by border lines as shown.
Gla Tophillips
Licensed Professional Engineer or Licensed Land Surveyor

## HAYSI-37 FINAL PLAT TRACT OWNERSHIP INFORMATION SCHEDULE 6/5/2017

## 1. Jas. M. Owens

409.73 Acres

ACIN LLC - coal

Paramont Contura, LLC - coal lessee

WBRD LLC - coal

Dickenson-Russell Contura, LLC - coal lessee

EnerVest Energy Institutional Fund XIV-A, L.P., EnerVest Energy Institutional Fund XIV-A1, L.P., & EnerVest Energy Institutional Fund XIV-WIC, L.P. - oil, gas & CBM

Gas 20.31 Ac. 34.55%

## 2. W. C. Owens

377.12 Acres

ACIN LLC - coal

Paramont Contura, LLC - coal lessee

WBRD LLC - coal

Dickenson-Russell Contura, LLC - coal lessee

EnerVest Energy Institutional Fund XIV-A, L.P., EnerVest Energy Institutional Fund XIV-A1, L.P., & EnerVest Energy Institutional Fund XIV-WIC, L.P. - oil, gas & CBM

Gas 26.55 Ac. 45.18%

## 3. W. C. Owens

115.81 Acres

ACIN LLC - coal

Paramont Contura, LLC - coal lessee

WBRD LLC - coal

Dickenson-Russell Contura, LLC - coal lessee

EnerVest Energy Institutional Fund XIV-A, L.P., EnerVest Energy Institutional Fund XIV-A1, L.P., & EnerVest Energy Institutional Fund XIV-WIC, L.P. - oil, gas & CBM

Gas 11.91 Ac. 20.27%

Coal seams			Well #	Haysi 37		
	Depth	Depth		Mining	in Area	
Names	Тор	Bottom	Thickness	Yes	No	Mined Out
Aily	901.60	903.20	1.60		No	No
Raven	981.90	984.10	2.20		No	No
Jawbone Rider	1090.90	1093.30	2.40		No	No
Jawbone	1134.60	1137.10	2.50		No	No
Jawbone	1144.80	1145.30	0.50		No	No
Tiller	1194.70	1195.20	0.50		No	No
Upper Seaboard A	1272.00	1272.10	0.10		No	No
Upper Seaboard	1303.00	1305.50	2.50		No	No
Greasy Creek	1448.30	1451.00	2.70		No	No
Middle Seaboard	1497.00	1497.10	0.10		No	No
Lower Seaboard	1510.50	1510.60	0.10		No	No
Unamed A	1551.50	1551.60	0.10		No	No
Unamed B	1569.50	1569.60	0.10		No	No
Upper Horsepen	1583.30	1584.10	0.80		No	No
Middle Horsepen	1646.30	1647.80	1.50		No	No
C Seam Rider	1667.50	1667.60	0.10		No	No
C Seam	1684.00	1684.10	0.10		No	No
War Creek	1723.70	1724.90	1.20		No	No
Unnamed C	1768.00	1768.10	0.10		No	No
Beckley	1812.40	1814.20	1.80		No	No
Lower Horsepen	1844.70	1845.20	0.50		No	No
Lower Horsepen	1853.60	1854.90	1.30		No	No
X Seam Rider	1881.50	1881.60	0.10		No	No
X Seam	1902.00	1902.10	0.10		No	No
Pocahontas #9	1914.50	1914.60	0.10		No	No
Pocahontas #8	1944.50	1944.60	0.10		No	No
Pocahontas #7	1969.50	1969.60	0.10		No	No
Pocahontas #6	2034.50	2034.60	0.10		No	No
Pocahontas #5	2045.80	2045.90	0.10		No	No
Pocahontas #4	2113.90	2115.70	1.80		No	No
Pocahontas #3	2193.00	2196.50	3.50		No	No
Pocahontas #3	2212.00	2212.50	0.50		No	No
Pocahontas #2	2252.90	2254.10	1.20		No	No
Pocahontas #1	2335.00	2335.10	0.10		No	No

Gas and Oil Shows

Haysi 37

FORMATION	DEPTH	THICKNESS	IPF (MCFD/BOPD)	PRESSURE	HOURS TESTED
	572		N/S		
	759		N/S		
	949		N/S		
	1138		N/S		
	1327		N/S		
	1517		N/S		
	1894		N/S		

Survey Results Haysi 37

Depth of Survey	Direction/Distance/Degree From True Vertical
194	1/4
383	1/4
572	1/2
759.00	1/4
949.00	1/2
1,138.00	1/2
1,327.00	1/2
1,517.00	1/2
1,707.00	1/2
1,894.00	3/4
2,082.00	1/2
2,270.00	1/4

1

Casing Program

Haysi-37	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs	Como	Cement Baskets (ft)		Centralizers	
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set	Cement Baskets (II)		L)	Centralizers	
Conductor	13 3/8	0-33'	16 1/4	Sanded in	No							
Water Protection	7	0-393'	8 7/8	132	Yes	06/04/17			131, 262		87, 131, 262, 350	
Coal Protection												
Intermediate	4 1/2	0-2342'	6 1/4	352	Yes	06/06/17			737'		737, 1008, 1264, 1521, 1779, 2038, 2294	
Tubing	23/8"	0-2272'										
Other Casing And			•									
Tubing Left In Well												
Liners												

Drillers Log		Haysi 37			
			Depth	Depth	
Geologic Age	Formation	General Lithology	Тор	Bottom	Thickness
Pennsylvanian	Lee	Sand/Shale/Coal	0.00	901.60	901.60
Pennsylvanian	Lee	Aily	901.60	903.20	1.60
Pennsylvanian	Lee	Sand/Shale	903.20	981.90	78.70
Pennsylvanian	Lee	Raven	981.90	984.10	2.20
Pennsylvanian	Lee	Sand/Shale	984.10	1090.90	106.80
Pennsylvanian	Lee	Jawbone Rider	1090.90	1093.30	2.40
Pennsylvanian	Lee	Sand/Shale	1093.30	1134.60	41.30
Pennsylvanian	Lee	Jawbone	1134.60	1137.10	2.50
Pennsylvanian	Lee	Sand/Shale	1137.10	1144.80	7.70
Pennsylvanian	Lee	Jawbone	1144.80	1145.30	0.50
Pennsylvanian	Lee	Sand/Shale	1145.30	1194.70	49.40
Pennsylvanian	Lee	Tiller	1194.70	1195.20	0.50
Pennsylvanian	Lee	Sand/Shale	1195.20	1272.00	76.80
Pennsylvanian	Lee	Upper Seaboard A	1272.00	1272.10	0.10
Pennsylvanian	Lee	Sand/Shale	1272.10	1303.00	30.90
Pennsylvanian	Lee	Upper Seaboard	1303.00	1305.50	2.50
Pennsylvanian	Lee	Sand/Shale	1305.50	1448.30	142.80
Pennsylvanian	Lee	Greasy Creek	1448.30	1451.00	2.70
Pennsylvanian	Lee	Sand/Shale	1451.00	1497.00	46.00
Pennsylvanian	Lee	Middle Seaboard	1497.00	1497.10	0.10
Pennsylvanian	Lee	Sand/Shale	1497.10	1510.50	13.40
Pennsylvanian	Lee	Lower Seaboard	1510.50	1510.60	0.10
Pennsylvanian	Lee	Sand/Shale	1510.60	1551.50	40.90
Pennsylvanian	Lee	Unamed A	1551.50	1551.60	0.10
Pennsylvanian	Lee	Sand/Shale	1551.60	1569.50	17.90
Pennsylvanian	Lee	Unamed B	1569.50	1569.60	0.10
Pennsylvanian	Lee	Sand/Shale	1569.60	1583.30	13.70
Pennsylvanian	Lee	Upper Horsepen	1583.30	1584.10	0.80
Pennsylvanian	Lee	Sand/Shale	1584.10	1646.30	62.20
Pennsylvanian	Lee	Middle Horsepen	1646.30	1647.80	1.50
Pennsylvanian	Lee	Sand/Shale	1647.80	1667.50	19.70
Pennsylvanian	Lee	C Seam Rider	1667.50	1667.60	0.10
Pennsylvanian	Lee	Sand/Shale	1667.60	1684.00	16.40
Pennsylvanian	Lee	C Seam	1684.00	1684.10	0.10
Pennsylvanian	Lee	Sand/Shale	1684.10	1723.70	39.60
Pennsylvanian	Lee	War Creek	1723.70	1724.90	1.20
Pennsylvanian	Lee	Sand/Shale	1724.90	1768.00	43.10
Pennsylvanian	Lee	Unnamed C	1768.00	1768.10	0.10
Pennsylvanian	Lee	Sand/Shale	1768.10	1812.40	44.30
Pennsylvanian	Lee	Beckley	1812.40	1814.20	1.80
Pennsylvanian	Lee	Sand/Shale	1814.20	1844.70	30.50
Pennsylvanian	Lee	Lower Horsepen	1844.70	1845.20	0.50
Pennsylvanian	Lee	Sand/Shale	1845.20	1853.60	8.40

Pennsylvanian	Lee	Lower Horsepen	1853.60	1854.90	1.30
Pennsylvanian	Lee	Sand/Shale	1854.90	1881.50	26.60
Pennsylvanian	Lee	X Seam Rider	1881.50	1881.60	0.10
Pennsylvanian	Lee	Sand/Shale	1881.60	1902.00	20.40
Pennsylvanian	Lee	X Seam	1902.00	1902.10	0.10
Pennsylvanian	Lee	Sand/Shale	1902.10	1914.50	12.40
Pennsylvanian	Lee	Pocahontas #9	1914.50	1914.60	0.10
Pennsylvanian	Lee	Sand/Shale	1914.60	1944.50	29.90
Pennsylvanian	Lee	Pocahontas #8	1944.50	1944.60	0.10
Pennsylvanian	Lee	Sand/Shale	1944.60	1969.50	24.90
Pennsylvanian	Lee	Pocahontas #7	1969.50	1969.60	0.10
Pennsylvanian	Lee	Sand/Shale	1969.60	2034.50	64.90
Pennsylvanian	Lee	Pocahontas #6	2034.50	2034.60	0.10
Pennsylvanian	Lee	Sand/Shale	2034.60	2045.80	11.20
Pennsylvanian	Lee	Pocahontas #5	2045.80	2045.90	0.10
Pennsylvanian	Lee	Sand/Shale	2045.90	2113.90	68.00
Pennsylvanian	Lee	Pocahontas #4	2113.90	2115.70	1.80
Pennsylvanian	Lee	Sand/Shale	2115.70	2193.00	77.30
Pennsylvanian	Lee	Pocahontas #3	2193.00	2196.50	3.50
Pennsylvanian	Lee	Sand/Shale	2196.50	2212.00	15.50
Pennsylvanian	Lee	Pocahontas #3	2212.00	2212.50	0.50
Pennsylvanian	Lee	Sand/Shale	2212.50	2252.90	40.40
Pennsylvanian	Lee	Pocahontas #2	2252.90	2254.10	1.20
Pennsylvanian	Lee	Sand/Shale	2254.10	2335.00	80.90
Pennsylvanian	Lee	Pocahontas #1	2335.00	2335.10	0.10
Pennsylvanian	Lee	Sand/Shale	2335.10	2377.00	41.90



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

Division of Gas and Oil

Tracking Number: 2311

**Company:** Range Resources-Pine Mountain

File Number: BU-3865

Completion Report Type: Original

## **COMPLETION REPORT (DGO-GO-15)**

Well Type: Coalbed/Pipeline Date Well Completed: 8/12/2008

**Driller's Total Depth:** 2350.00 **Log's Total Depth:** 2221.00

## 1. Changes In Casing/Tubing from Approved Drilling Report

Description	FileName

## 2. Stimulation Record

Stimulation Status: R Stimulated E GOB E Not Stimulated E Service Well

Description	FileName
Haysi #52 stimulation	Haysi 52 stimulation.rtf

### 3. Final Production

Description	FileName
Haysi 52 Final Production	Final_Prod.xls

#### 4. Comments

Form DGO-GO-15-E

Notes:							
NOIES.							
5. Signature							
Permittee:	Range R Mountair	esources-Pine า	Date:	3/15/20	12		(Company)
Ву:	Jonathar	n Horne	Title:	Engineering Tech			(Signature)
INTERNA	L USE	ONLY					
Subn	nit Date:	3/15/2012			_		
	Status:	Approved			Date:	3/28/2012	
Final PD	OF Date:	3/29/2012					

105010061 1 Haysi 52

Stage 1	
Stage Date	8/12/2008
Perf Date	8/12/2008
Logging Co.	Key
Formation	Poco 2, Poco 1
Top Perf	2118
Bottom Perf	2169
#Shots	20
Perf Size	0.49

Perf Comments

Service Co Fluid Type BD ISIP Avg Press Max Treat Pressure Final ISIP 2 Min SIP 5 Min SIP 10 Min SIP Sand Mesh:	Superior Gel + N2 foam (70Q) 2173 2917 2931 1621 1517	Avg DH Rate Max DH Rate Total Slurry Volume Total Fluid Volume Avg N2 Rate Max N2 Rate Total N2 Volume Max DH PPA Total Proppant Sks Total Acid Acid Type	30 32 123.7 112 19,500 167,600 159 250 15% HCL	BBLs BBLs scfm scf sks Gal
Sand Mesh: Frac Gradient:		Acid Type	15% HCL	

Stage 2	
Stage Date	8/12/2008
Perf Date	8/12/2008
Logging Co.	Key
Formation	Poco 3
Top Perf	2047.6
Bottom Perf	2048.8
#Shots	12
Perf Size	0.49
Perf Comments	

Service Co	Superior	Avg DH Rate	31	
Fluid Type	Gel + N2 Foam	Max DH Rate	35	
BD	2056	Total Slurry Volume	121	BBLs
ISIP		Total Fluid Volume	105	BBLs
Avg Press	1918	Avg N2 Rate	19,100	
Max Treat Pressure	2517	Max N2 Rate		scfm
Final ISIP	1917	Total N2 Volume	123,600	scf
2 Min SIP	1721	Max DH PPA		
5 Min SIP		Total Proppant Sks	116	sks
10 Min SIP		Total Acid	250	Gal
Sand Mesh:		Acid Type	15% hcl	
Frac Gradient:				

Stage 3	
Stage Date	8/12/2008
Perf Date	8/12/2008
Logging Co.	Key
Formation	Up.Horsepen,War
Top Perf	1398.5
Bottom Perf	1685.5
#Shots	32
Perf Size	0.34
Perf Comments	

Service Co	Superior	Avg DH Rate	25	
Fluid Type	Gel + N2 Foam	Max DH Rate	36	
BD	1513	Total Slurry Volume	173.0	BBLs
ISIP		Total Fluid Volume	151	BBLs
Avg Press	2131	Avg N2 Rate	21,000	
Max Treat Pressure	2217	Max N2 Rate		scfm
Final ISIP	1309	Total N2 Volume	254,200	scf
2 Min SIP	1207	Max DH PPA		
5 Min SIP	1108	Total Proppant Sks	191	sks
10 Min SIP		Total Acid		Gal
Sand Mesh:		Acid Type		
Frac Gradient:				

#### 3/15/2012 10:26:58 AM

BBLs

BBLs

scfm

scf

sks

Gal

30

33 151.4 138.2

18,170

208,600

15% HCL

242

250

Stage	4
-------	---

Stage Date Perf Date 8/12/2008 8/12/2008 Logging Co. Formation

Key Up. Seaboard, Greasy

Top Perf 1105.6 Bottom Perf 1254.5 #Shots 26 Perf Size 0.34 Perf Comments

Service Co	Superior	Avg DH Rate
Fluid Type	Gel + N2 Foam	Max DH Rate
BD	2825	Total Slurry Volume
ISIP		Total Fluid Volume
Avg Press	2491	Avg N2 Rate
Max Treat Pressure	3217	Max N2 Rate
Final ISIP	1712	Total N2 Volume
2 Min SIP	1610	Max DH PPA
5 Min SIP		Total Proppant Sks
10 Min SIP		Total Acid

Stage	5

Stage Date Perf Date 8/12/2008 8/12/2008 Logging Co. Formation Key Jawbone Rider,

Top Perf 888 Bottom Perf 992 #Shots 25 Perf Size 0.34 Perf Comments

Service Co	Superior	Avg DH Rate	22	
Fluid Type	Gel + N2 Foam	Max DH Rate	27	
BD	2378	Total Slurry Volume	160.5	BBLs
ISIP		Total Fluid Volume	147.2	BBLs
Avg Press	2725	Avg N2 Rate	19,500	
Max Treat Pressure	3170	Max N2 Rate		scfm
Final ISIP	1620	Total N2 Volume	236,500	scf
2 Min SIP	1147	Max DH PPA		
5 Min SIP	1012	Total Proppant Sks		sks
10 Min SIP		Total Acid		Gal
Sand Mesh:		Acid Type		
Frac Gradient:				

Acid Type

## Summary Total for All

Number of Stages	Total Slurry	Total Fluid Volume	Total N2 Volume	Total Proppant	Total Acid
5	729.6	653.4	990,500	708	750

Sand Mesh:

Frac Gradient:

Final Production After Stimulation				
	BOD	MCFD	<b>Hours Tested</b>	Rock Pressure
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		9	in-line	25



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

2359 **Tracking Number:** 

Range Resources-Pine Mountain Company:

File Number: BU-3865

**Operations Name:** Haysi #52 W/PL

Coalbed/Pipeline **Operation Type:** 

**Drilling Report Type:** Original

## **DRILLING REPORT (DGO-GO-14)**

## 1. Drilling Data

Date drilling commenced: 7/29/2008 Drilling Contractor: Noah Horn #17

Date drilling completed: 8/6/2008 Rig Type: Rotary Cable

Driller's Total Depth (feet): 2350.00

Log Total Depth (feet): Coal Seam at Total **POCAHONTAS** 2221.00

> Depth: #10

### 2. Final Location Plat (as required by 4 VAC25-150-360.C.)

Permitted State Plane X: Final Plat State Plane X: 10409493.0000 10409494.1500

Permitted State Plane Y: 3619371.8500 Final Plat State Plane Y: 3619372.0000

Plat Previously Submitted Or...

List of Attached Items:

Form DGO-GO-14-E

Page 1 of 3

Description	FileName		
Hasi 52 Final Plat	Haysi 52 Plat.pdf		

# 3. Geological Data

Fresh Water At:

Salt Water At:

Coal Seams:

List of Attached Items:

Description	FileName		
Haysi 52 Coal	Haysi 52 Coal.xls		

Gas and Oil Shows:

List of Attached Items:

Description	FileName		
Haysi #52 gas shows	Shows.xls		

# 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run: Res GR/Dens/Temp/Audio/PE/Caliper Data Pack, camera

Did logs disclose vertical locations of a coal seam?

R

# 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName		
Haysi #52 survey	Haysi 52 Survey.xls		

Form DGO-GO-14-E

Page 2 of 3

# 6. Casing and Tubing Program

List of Attached Items:

Description	FileName		
Haysi 52 casing	Casing.xls		

# 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

8. Drillers Log	g
-----------------	---

Compiled By: Range Resources

List of Attached Items:


Description	FileName		
Haysi 52 log	Haysi 52 Log.xls		

# 9. Comments

0. Signature						
Permitee:	Range	Resources-Pine Mountain	Date:	3/15/2012		
Signed By:	Jonath	an Horne	Title:	Engineering Tech		
INTERNAL USE ONLY						
Submi	t Date:	3/15/2012				
;	Status:	A		Date:	3/28/2012	
Final PDF	Date:	3/29/2012				

Form DGO-GO-14-E

Page 3 of 3



WELL LOCATION PLAT (Nora Grid AC-73)

COMPANY <u>Range Resources — Pine Mountain, Inc.</u> WELL NAME AND NUMBER <u>Haysi-52</u> TRACT NO. <u>Michael Phillips, et al.</u> ELEVATION <u>1.942.93'</u> QUADRANGLE <u>Prater</u>
COUNTY <u>Buchanan</u> DISTRICT <u>Prater</u> SCALE $1" = 400'$ DATE $7-30-2008$
This Plat is a new plat; an updated plat; or a final location platx
+ Denotes the location of a well on United States topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown.
24,000, latitude and longitude lines being represented by border lines as shown.
0 5 11 0

Licensed Professional Engineer or Licensed Land Surveyor

# HAYSI 52 PLAT TRACT OWNERSHIP INFORMATION SCHEDULE

3/12/2008

#### 1. Lease No.

Michael Phillips, et al - surface, coal, oil, gas & CBM 50.00 Acres
Gas 5.81 Ac. 9.89%

## 2. Lease No.

Ruby & Jim Perkins - gas
7.09 Acres
ACIN, LLC - coal
Alpha Land and Reserves, LLC - coal lessee
WBRD, LLC - coal
Dickenson-Russell Coal Company, LLC - coal lessee
Range Resources-Pine Mountain, Inc. - oil & CBM
Gas 3.88 Ac. 6.60%

# 3. Lease No.

Harmon Boyd, et ux - gas
21.34 Acres
ACIN, LLC - coal
Alpha Land and Reserves, LLC - coal lessee
WBRD, LLC - coal
Dickenson-Russell Coal Company, LLC - coal lessee
Range Resources-Pine Mountain, Inc. - oil & CBM
Gas 5.28 Ac. 8.98%

#### 4. Lease No.

Norman Boyd, et al. - gas
7.61 Acres
ACIN, LLC - coal
Alpha Land and Reserves, LLC - coal lessee
WBRD, LLC - coal
Dickenson-Russell Coal Company, LLC - coal lessee
Range Resources-Pine Mountain, Inc. - oil & CBM
Gas 2.79 Ac. 4.75%

#### 5. Lease No.

Norman Boyd, et al. - gas
0.54 Acres
ACIN, LLC - coal
Alpha Land and Reserves, LLC - coal lessee
WBRD, LLC - coal
Dickenson-Russell Coal Company, LLC - coal lessee
Range Resources-Pine Mountain, Inc. - oil & CBM
Gas 0.52 Ac. 0.88%

Norman Boyd - gas

12.5 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 11.92 Ac. 20.29%

## 7. Lease No.

Norman Boyd - gas

12.5 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 0.71 Ac. 1.21%

# 8. Lease No.

Bobby & Sheridan Compton - gas

12 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 1.06 Ac. 1.80%

# 9. Lease No.

Terry O'Quinn - gas

0.11 Acre

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 0.34 Ac. 0.58%

Woody Dales - gas

3 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 0.86 Ac. 1.46%

#### 11. Lease No.

Coleman United Methodist Church - gas

1 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 0.59 Ac. 1.00%

# 12. Lease No.

Jeffrey Dean Fuller - gas

0.75 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 0.64 Ac. 1.09%

## 13. Lease No.

Mark Deel - gas

3 & 5.5 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 2.86 Ac. 4.87%

James Vance Deel - gas

1.0 & 0.47 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 1.95 Ac. 3.32%

## 15. Lease No.

Johnny Michael Chambers - gas

6 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 0.30 Ac. 0.51%

# 16. Lease No.

Mark Deel - gas

6 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 1.64 Ac. 2.79%

## 17. Lease No.

Flornia Charles - gas

8 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 7.01 Ac. 11.93%

## 18. Lease No.

Jason Fuller - gas

7 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 4.98 Ac. 8.47%

Johnny Michael Chambers - gas

6 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 5.40 Ac. 9.19%

# 20. Lease No.

Sandra & Wayne Charles - gas

4.8 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 0.21 Ac. 0.36%

## 21. Lease No.

Charlie Powell Chambers - gas

32 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 0.02 Ac. 0.03%

# Coal Seams

			MINING IN AREA		
NAME	TOP	BOTTOM	THICKNESS	YES N	O MINED OUT
Aily Rider	674	675	1	N	O NO
Aily	708	710	2	N	O NO
Raven	789	790	1	N	O NO
Raven	803	804	1	N	O NO
Jawbone Rider	889	892	3	N	O NO
Jawbone	924	925	1	N	O NO
Tiller	990	991	1	N	O NO
Upper Seaboard	1107	1109	2	N	O NO
Greasy Creek	1253	1257	4	N	O NO
Upper Horsepen	1399	1400	1	N	O NO
War Creek	1535	1536	1	N	O NO
Beckley	1631	1633	2	N	O NO
Lower Horsepen	1692	1694	2	N	O NO
Poco 4	1997	1998	1	N	O NO
Poco 3	2048	2049	1	N	O NO
Poco 2	2118	2119	1	N	O NO
Poco 1	2165	2168	3	N	O NO

# Gas and Oil Shows

FORMATION	TOP	BOTTOM	THICKNESS	IPF (	(MCFD/BOPD)	PRESSURE	HOURS TESTED
TD w/csg		2350		103	MCFD		

**Survey Results** 

2011.05 1100	
Depth of Survey	Direction/Distance/Degree From True Vertical
200	1/4°
400	1/4°
600	1/2°
800	1/4°
1000	1/4°
1200	1/2°
1400	1/2°
1600	1/2°
1800	3/4°
2000	3/4°
2200	1°

# **Casing Program**

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs	Cement Baskets
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set	(ft)
Conductor	11¾"	0-39'	15"					
Water Protection	85/8"	0-540'	11"	302.5	Yes	08/01/08		
Production Casing	41/2"	0-2301'	6½"	536.8	No	08/07/08		294' 1344'
Squeeze Job				196.02	Yes	08/28/08	Bridge plug @ 470'	
Other Casing And								
Tubing Left In Well	23/8"	0-2199'						
Liners								

Driller's Log

		General		Depth	Depth		
Geologic Age	Formation	Lithology	Color	Тор	Bottom	Thickness	Remarks
Penn	Lee	Sand and shale		0	674	674	
Penn	Lee	Coal		674	675	1	Aily Rider
Penn	Lee	Sand and shale		675	708	33	
Penn	Lee	Coal		708	710	2	Aily
Penn	Lee	Sand and shale		710	789	79	
Penn	Lee	Coal		789	790	1	Raven
Penn	Lee	Sand and shale		790	803	13	
Penn	Lee	Coal		803	804	1	Raven
Penn	Lee	Sand and shale		804	889	85	
Penn	Lee	Coal		889	892	3	Jawbone Rider
Penn	Lee	Sand and shale		892	924	32	
Penn	Lee	Coal		924	925	1	Jawbone
Penn	Lee	Sand and shale		925	990	65	
Penn	Lee	Coal		990	991	1	Tiller
Penn	Lee	Sand and shale		991	1107	116	
Penn	Lee	Coal		1107	1109	2	Upper Seaboard
Penn	Lee	Sand and shale		1109	1253	144	
Penn	Lee	Coal		1253	1257	4	Greasy Creek
Penn	Lee	Sand and shale		1257	1399	142	
Penn	Lee	Coal		1399	1400	1	Upper Horsepen
Penn	Lee	Sand and shale		1400	1535	135	
Penn	Lee	Coal		1535	1536	1	War Creek
Penn	Lee	Sand and shale		1536	1631	95	
Penn	Lee	Coal		1631	1633	2	Beckley
Penn	Lee	Sand and shale		1633	1692	59	
Penn	Lee	Coal		1692	1694	2	Lower Horsepen
Penn	Lee	Sand and shale		1694	1997	303	
Penn	Lee	Coal		1997	1998	1	Poco 4
Penn	Lee	Sand and shale		1998	2048	50	
Penn	Lee	Coal		2048	2049	1	Poco 3
Penn	Lee	Sand and shale		2049	2118	69	
Penn	Lee	Coal		2118	2119	1	Poco 2
Penn	Lee	Sand and shale		2119	2165	46	
	Lee	Coal		2165	2168	3	Poco 1
	Lee	Sand and shale		2168	2350	182	



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

Tracking Number: 1873

**Company:** Range Resources-Pine Mountain

File Number: BU-3894

Completion Report Type: Original

# **COMPLETION REPORT (DGO-GO-15)**

Well Type: Coalbed/Pipeline Date Well Completed: 8/6/2008

**Driller's Total Depth:** 2465.00 **Log's Total Depth:** 2465.00

# 1. Changes In Casing/Tubing from Approved Drilling Report

Description	FileName

# 2. Stimulation Record

Stimulation Status: RStimulated & GOB & Not Stimulated & Service Well

Description	FileName
Haysi #53 Stimulation	Haysi #53 Stimulation.doc

# 3. Final Production

Description	FileName
Haysi #53 Production	Final_Prod.xls

# 4. Comments

Form DGO-GO-15-E

Notes:							
5. Signature							
Permittee:	Range R Mountain	esources-Pine	Date:	8/6/200	9		(Company)
Ву:	Laura Mu	ırray	Title:	Permit 9	Specialist		(Signature)
INTERNA	AL USE	ONLY					
					·		
Subr	mit Date:	8/6/2009			_		
Subr	mit Date: Status:	8/6/2009			Date:	8/13/2009	

# **STIMULATION RECORD**

ZONE 1: Poco 2/ Poco 1	Formation Stimulated With:	70QGel+N <sub>2</sub> Fm
Perforated 2143 to 2298 feet No. of F	Perforations 18 Perforation	n Size54
Formation Broke down at: 1454 PSIG	Average Injection Rate: 23.1	BPM
ISIP 1791 PSIG 2 Min SIP 1757 PSIG Avera	age Downhole Injection Pressure	2610 PSIG
Stimulated: No Date Stimulated:	8/6/2008	
ZONE 2: P4 / P3	Formation Stimulated With:	70QGel+N <sub>2</sub> Fm
		n Size <u>.33</u>
Formation Broke down at: 1910 PSIG	Average Injection Rate: 18	BPM
ISIP <u>2818</u> PSIG 2 Min SIP <u>2112</u> PSIG Avera	age Downhole Injection Pressure	2819 PSIG
Stimulated: Yes	8/6/2008	
ZONE 3: U. Horsepen, War Creek, Beckley, L. Horsepen	Formation Stimulated With:	70QGel+N <sub>2</sub> Fm
		n Size .33
Formation Broke down at: 3510 PSIG	Average Injection Rate: 22	BPM
ISIP 2871 PSIG 5 Min SIP 2571 PSIG Avera		3610 PSIG
Stimulated: Xes No Date Stimulated:	8/6/2008	1210
ZONE 4: U. Seaboard, Greasy Creek	Formation Stimulated With:	70QGel+N <sub>2</sub> Fm
	Perforations 20 Perforation	
Formation Broke down at: 2219 PSIG	Average Injection Rate: 21.5	
	age Downhole Injection Pressure	3180 PSIG
Stimulated: Xes No Date Stimulated:	8/6/2008	
	•	
ZONE 5: Jawbone Rider, Jawbone, Tiller	Formation Stimulated With:	70QGel+N <sub>2</sub> Fm
	Perforations 25 Perforation	
Formation Broke down at: 2451 PSIG	Average Injection Rate: 22	BPM
ISIP <u>1921</u> PSIG 5 Min SIP <u>1718</u> PSIG Avera	age Downhole Injection Pressure	2605 PSIG
Stimulated: Yes	8/6/2008	

Final Production After Stimula				
	BOD	MCFD	<b>Hours Tested</b>	<b>Rock Pressure</b>
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		113	in-line	49



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

**Tracking Number:** 1446

Range Resources-Pine Mountain Company:

File Number: BU-3894

**Operations Name:** Haysi #53 W/PL

Coalbed/Pipeline **Operation Type:** 

**Drilling Report Type:** Original

# **DRILLING REPORT (DGO-GO-14)**

# 1. Drilling Data

Date drilling commenced: 7/18/2008 Drilling Contractor: Noah Horn #17

Date drilling completed: 7/28/2008 Rig Type: Rotary Cable

Driller's Total Depth (feet): 2465.00

Log Total Depth (feet): Coal Seam at Total **POCAHONTAS** 2465.00

> Depth: #1

# 2. Final Location Plat (as required by 4 VAC25-150-360.C.)

Permitted State Plane X: 10409586.1600 Final Plat State Plane X: 10409587.0000

Permitted State Plane Y: 3618105.8000 Final Plat State Plane Y: 3618107.0000

Plat Previously Submitted Or...

List of Attached Items:

Form DGO-GO-14-E

Page 1 of 4

Description	FileName
Haysi #53 Final Plat	Haysi 53 Plat CBM.pdf

# 3. Geological Data

Fresh Water At:

Depth (in feet)	Rate	Unit of Measure
900	Damp	

Salt Water At:

Depth (in feet) Rate Unit of Measure
--------------------------------------

Coal Seams:

List of Attached Items:

Description	FileName		
Haysi #53 Coal	Haysi 53 Coal.xls		

Gas and Oil Shows:

List of Attached Items:

Description	FileName		
Haysi #53 shows	Haysi 53 Shows.xls		

# 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run: Hi Res GR/Dens/Temp/Audio/PE/Caliper Data Pack

Did logs disclose vertical locations of a coal seam?

R

# 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName			
Haysi #53 Survey	Haysi 53 deviation survey.tif			

Form DGO-GO-14-E

Page 2 of 4

# 6. Casing and Tubing Program

List of Attached Items:

Description	FileName		
Haysi #53 Casing	Casing.xls		

# 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

Cement Baskets(MD-ft): 406, 454, 1756

8. Dril	lers	Lo	g
---------	------	----	---

Compiled By: Range Resources


List of Attached Items:

Description	FileName		
Haysi #53 Log	Haysi 53 Log.xls		

## 9. Comments

10. Signature			
Permitee:	Range Resources-Pine Mountain	Date:	8/6/2009
Signed By:	Laura Murray	Title:	Permit Specialist

INTERNAL USE ONLY						
Submit Date:	8/6/2009					
Status:	<u>A</u>	Date:	8/13/2009			
Final PDF Date:	9/2/2009					



WELL LOCATION PLAT (Nora Grid 73-AD)

COMPANY Range Resources - Pine Mountain, Inc. WELL NAME AND NUMBER Haysi-53
TRACT NO. Michael Phillips, et al ELEVATION 2.068.12' QUADRANGLE Prater
COUNTY <u>Buchanan</u> DISTRICT <u>Prater</u> SCALE $1'' = 400'$ DATE $7-21-2008$
This Plat is a new plat; an updated plat; or a final location platx
Denotes the location of a well on United States topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown.
24,000, latitude and longitude lines being represented by border lines as shown.
0

Licensed Professional Engineer or Licensed Land Surveyor

# HAYSI 53 PLAT TRACT OWNERSHIP INFORMATION SCHEDULE

3/12/2008

1. Lease No.

Michael Phillips, et al - surface, coal, oil, gas & CBM 92.00 Acres
Gas 15.01 Ac. 25.54%

2. Lease No.

Michael Phillips, et al - surface, coal, oil, gas & CBM 50.00 Acres
Gas 22.04 Ac. 37.50%

3. Lease No.

Johnny Michael Chambers - gas

6 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 1.81 Ac. 3.08%

4. Lease No.

Sandra & Wayne Charles - gas

4.8 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 2.99 Ac. 5.09%

5. Lease No.

Roger Gene & Rita Kathy Deel - gas

2 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 2.55 Ac. 4.34%

Toby Deel - gas

2 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 2.44 Ac. 4.15%

# 7. Lease No.

Kelsie Stiltner - gas

5 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 7.12 Ac. 12.12%

## 8. Lease No.

Kelsie Stiltner, et al - gas

19 Acres

ACIN, LLC - coal

Alpha Land and Reserves, LLC - coal lessee

WBRD, LLC - coal

Dickenson-Russell Coal Company, LLC - coal lessee

Range Resources-Pine Mountain, Inc. - oil & CBM

Gas 4.81 Ac. 8.18%

# Coal Seams

				MINING IN AREA		
NAME	TOP	BOTTOM	THICKNESS	YES NO	MINED OUT	
Aily Rider	788	789	1	NO		
Aily	820	822	2	NO		
Raven	905	907	2	NO		
Jawbone Rider	1008	1011	3	NO		
Jawbone	1038	1039	1	NO		
Tiller	1105	1106	1	NO		
Upper Seaboard	1219	1221	2	NO		
Greasy Creek	1364	1366	2	NO		
Upper Horsepen	1515	1516	1	NO		
War Creek	1652	1653	1	NO		
Beckley	1747	1748	1	NO		
Lower Horsepen	1805	1807	2	NO		
Poco 4	2123	2126	3	NO		
Poco 3	2165	2168	3	NO		
Poco 2	2243	2244	1	NO		
Poco 1	2295	2298	3	NO		

# Gas and Oil Shows

FORMATION	TOP	BOTTOM	THICKNESS	IPF	(MCFD/BOPD)	PRESSURE	HOURS TESTED
Case hole TD				No s	show		

CALL PRINCIPAL P		CLIENT: PIN CLIENT: PIN HOLE ID: NE OF LOG PROBE: 9136
702 - 704 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	e countri-too	COI E MOUNTAIN O: RATER RSI SSI SSI SSI SSI O7/27/08 AA 955
11-39 91364, 100 878 978 978 978 978 978 978 978 978 978	an Troisean.	PL MPU-L,
PRODUCT OF IT PR	VILLE TO SEE SEE SEE SEE SEE SEE SEE SEE SEE SE	OG D
20 : 01762 227 : 48 ptg/2 227 : 48 ptg/2 0 : 50 ptg/2 0 :	100.00	IEW EVI,
7,000 9 1.1.0q 1		TIO
		z
BANGB 1190 1190 1190 1190 1190 1190 1190 119		SCAL TRUE AZIN DIST
	_ <b>[1</b> ]	E: 2: DEP DITH: DITH: BOTTO
	·	5 FT/ FH: 2 134. 134. 134. 134. 143.
		IN 326.4 9 7 FT CR HOLE
		ä

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set
Conductor	13%"	0-19'	15"				
Water Protection	85/8"	0-574'	12%"	363	Yes, circ 13bbls	7/21/2008	
Production Casing	41/2"	0-2428'	6½"	563.5	Yes, circ 5bbls	7/28/2008	
Other Casing And							
Tubing Left In Well	23/8"	0-2348'					
Liners							

Driller's Log

Ü		General		Depth	Depth		
Geologic Age	Formation	Lithology	Color	Тор	Bottom	Thickness	Remarks
Penn	Lee	Sandy Shale		0	788	788	
Penn	Lee	Coal		788	789	1	Aily Rider
Penn	Lee	Sandy Shale		789	820	31	
Penn	Lee	Coal		820	822	2	Aily
Penn	Lee	Sandy Shale		822	905	83	
Penn	Lee	Coal		905	907	2	Raven
Penn	Lee	Sandy Shale		907	1008	101	
Penn	Lee	Coal		1008	1011	3	Jawbone Rider
Penn	Lee	Sandy Shale		1011	1038	27	
Penn	Lee	Coal		1038	1039	1	Jawbone
Penn	Lee	Sandy Shale		1039	1105	66	
Penn	Lee	Coal		1105	1106	1	Tiller
Penn	Lee	Sandy Shale		1106	1219	113	
Penn	Lee	Coal		1219	1221	2	Upper Seaboard
Penn	Lee	Sandy Shale		1221	1364	143	
Penn	Lee	Coal		1364	1366	2	Greasy Creek
Penn	Lee	Sandy Shale		1366	1515	149	
Penn	Lee	Coal		1515	1516	1	Upper Horsepen
Penn	Lee	Sandy Shale		1516	1652	136	
Penn	Lee	Coal		1652	1653	1	War Creek
Penn	Lee	Sandy Shale		1653	1747	94	
Penn	Lee	Coal		1747	1748	1	Beckley
Penn	Lee	Sandy Shale		1748	1805	57	
Penn	Lee	Coal		1805	1807	2	Lower Horsepen
Penn	Lee	Sandy Shale		1807	2123	316	
Penn	Lee	Coal		2123	2126	3	Poco 4
Penn	Lee	Sandy Shale		2126	2165	39	
Penn	Lee	Coal		2165	2168	3	Poco 3
Penn	Lee	Sandy Shale		2168	2243	75	
Penn	Lee	Coal		2243	2244	1	Poco 2
Penn	Lee	Sandy Shale		2244	2295	51	
Penn	Lee	Coal		2295	2298	3	Poco 1
Penn	Lee	Sandy Shale		2298	2328	30	



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

Tracking Number: 3240

**Company:** Range Resources-Pine Mountain

File Number: DI-1791

Completion Report Type: Original

# **COMPLETION REPORT (DGO-GO-15)**

Well Type: Coalbed/Pipeline Date Well Completed: 9/25/2007

**Driller's Total Depth:** 2109.00 **Log's Total Depth:** 2094.00

# 1. Changes In Casing/Tubing from Approved Drilling Report

Description	FileName

## 2. Stimulation Record

Stimulation Status: RStimulated & GOB & Not Stimulated & Service Well

Description	FileName
Haysi #54 stimulation	Haysi 54 stimulation.rtf

## 3. Final Production

Description	FileName
Haysi #54 final production	Haysi 54 Final Prod.xls

# 4. Comments

Form DGO-GO-15-E

Notes:							
NOIES.							
5. Signature							
Permittee:	Range R Mountair	esources-Pine า	Date:	3/15/20	12		(Company)
Ву:	Jonathan Horne		Title:	Engineering Tech			(Signature)
INTERNA	L USE	ONLY					
Subn	nit Date:	3/15/2012			_		
	Status:	Approved			Date:	3/28/2012	
Final PD	OF Date:	3/29/2012					

105010076 1	Haysi 54					
Stage 1 Stage Date Perf Date Logging Co. Formation Top Perf Bottom Perf #Shots Perf Size Perf Comments	9/25/2007 9/25/2007 Poco 4 Rider, Poco 4, 1787.9 1901.1 12 0.33	Service Co Fluid Type BD ISIP Avg Press Max Treat Pressure Final ISIP 2 Min SIP 5 Min SIP 10 Min SIP Sand Mesh: Frac Gradient:	Foam 0 0 0	Avg DH Rate Max DH Rate Total Slurry Volume Total Fluid Volume Avg N2 Rate Max N2 Rate Total N2 Volume Max DH PPA Total Proppant Sks Total Acid Acid Type	0 0 0 0 0	BBLs BBLs scfm scf sks Gal
Stage 2 Stage Date Perf Date Logging Co. Formation Top Perf Bottom Perf #Shots Perf Size Perf Comments	9/25/2007 9/25/2007 Up Horsepen, M 1241 1751 29 0.33	Service Co Fluid Type BD ISIP Avg Press Max Treat Pressure Final ISIP 2 Min SIP 5 Min SIP 10 Min SIP Sand Mesh: Frac Gradient:	0 0 0	Avg DH Rate Max DH Rate Total Slurry Volume Total Fluid Volume Avg N2 Rate Max N2 Rate Total N2 Volume Max DH PPA Total Proppant Sks Total Acid Acid Type	0 0 0 0 0	BBLs BBLs scfm scf sks Gal
Stage 3 Stage Date Perf Date Logging Co. Formation Top Perf Bottom Perf #Shots Perf Size Perf Comments	9/25/2007 9/25/2007 Tiller, Up Seaboard 817.5 1081 32 0.33	Service Co Fluid Type BD ISIP Avg Press Max Treat Pressure Final ISIP 2 Min SIP 5 Min SIP 10 Min SIP Sand Mesh: Frac Gradient:	0 0 0	Avg DH Rate Max DH Rate Total Slurry Volume Total Fluid Volume Avg N2 Rate Max N2 Rate Total N2 Volume Max DH PPA Total Proppant Sks Total Acid Acid Type	0 0 0 0 0	BBLs BBLs scfm scf sks Gal

Page 2 of 2

3/15/2012 10:45:14 AM

Stage 4		Service Co		Avg DH Rate	0	
Stage Date	9/25/2007	Fluid Type		Max DH Rate	0	
Perf Date	9/25/2007	BD	0	Total Slurry Volume	0	BBLs
Logging Co.		ISIP		Total Fluid Volume	0	BBLs
Formation		Avg Press	0	Avg N2 Rate	0	
Top Perf	609.5	Max Treat Pressure	0	Max N2 Rate		scfm
Bottom Perf	741	Final ISIP		Total N2 Volume		scf
#Shots	28	2 Min SIP		Max DH PPA	0	
Perf Size	0.33	5 Min SIP		Total Proppant Sks	0	sks
Perf Comments	3	10 Min SIP		Total Acid	0	Gal
		Sand Mesh:		Acid Type		
		Frac Gradient:				

Summary Total for All

Number of Stages	Total Slurry	Total Fluid Volume	Total N2 Volume	Total Proppant	Total Acid
4	0	0		0	0

Final Production After Stimula				
	BOD	MCFD	<b>Hours Tested</b>	<b>Rock Pressure</b>
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		28	In Line	22



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Box 1416, Abingdon, VA 24212

Telephone: (276) 676-5423

Tracking Number:	1188
Company:	Range Resources-Pine Mountain
File Number:	DI-1791
Operations Name:	Haysi #54 W/PL
Operation Type:	Coalbed/Pipeline
Drilling Report Type:	Original

# **DRILLING REPORT (DGO-GO-14)**

1. Drilling Data				
Date drilling commenced:	9/10/2007	Drilling Contractor: Noah Horn		
Date drilling completed:	9/13/2007	Rig Type: ☑ Rotary ☐ Cable		
Driller's Total Depth (feet):	2109.00	_		
Log Total Depth (feet):	2094.00	Coal Seam at To		
2. Final Location Plat (as required by 4 VAC25-150-360.C.)				
Permitted State Plane X: 914644.00		Final Plat State Plane X:	914636.00	
Permitted State Plane Y: 333	3072.00	Final Plat State Plane Y:	333075.00	
Plat Previously Submitted Or				
List of Attached Items:				

Form DGO-GO-14-E

Page 1 of 4

Rev. 1/2007

•			
Haysi 54 Final Plat	Haysi 54 Plat.pdf		
3. Geological Data			
Fresh Water At:			
Depth (in feet)	Rate	Unit of Measure	
60	Wet		
Salt Water At:			
Depth (in feet)	Rate	Unit of Measure	
1080	Wet		
Coal Seams:			
List of Attached Items:			
Description	FileName		
Haysi 54 Coals	Haysi 54 Coal.xls		
Gas and Oil Shows:			
List of Attached Items:			
Description	FileName		
Haysi 54 Shows	Haysi 54 Shows.xls		
4. Electric Logs (As required by 4VAC25-150-2	280.A)		
List all logs run: Hi Res GR/Dens/Temp/Au	io/Pe/Caliper (Data Pack)		
Did logs disclose vertical locations of a coal seam?			
5. Survery Results (As required by 4VAC25-15	50-280.B.2)		
List of Attached Items:			

**FileName** 

Description

Form DGO-GO-14-E

Page 2 of 4

Rev. 1/2007

Description	FileName
Haysi 54 Surveys	Haysi 54 Survey.xls

# 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
Haysi 54 Casing	Haysi 54 Casing.xls

## 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

Circ 3 bbl to surf on 11" hole; Circ 9 bbls to surf on 6.5" hole.

8. Drillers Log	8.	Dril	lers	Log
-----------------	----	------	------	-----

Compiled By: Joshua Phillips, GEO Tech

List of Attached Items:

Description	FileName
Haysi 54 Log	Haysi 54 Log.xls


#### 9. Comments

10. Si	ignat	ture
--------	-------	------

Permitee: Range Resources-Pine Mountain Date: 3/3/2008

Signed By: Christian D. Moore Title: Permit/GIS Specialist

INTERNAL USE ONLY						
Submit Date:	3/3/2008					
Status:	A	Date:	3/6/2008			
Final PDF Date:	3/10/2008					



WELL LOCATION PLAT

COMPANY <u>Pine Mountain Oil &amp; Gas, Inc.</u> WELL NAME AND NUMBER TRACT NO. <u>Larkin Viers T-441</u> ELEVATION <u>1,606.73'</u> QUADRANGLE <u>Prate</u> COUNTY <u>Dickenson</u> DISTRICT <u>Sandlick</u> SCALE <u>1" = 400'</u>	27
This Plat is a new plat; an updated plat; or a final location platx  + Denotes the location of a well on United States topographic Maps, scale 24,000, latitude and longitude lines being represented by border lines as	1 to
Licensed Professional Engineer or Licensed Land Surveyor	

# Coal Seams

					MINING IN AREA
NAME	TOP	BOTTOM	THICKNESS	YES N	IO MINED OUT
Aily	512	513	1	N	10
Raven	591	592	1	N	10
Raven	610	611	1	N	10
Raven	625	626	1	N	10
Jawbone Rider	706	709	3	N	10
Jawbone	739	740	1	N	10
Tiller	818	819	1	N	10
Upper Seaboard	942	946	4	N	10
Greasy Creek	1078	1081	3	N	10
Upper Horsepen	1241	1244	3	N	10
Middle Horsepen	1281	1282	1	N	10
Beckley	1403	1404	1	N	10
Poco 5	1748	1751	3	N	10
Poco 4 Rider	1788	1789	1	N	10
Poco 4	1804	1805	1	N	10
Poco 3	1827	1828	1	N	10
Poco 2	1900	1901	1	N	10

Gas and Oil Shows

FORMATION TOP BOTTOM THICKNESS IPF (MCFD/BOPD) PRESSURE HOURS TESTED

Open Hole TD

NS

Survey Results

Depth of Survey	Direction/Distance/Degree From True Vertical
200	3/4°
400	3/4°
600	11⁄4°
800	11⁄4°
1000	1¼°
1200	11/4°
1400	1°
1600	1°
1800	1°
2000	1°

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set
Conductor	11¾"	0-15'	15"				
Surface	85/8"	0-332'	11"	115 sx	Yes	9/10/2007	
Water Protection	41/2"	0-2061'	6½"	195 sx	Yes	9/13/2007	
Tubing	23/8"	0-1953'					

Driller's Log

Driller's Log		General		Depth	Depth		
Geologic Age	Formation	Lithology	Color	Тор	Bottom	Thickness	Remarks
Penn	Lee	Sand, shale, thin coals		0	929	929	
Penn	Lee	Coal		929	931	2	Aily
Penn	Lee	Sand, shale, thin coals		931	1015	84	,
Penn	Lee	Coal		1015	1017	2	Raven
Penn	Lee	Sand, shale, thin coals		1017	1118	101	
Penn	Lee	Coal		1118	1121	3	Jawbone Rider
Penn	Lee	Sand, shale, thin coals		1121	1149	28	
Penn	Lee	Coal		1149	1153	4	Jawbone
Penn	Lee	Sand, shale, thin coals		1153	1213	60	
Penn	Lee	Coal		1213	1215	2	Tiller
Penn	Lee	Sand, shale, thin coals		1215	1313	98	
Penn	Lee	Coal		1313	1314	1	Upper Seaboard
Penn	Lee	Sand, shale, thin coals		1314	1333	19	
Penn	Lee	Coal		1333	1334	1	Upper Seaboard A
Penn	Lee	Sand, shale, thin coals		1334	1486	152	
Penn	Lee	Coal		1486	1490	4	Greasy Creek
Penn	Lee	Sand, shale, thin coals		1490	1635	145	
Penn	Lee	Coal		1635	1638	3	Upper Horsepen
Penn	Lee	Sand, shale, thin coals		1638	1691	53	
Penn	Lee	Coal		1691	1693	2	Middle Horsepen
Penn	Lee	Sand, shale, thin coals		1693	1853	160	
Penn	Lee	Coal		1853	1855	2	Beckley
Penn	Lee	Sand, shale, thin coals		1855	1903	48	
Penn	Lee	Coal		1903	1904	1	Lower Horsepen
Penn	Lee	Sand, shale, thin coals		1904	2233	329	
Penn	Lee	Coal		2233	2236		Poco 4
Penn	Lee	Sand, shale, thin coals		2236	2266	30	
Penn	Lee	Coal		2266	2268	2	Poco 3
Penn	Lee	Sand, shale, thin coals		2268	2279	11	
Penn	Lee	Coal		2279	2280	1	Poco 3
Penn	Lee	Sand, shale, thin coals		2280	2287	7	
Penn	Lee	Coal		2287	2288	1	Poco 3
Penn	Lee	Sand, shale, thin coals		2288	2350	62	
Penn	Lee	Coal		2350	2351		Poco 2
Penn	Lee	Sand, shale, thin coals		2351	2398	47	
Penn	Lee	Coal		2398	2401		Poco 1
Penn	Lee	Sand, shale, thin coals		2401	2438	37	



Commonwealth of Virginia
Department of Mines, Minerals, and Energy
Division of Gas and Oil
P.O. Box 1416, Abingdon, VA 24212

Telephone: (276) 676-5423

File Number: DI-1797 Completion Report Type: Original  COMPLETION REPORT (DGO-GO-15)  Well Type: Coalbed/Pipeline Date Well Completed: 10/2/2007 Driller's Total Depth: 2334.00 Log's Total Depth: 2273.00  Changes In Casing/Tubing from Approved Drilling Report  Description FileName Haysi 58 Casing Haysi 58 Comp Casing.xls  Stimulation Record  Stimulation Status: Stimulated GOB Not Stimulated Service Well  Description FileName Haysi 58 Stimulation Haysi 58 Stimulation.doc  Final Production  Description FileName Haysi 58 Final Production Haysi 58 Final Prod.xls	Telephone. (270) 070-3423						
File Number:		1261					
COMPLETION REPORT (DGO-GO-15)  Well Type: Coalbed/Pipeline Date Well Completed: 10/2/2007  Driller's Total Depth: 2334.00 Log's Total Depth: 2273.00  Changes In Casing/Tubing from Approved Drilling Report  Description FileName Haysi 58 Casing Haysi 58 Comp Casing.xls  Stimulation Record  Stimulation Status: Stimulated GOB Not Stimulated Service Well  Description FileName Haysi 58 Stimulation Haysi 58 Stimulation.doc  Final Production  Description FileName Haysi 58 Final Production Haysi 58 Final Prod.xls		Company:		Range Resources-Pine Mountain			
COMPLETION REPORT (DGO-GO-15)  Well Type: Coalbed/Pipeline Date Well Completed: 10/2/2007  Driller's Total Depth: 2334.00 Log's Total Depth: 2273.00  Changes In Casing/Tubing from Approved Drilling Report  Description FileName Haysi 58 Casing Haysi 58 Comp Casing.xls  Stimulation Record  Stimulation Status: Stimulated GOB Not Stimulated Service Well  Description FileName Haysi 58 Stimulation Haysi 58 Stimulation.doc  Final Production  Pescription FileName Haysi 58 Final Production Haysi 58 Final Prod.xls		File Numbe	er:	DI-1797			
Well Type:       Coalbed/Pipeline       Date Well Completed:       10/2/2007         Driller's Total Depth:       2334.00       Log's Total Depth:       2273.00         Changes In Casing/Tubing from Approved Drilling Report         Pescription       FileName         Haysi 58 Casing       Haysi 58 Comp Casing.xls         Stimulation Record         Stimulation Status:       Stimulated       GOB       Not Stimulated       Service Well         Description       FileName         Haysi 58 Stimulation.doc         Final Production         Description       FileName		Completion	n Report Type:	Original			
Driller's Total Depth:       2334.00       Log's Total Depth:       2273.00         Changes In Casing/Tubing from Approved Drilling Report         Description       FileName         Haysi 58 Casing       Haysi 58 Comp Casing.xls         Stimulation Record         Stimulation Status:       ✓ Stimulated       ☐GOB       ☐Not Stimulated       ☐Service Well         Description       FileName         Haysi 58 Stimulation.doc         Final Production         Haysi 58 Final Production       Haysi 58 Final Prod.xls		COMPLETION RE	EPORT (DGO-	-GO-15)			
Changes In Casing/Tubing from Approved Drilling Report  Description FileName Haysi 58 Casing Haysi 58 Comp Casing.xls  Stimulation Record  Stimulation Status: Stimulated GOB Not Stimulated Service Well  Description FileName Haysi 58 Stimulation Haysi 58 Stimulation.doc  Final Production  Description FileName Haysi 58 Final Production Haysi 58 Final Prod.xls	Well Type:	Coalbed/Pipeline	Date Well C	Completed: 10/2/2007			
Description     FileName       Haysi 58 Casing     Haysi 58 Comp Casing.xls       Stimulation Record       Stimulation Status: ✓ Stimulated ☐ GOB ☐ Not Stimulated ☐ Service Well       Description     FileName       Haysi 58 Stimulation     Haysi 58 Stimulation.doc       Final Production     FileName       Haysi 58 Final Production     Haysi 58 Final Prod.xls	Driller's Total Depth:	2334.00	Log's To	otal Depth: 2273.00			
Haysi 58 Casing Haysi 58 Comp Casing.xls  Stimulation Record  Stimulation Status: Stimulated GOB Not Stimulated Service Well  Description FileName  Haysi 58 Stimulation Haysi 58 Stimulation.doc  Final Production  Description FileName  Haysi 58 Final Production Haysi 58 Final Prod.xls			rilling Report	FileName			
Stimulation Status: Stimulated GOB Not Stimulated Service Well    Description FileName							
DescriptionFileNameHaysi 58 StimulationHaysi 58 Stimulation.docFinal ProductionFileNameDescriptionFileNameHaysi 58 Final ProductionHaysi 58 Final Prod.xls	Stimulation Record						
Haysi 58 Stimulation  Haysi 58 Stimulation.doc  Final Production  Description  FileName  Haysi 58 Final Production  Haysi 58 Final Prod.xls	Stimulation Status: St	imulatedGOB	☐Not Stimulated	d Service Well			
Final Production  Description FileName  Haysi 58 Final Production Haysi 58 Final Prod.xls	Descript	tion		FileName			
DescriptionFileNameHaysi 58 Final ProductionHaysi 58 Final Prod.xls	Haysi 58 Stir	nulation	Ha	aysi 58 Stimulation.doc			
Haysi 58 Final Production Haysi 58 Final Prod.xls	Final Production						
	Descript	tion		FileName			
Comments	Haysi 58 Final	Production	H	aysi 58 Final Prod.xls			

Form DGO-GO-15-E

Page 1 of 2

Rev. 1/2007

	Notes:							
5	. Signature							
	Permittee:	Range Re Mountain	Resources-Pine า	Date:	5/1/200	8		(Company)
	Ву:	Laura Mu	urray	Title:	Permit /	Assistant		(Signature)
							_	
,	INTERNA	AL USE	ONLY					
	Subr	mit Date:	5/1/2008			_		
		Status:				Date:	5/5/2008	
	Final PΓ	DF Date:	6/11/2008			_		

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set
Conductor	11¾"	0-63'	15"				
Surface	85/8"	0-309'	11"	143	Yes	09/14/07	
Water Protection	41/2"	0-2281'	6½"	569	Yes	09/19/07	
Other Casing and							
Tubing Left in Well	23/8"	0-2223'					

STIMULATION RECORD (Use additional sheets with this format, if more than three zones are stimulated.)

ZONE 1: Poco 4	Formation Stimulated With:	Gel+70QN <sub>2</sub> Fm
	erforations 15 Perforation	
Formation Broke down at: PSIG		
ISIP 1620 PSIG 5 Min SIP PSIG Avera	ge Downhole Injection Pressure	2804 PSIG
Stimulated:  Yes	10/02/2007	
ZONE 2: Middle Horsepen	Formation Stimulated With:	Gel+70QN <sub>2</sub> Fm
Perforated 1493 to 1605 feet No. of Pe	erforations 26 Perforation	n Size33
Formation Broke down at: 3376 PSIG	Average Injection Rate: 19	BPM
ISIP 1770 PSIG 5 Min SIP PSIG Avera	ge Downhole Injection Pressure	3442 PSIG
Stimulated: No Date Stimulated:	10/02/2007	
ZONE 3: Greasy Creek	Formation Stimulated With:	Gel+70QN <sub>2</sub> Fm
Perforated 1290 1295 feet No. of Pe	-	n Size .33
Formation Broke down at: 3914 PSIG	Average Injection Rate: 16	
	age Downhole Injection Pressure	
Stimulated:	=	
ZONE 4. Hanna Carla and A	E	C-1-700N E
	Formation Stimulated With: erforations 24 Perforation	
Perforated 1136 to 1164 feet No. of Performation Broke down at: 3478 PSIG		
	Average Injection Rate: 21 ge Downhole Injection Pressure	
	•	<u>2774</u> 1510
Stimulated:  Yes	10/03/2007	
ZONE 5: Jawbone Rider	Formation Stimulated With:	Gel+70QN <sub>2</sub> Fm
Perforated 919 to 1027 feet No. of Pe	erforations 23 Perforation	<u> </u>
Formation Broke down at: 1714 PSIG	Average Injection Rate: 23	BPM
ISIP 1032 PSIG 5 Min SIP PSIG Avera	ge Downhole Injection Pressure	2609 PSIG
Stimulated: No Date Stimulated:	•	

Final Production After Stimula				
	BOD	MCFD	<b>Hours Tested</b>	<b>Rock Pressure</b>
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		54	In Line	62



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Box 1416, Abingdon, VA 24212

Telephone: (276) 676-5423

Tracking Number:	1293
Company:	Range Resources-Pine Mountain
File Number:	DI-1797
Operations Name:	Haysi #58 W/PL
Operation Type:	Coalbed/Pipeline
Drilling Report Type:	Original

# **DRILLING REPORT (DGO-GO-14)**

9/13/2007	Drilling Contracto	or: Noah Horn			
9/19/2007	Rig Type:☑Ro	tary			
2334.00	_				
2273.00	Coal Seam at To Dept				
2. Final Location Plat (as required by 4 VAC25-150-360.C.)					
15679.00 31654.00	Final Plat State Plane X: Final Plat State Plane Y:	915672.00 331651.00			
	9/19/2007 2334.00 2273.00  red by 4 VAC25-150 15679.00 31654.00	9/19/2007 Rig Type: ☐Ro  2334.00  2273.00 Coal Seam at To Dept  red by 4 VAC25-150-360.C.)  15679.00 Final Plat State Plane X: Final Plat State Plane Y:			

Form DGO-GO-14-E

Page 1 of 4

Rev. 1/2007

Description	FileName	
Haysi 58 Final Plat	Haysi 58 Final Plat.pdf	

# 3. Geological Data

Fresh Water At:

## Salt Water At:

Depth (in feet)	Rate	Unit of Measure
1200	Damp	

## Coal Seams:

List of Attached Items:

Description	FileName		
Haysi 58 Coal	Haysi 58 Coal.xls		

# Gas and Oil Shows:

List of Attached Items:

Description	FileName		
Haysi 58 Shows	Haysi 58 Shows.xls		

# 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run: Hi Res GR/Dens/Temp/Audio/Pe/Caliper (Data Pack)

Did logs disclose vertical locations of a coal seam?

 $\checkmark$ 

# 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName
Haysi 58 Survey	deviation log.tif

Form DGO-GO-14-E

Page 2 of 4

Rev. 1/2007

# 6. Casing and Tubing Program

List of Attached Items:

Description	FileName		
Haysi 58 Casing/Tubing	Haysi 58 Casing.xls		

## 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

Circ 11 bbl to surf on 11" hole; Circ 12 bbl to surf on 6.5" hole.

8.	Dril	lers	Loc

Compiled By: Joshua Phillips


List of Attached Items:

Description	FileName		
Haysi 58 Log	Haysi 58 Log.xls		

# 9. Comments

I0. Signature			
Permitee:	Range Resources-Pine Mountain	Date:	4/23/2008
Signed By:	Christian D. Moore	Title:	GIS/Permit Specialist

INTERNAL USE ONLY						
Submit Date:	4/23/2008					
Status:	Α	Date:	4/25/2008			
Final PDF Date:	6/10/2008					



#### WELL LOCATION PLAT

COMPANY Pine Mountain Oil & Gas, Inc. WELL NAME AND NUMBER Haysi-58
TRACT NO. <u>1-442</u> ELEVATION <u>1,846.20'</u> QUADRANGLE <u>Prater</u>
COUNTY <u>Dickenson</u> DISTRICT <u>Sandlick</u> SCALE $1'' = 400'$ DATE $9-18-2007$
This Plat is a new plat; an updated plat; or a final location platx
, Denotes the location of a well on United States topographic Maps, scale 1 to
<sup>+</sup> 24,000, latitude and longitude lines being represented by border lines as shown.
0 11-0

Licensed Professional Engineer or Licensed Land Surveyor

# Coal Seams

				N	IINING IN AREA
NAME	TOP	BOTTOM	THICKNESS	YES NO	MINED OUT
Aily	711	713	2	NO	
Raven	792	793	1	NO	
Raven	815	816	1	NO	
Raven	823	824	1	NO	
Jawbone Rider	920	922	2	NO	
Jawbone	957	961	4	NO	
Tiller	1025	1026	1	NO	
Upper Seaboard A	1137	1139	2	NO	
Upper Seaboard	1161	1163	2	NO	
Greasy Creek	1290	1292	2	NO	
Middle Horsepen	1494	1495	1	NO	
War Creek Rider	1565	1566	1	NO	
War Creek	1603	1604	1	NO	
Poco 4	2007	2008	1	NO	
Poco 4	2019	2020	1	NO	
Poco 3	2064	2065	1	NO	
Poco 2	2132	2133	1	NO	
Poco 1	2173	2175	2	NO	

Gas and Oil Shows
FORMATION TOP BOTTOM THICKNESS IPF (MCFD/BOPD) PRESSURE HOURS TESTED

# PLAN VIEW COMPU-LOG DEVIATION

CLIENT: Pine Mountain Oil and Gas


LOCATION: Prater HOLE ID: Haysi 58 DATE OF LOG: 09/19/07

PROBE: 9136AA 962

MAG DECL: -6.9

SCALE: 25 FT/IN TRUE DEPTH: 2257.81 FT AZIMUTH: 254.0 DISTANCE: 50.5 FT + = 300 FT INCR

= BOTTOM OF HOLE



CLIENT : Pine Mountain Oil a HOLE ID. : Haysi 58 FIELD OFFICE : DATE OF LOG : 09/19/07

DATA FROM : PROBE : 9136AA MAG. DECL. : -6.900 DEPTH UNITS : FEET

LOG: Haysi58\_09-19-07\_12-34\_9136AA\_.02\_3.02\_2259.76\_DEVI.log

CABLE DEPTH	TRUE DEPTH	NORTH DEV.	EAST DEV.	DISTANCE	AZIMUTH	SANG	SANGB
50.0	50.00	-0.09	-0.04	0.1	202.4	0.8	270.2
60.0	60.00	-0.01	0.02	0.0	104.5	1.1	19.9
70.0	70.00	0.14	0.05	0.1	20.5	1.0	47.6
80.0	79.99	0.19	0.23	0.3	50.8	1.2	67.7
90.0	89.99	0.26	0.38	0.5	55.4	1.4	22.8
100.0	99.99	0.23	0.35	0.4	56.2	1.3	275.1
110.0	109.99	0.23	0.21	0.3	42.6	1.2	261.5
120.0	119.98	0.24	0.02	0.2	4.3	1.1	280.1
130.0	129.98	0.22	-0.11	0.2	333.6	1.1	269.0
140.0	139.98	0.18	-0.30	0.3	302.0	1.1	258.8
150.0	149.98	0.19	-0.46	0.5	292.2	1.2	293.8
160.0	159.98	0.24	-0.59	0.6	292.5	1.1	113.3
170.0	169.97	0.30	-0.75	0.8	291.5	1.1	276.7
180.0	179.97	0.34	-0.88	0.9	291.1	1.1	100.1
190.0	189.97	0.35	-0.89	1.0	291.3	1.0	131.7
200.0	100 07	0.05	_0 07	0.0	225 7	0 0	345 5

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set
Conductor	11¾"	0-63'	15"				
Surface	85/8"	0-309'	11"	143	Yes	09/14/07	
Water Protection	41/2"	0-2281'	6½"	569	Yes	09/19/07	
Other Casing and Tubing Left in Well	23/8"	0-2223'					

Driller's Log

Diffici & Log		General		Depth	Depth		
Geologic Age	Formation	Lithology	Color	Тор	Bottom	Thickness	Remarks
Penn	Lee	Sand, shale, thin coals		0	711	711	
Penn	Lee	Coal		711	713	2	Aily
Penn	Lee	Sand, shale, thin coals		713		79	
Penn	Lee	Coal		792	793	1	Raven
Penn	Lee	Sand, shale, thin coals		793	815	22	
Penn	Lee	Coal		815	816	1	Jawbone Rider
Penn	Lee	Sand, shale, thin coals		816	823	7	
Penn	Lee	Coal		823	824	1	Jawbone
Penn	Lee	Sand, shale, thin coals		824	920	96	
Penn	Lee	Coal		920	922	2	Jawbone Rider
Penn	Lee	Sand, shale, thin coals		922	957	35	
Penn	Lee	Coal		957	961	4	Jawbone
Penn	Lee	Sand, shale, thin coals		961	1025	64	
Penn	Lee	Coal		1025	1026	1	Tiller
Penn	Lee	Sand, shale, thin coals		1026	1137	111	
Penn	Lee	Coal		1137	1139	2	Upper Seaboard A
Penn	Lee	Sand, shale, thin coals		1139	1161	22	
Penn	Lee	Coal		1161	1163	2	Upper Seaboard
Penn	Lee	Sand, shale, thin coals		1163	1290	127	
Penn	Lee	Coal		1290	1292	2	Greasy Creek
Penn	Lee	Sand, shale, thin coals		1292	1494	202	
Penn	Lee	Coal		1494	1495	1	Middle Horsepen
Penn	Lee	Sand, shale, thin coals		1495	1565	70	
Penn	Lee	Coal		1565	1566		War Creek Rider
Penn	Lee	Sand, shale, thin coals		1566	1603	37	
Penn	Lee	Coal		1603	1604	1	War Creek
Penn	Lee	Sand, shale, thin coals		1604	2007	403	
Penn	Lee	Coal		2007	2008	1	Poco 4
Penn	Lee	Sand, shale, thin coals		2008	2019	11	
Penn	Lee	Coal		2019	2020		Poco 4
Penn	Lee	Sand, shale, thin coals		2020	2064	44	
Penn	Lee	Coal		2064	2065	1	Poco 3
Penn	Lee	Sand, shale, thin coals		2065		67	
Penn	Lee	Coal		2132	2133		Poco 2
Penn	Lee	Sand, shale, thin coals		2133	2173	40	
Penn	Lee	Coal		2173	2175	2	Poco 1
Penn	Lee	Sand, shale, thin coals		2175	2271	96	



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

Tracking Number: 3246

**Company:** Range Resources-Pine Mountain

File Number: DI-2064

Completion Report Type: Original

# **COMPLETION REPORT (DGO-GO-15)**

Well Type: Coalbed/Pipeline Date Well Completed: 12/3/2008

Driller's Total Depth: 2494.00 Log's Total Depth: 2494.00

## 1. Changes In Casing/Tubing from Approved Drilling Report

Description	FileName

## 2. Stimulation Record

Stimulation Status: R Stimulated E GOB E Not Stimulated E Service Well

Description	FileName
Haysi #63 stimulation	haysi 63 stimulation.rtf

#### 3. Final Production

Description	FileName
Haysi #63 final production	Final_Prod.xls

## 4. Comments

Form DGO-GO-15-E

Notes:							
NOIES.							
5. Signature							
Permittee:	Range R Mountair	esources-Pine า	Date:	3/15/20	12		(Company)
Ву:	Jonathar	n Horne	Title:	Engine	ering Tech		(Signature)
INTERNA	L USE	ONLY					
Subn	nit Date:	3/15/2012			_		
	Status:	Approved			Date:	3/28/2012	
Final PD	OF Date:	3/29/2012					

BBIs

**BBLs** 

scfm

scf

sks

Gal

15% HCL

#### 105010115 1 Haysi 63

Stage	1	
Sta	ge	Da

Stage Date 12/3/2008
Perf Date 12/3/2008
Logging Co. Key Energy

Formation Poca 4 Rider, Poca 4,

Top Perf 2034
Bottom Perf 2118.5
#Shots 25
Perf Size 0.33
Perf Comments

Service Co Superior Avg DH Rate 27.3 Fluid Type 15 lb Gel Fresh Water Max DH Rate 28.2 119 BD 2255 Total Slurry Volume ISIP n/a Total Fluid Volume 105 Avg Press 2854 Avg N2 Rate 18,000 Max Treat Pressure Max N2 Rate 4193 Final ISIP Total N2 Volume 189,100 s/o 2 Min SIP s/o Max DH PPA Total Proppant Sks 5 Min SIP 14300 s/o 10 Min SIP Total Acid 500

Sand Mesh:

Frac Gradient:

### Stage 2

Stage Date 12/3/2008
Perf Date 12/3/2008
Logging Co. Key Energy

Formation Upper Horsepen, Mid

 Top Perf
 1393.5

 Bottom Perf
 1570.5

 #Shots
 23

 Perf Size
 0.33

 Perf Comments

Service Co Superior Avg DH Rate 28.5 Fluid Type 15 lb Gel Fresh Water Max DH Rate 29.3 Total Slurry Volume Total Fluid Volume BD 2114 230 BBLs ISIP 210 **BBLs** n/a Avg N2 Rate Avg Press 2808 18.500 Max Treat Pressure 4103 Max N2 Rate scfm Final ISIP 1605 Total N2 Volume 349,000 scf 2 Min SIP Max DH PPA 1120 5 Min SIP 1079 Total Proppant Sks 21400 sks 10 Min SIP Total Acid 550 Gal Sand Mesh: Acid Type 15% + 7.5% Frac Gradient:

Acid Type

#### Stage 3

Stage Date 12/3/2008 Perf Date 12/3/2008 Key Energy Logging Co. Formation Upper Seaboard, Top Perf 1122 **Bottom Perf** 1258.5 #Shots 20 Perf Size 0.33

Perf Comments

Service Co Superior Avg DH Rate 28 Max DH Rate Fluid Type 15 lb Gel - Fresh 29 BD 2417 Total Slurry Volume 112 **BBLs** ISIP Total Fluid Volume 98 **BBLs** n/a Avg Press 2233 Avg N2 Rate 14,000 Max N2 Rate Max Treat Pressure 2610 scfm Final ISIP 1060 Total N2 Volume 141,000 scf 2 Min SIP Max DH PPA 977 5 Min SIP 864 Total Proppant Sks 16700 sks 10 Min SIP Total Acid 250 Gal Sand Mesh: 7.5% Acid Type Frac Gradient:

# Range Resources - Pine Mountain **Completion Report**

Page 2 of 2 3/15/2012 9:56:10 AM

Stage 4 Stage Date Perf Date 12/3/2008 12/3/2008 Logging Co. Formation Key Energy Jawbone Rider, 875

Top Perf Bottom Perf 979 #Shots 22 Perf Size 0.33 Perf Comments

Service Co	Superior	Avg DH Rate		
Fluid Type	15 lb Gel - Fresh	Max DH Rate	29.1	
BD	2603	Total Slurry Volume	146	BBLs
ISIP	n/a	Total Fluid Volume	125	BBLs
Avg Press		Avg N2 Rate	13,000	
Max Treat Pressure	3302	Max N2 Rate		scfm
Final ISIP	1021	Total N2 Volume	241,000	scf
2 Min SIP	933	Max DH PPA		
5 Min SIP	918	Total Proppant Sks	17000	sks
10 Min SIP		Total Acid	350	Gal
Sand Mesh:		Acid Type	7.5%	
Frac Gradient:				

Summary Total for All

Number	Total	Total Fluid	Total N2	Total	
of Stages	Slurry	Volume	Volume	Proppant	Total Acid
4	607	538	920,100	69400	1650

Final Production After Stimulation				
	BOD	MCFD	<b>Hours Tested</b>	<b>Rock Pressure</b>
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		7	in-line	9



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

Tracking Number: 3313

Range Resources-Pine Mountain

Company: File Number:

DI-2064

**Operations Name:** 

Haysi #63 W/PL

**Operation Type:** 

Coalbed/Pipeline

**Drilling Report Type:** 

Original

# **DRILLING REPORT (DGO-GO-14)**

## 1. Drilling Data

Date drilling commenced: 11/13/2008 Drilling Contractor: Noah Horn #109

Date drilling completed: 11/18/2008 Rig Type: Rotary ← Cable

Driller's Total Depth (feet): 2494.00

Log Total Depth (feet): 2494.00 Coal Seam at Total Pocahontas

Depth:

#### 2. Final Location Plat (as required by 4 VAC25-150-360.C.)

Permitted State Plane X: 10400117.9500 Final Plat State Plane X: 10400125.7800

Permitted State Plane Y: 3610375.3900 Final Plat State Plane Y: 3610370.3600

Plat Previously Submitted Or... 🗲

List of Attached Items:

Form DGO-GO-14-E

Page 1 of 3

Description	FileName
Haysi #63 final location	Haysi 63 Plat.pdf

# 3. Geological Data

Fresh Water At:

Depth (in feet)	Rate	Unit of Measure

Salt Water At:

Depth (in feet)	Rate	Unit of Measure
-----------------	------	-----------------

Coal Seams:

List of Attached Items:

Description	FileName
Haysi #63 coals	Haysi 63 Coal.xls

Gas and Oil Shows:

List of Attached Items:

Description	FileName
Haysi #63 gas shows	Shows.xls

## 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run: Hi Res GR/Dens/Temp/Audio/PE/Caliper Data Pack, camera

Did logs disclose vertical locations of a coal

seam?

R

# 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName
Haysi #63 survey	Haysi 63 Deviation Log.pdf

Form DGO-GO-14-E

Page 2 of 3

# 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
Haysi #63 casing	Casing.xls

## 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

8. Drillers Log	g
-----------------	---

Compiled By: Range Resources

List of Attached Items:


Description	FileName
Haysi #63 log	Haysi 63 Log.xls

## 9. Comments

0. Signature					
Permitee:	Range	Resources-Pine Mountain	Date:	3/15/2012	
Signed By:	Jonath	an Horne	Title:	Engineerin	g Tech
INTERNAL	USE	ONLY			
Submi	t Date:	3/15/2012			
5	Status:	A		Date:	3/28/2012
Final PDF	Date:	3/29/2012			

Form DGO-GO-14-E

Page 3 of 3



WELL LOCATION PLAT (Nora Grid Al-67)

COMPANY <u>Range Resources - Pine Mountain, Inc.</u> WELL NAME AND NUMBER <u>Haysi-63</u> TRACT NO. <u>George H. Fuller/T-293</u> ELEVATION <u>1.882.41</u> QUADRANGLE <u>Prater</u>	<del></del>
COUNTY <u>Dickenson</u> DISTRICT <u>Sandlick</u> SCALE <u>1" = 400'</u> DATE <u>11-14-200</u>	08
This Plat is a new plat; an updated plat; or a final location plat	
Denotes the location of a well on United States topographic Maps, scale 1 to	
24,000, latitude and longitude lines being represented by border lines as shown.	
Jam E. Helmy	

# Coal Seams

		MINING IN AREA			
NAME	TOP	BOTTOM	THICKNESS	YES N	MINED OUT
Jawbone Rider	876	878	2	N	O NO
Jawbone	924	925	1	N	O NO
Tiller	977	978	1	N	O NO
Upper Seaboard	1123	1125	2	N	O NO
Greasy Creek	1255	1257	2	N	O NO
Upper Horsepen	1394	1396	2	N	O NO
Middle Horsepen	1450	1452	2	N	O NO
Lower Horsepen	1569	1570	1	N	O NO
Poco 4 Rider	2034	2035	1	N	O NO
Poco 4	2044	2047	3	N	O NO
Poco 2	2117	2118	1	N	O NO

# Gas and Oil Shows

FORMATION	TOP	воттом	THICKNESS	IPF (	(MCFD/BOPD)		PRESSURE	HOURS TESTED
TD w/csg		2490			49.	1		

# PLAN VIEW COMPU-LOG DEVIATION

CLIENT: Range Resources/Pine Mountain LOCATION: PawPaw HOLE ID: Haysi #63 DATE OF LOG: 11/19/08 PROBE: 9136AA 4520

2450.0

2480.5

2448.69


2479.37

-43.33

-44.32

MAG DECL: -6.9

SCALE: 25 FT/IN TRUE DEPTH: 2479.07 FT AZIMUTH: 135.7 DISTANCE: 61.9 FT + = 300 FT INCR  $\circ$  = Bottom of Hole



	T : Range OFFICE :	Resources/Fi		. : Hay		j	İ
DATA			PROBE		6AA	4520	
		00		NITS : FEE	,		
	Haysi#63_11-19-0						
200.	114/01/00_11 15 0	0_10 1,_3100	/1·		2111104		
CABLE DE		NORTH DEV.					SANGB
13.8	13.80	0.00	0.00	0.0	0.0	0.0	0.0
50.0	50.00	+0.04	-0.12			0.6	
100.0	100.00	-0.08	<del>-</del> 0.36	0.4	258.2	0.8	
150.0	149.99	0.23	<del>-</del> 0.72	0.8	287.8	0.6	
200.0	199.99	0.39	-0.83	0.9	295.4	ା. ଚ	191.9
250.0	249.99	0.47	-0.86	1.0	298.6	0.4	
300.0	299.98	្.50	-0.97	1.1	297.0	0.3	274.7
350.0	349.98	0.41	-1.16	1.2	289.4	0.4	227.7
400.0	399.98	0.12	-1.35	1.4	275.1	0.3	212.1
450.0	449.98	-0.14	-1.55	1.6	264.8	0.5	245.6
500.0	499.98	-0.43	-1.69	1.7	255.8	0.4	200.9
550.0	549.98	-0.92	-1.55	1.8	239.5	0.9	
600.0	599.95	-1.79	-0.66	1.9	200.2	1.9	
650.0	649.92	-3.26	0.35	3.3	173.9	2.1	
700.0	699.88		1.48	5.1		2.4	
750.0	749.83		2.78			2.9	
800.0	799.75	-8.94	4.61			3.5	
850.0	849.66	-11.16	6.63	13.0	149.3	3.3	138.8
900.0	899.58	-13.28		15.7	147.6	3.0	
950.0	949.52	-15.21	10.05	18.2	146.6	2 . 9	
1000.0	999.44	-17.22	12.02	21.0	145.1		151.5
1050.0	1049.36	-19.10		23.7	143.7		134.9
1100.0	1099.30	-20.17					38.5
1150.0	1149.26	-21.12	17.47	27.4	140.4		117.9
1200.0	1145.20	-23,13	10,11	27.4	190.9	2 · 4	136.9
1250.0	1249.19	-23.04		30.9		11 7 7 7	135. <b>7</b>
1300.0	1299.15	-23.95	20.67 22.19	32.6	138.1 137.2	2: 6	132.2
1350.0	1349.13	-24.61	23.43	34.0	136.4	2.0	97.0
1400.0	1399.11	-24.54	24.21	34.5	135.4	2.0	65.4
1450.0	1449.08	-25.25	25.52	35.9	134.7	1.6	116.4
1500.0	1499.06	-26.12	26.78	37.4	134.3	1.7	123.6
1550.0	1549.04	-26.65	27.65	38.4	134.0	1.6	135.4
1600.0	1599.01	-27.09	28.71	39.5	133.3	1.9	132.2
1650.0	1648.99	-28.14	29.80	41.0	133.4	1.8	137.4
1700.0	1698.96	-29.25	30.90	42.5	133.4	1.7 1.7	155.7
1750.0	1748.94	-30.35	32.00	44.1	133.5	1 7	135.7
1800.0	1798.32	-31.39	33.06	45.6	133.5	1.6	136.7
1850.0	1848.89	-32.30	34.19	47.0	133.4	1.7	128.7
1900.0	1898.87	-33.16	35.43	48.5	133.1	1 7	132.5
1950.0	1948.85	-33.84	36.50	49.8	132.8	1.7	151.4
2000.0	1998.84	-34.48	37.30	50.9	132.8	1.0	125.2
2050.0	2048.83	-35.18	37.85	51.7	132.9	1.0	146.4
2100.0	2098.82	-36.14	38.20	52.8	133.4	11. 6	166.8
2150.0	2148.80	-37.49	38.51	53.7	134.2	1.6 1.9	169.6
2200.0	2198.76	-38.81	36.92	55.0	134.9	1.6	165.2
2250.0	2248.7€	-39.84	39.54	56.1	135.2	1 2	113.3
2300.0	2298.75	-40.90	39.74	57.0	135.8	1.6	146.5
2350.0	2348.74	-41.53	40.18	57.8	135.6	1.2	150.1
2400.0	2398.72	-42.22	40.87	58.8	135.9	1.8	115.7
2450.0	2448.69	-43.33	42.24	60.5	135.7	2 . 4	133.7

60.5

61.9

135.7

2.4 | 133.1

135.7 - 999999.0 - 999639.0

42.24

43.27

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented
Conductor	11¾"	0-21'	15"			
Water Protection	8%"	0-313'	11"	133.1	Yes, circ 5bbls	11/14/08
Production Casing	41/2"	0-2450'	6½"	439.2	Yes, circ 4bbls	11/19/08
Other Casing And						
Tubing Left In Well	2¾"					
Liners						

Packers Or Bridge Plugs Kind/Size/Set	Cement Baskets (ft)
	84'
	334' 1874'

# Driller's Log

, and the second		General	
Geologic Age	Formation	Lithology	Color
Penn	Lee	Sand and shale	
Penn	Lee	Coal	
Penn	Lee	Sand and shale	
Penn	Lee	Coal	
Penn	Lee	Sand and shale	
Penn	Lee	Coal	
Penn	Lee	Sand and shale	
Penn	Lee	Coal	
Penn	Lee	Sand and shale	
Penn	Lee	Coal	
Penn	Lee	Sand and shale	
Penn	Lee	Coal	
Penn	Lee	Sand and shale	
Penn	Lee	Coal	
Penn	Lee	Sand and shale	
Penn	Lee	Coal	
Penn	Lee	Sand and shale	
Penn	Lee	Coal	
Penn	Lee	Sand and shale	
Penn	Lee	Coal	
Penn	Lee	Sand and shale	
Penn	Lee	Coal	
Penn	Lee	Sand and shale	

Depth	Depth		
Тор	Bottom	Thickness	Remarks
0	876	876	
876	878	2	Jawbone Rider
878	924	46	
924	925	1	Jawbone
925	977	52	
977	978	1	Tiller
978	1123	145	
1123	1125	2	Upper Seaboard
1125	1255	130	
1255	1257	2	Greasy Creek
1257	1394	137	
1394	1396	2	Upper Horsepen
1396	1450	54	
1450	1452	2	Middle Horsepen
1452	1569	117	
1569	1570	1	Lower Horsepen
1570	2034	464	
2034	2035	1	Poco 4 Rider
2035	2044	9	
2044	2047	3	Poco 4
2047	2117	70	
2117	2118	1	Poco 2
2118	2494	376	



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

Tracking Number: 2320

**Company:** Range Resources-Pine Mountain

File Number: BU-4074

Completion Report Type: Original

## **COMPLETION REPORT (DGO-GO-15)**

Well Type: Coalbed/Pipeline Date Well Completed: 1/9/2009

Driller's Total Depth: 2461.00 Log's Total Depth: 2474.00

### 1. Changes In Casing/Tubing from Approved Drilling Report

Description	FileName
-------------	----------

### 2. Stimulation Record

Stimulation Status: RStimulated EGOB ENot Stimulated EService Well

Description	FileName
Haysi 142 Stimulation Record	Stimulation Report.doc

### 3. Final Production

Description	FileName
Haysi 142 Final Production	Final_Prod.xls

### 4. Comments

Form DGO-GO-15-E

Notes:							
5. Signat	ure						
Permitte	ee: Range R Mountai	Resources-Pine n	Date:	1/27/20	10		(Company)
Ву:	Laura M	urray	Title:	Permit S	Specialist		(Signature)
			_				
INTER	RNAL USE	ONLY					
S	Submit Date:	1/27/2010					
ı	Status:	Approved			Date:	3/5/2012	
Fina	ll PDF Date:	3/6/2012					

# **STIMULATION RECORD**

ZONE 1: Poca 2, Poca 1	Formation Stimulated With:	$N_2Fm$	
Perforated 2274 to 2325 feet No. of P	Perforations 24 Perforation	n Size	.33
Formation Broke down at: 2217 PSIG	Average Injection Rate: 20	BPM	
ISIP 1719 PSIG 2 Min SIP 1660 PSIG Avera	age Downhole Injection Pressure	3498	PSIG
Stimulated: No Date Stimulated:	1/9/2009		
ZONE 2: Poca 4, Poca 3, Poca	Formation Stimulated With:	N <sub>2</sub> Fm	
	Perforations 30 Perforation	_	.33
Formation Broke down at: 3716 PSIG	Average Injection Rate: 22	BPM	
ISIP <u>2041</u> PSIG 2 Min SIP <u>1836</u> PSIG Avera	age Downhole Injection Pressure	2785	PSIG
Stimulated: Yes	1/9/2009		
ZONE 3: Upper Horsepen	Formation Stimulated With:	N <sub>2</sub> Fm	
	Perforations 30 Perforation		.33
Formation Broke down at: 2925 PSIG	Average Injection Rate: 23	_	
ISIP 2310 PSIG 2 Min SIP 2075 PSIG Avera			PSIG
Stimulated:	1/9/2009		
ZONE 4: Upper Seaboard	Formation Stimulated With:	N <sub>2</sub> Fm	
Perforated 1219 to 1451 feet No. of F	<del>.</del>		33
Formation Broke down at: 2012 PSIG	Average Injection Rate: 25	BPM	.33
ISIP 1270 PSIG 2 Min SIP 1187 PSIG Avera		2720	PSIG
	1/9/2009	2120	1510
Stimulated: Yes	1/9/2009		
ZONE 5: Raven, Jawbone Rider	Formation Stimulated With:	N <sub>2</sub> Fm	
	Perforations 30 Perforation	i Size	.33
Formation Broke down at: 2119 PSIG	Average Injection Rate: 26	BPM	
ISIP 1182 PSIG 2 Min SIP 1115 PSIG Avera		2363	PSIG
Stimulated: Yes No Date Stimulated:	1/9/2009		
	-		

Final Production After Stimulation				
	BOD	MCFD	<b>Hours Tested</b>	Rock Pressure
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		14	in-line	10



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

Tracking Number: 2368

**Company:** Range Resources-Pine Mountain

File Number: BU-4074

Operations Name: Haysi #142 W/PL

Operation Type: Coalbed/Pipeline

**Drilling Report Type:** Original

## **DRILLING REPORT (DGO-GO-14)**

### 1. Drilling Data

Date drilling commenced: 12/17/2008 Drilling Contractor: Noah Horn #109

Date drilling completed: 12/20/2008 Rig Type: Rotary Cable

Driller's Total Depth (feet): 2461.00

Log Total Depth (feet): 2474.00 Coal Seam at Total POCAHONTAS

Depth: #2

### 2. Final Location Plat (as required by 4 VAC25-150-360.C.)

Permitted State Plane X: 10408237.0100 Final Plat State Plane X: 10408236.5300

Permitted State Plane Y: 3612091.4000 Final Plat State Plane Y: 3612091.8200

Plat Previously Submitted Or... 🗲

List of Attached Items:

Form DGO-GO-14-E

Page 1 of 4

Description	FileName
Haysi 142 Final Plat	Haysi 142 Plat.pdf

# 3. Geological Data

Fresh Water At:

Depth (in feet)	Rate	Unit of Measure

Salt Water At:

Depth (in feet)	Rate	Unit of Measure
-----------------	------	-----------------

Coal Seams:

List of Attached Items:

Description	FileName		
Haysi 142 Coal	Haysi 142 Coal.xls		

Gas and Oil Shows:

List of Attached Items:

Description	FileName
Haysi 142 Gas Shows	Shows.xls

£

### 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run: Hi Res GR/Dens/Temp/Audio/PE/Caliper Data Pack

Did logs disclose vertical locations of a coal seam?

## 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName			
Haysi #142 Survey	Haysi #142 Survey.pdf			

Form DGO-GO-14-E

Page 2 of 4

## 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
Haysi 142 Casing	Casing.xls

### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.


. Drillers Log							
Compiled By:							
List of Attached Items:							
Description	FileName						
Haysi 142 Driller's Log	Haysi 142 Log.xls						

## 9. Comments

updated casing file to include basket depths [7/12/2011, jhorne] Cement baskets [3/10/2010, jah] Need depth of cement baskets [3/4/2010, jah] Deviation survey not legible [3/4/2010, jah]

10. Signature			
Permitee:	Range Resources-Pine Mountain	Date:	7/12/2011
Signed By:	Laura Murray	Title:	Permit Specialist

INTERNAL USE ONLY					
Submit Date:	7/12/2011				
Status:	A	Date:	3/1/2012		
Final PDF Date:	3/2/2012				



COMPANY Range Resources-Pine Mountain, lac. WELL NAME AND NUMBER Haysi-142
TRACT NO. Legas No. 243344 ELEVATION 2.061.40 QUADRANGLE Prater
COUNTY Buchanan DISTRICT Prater. SCALE 1" = 400' DATE 12-18-2008
This Plat is a new plat; an updated plat; or a final location platx
Denotes the location of a well on United States topographic Maps, scale 1 to
<sup>+</sup> 24,000, latitude and longitude lines being represented by border lines as shown.
Gran E. Haling
Licensed Professional Engineer or Licensed Land Surveyor

# Coal Seams

	M	INING IN AREA			
NAME	TOP	BOTTOM	THICKNESS	YES NO	MINED OUT
Kennedy	682	684	2	NO	NO
Aily	813	814	1	NO	NO
Raven	906	909	3	NO	NO
Jawbone Rider	1007	1011	4	NO	NO
Jawbone	1037	1040	3	NO	NO
Tiller	1105	1106	1	NO	NO
Upper Seaboard A	1219	1220	1	NO	NO
Upper Seaboard	1245	1246	1	NO	NO
Greasy Creek	1389	1393	4	NO	NO
Lower Seaboard	1448	1449	1	NO	NO
Upper Horsepen	1528	1529	1	NO	NO
Middle Horsepen	1594	1595	1	NO	NO
Unnamed	1657	1658	1	NO	NO
Lower Horsepen	1736	1737	1	NO	NO
Poco 4	2551	2553	2	NO	NO
Poco 3	2186	2189	3	NO	NO
Poco 3	2204	2205	1	NO	NO
Poco 3	2214	2215	1	NO	NO
Poco 2	2274	2276	2	NO	NO
Poco 1	2321	2323	2	NO	NO

# Gas and Oil Shows


FORMATION	TOP	BOTTOM	THICKNESS	IPF (MCFD/BOPD)	PRESSURE	HOURS TESTED
TD	2461			NA		
TD w/csg	2461			NA		

# PLAN VIEW COMPU-LOG DEVIATION

CLIENT: Range Resources/Pine Mt.

LOCATION: PawPaw HOLE ID: Haysi 142 DATE OF LOG: 12/20/08 PROBE: 9136AA 4520 MAG DECL: -6.9

SCALE: 10 FT/IN
TRUE DEPTH: 2462.49 FT
AZIMUTH: 112.2
DISTANCE: 22.6 FT
+ = 300 FT INCR
= BOTTOM OF HOLE



CLIENT : Range Resources/Pin HOLE ID. : Haysi 142 FIELD OFFICE : DATE OF LOG : 12/20/08

DATA FROM : PROBE : 9136AA , 4520

MAG. DECL. : -6.900 DEPTH UNITS : FEET

LOG: Haysi142\_12-20-08\_06-49\_9136AA\_.1\_12.20\_2463.10\_DEVI.log

CABLE DEPTH	TRUE DEPTH	NORTH DEV.	EAST DEV.	DISTANCE	AZIMUTH	SANG	SANGB
13.8	13.72	0.02	0.10	0.1	81.0	0.0	0.0
50.0	49.91	0.14	0.15	0.2	47.3	0.7	30.4
100.0	99.91	0.34	0.09	0.4	14.6	0.8	227.1
150.0	149.90	0.18	-0.24	0.3	307.7	0.9	201.1
200.0	199.90	-0.32	-0.26	0.4	219.0	1.1	198.0
250.0	249.89	-0.54	-0.05	0.5	184.8	0.9	342.0
300.0	299.88	-0.13	-0.05	0.1	202.0	0.9	288.4
350.0	349.87	-0.67	0.06	0.7	175.1	1.3	152.1
400.0	399.86	-1.38	0.10	1.4	176.0	0.9	152.9
450.0	449.85	-2.12	0.16	2.1	175.6	0.9	190.5
500.0	499.84	-2.81	0.28	2.8	174.4	0.9	303.6
550.0	549.84	-3.25	0.19	3.3	176.7	0.6	181.8
600.0	599.84	-3.67	0.18	3.7	177.2	0.5	166.1
650.0	649.84	<b>-</b> 3.95	0.14	4.0	177.9	0.3	146.1
700.0	699.83	-4.30	0.14	4.3	178.1	0.5	145.3
750.0	749.83	-4.68	0.03	4.7	179.6	0.4	245.0
800.0	799.83	-4.76	-0.04	4.8	180.5	0.1	90.8
850.0	849.83	-4.83	0.03	4.8	179.6	0.2	79.4
900.0	899.83	-4.81	0.22	4.8	177.4	0.4	107.7
950.0	949.83	-4.65	0.53	4.7	173.5	0.5	55.8
1000.0	999.83	-4.48	0.78	4.5	170.1	0.5	48.2
1050.0	1049.82	-4.34	1.14	4.5	165.3	0.4	151.9
1100.0	1099.82	-4.23	1.37	4.4	162.0	0.6	55.7
1150.0	1149.82	-4.24	1.78	4.6	157.2	0.7	96.7
1200.0	1199.81	-4.42	2.28	5.0	152.7	0.8	98.3

1250.0 1300.0	1249.81 1299.79	-4.77 -5.60	2.97 3.66	5.6 6.7	148.1 146.8	1.2 115.6 1.1 275.7
1350.0	1349.77	-6.41	4.23	7.7	146.6	1.5 141.1
1400.0	1399.76	-7.45	4.99	9.0	146.2	1.5 158.0
1450.0	1449.74	-8.52		10.2	146.3	
1500.0	1499.72	-9.59	6.39	11.5	146.3	
1550.0	1549.71	-10.23	6.92	12.4	145.9	
1600.0	1599.70	-11.04	7.64	13.4	145.3	
1650.0	1649.68	-11.85	8.53	14.6	144.2	1.4 132.6
1700.0	1699.67	-12.67	9.46	15.8	143.3	1.4 132.8
1750.0	1749.65	-13.13	9.72	16.3	143.5	1.4 148.2
1800.0	1799.64	-13.93	10.32	17.3	143.5	
1850.0	1849.63	-14.19	10.91	17.9	142.5	
1900.0	1899.61	-13.68	12.14	18.3	138.4	
1950.0	1949.59	-12.72	13.41	18.5	133.5	
2000.0	1999.56	-11.89	14.63	18.9	129.1	1.4 48.5
2050.0	2049.54	-11.04	15.73	19.2	125.1	1.5 49.6
2100.0	2099.53	-10.46	16.50	19.5	122.4	1.4 59.3
2150.0	2149.52	-9.92	17.47	20.1	119.6	1.4 59.8
2200.0	2199.50	-9.57	18.46	20.8	117.4	1.5 67.5
2250.0	2249.49	-9.21	19.10	21.2	115.7	1.0 26.4
2300.0	2299.49	-9.25	19.68	21.7	115.2	0.6 78.4
2350.0	2349.48	-9.11	20.20	22.2	114.3	0.6 63.0
2400.0	2399.48	-9.08	20.33	22.3	114.1	0.9 277.6
2450.0	2449.47	-8.62	20.71	22.4	112.6	0.7 49.1
2463.1	2462.49	-8.53	20.92	22.6	112.2	-999999.0 -999639.0

# **Casing Program**

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs		
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set	Cement	Baskets
Conductor	11¾"	0-16'	15"						
Water Protection	85/8"	0-305'	11"	139.15	Yes, circ 3bbls	12/18/08		215'	
Production Casing	41/2"	0-2416'	6½"	475.8	Yes, circ 5bbls	12/21/08		533'	1927'
Other Casing And									
Tubing Left In Well	23/8"	0-2377'							
Liners									

Driller's Log

		General		Depth	Depth		
Geologic Age	Formation	Lithology	Color	Тор	Bottom	Thickness	Remarks
Penn	Lee	Sand and shale		0	682	682	
Penn	Lee	Coal		682	684	2	Kennedy
Penn	Lee	Sand and shale		684	813	129	·
Penn	Lee	Coal		813	814	1	Aily
Penn	Lee	Sand and shale		814	906	92	
Penn	Lee	Coal		906	909	3	Raven
Penn	Lee	Sand and shale		909	1007	98	
Penn	Lee	Coal		1007	1011	4	Jawbone Rider
Penn	Lee	Sand and shale		1011	1037	26	
Penn	Lee	Coal		1037	1040	3	Jawbone
Penn	Lee	Sand and shale		1040	1105	65	
Penn	Lee	Coal		1105	1106	1	Tiller
Penn	Lee	Sand and shale		1106	1219	113	
Penn	Lee	Coal		1219	1220	1	Upper Seaboard A
Penn	Lee	Sand and shale		1220	1245	25	
Penn	Lee	Coal		1245		1	Upper Seaboard
Penn	Lee	Sand and shale		1246	1389	143	
Penn	Lee	Coal		1389	1393	4	Greasy Creek
Penn	Lee	Sand and shale		1393	1448	55	
Penn	Lee	Coal		1448	1449	1	Lower Seaboard
Penn	Lee	Sand and shale		1449	1528	79	
Penn	Lee	Coal		1528	1529	1	Upper Horsepen
Penn	Lee	Sand and shale		1529	1594	65	
Penn	Lee	Coal		1594	1595	1	Middle Horsepen
Penn	Lee	Sand and shale		1595	1657	62	·
Penn	Lee	Coal		1657	1658	1	Unnamed
Penn	Lee	Sand and shale		1658	1736	78	
Penn	Lee	Coal		1736	1737	1	Lower Horsepen
Penn	Lee	Sand and shale		1737	2151	414	
Penn	Lee	Coal		2151	2153	2	Poco 4
Penn	Lee	Sand and shale		2153	2186	33	
Penn	Lee	Coal		2186	2189	3	Poco 3
Penn	Lee	Sand and shale		2189	2204	15	
Penn	Lee	Coal		2204	2205	1	Poco 3
Penn	Lee	Sand and shale		2205	2214	9	
Penn	Lee	Coal		2214	2215	1	Poco 3
Penn	Lee	Sand and shale		2215	2274	59	
Penn	Lee	Coal		2274	2276	2	Poco 2
Penn	Lee	Sand and shale		2276		45	
Penn	Lee	Coal		2321	2323		Poco 1
Penn	Lee	Sand and shale		2323	2474	151	



Commonwealth of Virginia
Department of Mines, Minerals, and Energy
Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

	Tracking	Number:	3540			
	Company:			Range Resources-Pine Mountain		
	File Num	ber:	BU-4949			
	Operatio	ns Name:	900109			
	Operatio	n Type:	Gas			
	Drilling R	Report Type:	Original			
D I. Drilling Data	RILLING REPO	RT (DGO-G	O-14)			
Date drilling commenced: 7/11/2012		Drilling Contractor: Gasco #5				
Date drilling completed: 8/31/2012		Rig Type:[☑Rotary ☐Cable				
Driller's Total Depth (feet): 5156.00						
Log Total Depth (feet):	5162.00	Formation At Total Depth Cleveland Sha				
2. Final Location Plat (as requi	red by 4 VAC25-15	60-360.C.)				
Permitted State Plane X: 10	403973.6600	Final Plat Sta	te Plane X:	10403966.8700		
Permitted State Plane Y: 36	16063.8300	Final Plat Sta	Final Plat State Plane Y: 3616065.5500			
Plat Previously Submitted Or						
List of Attached Items:						
Description		FileName				
900109 final pla	at	900109 Final Plat.pdf				

Form DGO-GO-14-E

Page 1 of 3

## 3. Geological Data

Fres	Ь	144	at.	or	Λŧ
Fres	11	Vν	an	97	Αı

	Depth (in feet)	Rate	Unit of Measure
Salt Water At:			

D - -- 41-

Depth (in feet) Rate Unit of Measure

Coal Seams:

List of Attached Items:

Description	FileName		
900109 coal	V-900109 Coal.xlsx		

Gas and Oil Shows:

List of Attached Items:

Description	FileName
900109 gas shows	Shows.xls

## 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run:

GR/CDL/PE/DIL/Neu/TEMP/Petrosolve

Did logs disclose vertical locations of a coal

 $\checkmark$ 

seam?

## 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName
900109 survey	Survey.xls

## 6. Casing and Tubing Program

Form DGO-GO-14-E

Page 2 of 3

### List of Attached Items:

Description	FileName
900109 casing	Casing.xlsx

### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

2	Dril	lore	Log
ο.	DIII	1613	LUG

Compiled By:

Range Resources

List of Attached Items:

Description	FileName
900109 log	V-900109 Log.xlsx

### 9. Comments

Approved [11/7/2012, cbl]

### 10. Signature

Permitee:

Range Resources-Pine Mountain

Date:

10/23/2012

Signed By:

Jonathan Horne

Title:

**Engineering Tech** 

## INTERNAL USE ONLY

Submit Date:

10/23/2012

Status:

Δ

Date:


11/7/2012

Final PDF Date:

11/16/2012

Form DGO-GO-14-E

Page 3 of 3



COMPANY Range Resources—Fine Mountain, Inc. WELL NAME AND NUMBER 300109 TRACT NO. W.C. Owens . ELEVATION 2.056.90' QUADRANGLE Proter COUNTY Buchangu DISTRICT Prater SCALE  $L^* = 400'$  DATE g-04-2012. This Plat is a new plat ...; an updated plat ...; or a final location plat  $\times$  ... Denotes the location of a well on United States topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown.

Licensed Professional Engineer or Licensed Land Surveyor

Coal Seams V-900109

			MIN	ING IN AR	EA
TOP	BOTTOM	THICKNES	YES N	O   V	INED OUT
98	99	1	N	0 I	10
320	321	1	N	0 N	10
470	471	1	N	۱ ٥	10
513	514	1	N	0 1	10
857	858	1	N	0 0	10
898	899	1	N	0 1	10
980	981	1	N	0 1	10
1120	1121	1	N	0 1	10
1305	1306	1	N	0 1	10
1585	1586	1	N	0 1	10
1800	1801	1	N	0 1	10
	98 320 470 513 857 898 980 1120 1305	98 99 320 321 470 471 513 514 857 858 898 899 980 981 1120 1121 1305 1306 1585 1586	98 99 1 320 321 1 470 471 1 513 514 1 857 858 1 898 899 1 980 981 1 1120 1121 1 1305 1306 1 1585 1586 1	TOP         BOTTOM THICKNES YES         N           98         99         1         N           320         321         1         N           470         471         1         N           513         514         1         N           857         858         1         N           898         899         1         N           980         981         1         N           1120         1121         1         N           1305         1306         1         N           1585         1586         1         N	98 99 1 NO

## Gas and Oil Shows

FORMATION	DEPTH	THICKNESS IPF (MCFD/BOPD)	DRESSURE	HOURS TESTED
FORMATION	DEFIII	THICKNESS III (MCI DIDOI D)	1 KLOOOKL	NIOOKO ILOILD
Ravencliff	3385	NS		
Maxton	3764	odor		
Big Lime	4302	odor		
Cleveland	5029	84 MCFD		
Cleveland	5093	103 MCFD		

Survey Results

Depth of Survey	Direction/Distance/Degree From True Vertical
195	1/4°
380	1⁄4°
564	½°
752	3/4°
939	1/2°
1128	1/2°
1314	1/4°
1503	1/2°
1691	3/4°
1881	1/2°
2005	1/2°
2191	1/2°
2380	3/4°

Casing Program

Casing		Casing	Casing	Casing	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date	Packers Or Bridge Plugs	Cement Baskets
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented	Kind/Size/Set	(ft)				
Conductor	13%	0-41'	15"									
Water Protection	9%"	0-345	121/4"	270	Yes, grouted to surface	09/04/12		126'				
Coal Protection	7"	0-2387'	81/8"	575	Yes	09/06/12		301'				
Production Casing	41/2"	0-5093'	6¼"	408	No	09/09/12		4066' 4722'				
Other Casing And												
Tubing Left In Well	23/4"	0-4966'										
Liners												

Driller's Log V-900109

Driller's Log		General		Depth	Depth	
Geologic Age	Formation		Color	Тор	Bottom	Thickness
		OVERBURDEN		0	3	3
PENNSYLVANIAN		SANDSTONE		3	98	95
PENNSYLVANIAN		COAL		98	99	1
PENNSYLVANIAN		SANDSTONE		99	320	221
PENNSYLVANIAN		COAL		320	321	1
PENNSYLVANIAN		SANDY SHALE		321	470	149
PENNSYLVANIAN		COAL		470	471	1
PENNSYLVANIAN		SANDSTONE		471	513	42
PENNSYLVANIAN		COAL		513	514	1
PENNSYLVANIAN		SANDY SHALE		514	857	343
PENNSYLVANIAN		COAL		857	858	1
PENNSYLVANIAN		SANDY SHALE		858	898	40
PENNSYLVANIAN		COAL		898	899	1
PENNSYLVANIAN		SANDY SHALE		899	980	81
PENNSYLVANIAN		COAL		980	981	1
PENNSYLVANIAN		SANDY SHALE		981	1120	139
PENNSYLVANIAN		COAL		1120	1121	1
PENNSYLVANIAN		SANDY SHALE		1121	1305	184
PENNSYLVANIAN		COAL		1305	1306	1
PENNSYLVANIAN		SANDSTONE		1306	1585	279
PENNSYLVANIAN		COAL		1585	1586	1
PENNSYLVANIAN		SANDY SHALE		1586	1800	214
PENNSYLVANIAN		COAL		1800	1801	1
PENNSYLVANIAN		SANDSTONE		1801	2150	349
PENNSYLVANIAN		SANDY SHALE		2150	2300	150
MISSISSIPPIAN		SANDSTONE		2300	2750	450
MISSISSIPPIAN	RAVENCLIFF	SANDSTONE		2750	3380	630
MISSISSIPPIAN	MAXTON	SANDSTONE/SHA	LE	3380	3740	360
MISSISSIPPIAN	LITTLE LIME/BIG	LIFLIMESTONE		3740	4290	550
MISSISSIPPIAN	WEIR	SILTSTONE		4290	4535	245
MISSISSIPPIAN	WEIR SHALE	SHALE		4535		
MISSISSIPPIAN	SUNBURY	SHALE		4920	4970	50
MISSISSIPPIAN	BEREA	SANDSTONE		4970		
DEVONIAN	CLEVELAND	SHALE		5014		
· · · · · · · ·						

Remarks



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

	Track	ing Number:	3532	
	Comp	any:	Range Res	ources-Pine Mountai
	File N	umber:	BU-4949	
	Comp	letion Report Type:	Original	
	COMPLETIO	N REPORT (DGO-	·GO-15)	
Well Ty	oe: Gas	Date Well C	Completed:	9/17/2012
Driller's Total Dep	th: 5156.00	Log's To	otal Depth: _	5162.00
Desc	cription		FileNam	е
Changes In Casing/T	ubing from Approv	red Drilling Report		
				-
Stimulation Record				
Stimulation Status: [	☑Stimulated ☐G	OB    Not Stimulated	d	Well
Desc	cription		FileNam	e
	stimulation	9	00109 stimul	ation.rtf
900109	ournalation			
	- Turking the state of the stat	L		
Final Production	cription		FileNam	е
Final Production				

Notes:

5. Signature

Ву:

Permittee: Range Resources-Pine

Date: 11/7/2012 (Company)

Mountain

Jonathan Horne

Title:

Engineering Tech (Signature)

INTERNAL USE ONLY

Submit Date:

11/7/2012

Status:

Approved

Date:

11/7/2012

Final PDF Date:

11/16/2012

# Range Resources - Pine Mountain Completion Report

105010393 1 900109

age 1	
Stage Date	9/17/2012
Perf Date	9/17/2012
Logging Co.	Gray Wireline
Formation	Berea
Top Perf	4963
Bottom Perf	4976
#Shots	27
Perf Size	0.52
Perf Comments	

Service Co	Superior	Avg DH Rate	34	
Fluid Type	75Q Foam	Max DH Rate	35.5	
BD	555	Total Slurry Volume	135	BBLs
ISIP	0	Total Fluid Volume	111	BBLs
Avg Press	1810	Avg N2 Rate	16,100	
Max Treat Pressure	1895	Max N2 Rate	16,300	scfm
Final ISIP	1880	Total N2 Volume	269,000	scf
2 Min SIP	0	Max DH PPA	3	
5 Min SIP	0	Total Proppant Sks	241	sks
10 Min SIP	0	Total Acid	0	Gal
Sand Mesh:	20/40 OttawaWhite	Acid Type		
Frac Gradient:	0.5			

Stage 2	
Stage Date	9/17/2012
Perf Date	9/17/2012
Logging Co.	Gray Wireline
Formation	Big Lime
Top Perf	4260
Bottom Perf	4273
#Shots	27
Perf Size	0.42
Perf Comments	

Service Co Fluid Type	Superior 60Q Foam	Avg DH Rate Max DH Rate	22 23	
BD	3304	Total Slurry Volume	295	BBLs
ISIP	0	Total Fluid Volume	295	BBLs
Avg Press	3059	Avg N2 Rate	14,300	
Max Treat Pressure	3172	Max N2 Rate	15,300	scfm
Final ISIP	470	Total N2 Volume	375,000	scf
2 Min SIP	0	Max DH PPA	0	
5 Min SIP	0	Total Proppant Sks	0	sks
10 Min SIP	0	Total Acid	4500	Gal
Sand Mesh:	n/a	Acid Type	15% HCL	
Frac Gradient:	0.6			

Baffle	Depth -	- 4295'
--------	---------	---------

Stage 3	
Stage Date	9/17/2012
Perf Date	9/17/2012
Logging Co.	Gray Wireline
Formation	Big Lime
Top Perf	3943
Bottom Perf	4117
#Shots	28
Perf Size	0.42
Perf Comments	

Service Co	Superior	Avg DH Rate	14	
Fluid Type	60Q Foam	Max DH Rate	15.5	
BD	Feed @ 600	Total Slurry Volume	153	BBLs
ISIP	0	Total Fluid Volume	153	BBLs
Avg Press	3280	Avg N2 Rate	10,000	
Max Treat Pressure	3356	Max N2 Rate	10,300	scfm
Final ISIP	1217	Total N2 Volume	132,000	scf
2 Min SIP	0	Max DH PPA	0	
5 Min SIP	0	Total Proppant Sks	0	sks
10 Min SIP	0	Total Acid	2020	Gal
Sand Mesh:	n/a	Acid Type	15% HCL	
Frac Gradient:	0.7	<b>5.</b>		

Baffle Depth - 4197'

### Range Resources - Pine Mountain Completion Report

Stage	4
Otage	-

**Stage Date** 9/17/2012 Perf Date 9/17/2012 Gray Wireline Logging Co. Formation Maxton Top Perf 3510 **Bottom Perf** 3521 #Shots 45 Perf Size 0.52 Perf Comments

Service Co Superior 75Q Foam Fluid Type BD 682 ISIP 0 2108 Avg Press Max Treat Pressure 2168 Final ISIP 1025 2 Min SIP 0 5 Min SIP 0 10 Min SIP Sand Mesh: 20/40 OttawaWhite

Frac Gradient:

Avg DH Rate 34 Max DH Rate 35 Total Slurry Volume 216 **BBLs** Total Fluid Volume 186 **BBLs** Avg N2 Rate 16,800 Max N2 Rate 17,300 scfm Total N2 Volume 269,000 scf Max DH PPA Total Proppant Sks 315 sks Total Acid 750 Gal 15% HCL Acid Type

Baffle Depth - 3541'

0.7

Stage 5

9/17/2012 Stage Date Perf Date 9/17/2012 Logging Co. Gray Wireline Formation Ravencliff Top Perf 2892 Bottom Perf 2929 #Shots 104 Perf Size 0.39 Perf Comments

Service Co Superior Fluid Type 75Q Foam BD 831 ISIP 0 2331 Avg Press Max Treat Pressure 2371 Final ISIP 1977 2 Min SIP 1870 5 Min SIP 1778 10 Min SIP Sand Mesh: 20/40 OttawaWhite


Frac Gradient: 0.6 Avg DH Rate 33 Max DH Rate 34.5 Total Slurry Volume 245 **BBLs** Total Fluid Volume **BBLs** 197 Avg N2 Rate 18,900 Max N2 Rate 19,400 scfm Total N2 Volume 421,000 scf Max DH PPA 3.5 Total Proppant Sks 502 sks 750 Total Acid Gal 15% HCL Acid Type

Baffle Depth - 2950'

Summary Total for All

Number Total Total Fluid Total N2 Total Total Acid of Stages Slurry Volume Volume Proppant 5 1044 942 1.466,000 1058 8020

Final Production After Stimula	tion			
	BOD	MCFD	Hours Tested	Rock Pressure
Final/Commingled Zones		802	3	280



Licensed Land Surveyor (Affix Seal)

No. 002066 6-28-99



Commonwealth of Virginia
Department of Mines, Minerals and Energy
Division of Gas and Oil
P.O. Box 1416
Abingdon, VA 24212

Telephone: (540) 676-5423

Operations Name CNR - 23606
Permit Number 4190
COMPLETION REPORT
WELL TYPE: OIL Gas X Coalbed Methane Injection
Date Well Completed 08/23/99 Total Depth 6048 LTD
Attach the Drilling Report, if not previously submitted. In addition, submit any changes in casing or tubing that were approved after the Drilling Report was submitted.
STIMULATION RECORD*  * Use additional sheets with this format, if more than three zones are stimulated
ZONE 1: Devonian Shale Formation Stimulated With 250 gal. 15% HCL & 1,000,000 scf N2
Perforated 6023 To 5864 No. of Perforations 18 Perforation Size .35
Formation Broke Down At: 3510 PSIG Average Injection Rate 60,000 scf/min
ISIP 2672 (PSIG) 5 MIN. SIP 2252 (PSIG) Average Downhole Injection Pressure 3319 (PSIG).
Stimulated X Yes No Date Stimulated 08/17/99
ZONE 2: Cleveland/Berca Formation Stimulated With 250 gal. 15% HCL & 1,300,000 scf N2
Perforated 5235 To 4934 No. of Perforations 28 Perforation Size .35
Formation Broke Down At: 2975 PSIG Average Injection Rate 09,917 scoring
ISIP 2083 (PSIG) 5 MIN. SIP 2031 (PSIG) Average Downhole Injection Pressure 3561 (PSIG).
Stimulated X Yes No Date Stimulated 08/17/99
ZONE 3: Formation Stimulated With
Perforated To No. of Perforations Perforation Size
Formation Broke Down At: PSIG Average Injection Rate
ISIP (PSIG) MIN. SIP (PSIG) Average Downhole Injection Pressure (PSIG).
Stimulated Yes No Date Stimulated
FINAL PRODUCTIONNaturalX_ After Stimulation
The stimulation method used did not allow for testing of separate zones.  BOD MCFD HOURS TESTED ROCK PRESSURE TESTED
ZONE (1)
ZONE (2)
ZONE (3)
Final production if gas zones are comingled 297 MCFD 72 Hours Tested 850 PSIG 72 Hours Tested
Permittee Columbia NATURAL RESOURCES (Company)
By (Signature)
Date 9-30-99

Form DGO-GO-15 Rev. 10/96

Crerations Name: CNR-21617

Permit # 3917

Department of Mines, Minerals and Energy
Division of Gas and Oil
P. O. Box 1416
Abingdon, Virginia 24210
703/676-5423

### DRILLING REPORT

Pursuant to VR-480-05-22.1, Section 1.36, the undersigned Permittee submits this report on <u>Well 21617</u> in the <u>Prater</u> District of the <u>Buchanan</u> City/County, Virginia on the <u>4th</u> day of December, 1998.

LO	CA	ΤI	O.	N

City/County: Buchanan

District: Prater

Surface Elevation: 1983.94 Elevation of Kelly Bushing: 1993.94 Quadrangle: Prater

_3496 Ft. S. of	Latitude 37 d	leg 12' 30" and _	1359 Ft. W. o	of Longitude 82 de	eg 12' 30"		
or, State Plans Co	ordinates: N-3	336,337 and E-918,81	19.	<u> </u>			
Attach a final loc	ation plat as re	quired by VR 480-05	-22.1, Section 1.36.				
DRILLING DAT	<u>'A</u>						
	mpleted: <u>09/1</u>	02/98 Drilling 6/98 Rig Type: _			ny Rig		
GEOLOGICAL I	<u>DATA</u>					at E	
Fresh Water at:	1170 Feet	2 GPM	Feet	GPM		DEC	17 208
Salt Water at: <u>n</u>	Feet	GPM GPM GPM	Feet	GPM	k <sub>ara-</sub>	er seen and an erect of the seen and the see	to Maria Linguis
COAL SEAMS:				MINI	NG IN ARI	EA_	
NAME:	<u>TOP</u>	BOTTOM	_			MINED O	<u>UT</u>
Unknown Unknown	900' 1158'	. 903' 1162'	3' 4'		X X	X X	
CHRIOWII	1136	1102					
GAS AND OIL S	SHOWS:						
FORMATION	TOP	BOTTOM		IPF (MCFD/BOPD			HOURS TESTED
Maxon Berea	2866' 4906'	3269' 4964'	403' 58'	133 297	•	<u>//A</u> //A	N/A . N/A
Dolou	7700	1704	30	M. / 1			17/11

Department of Mines, Minerals and Energy Division of Gas and Oil							erations Name: CNR-21617 mit # 3917
Cuttings or sampl Cuttings or sampl							vision of Mineral Resources esources
ELECTRIC LOG	S AND S	URVEYS:					
List logs ran on w	vellbore;	GR, TEMI	P, AUDIO, THI	REE DETECTO	OR DENSITY, C	N & AI.	
Did log disclose v	vertical lo	cation of a c	oal seam? Y	es X N	IoN/A	·	
SURVEY RESUI DEPTH OF SURVEY			DISTANCE/DI RUE VERTICA		DEPTH OF SURVEY		CTION/DISTANCE/DEGREES ROM TRUE VERTICAL
200 400 600 800 902 1100 *Use additional	sheets if r	1/2_DE 1/2_DE 3/4_DE 3/4_DE 3/4_DE necessary.	GREE GREE GREE GREE	  	1300 1500 1700 1900 2100		3/4 DEGREE 1/4 DEGREE 1/2 DEGREE 1/2 DEGREE 3/4 DEGREE
				CASING ANI	<u>TUBING</u>		
	SIZE	TOP	<u>ВОТТОМ</u>	<u>LENGTH</u>	CEMENT USE IN CU/FT	D DATE CEMENTED	PACKERS OR BRIDGE PI KIND SIZE SET
Conductor	13 3/8"	Surface	35'	35'			
Surface	9 5/8"	Surface	529'	529'	201 cu.ft.	09/03/98	
Water Protection							
Coal Protection	7"	Surface	2425'	2425'	455 cu.ft.	09/10/98	
Other Casing and Tubing Left	4 ½" in Well	Surface	6072'	6072'	183 cu.ft.	09/16/98	
<u>Liners</u>							
REMARKS: Shi	ut down,	fishing jobs	, depths and da	tes, caving, los	circulation, etc.		

Permit # 3917

### DRILLER'S LOG


## Compiled by Geologist

GEOLOGICAL		GENERAL			DEPTH		
<u>AGE</u>	<b>FORMATION</b>	<u>LITHOLOGY</u>	<b>COLOR</b>	TOP	BOTTOM	<b>THICKNESS</b>	<u>REMARKS</u>
PENNSYLVANIAN	Lee	Siltstone & Shale		0	1376	1376	
	Salt Sand	Sandstone		1376	1504	128	
	Lee	Siltstone & Shale		1504	1918	414	
	Salt Sand	Sandstone		1918	2167	249	
MISSISSIPPIAN	Bluefield	Siltstone & Shale		2167	2866	699	
	Maxon	Sandstone		2866	2946	80	
	Bluefield	Siltstone & Shale		2946	3180	234	
	Maxon	Sandstone		3180	3269	89	
	Bluefield	Siltstone & Shale		3269	3888	619	
	Little Lime	Argillaceous Lime		3888	3998	110	
	Big Lime	Limestone		3998	4252	254	
	Weir	Siltstone		4252	4454	202	
	Pocono	Shale		4454	4852	398	
	Sunbury	Shale		4852	4906	54	
	Berea	Sandstone		4906	4964	58	
BENOMAN	Danasia	Gl1.		4064	6770	904	
DEVONIAN	Devonian	Shale		4964	5770	806	
	Lower Huron	Shale		5770	5976	206	
	Java	Shale		5976	6102 (TD)	126	

Permittee: Columbia Natural Resources (Company)

By: Joson E. Sticklam (Signature)





WELL LOCATION PLAT

COMPANY Columbia	Natural Resources, Inc.	well name and numbi	ER21	1617	
TRACT NO. W. C. Owens	ELEVATION1983.	.94 QUADRANGLE _Pro	ter		
COUNTY Buchanan	DISTRICT Proter	SCALE _1" == 400'	DATE _09	-07-98	
This Plat is a new plat	; an updated plat; on of a well on United State and longitude lines being represented the control of the contro	or a final location plat		X	PPFE A
. Denotes the location	on of a well on United State	s topographic Maps, scale	1 to	MEAD	11 05
<sup>+</sup> 24,000, latitude ar	id longitude lines being repre	esented by border lines as	shown.	10°	. ز ر
• • • • • • • • • • • • • • • • • • • •	(1 00 0	/ l		* Z/Wlul	Vem
	iorea Mull	ens		₹3 GRÉGORY LE	E MULLI

Range Resources - Pine Mountain, Inc. certifies that, to the best of its knowledge, information and belief, the original plat by Greg Mullins is correct and accurate "as-drilled" but for the change of operator name. Range Resources - Pine Mountain, Inc. is the new operator of the asset and accepts and assumes any and all



Commonwealth of Vi a Department of Mines, Minerals and Energy Division of Gas and Oil P.O. Box 1416; Abingdon, VA 24212 Telephone: (540) 676-5423

		Operations N Permit Numb	ame: Columbia N er: #3917	latural Resources V	Vell #21617
		COMPLI	ETION REPORT		_
Vell type:	Gas [	Coalbed Meth	ane 🔲 Injection	ı Well	
Date Well Completed:	1/1/02	,	Гotal Depth: <u>LTD</u>	– 6028' KB	
TIMULATION REC	ORD (Use addit	ional sheets with	this format, if more	than three zones a	re stimulated.)
CONE 1: Weir Sand Perforated 4356' Formation Broke down SIP 1304 (PSIG) 5 Stimulated: X Yes	to 4432 1 at: 2275 5 MIN SIP. 1		o. of Perforations _ PSIG Average Inje Average In	ection Rate: 30 jection Pressure	BPM
CONE 2:Big Lime Perforated 4227' nation Broke down NA (PSIG) 5 timulated: X Yes	MIN SIP. N	A (PSIG)	ation Stimulated Wo. of Perforations _ PSIG Average Inje Average Injed:	Perforation Rate: 15 ection Pressure	ion Size <u>0.38"</u> BPM 2070 (PSIG)
Vell was worked over and all plugs drilled out following completion of workover operations. Shale and berea roduction were maintained.  INAL PRODUCTION: Natural _X After Stimulation					
	BOD	MCFD	HOURS	ROCK	HOURS
ZONE 1, 2 0		377	TESTED 6	PRESSURE 650	TESTED 48
ermittee: Columbia y:	Natural Resour		(Company) (Signature) Date:	5/2/	/ oz

'orm DGO-GO-15 'ev. 1/98

Permit # 3807

Department of Mines, Minerals and Energy
Division of Gas and OilP. O. Box 1416
Abingdon, Virginia 24210
703/676-5423

#### DRILLING REPORT

Pursuant to VR-480-05-22.1, Section 1.36, the undersigned Permittee submits this report on Well 23309 in the Prater District of the Buchanan City/County, Virginia on the 4th day of December, 1998.

<u>LOCATION</u>						
Surface Elevation   Surface   Surfac	of Latitude <u>37</u>	vation of Kelly Bus	shing: <u>1953.83</u> Quae <u>3283</u> Ft. W ,588.	lrangle: <u>Prater</u> '. of Longitude <u>82 deg</u>	12' 30"	
Attach a final lo	ocation plat as re	quired by VR 480-	05-22.1, Section 1.36			
DRILLING DA	<u>TA</u>					
Date Drilling Co Date Drilling Co Fotal Depth of V	ompleted: <u>08//</u> Well: <u>6054'</u>	<u>/07/98</u> Drill 21/98 Rig Type	ing Contractor: <u>S W</u> :X Rotary	Jack Drilling Company Cable Tool	<sup>7</sup> Rig	
GEOLOGICAL	,DATA					
Fresh Water at:	Feet	GPM	FeetFeetFeetFeetFeetFeet	GPM GPM GPM		
Salt Water at:	1420 Feet 1832 Feet Feet	3 GPM 	Feet Feet Feet	GPM GPM GPM		
COAL SEAMS: NAME: Unknown Unknown		<u>BOTTC</u> 1108	<u>)M                                    </u>	SS YES NO	G IN AREA MINED	·
CHRIIOWII	1277	1303	4	X	X	
GAS AND OIL FORMATION Maxon	<u>TOP</u>	BOTTOM 3211'	THICKNESS 345'	IPF (MCFD/BOPD) 503	PRESSURE 672#	HOURS TESTED
THUAUII	2000	117د	J4J	303	0/2#	96 hr .

Department of Mines, Minerals and Energy Division of Gas and Oil							rations Name: Ci	NR-23309
Cuttings or sample Cuttings or sample								Resources
ELECTRIC LOGS	s and s	URVEYS:						
List logs ran on w	ellbore:	Photo Der	isity, Digital Dua	l Induction, E	pithermal Neutro	n, TEMP		
Did log disclose v	ertical lo	cation of a	coal seam? Ye	s <u>X</u> N	lo N/A	<u> </u>		<u></u>
SURVEY RESUL DEPTH OF SURVEY			DISTANCE/DE		DEPTH OF SURVEY		TION/DISTANC ROM TRUE VER	
200 400 600 800 1000 1100 *Use additional s	sheets if 1	3/4_DE 3/4_DE	GREE GREE EGREE GREE	-	1300 1600 1800 2040 2300	  	3/4 DEGREE 3/4 DEGREE 1/4 DEGREE 1 DEGREE 1-1/4 DEGREE 1-1/2 DEGREE	
			9	CASING ANI	TUBING			
	SIZE	<u>TOP</u>	воттом	LENGTH	CEMENT USE IN CU/FT	D DATE 1 CEMENTED	PACKERS OR BI KIND SIZE	
Conductor	13 3/8"	Surface	45'KB	35*				
Surface	9 5/8"	Surface	351'KB	341'	153 cu.ft.	08/09/98		
Water Protection	7"	Surface	2266'KB	2256'	425 cu.ft.	08/12/98		
Coal Protection								
Other Casing and Tubing Left in	4 ½" n Well	Surface	6016'KB	6006'	184 cu.ft.	08/20/98		
<u>Liners</u>								
REMARKS: Shu N/A	t down,	fishing jobs	, depths and date	s, caving, lost	circulation, etc.			

Permit # 3807


### DRILLER'S LOG

## Compiled by Geologist

GEOLOGICAL	•	GENERAL		Γ	DEPTH		
<u>AGE</u>	<b>FORMATION</b>	LITHOLOGY	<b>COLOR</b>	TOP	BOTTOM	<b>THICKNESS</b>	<u>REMARKS</u>
PENNSYLVANIAN	Lee	Siltstone & Shale		0	1350	1350	
	Salt Sand	Sandstone		1350	1493	143	
	Lee	Siltstone & Shale		1493	2058	565	
	Salt Sand	Sandstone		2058	2148	90	
MISSISSIPPIAN	Bluestone	Siltstone & Shale		2148	2866	718	
	Maxon	Sandstone		2866	2908	42	
	Bluefield	Siltstone & Shale		2908	3185	277	
	Maxon	Sandstone		3185	3211	26	
	Bluefield	Siltstone & Shale		3211	3716	505	
	Little Lime	Limestone		3716	3820	104	
	Big Lime	Limestone		3820	4260	440	
	Pocono	Shale		4260	4346	86	
	Weir	Siltstone		4346	4458	112	
	Pocono	Shale		4458	4882	424	
	Sunbury	Shale		4882	4904	22	
	Berea	Sandstone		4904	4953	49	
DEVONIAN	Cleveland	Shale		4953	4977	24	
DE COMMIT	Cit, Ciana	Shale		4977	5754	777	
	Lower Huron	Shale		5754	5954	200	
	Java	Shale		5954	TD		

Permittee: Columbia Natural Resources (Company)

By: June Signature)



COMPANYCol	umbia Natural Resources, inc.	WELL NAME AND NUMBE	R23309
TRACT NO. B. F. DO	ELEVATION 194	3.83 QUADRANGLE Prat	er
COUNTY Buchanan	DISTRICT Prater	SCALE <u>1" = 400'</u>	DATE <u>08-31-98</u>
This Plat is a new	plat; an updated plat	.; or a final location plat $oxdot$	X ************************************
_ Denotes the	location of a well on United Sta	tes topographic Maps, scale	1 to ***********************************
<sup>™</sup> 24,000, latitu	plat; an updated plat location of a well on United Sta de and longitude lines being rep	gesented by border lines as	shown.
	(// ///		GREGORY LEE MU
	Strea /	allens	<b>∄</b> ○ GREGORY LEE MU
	Licensed Land	Surveyor	No. 002068

Permit # 3807

Department of Mines, Minerals and Energy
Division of Gas and Oil
P. O. Box 1416
Abingdon, Virginia 24210
703/676-5423

## COMPLETION REPORT

WELL TYPE: Oil Gas _X_ Coalbed				
Date Well Completed: 10/10/98 To	tal Depth of Well:	6054 (LTD)	-1/2 3225	·
Attach the Drilling Report, if not previously After the Drilling Report was submitted.	submitted. In addition	n, submit any changes	in casing or tubing that we	ere appr.
STIMULATION RECORD Zone 1: Devonian Shale	Formation Stir	mulated With: 250	gal 7 ½% HC1 1,207,60	0 SCF of Nitrogen
Perforated:         5760         to         5945           Formation Broke down at:         3081         PSISITED           ISIP         2477         PSIG         5         MISITED           Date Stimulated:         09/01/98         .	SIG Average Inject	ion Rate:72,3	325 SCF/M	BPM PSIG
Zone 2: Berea  Fluid, 44,000 lbs 20/40 sand  Perforated: 4910' to 4920'  Formation Broke Down at: 2005  ISIP 1347 PSIG 5 MIN S  Date stimulated: 10/05/98	No. of Perforations _PSIG Average I	s: <u>14</u> Perforation	on Size: 0.44" BPM Foam Rate	BPM
Zone 3:N/A	Formation Stim	ulated With:		
Perforated: to N	o. of Perforations:		Perforation Size:	
Formation Broke Down at:	PSIG	Average Injection Rat	e:	BPM
ISIP PSIG MIN	SIP	PSIG Aver	age Injection Pressure:	PSIG
Date stimulated:	•			
FINAL PRODUCTION: Natural BOD		ion HOURS TESTED	ROCK PRESSURE	HOURS TESTEI
BOD	MCFD	HOURS TESTED 72	750	96
BOD Zone (1) Devonian Shale	MCFD 146	HOURS TESTED 72	750 585	96 72
Zone (1) Devonian Shale  Zone (2) Berea  Zone (3) Maxon **	MCFD 146 222 503	HOURS TESTED  72  48  6	750 585 672	96 72 96
Zone (1) Devonian Shale Zone (2) Berea Zone (3) Maxon ** Final Production if Gas Zones are Comingle	MCFD 146 222 503 ed 368 MCFD	HOURS TESTED  72  48  6  48  Hours Tester	750 585 672 d 585 PSIG 72	96 72 96
Zone (1) Devonian Shale Zone (2) Berea	MCFD 146 222 503 ed 368 MCFD n annulus. Not inclu	HOURS TESTED  72  48  6  48  Hours Testered in final comingle	750 585 672 d 585 PSIG 72	96 72 96

By: Joson C. Stidham

Form DGO-GO-15 Rev. 9/91



Commonwealth of Virginia
Department of Mines, Minerals and Energy
Division of Gas and Oil
P.O. Box 1416
Abingdon, VA 24212
Telephone: (540) 676-5423

Operations Name	CNR -	23310
Permit Number	4209	

				DR	ILLING RE	PORT			
ATTACH A FINAL	LOCATIO	)N P	LAT AS REQ	UIRED B	Y 4 VAC 25	·150-360.C.			
DRILLING DATA									
Date drilling com Drilling Contract Date drilling com Total Depth of W	tor <u>S.W.</u> ipleted	<u>J</u>	ack Dril /24/99	ling (	Co. Rig Type	Rotary	X Cat	ole Tool	
GEOLOGICAL DA	<u>TA</u>								
Fresh water at	80	Feet	Damp	GPM/Inc	h Stream		Feet		GPM/Inch Stream
			Damp						GPM/Inch Stream
Salt water at									GPM/Inch Stream
							Feet		_ GPM/Inch Stream
Coal Seams									
NAME	3	ОР	вотт	<u>rom</u>	THICKNE		NG IN AREA NO		DUT
Unknown	5	L 5	51	8	3			N/A	
Gas and Oil Shows									
FORMATIO	<u>N</u> <u>T</u>	<u>OP</u>	вотто	M TH	<u>ICKNESS</u>	<u>IPF</u> (MCFD/BOP	_	RESSURE	HOURS TESTED
Maxon Berea		390 920			65 45	241 286		N/A N/A	N/A N/A
Cuttings or samples Cuttings or samples ELECTRIC LOGS List logs ran on we Did logs disclose ver	AND SURY Three	have VEY:	enotXbeen Setector ., array	densi indci	ed to the Virgity, constitution, constitutio	ginia Division o npensated caliper	f Mineral Res	sources	ray,

Operations Name	CNR - 23310
Permit Number	4209

## SURVEY RESULTS

DEPTH OF SURVEY	DIRECTION/DISTANCE/ DEGREES FROM TRUE VERTICAL	DEPTH OF SURVEY	DIRECTION/DISTANCE DEGREES FROM TRUE VERTICAL
200'	1/2°	1340'	1 °
400'	1/2°	1550'	1°
518'	1/4°	1750'	1 1/2°
718'	1/4°	1950'	1 1/2°
920'	1/2°	2150'	1 1/2°
1140'	3/4°		,

Use additional sheets as necessary

## CASING AND TUBING PROGRAM

CONDUCTOR	CASING 13-3/8"	CASING INTERVAL 25 <sup>†</sup>	HOLE SIZE 17"	CEMENT USED IN CU/FT Surface	CEMENTED TO SURFACE YES NO Yes	DATE CEMENTED 6/15/99	PACKERS OR BRIDGE PLUGS KIND/SIZE/SET N/A
SURFACE	9-5/8"	400'	12-1/4"	153	Yes	6/16/99	N/A
WATER PROTECTION	7"	2337'	8-3/4"	457	Yes	6/20/99	N/A
COAL PROTECTION	4-1/2"	6046'	6-1/4"	247	No	6/25/99	N/A

OTHER CASING AND TUBING LEFT IN WELL

LINERS

REMARKS: Shut do	own, fishing jobs, depths and da	ites, caving, lost circulation, etc.	
			4

Operations Name:
Permit#

Pine Mt. #23310 45-027-24209

DRILLER'S LOG

Compiled by	Ed Rothman		<del></del>				
GEOLOGIC		GENERAL		DEPTH			
AGE	FORMATION	LITHOLGY	TOP		воттом	THICKNESS	REMARKS
	Lee	siltstone & shale	0		316	316	
	Lee	sandstone	316		383	67	
Р	Lee	siltstone & shale	383		1346	963	
E	Salt Sand (Lee)	sandstone	1346		1498	152	
N	Lee	siltstone & shale	1498		1876	378	
N	Salt Sand (Lee)	sandstone	1876		1924	48	
	Lee	siltstone & shale	1924		2050	126	
	Salt Sand (Lee)	sandstone	2050		2164	114	
	Pennington	siltstone & shale	2164		2870	706	
	Maxon	sandstone	2870		2904	34	
	Pennington	siltstone & shale	2904		3396	492	
	Maxon	sandstone	3396		3434	38	
	Pennington	siltstone & shale	3434		3674	240	
M	Little Lime	limestone	3674		3742	68	
1	Big Lime	limestone	3742		4264	522	
S	Pocono	shale	4264		4354	90	
S	Weir	siltstone	4354		4463	109	
	Pocono	shale	4463		4894	431	
	Sunbury	shale	4894		4916	22	
	Berea	sandstone	4916		4972	56	
	Cleveland	siltstone	4972		4996	24	
D	Devonian Shale	shale	4996		5760	764	
E	Lower Huron	shale	5760		5982	222	
V	Java	shale	5982		6093	111	

Permittee: Columbia Natural Resources, Inc.


(Company)

В١

graner

LTD

(Signature)



WELL LOCATION PLAT

COMPANY Range Resources-Pine Mountain, Inc. WELL NAME AND NUMBER 823310
TRACT NO Jerry Coleman et al. FLEVATION 2.023.38 OUADRANGLE PRAIER
COUNTY BUCHANAN DISTRICT PRATER SCALE 1" = 400' DATE 1-26-2011
This Piot is a new plot $\cdot$ an undated plot $\rightarrow$ or a final location plot $\xrightarrow{X}$
Denotes the location of a well on United States topographic Maps, scale 1 to
Denotes the location of a well on United States topographic Maps, scale 1 to 24,000, ratifude and longitude lines being represented by border lines as snown.
0 110

Licensed Professional Engineer on Juansed Land Surveyor

#### 823310 PLAT TRACT OWNERSHIP INFORMATION SCHEDULE 1/26/2011

Lease No.
 Jerry Coleman, et al - coal, oil & gas
 32.4 Acres
 Gas 20.88 Ac. 18.53%

Lease No. 906889 / T-105
 W.C. Owens
 115.81 Acres
 Range Resources-Pine Mountain, Inc. - oil & gas
 Gas 9.66 Ac. 8.57%

. Lease No.
W.C. Owens
377.12 Acres
ACIN LLC - coal
Alpha Land & Reserves LLC - coal lessee
WBRD LLC - coal
Dickenson-Russell Coal company LLC - coal lessee
Range Resources-Pine Mountain, Inc. - oil & gas
Gas 18.63 Ac. 16.53%

Lease No.
 S.M. Compton
 125.66 Acres
 ACIN LLC - coal
 Alpha Land & Reserves LLC - coal lessee
 WBRD LLC - coal
 Dickenson-Russell Coal company LLC - coal lessee
 Range Resources-Pine Mountain, Inc. - oil & gas
 Gas 16.45 Ac. 14.60%

5. Lease No.
S.M. Compton
111.88 Acres
ACIN LLC - coal
Alpha Land & Reserves LLC - coal lessee
WBRD LLC - coal
Paramount Coal Company - coal lessee
Range Resources-Pinc Mountain, Inc. - oil & gas
Gas 25.35 Ac. 22.50%

6. Lease No.
Jno. Raines
105.89 Acres
Range Resources-Pine Mountain, Inc. - oil & gas
Gas 17.28 Ac. 15.33%

7. Lease No.
Chesapeake Appalachia LLC - oil & gas
p/o 6 Acres
Gas 1.44 Ac. 1.28%

. Lease No.
B.E. Arrington
68.39 Acres
Range Resources-Pinc Mountain, Inc. - oil & gas
Gas 3.00 Ac. 2.66%



Commonwealth of Virginia
Department of Mines, Minerals and Energy
Division of Gas and Oil
P.O. Box 1416
Abingdon, VA 24212

Operations Name CNR - 23310
Permit Number 4209

Telephone: (540) 676-5423

#### COMPLETION REPORT WELL TYPE: OIL \_\_\_ Gas X Coalbed Methane \_\_\_ Injection \_\_\_ Date Well Completed 8/16/99 Total Depth 6093' LTD Attach the Drilling Report, if not previously submitted. In addition, submit any changes in casing or tubing that were approved after the Drilling Report was submitted. STIMULATION RECORD\* \* Use additional sheets with this format, if more than three zones are stimulated ZONE 1: Devonian Shale Formation Stimulated With 250 gal. 15% acid & 850,000 scf of N2 To 5834 No. of Perforations 14 Perforation Size .35 74 PSIG Average Injection Rate 46,871 scf/min 5 MIN. SIP 2208 (PSIG) Average Downhole Injection Pressure 3417 (PSIG). No Date Stimulated 8/10/99 Perforated 5958 Formation Broke Down At: 38<u>74</u> ISIP 2717 (PSIG) Stimulated X Yes Formation Stimulated With 250 gal. 15% acid & 1,400,000 ZONE 2: Berea ONE 2: scf of N2 4951 To 4921 No. of Perforations 16 Perforation Size .35 Average Injection Rate 55,370 scf/min \_\_ No. of Perforations \_\_\_ Perforated Formation Broke Down At: PSIG ISIP 2198 (PSIG) 5 MIN. SIP 1668 (PSIG) Average Downhole Injection Pressure 3571 Stimulated X Yes No Date Stimulated 8/10/99 (PSIG) Stimulated X Yes No ZONE 3:\_ \_\_\_\_\_ Formation Stimulated With \_ No. of Perforations Perforation Size **PSIG** Formation Broke Down At: Average Injection Rate \_ \_\_\_(PSIG) \_\_ MIN. SIP \_\_\_\_ \_(PSIG) Average Downhole Injection Pressure \_\_\_ Yes No Date Stimulated FINAL PRODUCTION \_\_\_\_Natural X After Stimulation Unable to test zones separately due to stimulation technique. BOD MCFD HOURS TESTED ROCK PRESSURE HOURS TESTED ZONE (1) ZONE (2) ZONE (3) Final production if gas zones are comingled 606 MCFD 48 Hours Tested 450 PSIG 96 Hours Tested Permittee Columbia Natural Resources (Company) (Signature) 10-29-99

Form DGO-GO-15 Rev. 10/96



Commonwealth of Virginia
Department of Mines, Minerals and Energy
Division of Gas and Oil
P.O. Box 1416
Abingdon, VA 24212

Telephone: (540) 676-5423

				ations Name <u>CN</u> nit Number <u>41</u>		
			DRILLING RE	EPORT		
ATTACH A FINAL LO	CATION PLA	T AS REQUIR	ED BY 4 VAC 25	5-150-360.C.		
DRILLING DATA						
Date drilling commen Drilling Contractor _ Date drilling complet Total Depth of Well _	S. W. Jack D ed 7/27/99	rilling Co.	Rig Type	X Rotary	_ Cable Tool	
GEOLOGICAL DATA						
Fresh water at975	Feet Da	ımp GPM	I/Inch Stream	F	eet	_ GPM/Inch Stream
	Feet	GPN	I/Inch Stream	F	eet	GPM/Inch Stream
Salt water at34	00 Feet D	amp GPM	1/Inch Stream	F	ect	GPM/Inch Stream
<del></del>	Feet	GPN	I/Inch Stream		Feet	GPM/Inch Stream
Coal Seams						
<u>NAME</u>	TOP	BOTTOM	THICKN)	ESS MINING I YES		<u>D OUT</u>
Hagy	335	337	2	No	Yes	
Gas and Oil Shows						
FORMATION	TOP	воттом	THICKNESS	<u>IPF</u> (MCFD/BOPD)	PRESSURE	HOURS TESTED
Big Lime Berea	4009 5006	4294 5040	285 36	60 mcl/d 43 mcl/d	N/A N/A	Unknown Unknown
Cuttings or samples 2	(_arear /ehave n	e not available ot <u>X</u> been 1	for examination l furnished to the V	by a member of the Virginia Division of N	Virginia Division of N Mineral Resources	Mineral Resources
ELECTRIC LOGS AND	D SURVEYS					
List logs ran on wellbor Did logs disclose vertica					o; array deduction; c	aliper

Operations Name	CNR-23605
Permit Number	4189

### SURVEY RESULTS

	DIRECTION/DISTANCE/ DEGREES FROM TRUE		DIRECTION/DISTANCE DEGREES FROM TRUE
DEPTH OF SURVEY	VERTICAL	DEPTH OF SURVEY	VERTICAL
200'	1/4 degree	1460'	¾ degree
460'	1/2 degree	1660'	¾ degree
660'	¾ degree	1860'	1 degree
860'	¾ degree	2060'	1 ¼ degree
1060'	1/2 degree	2480'	1 ¼ degree
1260'	⅓ degree		

### Use additional sheets as necessary

## CASING AND TUBING PROGRAM

CONDUCTOR	CASING 13-3/8"	CASING INTERVAL 45'	HOLE SIZE 17-1/2"	CEMENT USED IN CU/FT 24	CEMENTED TO SURFACE YES NO Yes	DATE CEMENTED 7-16-99	PACKERS OR BRIDGE PLUGS KIND/SIZE/SET N/A
SURFACE	9-5/8"	406'	12-1/4"	155	Yes	7-17-99	N/A
WATER PROTECTION	7"	2443'	8-3/4"	433	Yes	7-20-99	N/A
COAL PROTECTION	4-1/2"	6136'	6-1/4"	178	No	7-27-99	N/A
OTHER CASING AND TUBING LEFT IN WELL	N/A						
LINERS	N/A						
REMARKS: Shut down	, fishing jobs, dep	ths and dates, cav	ing, lost circulatio	n, etc.		**************************************	


Operations Name:	Pine Mt. #23605
Permit#	51-027-24189

### DRILLER'S LOG

Compiled by	Ed Rothman					
GEOLOGIC AGE	FORMATION	GENERAL LITHOLGY	тор	DEPTH BOTTOM	THICKNESS	REMARKS
Р	Lee	siltstone & shale	0	1362	1362	
E	Salt Sand (Lee)	sandstone	1362	1500	138	
N	Lee	siltstone & shale	1500	2054	554	
N	Salt Sand (Lee)	sandstone	2054	2204	150	
	Pennington	siltstone & shale	2204	2903	699	
	Maxon	sandstone	2903	2942	39	
	Pennington	siltstone & shale	2942	3234	292	
	Maxon	sandstone	3234	3262	28	
	Pennington	siltstone & shale	3262	3527	265	
M	Maxon	sandstone	3527	3566	39	
1	Pennington	siltstone & shale	3566	3900	334	
S	Little Lime	limestone	3900	4009	109	
S	Big Lime	limestone	4009	4294	285	
	Pocono	shale	4294	4462	168	
	Weir	siltstone	4462	4540	78	
	Pocono	shale	4540	4986	446	
	Sunbury	shale	4986	5006	20	
	Berea	sandstone	5006	5040	34	
	Cleveland	siltstone	5040	5054	14	
D	Devonian Shale	shale	5054	5840	786	
E	Lower Huron	shale	5840	6064	224	
V	Java	shale	6064	6176	112	
				LTD		

Permittee:	Columbia Natural Resources, Inc.	(Company)
Ву:	Jamo Alina	(Signature)
	3 of 3	

Form DGO-GO-14 Re 9/91



## WELL LOCATION PLAT

	: Columbia Natural I		WELL	NAME OR	NUMBER:	23605	BU-1613
TRACT NU	MBER: W. C. Ower	ış	QUADR.	ANGLE: Pr	ater		
DISTRICT:	Prater		•	-			
WELL COO	ORDINATES (VIRGI	NIA STATE PLAI	NE): N - 3	36,170 E-	922,697		
	N: 2,094.58	METHOD U				N:	
Trigonome	etric Leveling from De						
COUNTY:_	Buchanan	SCALE:	1" = 400"	DATE:	07-2	8-1999	
THIS PLAT	IS A NEW PLAT	; AN UPDATE	D PLAT	; OR A F	NAL LOCA	TION PL	AT X
		- <del></del>					
+-	Danielas da la catala de c	31. 11.5 10.4 7			4.000		_
1	Denotes the location of a valuatitude and longitude line	vell on United States 1 s being represented by	opographic M border lines a	laps, scale 1 to 2 s shown (ontion	4,000, ab	BALTH	Sagara.
	manual management into	s semigroprosented by	eorder mics a	a anown (opnon	a.).	<i>h</i> .	
					34	IM. O	93
	<del></del>	······································	Licensed Lor	d Surveyor (Af	Sur Sant C GR	GORY LEE MA	ILINS =
			Licensed Lap	ni burveyor (Ali	ix Seal)	No. 002066	
Porm DGO-GO-7						7-28-99	9 <b></b>
Rev. 1/98					* <	Wn	(O) 10 TO



Commonwealth of Virginia
Department of Mines, Minerals and Energy
Division of Gas and Oil
P.O. Box 1416
Abingdon, VA 24212

Telephone: (540) 676-5423

Operations Name CNR - 23605
Permit Number 4189

COMPLETION REPORT
WELL TYPE: OIL Gas X Coalbed Methane Injection
Date Weil Completed 8-23-99 Total Depth 6058/PBTD
Attach the Drilling Report, if not previously submitted. In addition, submit any changes in casing or tubing that were approved after the Drilling Report was submitted.
STIMULATION RECORD*  * Use additional sheets with this format, if more than three zones are stimulated
ZONE 1: Devonian Shale Formation Stimulated With 250 gal 15% HCl acid & 850,000 scf of N2
Perforated 5572 To 6060 No. of Perforations 18 Perforation Size .35 Formation Broke Down At: 4009 PSIG Average Injection Rate 30,000 scf/min ISIP 3296 (PSIG) 5 MIN. SIP 2493(PSIG) Average Downhole Injection Pressure 3565 (PSIG). Stimulated X Yes No Date Stimulated 8-16-99
ZONE 2: Berea Formation Stimulated With 250 gal 15% HCl & 1,400,000 of scf N2
Perforated 5026 To 5134 No. of Perforations 20 Perforation Size .35  Formation Broke Down At: 3051 PSIG Average Injection Rate 63,300 scf/min  ISIP 2150 (PSIG) 5 MIN. SIP 1966 (PSIG) Average Downhole Injection Pressure 3504 (PSIG)  Stimulated X Yes No Date Stimulated 08/16/99  ZONE 3: Formation Stimulated With
Perforated To No. of Perforations Perforation Size  Formation Broke Down At: PSIG Average Injection Rate  ISIP (PSIG) MIN. SIP (PSIG) Average Downhole Injection Pressure (PSIG).  Stimulated Yes No Date Stimulated
FINAL PRODUCTIONNatural _X After Stimulation
The stimulation method used did not allow for testing of separate zones.  BOD MCFD HOURS TESTED ROCK PRESSURE HOURS TESTED TESTEL
ZONE (1)
ZONE (2)
ZONE (3)
Final production if gas zones are comingled 350 MCFD 72 Hours Tested 815 PSIG 96 Hours Tested
Permittee Columbia Natural Resources, Inc. (Company)
By Miny & Rie (Signature)
Date 11-16 - 99

Form DGO-GO-15 Rev. 10/96



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

	Tracking Nu		lumber:	ımber: 2731	
	(	Company:		Range Res	ources-Pine Mountai
	ı	File Numbe	er:	BU-1613	
	(	Completio	n Report Type:	Drill Deepe	r Recompletion
	COMPLE	ETION RI	EPORT (DGO-	GO-15)	
Well Type	: Gas/P	Pipeline	Date Well C	Completed:	8/25/2010
Driller's Total Depth:		Log's To	otal Depth:		
Changes In Casing/Tul	oing from A	pproved D	rilling Report	FileNam	0
Changes In Casing/Tu		pproved D	rilling Report		
	oing from A	pproved D	rilling Report		
Changes In Casing/Tul Descri Cas	oing from A	pproved D	rilling Report	FileNam	
Changes In Casing/Tul Descri Cas Stimulation Record	oing from A	pproved D	rilling Report	FileNam Casing.x	ls
Changes In Casing/Tul Descri Cas Stimulation Record	ption ing Stimulated			FileNam Casing.x	e Well
Changes In Casing/Tul Descri Cas Stimulation Record	ption ing Stimulated		Not Stimulated	FileNam Casing.x d	e Well
Changes In Casing/Tul  Descri  Cas  Stimulation Record  Stimulation Status:	ption ing Stimulated		Not Stimulated	FileNam  Casing.x  d	e Well
Changes In Casing/Tul  Descri  Cas  Stimulation Record  Stimulation Status:	ption ing Stimulated ption		Not Stimulated	FileNam  Casing.x  d	e Well e Wiell ne ation.doc

Form DGO-GO-15-E

Page 1 of 2

Rev. 04/2009

5. Signature				
Permittee:	Range Resources-Pine Mountain	Date:	4/28/2011	(Company)
Ву:	Laura Murray	Title:	Permit Specialist	(Signature)

Date: 3/5/2012

Approved

3/6/2012

Status:

Final PDF Date:

Casing Program

Casing Program													
	Casing	Casing	Holes	Cement	Jsed! C	emented		🙀 Date	Pack	ers,Or,Bri	dge Plugs	Сеще	Date.   Packers Or Bridge Plugs   Cement Baskets
Casingatiype	Sizex	Intervale	Size	Historia	*Ft*	* Yes	HINTOUDICIFUL TO THE TRESINO	Cemente	P	Kind/Siz	e/Set		(年)
Conductor	13%"	0-45'	15"										
Water Protection	.,%6	0-406'	121/4"			•							
Coal Protection	1	0-2443'  87/8"	87/8"										
Production Casing 41/2"	41/2"	0-6126' 61/4"	614"	25	250 ft³		No	08/17/10				_	
Other Casing And													
Tubing Left In Well 23%"	23/8"	0-6118											
Liners													



## STIMULATION RECORD

ZONE I: Big Lime	Formation Stimulated with: 00Q roam
Perforated 4042 to 4158 feet No. of	of Perforations 29 Perforation Size .52
Formation Broke down at: 2980 PSIG	Average Injection Rate: 24.5 BPM
ISIP 0 PSIG 2 Min SIP 0 PSIG A	verage Downhole Injection Pressure 3061 PSIG
Stimulated: Yes	: 8/25/2010
ZONE 2: Maxton	Formation Stimulated With: 75Q Foam
Perforated 3661 to 3675 feet No. 6	of Perforations 29 Perforation Size .42
Formation Broke down at: 2776 PSIG	Average Injection Rate: 36.5 BPM
ISIP 2144 PSIG 2 Min SIP 0 PSIG A	verage Downhole Injection Pressure 2482 PSIG
Stimulated:  Yes  No Date Stimulated	8/25/2010
ZONE 3: Ravencliff	Formation Stimulated With: 75Q Foam
Perforated 2905 to 2944 feet No. (	of Perforations 30 Perforation Size .42
Formation Broke down at: 2560 PSIG	Average Injection Rate: 38 BPM
ISIP 1761 PSIG 2 Min SIP 1719 PSIG A	verage Downhole Injection Pressure 2788 PSIG
Stimulated: Yes	: 8/25/2010

Final Production After Stimula	tion	Stricker.		s Mario das Jacobsonias i
Committee of the second committee of	BOD	MCFD	Hours Tested	Rock Pressure
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		N/A		



Commonwealth of Virginia
Department of Mines, Minerals and Energy
Division of Gas and Oil
P.O. Box 1416
Abingdon, VA 24212
Telephone: (540) 676-5423

Operations Name CNR Well # 24153 Permit Number 4602 DRILLING REPORT ATTACH A FINAL LOCATION PLAT AS REQUIRED BY 4 VAC 25-150-360.C. DRILLING DATA Date drilling commenced 6/17/2000 Date drilling completed 6/27/2000 Co. Rig #18 Rig Type X Rotary Cable Tool Total Depth of Well DTD: 5995 LTD: 5990 GEOLOGICAL DATA Fresh water at 80 Feet Damp GPM/Inch Stream 650 Feet Damp GPM/Inch Stream Feet \_\_\_\_ GPM/Inch Stream \_-\_ Feet \_\_ GPM/Inch Stream Salt water at Feet \_\_\_\_ GPM/Inch Stream \_\_\_\_ Feet \_\_\_\_\_ GPM/Inch Stream Feet \_\_\_\_ GPM/Inch Stream \_\_\_\_\_ Feet \_\_\_\_ GPM/Inch Stream Coal Seams NAME TOP BOTTOM THICKNESS MINING IN AREA MINED OUT YES NO Gas and Oil Shows FORMATION TOP BOTTOM THICKNESS IPF **PRESSURE** HOURS (MCFD/BOPD)\_ TESTED Ravencliff, Maxon 2350 4050 1700 853 700 192 , & Big Lime Cuttings or samples \_\_\_\_ are X\_ are not available for examination by a member of the Virginia Division of Mineral Cuttings or samples have \_\_\_\_ have not X\_ been furnished to the Virginia Division of Mineral Resources

Form DGO-GO-14 Rev. 10/96

List logs ran on wellbore

**ELECTRIC LOGS AND SURVEYS** 

Gamma Ray, Lithodensity, Compensated Neutron, Dual Induction, Audio, and Temperature

Did logs disclose vertical location of a coal seam? Yes No X

Operations Name	CNR Well #24153
Permit Number_	4602

### SURVEY RESULTS

DEPTH OF SURVEY 200 400 600 800	DIRECTION/DISTANCE/ DEGREES FROM TRUE VERTICAL ¼ Degree 1 Degree ¾ Degree ½ Degree	' DEPTH OF SURVEY 1200 1400 1600 1800	DIRECTION/DISTANCE DEGREES FROM TRUE VERTICAL % Degree % Degree % Degree 1 Degree
1000	% Degree	2000	1 Degree

Use additional sheets as necessary

### CASING AND TUBING PROGRAM

CONDUCTOR	CASING 13 3/8"	CASING INTERVAL 45' KB	HOLE SIZE - 17 ½"	CEMENT USED IN CU/FT N/A	CEMENTED TO SURFACE YES NO	DATE CEMENTED	PACKE BRIDGE KIND/SI
SURFACE	9 5/8"	317' KB	12 3/8"	142	Yes	6/18/2000	
WATER PROTECTION							
COAL PROTECTION	7"	2130' KB	8 1/4"	417	Yes	6/21/2000	
OTHER CASING AND TUBING LEFT IN WELL	4 ½"	5936' KB	6 ¼"	189	No	6/27/2000	
LINERS							

LINERS

REMARKS: Shut down, fishi	ng jobs, depths and dates	, caving, lost circulation	, etc.	
<del></del>				
	· · · · · · · · · · · · · · · · · · ·			

Form DGO-GO-14 Rev. 10/9

Operations Name _	CNR Well #24153	
Permit Number	4602	

## DRILLER'S LOG

Compiled by Jason Stidham

			•				
		GENERAL		D	EPTH		
GEOLOGIC AGE	FORMATION	LITHOLOGY	COLOR	TOP	BOTTOM	THICKNESS	REM
Penn	Lee	Shale & Siltstone		0	1258	1258	
Penn	Salt Sand (Lee)	Sandstone		1258	1396	138	
Penn	Lee	Shale & Siltstone		1396	1530	134	
Penn	Salt Sand (Lee)	Sandstone		1530	1574	44	
Penn	Lee	Shale & Siltstone		1574	1600	26	
Penn	Salt Sand (Lee)	Sandstone		1600	1640	40	
Penn	Lee	Shale & Siltstone		1640	1660	20	
Penn	Salt Sand (Lee)	Sandstone		1660	1720	60	
Penn	Lee	Shale & Siltstone		1720	1750	30	
Penn	Salt Sand (Lee)	Sandstone		1750	1880	130	
Репп	Lee	Shale & Siltstone		1880	1934	54	
Penn	Salt Sand (Lee)	Sandstone		1934	2054	120	
Miss	Pennington	Shale & Siltstone		2054	2322	268	
Miss	Ravencliff	Sandstone		2322	2376	54	
Miss	Pennington	Shale & Siltstone		2376	2484	108	
Miss	Maxon	Sandstone		2484	2518	34	
Miss	Pennington	Shale & Siltstone		2518	2754	236	
Miss	Maxon	Sandstone		2754	2800	46 ~	
Miss	Pennington	Shale & Siltstone		2800	3072	272	
Miss	Maxon	Sandstone		3072	3134	62	
Miss	Pennignton	Shale & Siltstone		3134	3362	228	
Miss	Maxon	Sandstone		3362	3378	16	
Miss	Pennignton	Shale & Siltstone		3378	3484	106	
Miss	Maxon	Sandstone		3484	3506	22	
Miss	Pennington	Shale & Siltstone		<b>3</b> 506	3560	54	
Miss	Little Lime	Limestone		3560	3612	52	
Miss	Big Lime	Limestone		3612	4150	538	
Miss	Pocono	Shale		4150	4252	102	
Miss	Weir	Siltstone		4252	4360	108	
Miss	Pocono	Shale		4360	4792	432	
Miss	Sunbury	Shale		4792	4810	18	
Miss	Berea	Sandstone		4810	4880	70	
Dev	Devonian Shale	Shale		4880	5672	862	
Dev	Lower Huron	Shale		5672	5872	200	
Dev	Java	Shale		5872	5990	118	

Permittee: _	Columbia Natural Resources, Inc.	(Company)
Ву:		(Signature)



Commonwealth of Virginia
Department of Mines, Minerals and Energy
Division of Gas and Oil
P.O. Box 1416
Abingdon, VA 24212

Telephone: (540) 676-5423

Operations Name CNR Well # 24153

		Permit N	umber 4602		
		COMPLETION	REPORT		
WELL TYPE: OIL	Gas X Coalbed	Methane Inj	ection		
Date Well Completed <u>Ju</u>	ly 18, 2000	To	otal Depth <u>DTD: 5995 LTD: 59</u>	95	
Attach the Drilling Repo approved after the Drillin			lition, submit any changes in ca	asing or tubing that were	
STIMULATION RECOR * Use additional sheets wi		than three zones	are stimulated		
ZONE 1: Devonian Shale		_ Formation Stim	ulated with 250 gal 7 1/3% HCl.	1,113,700 SCF N2	
ISIP 2479 (PSIG	) <u>5</u> MIN. SIP	2288 (PSIG) A	ons <u>20</u> Perforation Size verage Downhole Injection Press 10/2000	0.38" ure 3870 (PSIG)	
ZONE 2: Berea		_ Formation Stim	ulated with 250 gal 7 1/2% HCl.	1,120,000 SCF N2	
Perforated 4816 ISIP 1884 (PSIG Stimulated X Yes	)5_MIN. SIP	1825_(PSIG) A1	ons <u>20</u> Perforation Size_ verage Downhole Injection Press /10/2000	0.38" (PSIG)	
			ulated with		
Perforated ISIP (PSIG Stimulated Yes	To MIN. SIP No Date	No. of Perforati (PSIG) At	ons Perforation Size_ verage Downhole Injection Press	ure(PSIG)	
FINAL PRODUCTION	Natural X	After Stimulatio	n		
	BOD	MCFD	HOURS TESTED	ROCK PRESSURE	HOURS TESTEI
ZONE (I)	Devonian Shale Berea	428	72	340	120
ZONE (2)	Big Lime, Maxon, And Ravencliff	853	24	700	192
ZONE (3)	Alid Ravellelli				
Final production if gas zo Tested	nes are comingled	MCFD	Hours Tested	PSIGHours	
Permittee <u>Columbia Nat</u>	ural Resources, Inc		(Company)		
Ву		<del> </del>	(Signature)		
Date	. <u></u>				

Form DGO-GO-15 Rev. 10/96



Commonwealth of Virginia
Department of Mines, Minerals, and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212
Telephone: (276) 676-5423

**Tracking Number:** 774 Chesapeake Appalachia, LLC Company: BU-3349 File Number: 824155 (HY-37) W/PL **Operations Name:** Gas/Pipeline Operation Type: Drilling Report Type: Original DRILLING REPORT (DGO-GO-14) 1. Drilling Data Date drilling commenced: 5/30/2007 Drilling Contractor: S.W. Jack Drilling Date drilling completed: 6/9/2007 Rig Type: ✓ Rotary ☐ Cable Tool Driller's Total Depth (feet): 6,625 6,630 Formation At Total Depth Onandoga Log Total Depth (feet): 2. Final Location Plat (as required by 4 VAC25-150-360.C.) Final Plat State Plane X: 922,417 Permitted State Plane X 922,416 Permitted State Plane Y: 333,319 Final Plat State Plane Y: 333,318 Plat Previously Submitted Or... List of Attached Items: FileName Description Final Plat 824155.tif Final Plat Well #824155 3. Géological Data Fresh Water At: Depth (in feet) Rate Unit of Measure 30 Damp Salt Water At: Unit of Measure Depth (in feet) Rate 1,316 Damp

Form DGO-GO-14-E

Rev. 1/2007

# Coal Seams List of Attached Items: FileName Description Coal Seams Well #824155 CoalBeds 824155.xls Gas and Oil Shows List of Attached Items: FileName Description 4. Electric Logs (As required by 4VAC25-150-280.A.) List all logs run: GR,CNL,DLT,SIB,TEMP,AUDIO Did logs disclose vertical locations of a coal seam? <a>✓</a> Yes <a></a> No 5. Survey Results (As required by 4VAC25-150-280.B.2) List of Attached Items: FileName .... Description ( Survey Results 824155.xls Survey Results Well #824155 6. Casing and Tubing Program List of Attached Items: FileName Description Casing Program Well #824155 Casing Program 824155.xls 7. Remarks Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence. 8. Drillers Log Compiled By: Chad L Satterfield List of Attached Items: FileName Description

Form DGO-GO-14-E

Drillers Log Well #824155

DrillersLog 824155.xls

9. Comments

10. Signature 2. A to the second of the control of

Permitee: Chesapeake Appalachia, LLC Date: 10/19/2007 (Company)

Signed By: Chad L Satterfield Title: Drilling Engineer (Signature)

INTERNAL USE ONLY

Submit Date: 10/19/2007


Status: Inspr Approved Date: 10/23/2007

Final PDF Date: 10/23/2007

Form DGO-GO-14-E

Page 3 of 3

Rev. 1/2007



Well 824155 COALBEDS					MINING IN AREA		
NAME	TOP	BOTTOM	THICKNESS	YES	NO.	MINED OUT	
Unknown	650	652	2		Χ	No	
Unknown	780	782	2		X	No	
Unknown	870	872	2		X	No	
Unknown	972	974	2		X	No	
Unknown	1012	1014	2		X	No	

Well 824155 SURVEY RE	SULTS
Depth of Survey	Direction/Distance/Degree From True Vertical
200	1/4 degree
414	1/4 degree
626	1/4 degree
845	1/4 degree
1064	1/4 degree
1251	1/4 degree
1689	1/4 degree
1876	1/4 degree
2064	1/4 degree

Well 824155 CASING PRO	SING PF	OGRAM					
						Separate to a series of the series of the series of	
The second second	Casino	Casing	Hole	Cement Used:	Cemented ToySurfac	:east   September   September	Sasings Holessa (Cementiused) Cemented (Fig. 1) Surface (Section Section Secti
Casinoniyobea	Size	Intervall	Sizer	WINT CUBICIE	N. S.	Fre Comented	gingubicification was a yes/No. 10 comented a refinal/Size/Set
Conductor	13-3/8"	30'KB	17 1/2"	Driven			
Surface	9-5/8"	451'KB 12-3/8"	12-3/8"	295	Yes	5/31/2007	Grout basket at 98'KB
Intermedate	7	2217"KR	8-7/8"	465.5	Yes	6/3/2007	6/3/2007 Grout basket at 98'KB
ווונפווופחמופ		2000			2	5/00/2/0/2	
Production	4-1/2	902 KB 9-1/4	4/1-0	180	021	0.02.00	

etwiceneral strains and secretaristic secret	eagliithdiogyasassa assassi Colorsassis   States Copasiassis   States Copasiasis   Thickness   This Copasiasis   This																												
	Thickness	1234	848	460	22	256	42	222	100	180	132	51	46	53	46	562	164	55	446	21	45	825	228	97	- 67	324	11	93	
A Depth 12	*** Bottom ***	1234	2082	2542	2564	2820	2862	3084	3184	3364	3496	3547	3593	3646	3692	4254	4418	4473	4919	4940	4985	5810	6038	6135	6202	6526	6537	6630	
Complete Com	S. S. Top S. T. S.	0	1234	2082	2542	2564	2820	2862	3084	3184	3364	3496	3547	3593	3646	3692	4254	4418	4473	4919	4940	4985	5810	6038	6135	6202	6526	6537	
	STATE COLOT SENSON																												
**************************************	Were Seletthology as a selection	Siltstone & Shale/Coal	Sandstone	Siltstone & Shale	Sandstone	Siltstone & Shale	Sandstone	Siltstone & Shale	Sandstone	Siltstone & Shale	Sandstone	Siltstone & Shale	Sandstone	Siltstone & Shale	Limestone	Limestone	Siltstone & Shale	Sandstone	Shale	Shale	Sandstone	Shale	Shale	Shale	Shale	Shale	Shale	Limestone	
	Se Se Formation Se	Lee	nđ	Pennington	Ravencliff	Pennington	Upper Maxon	Pennington	Middle Maxon	Pennington	Lower Maxon	Pennington	Bradley	Pennington	Little Lime	Big Lime	Pennington	Weir	Pocono	Sunbury	Berea	Devonian	Lower Huron	Java	Angola	Rhinestreet	Marcellus	Onondoga	
Walipszansjoriuler/Silogan	and the second of the second o	Penn	Penn	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Devonian	Devonian	Devonian	Devonian	Devonian	Devonian	Devonian	



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

	Tracki	ing Number:	686
	Comp	any:	Chesapeake Appalachia, LLC
	File N	umber:	BU-3349
	Opera	tions Name:	824155 (HY-37) W/PL
	Opera	tion Type:	Gas/Pipeline
	Comp	letion Report Type	e: Original
	COMPLETION	REPORT (DGC	O-GO-15)
Well Type:	Gas/Pipeline	Date Well Co	ompleted: 7/4/2007
Driller's Total Depth:	6,625	Log's Total I	Depth: 6,630
especial entre especial control of the estimate of the estimat			FileName
☑ Stimulated ☐	] Not Stimulated	□Gob	FileName
☑ Stimulated ☐ Des Stimulation R	] Not Stimulated scription ecord Well #824155	□Gob	FileName imulation Record 824155.doc
Stimulated  Des  Stimulation R  Final Production	Not Stimulated scription ecord Well #824155	□ Gob	FileName imulation Record 824155.doc
✓ Stimulated	Not Stimulated scription ecord Well #824155	□ Gob	FileName imulation Record 824155.doc FileName
Stimulated  Des Stimulation R Final Production  Des Final Production	Not Stimulated scription ecord Well #824155	□ Gob	FileName imulation Record 824155.doc
Stimulation R Final Production Des	Not Stimulated scription ecord Well #824155 scription	☐ Gob	FileName imulation Record 824155.doc FileName FinalProduction 824155.xls
Stimulated  Des Stimulation R Final Production  Des Final Product  Comments	Not Stimulated scription ecord Well #824155 scription ction Well #824155	☐ Gob	FileName imulation Record 824155.doc  FileName FinalProduction 824155.xls

Form DGO-GO-15-E

Page 1 Of 2

By: Chad L Satterfield Title: Drilling Engineer (Signature)

INTERNAL USE ONLY

Submit Date: 10/19/2007

Status: Inspr Approved Date: 10/23/2007

Final PDF Date: 10/23/2007

Form DGO-GO-15-E

Rev. 1/2007

Page 2 Of 2

# **Stimulation Record Well 824155**

#### Zone 1

Name Marcellus/Rhinestreet

Formation Stimulated With: Nitrogen

Perforated from 6205' to 6530'

**Number of Perforations** 60

Perforation Size .44

Formation Broke Down at 4220 (PSIG)

Average Injection Rate 41,322 (SCFM)

ISIP: 3492 PSIG 5 Min SIP 3110 PSIG

Average Treating Pressure 1346 PSIG Stimulated Yes Date 06/22/2007

## Zone 2

Name Lower Huron

Formation Stimulated With: Nitrogen

Perforated from 5698' to 6024'

Number of Perforations 60

Perforation Size .44

Formation Broke Down at 4069 (PSIG)

Average Injection Rate 74,812 (SCFM)

ISIP: 2936 (PSIG) 5 Min SIP 2699 (PSIG)

Average Treating Pressure 4184 (PSIG)

Stimulated Yes Date 06/22/2007

# Zone 3

Name: Big Lime

Formation Stimulated With: 65% Quality Foam

Perforated from 4229' to 4239'

**Number of Perforations** 

31

**Performation Size** 

.44

Formation Broke Down at 3695 (PSIG)

Average Injection Rate 1

15(BPM)

ISIP: 2688 (PSIG)

5 Min SIP 2270 (PSIG)

**Average Treating Pressure 2728 (PSIG)** 

Stimulated Yes

Date 06/22/2007

#### Well 824155 FINAL PRODUCTION

Final Production After Stimulation	né	特地區			STEEL SERVICE
				Rock Pressure	
Zone (1 september 200 miles)					
Zone 2					
Zone 3					
Final/Commingled Zones		561	48	1007 psig	192



Commonwealth of Virginia
Department of Mines, Minerals, and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

				000	
		Tracking N	lumber:	920 Chassana	ake Appalachia, LLC
		Company: File Number	<b></b>	BU-3396	
		Operations			HY-145) W/PL
		Operation		Gas/Pipe	
		Drilling Re			
a managanan menganan sebagai s		ING REPO	•	D-GO-14	
1. Drilling Data					활기가 (1914년 1일 전투일의 1941년) -
Date drilling commenced:	8/3/2007	D	rilling Contr	actor: S	S.W. Jack Drilling
Date drilling completed:	8/18/2007	•	Rig	Type: 🔽	Rotary Cable Tool
Driller's Total Depth (feet):	6,720		~	, ,,	· —
Log Total Depth (feet):	6,728	 Fo	rmation At	Total Depti	h Onandoga
2. Final Location Plat (as requestre) Permitted State Plane X 925			-360.C.) nal Plat Stat	e Plane X	1257 (2514) (2514) (403 : 925,002
Permitted State Plane Y: 334		Fir	nal Plat Stat	e Plane Y:	334,559
☐ Plat Previously Submitted (		•			
List of Attached Items:					
Descript	ion.			V. 12.2.3.8F	ileName
Final Plat Well	#826203			Final	Plat 826203.pdf
3. Geological Data					
Fresh Water At:					
Depth	(in feet)			1 414.00	Unit of Measure
	446			Damp	
	46		L	Damp	was a grant and the same of th
Salt Water At:					\$\$P\$《日本》中《智能》的《图图图》的《 ************************************
Depth	(in feet)			Rate	Unit of Measure
	2,015			Damp	

# Coal Seams List of Attached Items: FileName Description CoalBeds 826203.xls Coal Seams Well #826203 Gas and Oil Shows List of Attached Items: FileName : -Description 4. Electric Logs (As required by 4VAC25-150-280.A.) List all logs run: GR,CNL,LDT,SIB,TEMP,AUDIO Did logs disclose vertical locations of a coal seam? ✓ Yes No 5. Survey Results (As required by 4VAC25-150-280.B.2) List of Attached Items: Description FileName Survey Results 826203.xls Survey Results Well #826203 6. Casing and Tubing Program List of Attached Items: FileName Description Casing Program Well # 826203 Casing Program 826203.xls 7. Remarks Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence. 9 5/8" Job: Job locked up into displacement of the plug, grouted back to surface w/ 25 sks Class A cement 8. Drillers Log Compiled By: Chad L Satterfield List of Attached Items:

Form DGO-GO-14-E

Description

Drillers Log Well # 826203

FileName

DrillersLog 826203.xls

# 9. Comments (In the second sec

10. Signature and the first the state of the

Permitee: Chesapeake Appalachia, LLC Date: 12/11/2007 (Company)


Signed By: Chad L Satterfield Title: Drilling Engineer (Signature)

INTERNAL USE ONLY

Submit Date: 12/11/2007

Status: Inspr Approved Date: 12/11/2007

Final PDF Date: 12/12/2007



# Area of Unit-112.69 Acres WELL LOCATION PLAT

Company .	Chesapeake Appalachia, L	LC Well Name or Numb	ber 826203 (HY-145)
Tract No	Samuel J. Breeding, Jr.	Quadrangle	Thursday.
District _	Prater		
	inates (Virginia State Plane)	N 334,559,47 E 925,001	.,88
Elevation:		od Used to Determine Elevation:	Trig, Levels from GPS derived elevation.
County _	Buchanan		hal location platX   X
This Plat is	a new plat; an	updated plat; or a fin	nal location platX a figure
— Der Iati	notes the location of a well on U tude and longitude lines being :	Inited States topographic maps, scale represented by border lines as show	le 1 to 24,000,
		Muchak	July DOUGLAS R. LIGHT
Form DG0	 )−G0−7 <del>Lice</del> n	sed Professional-Engineer or Licens	sed Land Surveyor No. 002285
Rev. 1-98			SURVEYOR SURVEYOR

# DGO-7 Supplement WELL UNIT PROPERTY OWNER INDEX Chesapeake Appalachia, L.L.C. 826203 (HY-145) with pipeline

(1)
"Drill Tract"

Surface, Oil & Gas Samuel J. Breeding, Jr. 218.98 Ac. Tract 40.36 Ac. ~ 35.82% of 112.69 Ac.

> Coal: ACIN, LLC WBRD, LLC

(2)
Henry M. Owens Heirs, et al
92 Ac. Tract
0.54 Ac. ~ 0.48% of 112.69 Ac.

(3)
George W. Owens Heirs (3/13 Int.) & of Henry M. Owens Heirs (10/13 Int.)
57.5 Ac. Tract
37.08 Ac. ~ 32.90% of 112.69 Ac.

(4)
War Fork Coals Partnership
410 Ac, Tract
34.71 Ac, ~ 30.80% of 112.69 Ac.

Well 8262	03 COA	LBEDS	The selection of the second	A LAN	INING IN AREA
NAME	TOP	BOTTOM	THICKNESS	YES NO	MINED OUT
Unknown	443	446	3	X	NO

Well 826203 SURVEY RE	SULTS
Depth of Survey	Direction/Distance/Degree From True Vertical
200	1/4 degree
446	1/4 degree
600	1/4 degree
813	1/4 degree
1001	1/4 degree
1220	1/4 degree
1345	1/4 degree
1532	1/4 degree
1751	1/4 degree
1970	1/4 degree

	Date Dackers Or Bridge Plugs	rcemented   *** ** Kind/Size/Set		8/5/2007 Grout basket at 98' KB	8/8/2007 Grout basket at 98' KB	-	8/9/2007 Grout basket at 98 KB	8/18/2007	
	ace	349	No	Yes 8/5/			Yes : 8/9/		
	120	-	Driven	354		354	479.4	204 AE	361.43
JGRAM	Casing Holer Cementilised	nterval Sizer	30' KB 26"	378' KB 17 1/2"	1000	583'KB 12-3/8"	2306'KB 8-7/8"		5687 KB 6-1/4
ASING PRO	MICASIFICIA	Size	20"	ā	+	9-2/8	1.	1	4-1/2"   6(
Well 826203 CASING PRO		Castino Inviole	Conductor	Conference of the conference o	Surface	Surface #2	Intormodiate	וועבווונסחמונ	Production

	A SAME OF THE PROPERTY OF THE PARTY OF THE P		Mark Colorate を表現	Top was a	**Bottom*	menumblody was as Colors ***   ** ****   ****   *****   ******   *****   ****   *****   *****   *****   ******	The second control of
	ad	Silfstone & Shale/Coal		0	1404	1404	
T GILL	Salt Sand	Sandstone		1404	2234	830	
Miss	Pennington	Siltstone & Shale		2234	2330	96	
Miss	Ravencliff	Sandstone		2330	2399	69	
Miss	Pennington	Siltstone & Shale		2399	2660	261	
Miss	Upper Maxon	Sandstone		2660	2712	52	
Miss	Pennington	Siltstone & Shale		2712	2980	268	
Miss	Middle Maxon	Sandstone		2980	3009	29	
Miss	Pennington	Siltstone & Shale		3009	3227	218	
Miss	Lower Maxon	Sandstone		3227	3273	46	
Miss	Pennington	Siltstone & Shale		3273	3732	459	
Miss	Bradlev	Sandstone		3732	3756	24	
Miss	Pennington	Siltstone & Shale		3756	3852	96	
Miss	Little Lime	Limestone		3852	3883	31	
Miss	Bio 1 ime	Limestone		3883	4392	206	
Miss	Pocono	Shale		4392	4576	184	
Miss	Weir	Sandstone		4576	4642	99	
Miss	Pocono	Shale		4642	5089	447	
Miss	Sunbury	Shale		5089	5111	22	
Miss	Berea	Sandstone		5111	5152	41	
Devonian	Devonian	Shale		5152	5997	845	
Devonian	l ower Huron	Shale		2997	6208	211	
Devotion	evel.	Shale		6208	6317	109	
Devonian	Angola	Shale		6317	6404	87	
Devonian	Rhinestreet	Shale		6404	6623	219	
Devonian	Marcellus	Shale		6623	6632	6	
				CCCC	0720	90	

(



Commonwealth of Virginia
Department of Mines, Minerals, and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212

T T TANK AND CITES OF		Teleph	one: (276) 676-5423
	Tracking Compan	g Number:	875 Chesapeake Appalachia, LLC
	File Nun	nber:	BU-3396
	Operation	ons Name:	826203 (HY-145) W/PL
	Operation	on Type:	Gas/Pipeline
	Comple	tion Report Type	: Original
	COMPLETION F	REPORT (DGC	O-GO-15)
Well Type:	Gas/Pipeline	Date Well Co	ompleted: 9/3/2007
Driller's Total Depth:	6,720	Log's Total	Depth: 6,728
Des	scription		FileName
. Stimulation Record	scription	Gob	FileName
Description Record  Stimulation Record  Stimulated  Description	scription  ] Not Stimulated scription	☐ Gob	FileName FileName
Description Record  ✓ Stimulated  Description  Description	Scription  Not Stimulated  Scription Secord Well # 826203	☐ Gob	FileName
Description Record  ✓ Stimulated  Description  Description	Scription  Not Stimulated  Scription Secord Well # 826203	□ Gob	FileName imulation Record 826203.doc
Stimulation Record  Stimulated  Description  Stimulation R  Stimulation R  Final Production	scription  Not Stimulated scription lecord Well # 826203	□ Gob	FileName imulation Record 826203.doc FileName
Stimulation Record  Stimulated  Description  Stimulation R  Stimulation R  Stimulation R	Scription  Not Stimulated  Scription Secord Well # 826203	☐ Gob	FileName imulation Record 826203.doc  FileName FinalProduction 826203.xls
Stimulation Record  Stimulated  Decord Stimulated  Decord Stimulation R  Stimulation R  Final Production  Decord Final Production	scription  Not Stimulated scription lecord Well # 826203	☐ Gob	FileName imulation Record 826203.doc FileName
Stimulation Record  Stimulated  Decord Stimulated  Decord Stimulation R  Stimulation R  Final Production  Decord Final Production	Scription  Not Stimulated  Scription Lecord Well # 826203  Scription Ction Well # 826203	☐ Gob	FileName imulation Record 826203.doc  FileName FinalProduction 826203.xls
Stimulation Record  Stimulated  Description R Stimulation	Not Stimulated scription ecord Well # 826203 scription ction Well # 826203	□ Gob	FileName imulation Record 826203.doc  FileName FinalProduction 826203.xls

Form DGO-GO-15-E Rev. 1/2007 Page 1 Of 2

Г.

Ву:	Chad L Satterfield	Title: Drilling Engineer	(Signature)
INTER	NAL USE ONLY		
Su	ıbmit Date: 12/11/2007		
	Status: Inspr Approved	Date: 12/11/200	)7

Form DGO-GO-15-E Rev. 1/2007

Final PDF Date: 12/12/2007

# Stimulation Record Well 826203

#### Zone 1

Name: Marcellus/Rhinestreet

Formation Stimulated With: Nitrogen

Perforated from 6410' to 6628'

Number of Perforations 60

Perforation Size .44

Formation Broke Down at 3648 (PSIG)

Average Injection Rate 69,500 (SCFM)

ISIP: 3080 (PSIG) 5 Min SIP 2892 (PSIG)

**Average Treating Pressure 4162 (PSIG)** 

Stimulated Yes Date 08/21/2007

# Zone 2

Name: Lower Huron

Formation Stimulated With: Nitrogen

Perforated from 5884' to 6199'

Number of Perforations 60

Perforation Size .44

Formation Broke Down at 3701 (PSIG)

Average Injection Rate 81,967 (SCFM)

ISIP: 2279 (PSIG) 5 Min SIP 2218 (PSIG)

**Average Treating Pressure 3770 (PSIG)** 

Stimulated Yes Date 08/21/2007

### Zone 3

Name: Weir

Formation Stimulated With: 75% Quality Foam

Perforated from 4582' to 4608'

Number of Perforations 44

Perforation Size .44

Formation Broke Down at 2751 (PSIG)

Average Injection Rate 25 (BPM)

ISIP: 2192 (PSIG) 5 Min SIP 2090 (PSIG)

**Average Treating Pressure 1903 (PSIG)** 

Stimulated Yes Date 08/21/2007

### Zone 4

Name: Big Lime

Formation Stimulated With: 65% Quality Foam

Perforated from 4216' to 4228'

Number of Perforations 37

Perforation Size .44

Formation Broke Down at 3389 (PSIG)

**Average Injection Rate 15 (BPM)** 

ISIP: 3150 (PSIG) 5 Min SIP 3015 (PSIG)

**Average Treating Pressure 2777 (PSIG)** 

Stimulated Yes Date 08/21/2007

# Well 826203 FINAL PRODUCTION

Final Production After Stimula	tion	Service Services	CONTRACTA		<b>第五章第二章</b>
	BOD	MCFD	Hours Tested	Rock Pressure	Hours Tested
Zone 1					
Zone 2					
Zone 3					
Final/Commingled Zones		1,030	48	950 psig	48



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil

P.O. Box 1416; Abingdon, VA 24212 Telephone: (276) 676-5423

-			
	Tracking	Number: 89	97
	Company	<u> </u>	nesapeake Appalachia, LLC
	File Num	_	J-3391
	Operatio	ns Name: 82	26204 (HY-146) W/PL
	Operatio		as/Pipeline
	Drilling F	Report Type: O	riginal
D	RILLING REF	PORT (DGO-	GO-14)
1. Drilling Data			
Date drilling commenced: 7/19	/2007	Drilling Contract	or: S.W. Jack Drilling
Date drilling completed: 8/1/2	2007	•	/pe: 🗸 Rotary 🔲 Cable Tool
Driller's Total Depth (feet): 6,70	7	····g	, po. [2] (total)
Log Total Depth (feet): 6,70		Formation At Tot	al Depth Onandoga
2. Final Location Plat (as required	l by 4 VAC25-1	50-360.C.)	
Permitted State Plane X 925,341	F	Final Plat State F	Plane X: 925,341
Permitted State Plane Y: 337,098	f	inal Plat State F	Plane Y: 337,099
Plat Previously Submitted Or			
List of Attached Items:			
Description	saudije Bje war i je i sauju sa Destrem seko ta sa terak i se		FileName
Final Plat Well #82	26204		final plat 826204.pdf
3. Geological Data	enistra e e e e e e e e e e e e e e e e e e e		
Fresh Water At:	<b>5</b> 0.8 加多		
Depth (in f	eet)	R	te Unit of Measure
	45	Dar	
	450	Dar	1р
Salt Water At:			
Depth (in f		Re	
1,	452	Dar	np

Form DGO-GO-14-E

Page 1 of 3

Rev. 1/2007

Coal Seams		. : :
------------	--	-------

List of Attached Items:

Description	FileName
Coal Seams Well #826204	CoalBeds 826204.xls

# Gas and Oil Shows

List of Attached Items:

Description	10 10 10		 FileName
	 	•	 

4. Electric Logs (As required by 4VAC25-150-280.A.)

List all logs run: GR,CNL,LDT,SIB,TEMP,AUDIO

Did logs disclose vertical locations of a coal seam? 

✓ Yes 

No

#### 5. Survey Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName
Survey Results Well #826204	Survey Results 826204.xls

# 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
Casing Program Well # 826204	Casing Program 826204.xls

# 7. Remarks Albertal Barbara Ba

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

13 3/8" csg Job: Open Mine 347-352, Grout Basket @ 290', Grouted back to surface w/200 sks Class A cement

# 8. Drillers Log

Compiled By: Chad L Satterfield

List of Attached Items:

Description	FileName
Drillers Log Well # 826204	DrillersLog 826204.xls

Form DGO-GO-14-E

# 

10. Signature

Permitee: Chesapeake Appalachia, LLC Date: 12/4/2007 (Company)

Signed By: Chad L Satterfield

Title: Drilling Engineer (Signature)

INTERNAL USE ONLY

Submit Date: 12/4/2007

Status: Inspr Approved


Date: 12/10/2007

Final PDF Date: 12/11/2007

Form DGO-GO-14-E

Page 3 of 3

Rev. 1/2007



# DGO-7 Supplement WELL UNIT PROPERTY OWNER INDEX Chesapcake Appalachia, L.L.C. 826204 (HY-146) with pipeline

(1)
"Drill Tract"
Fee:
Henry M. Owens Heirs
50 Acre Tract
55.12 Ac. ~ 48.91% of 112.69 Ac.

(2)
Henry M. Owens Heirs, et al
92 Acre Tract
29.53 Ac. ~ 26.20% of 112.69 Ac.

(3)
Samuel J. Breeding, Jr
218.98 Acre Tract
21.28 Ac. ~ 18.89% of 112.69 Ac.

(4)
Pine Mountain Oil & Gas, Inc.
412 Acre Tract
3.93 Ac. ~ 3.49% of 112.69 Ac.

(5) Tim & Amy Ratliff 2.83 Ac. ~ 2.51% of 112.69 Ac.

Well 8262	04.COA	LBEDS.		M	INING IN AREA
NAME	TOP.	BOTTOM	THICKNESS	YES NO	MINED OUT
Unknown	347	352	5	X	YES
Unknown	934	936	2	Х	NO

-

Well 826204 SURVEY F	
Depth of Survey	Direction/Distance/Degree From True Vertical
200	1/4 degree
409	1/4 degree
626	1/4 degree
844	1/4 degree
1063	1/4 degree
1282	1/4 degree
1564	1/4 degree
1750	1/4 degree
1969	1/4 degree

Well 826204 CASING PF	SING PR	ROGRAM					
	Casing	Casing	Hole	Cement Used	Casings Hole Cement Used Cemented To Surface	∑.sDate	1
Casind Type**	Size	Interval   Size	Size	zin Gubic Et :	**************************************	Cemented	Kind/Size/Set
Conductor	20"	22 KB	26"	Driven	οN		
Onen Mine	13.3/8"		17 1/2"	330.4	Yes	7/20/2007	Grout basket at 98' KB
Sinfa Contracts	0_5/8"	1	12-3/8"	354	Yes	7/21/2007	Grout basket at 98' KB
Informodiate	7	- 7	8-7/8"		Yes	7/28/2007	Grout basket at 98' KB
Droduction	4-10"	6677'KB 6-1/4"	6-1/4"	352 8	NO NO	8/2/2007	
	7.		,	0:100			

•

1

* Depth also a second and a second a second and a second	Section of the Section of the Section	1393 1393	2197 804	2950 753			3359 42			3690 168	3715 25	3774 59		-	4522 175		5031 437	5050 19	5090 40					6601 128	6612 11	96 820
**************************************	*Color**********************************	0	1393	2197	2950	2983	3317	3359	3484	3522	0698	3715	3774	3815	4347	4522	4594	5031	5050	2090	5891	6132	6246	6473	6601	6612
			Sandstone	Siltstone & Shale	Sandstone	Siltstone & Shale	Sandstone	Siltstone & Shale	Sandstone	Siltstone & Shale	Sandstone	Siltstone & Shale	Limestone	Limestone	Shale	Sandstone	Shale	Shale	Sandstone	Shale	Shale	Shale	Shale	Shale	Shale	Limestone
Gale of the second and the second	- Formation:	Lee	Salt Sand	Pennington	Upper Maxon	Pennington	Middle Maxon	Pennington	Lower Maxon	Pennington	Bradley	Pennington	Little Lime	Big Lime	Pocono	Weir	Pocono	Sunbury	Berea	Devonian	Lower Huron	Java	Angola	Rhinestreet	Marcellus	Onondoga
Well 826204 DRIELER'S 4:0G	**************************************	Penn	Penn	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Miss	Devonian	Devonian	Devonian	Devonian	Devonian	Devonian	Devonian

Welli826204/DRILLER'S LOG	のなかのますりできたいないのであるという	ct *: General		C Copth	- Depth -	The second second	:
Geologic#Age	Formation	Formation - Lithology	SCOlor Color	Top Top	Bottom	Thickness	Remarks
Penn	Lee	Siltstone & Shale/Coal		0	1393	1393	
Penn	Salt Sand	Sandstone		1393	2197	804	
Miss	Pennington	Siltstone & Shale		2197	2950	753	
Miss	Upper Maxon	Sandstone		2950	2983	33	
Miss	Pennington	Siltstone & Shale		2983	3317	334	
Miss	Middle Maxon	Sandstone		3317	3359	42	
Miss	Pennington	Siltstone & Shale		3359	3484	125	
Miss	Lower Maxon	Sandstone		3484	3522	38	
Miss	Pennington	Siltstone & Shale		3522	3690	168	
Miss	Bradlev	Sandstone		3690	3715	25	
Miss	Pennington	Siltstone & Shale		3715	3774	59	
Miss	Little Lime	Limestone		3774	3815	41	
Miss	Big Lime	Limestone		3815	4347	532	
Miss	Pocono	Shale		4347	4522	175	
Miss	Weir	Sandstone		4522	4594	72	
Miss	Pocono	Shale		4594	5031	437	
Miss	Sunbury	Shale		5031	5050	19	
Miss	Berea	Sandstone		5050	5090	40	
Devonian	Devonian	Shale		5090	5891	801	
Devonian	Lower Huron	Shale		5891	6132	241	
Devonian	Java	Shale		6132	6246	114	
Devonian	Angola	Shale		6246	6473	227	
Devonian	Rhinestreet	Shale		6473	6601	128	
Devonian	Marcellus	Shale		6601	6612	7	
Devonian	Onondoga	Limestone		6612	6708	96	



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil P.O. Box 1416; Abingdon, VA 24212 Telephone: (276) 676-5423

			elephone. (270) 070-3423
	Tra	acking Number:	812
	Co	ompany:	Chesapeake Appalachia, LLC
	Fil	e Number:	BU-3391
	Op	perations Name:	826204 (HY-146) W/PL
	Op	peration Type:	Gas/Pipeline
	Co	ompletion Repor	t Type: Original
	COMPLET	ON REPORT	(DGO-GO-15)
Well Type:	Gas/Pipeline	Date V	Vell Completed: 8/21/2007
Driller's Total Depth:	6,707	Log's	Total Depth: 6,708
Stimulation Record	]Not Stimulated	□Gob	
Des	scription		FileName
	ecord Well # 8262	04	Stimulation Record 826204.doc
. Final Production		The second of	and high resembly the order of the
De:	scription		FileName
Final Produc	ction Well # 82620	4	FinalProduction 826204.xls
. Comments			
Notes:  Signature			

Form DGO-GO-15-E

Page 1 Of 2

Rev. 1/2007

Ву:	Chad	d L Satterfield		Drilling Engineer	(Signature)
INTERNA	L USE (	DNLY			
Subm	it Date:	12/4/2007			
	Status:	Inspr Approved		Date: 12/10/2007	
Final PD	F Date:	12/11/2007			

Form DGO-GO-15-E

Rev. 1/2007

# Stimulation Record Well 826204

# Zone 1

Name: Marcellus/Rhinestreet

Formation Stimulated With: Nitrogen

to 6606' Perforated from 6336'

Number of Perforations 60

**Perforation Size** .44

Formation Broke Down at 4275 (PSIG)

30,289 (SCFM) Average Injection Rate

5 Min SIP 3190 (PSIG) ISIP: 3450 (PSIG)

**Average Treating Pressure 4127 (PSIG)** Stimulated Yes 08/08/2007 Date

#### Zone 2

Name: Lower Huron

Formation Stimulated With: Nitrogen

Perforated from 5776' to 6124'

Number of Perforations 60

**Perforation Size** .44

Formation Broke Down at 3997 (PSIG)

80,940 (SCFM) Average Injection Rate

5 Min SIP 2478 (PSIG) ISIP: 2565 (PSIG)

Average Treating Pressure 3967 (PSIG)

Stimulated Yes Date 08/08/2007

#### Zone 3

Name: Weir

Formation Stimulated With: 75% Quality Foam

Perforated from 4530' to 4552'

Number of Perforations 44

Perforation Size .44

Formation Broke Down at 2213 (PSIG)

Average Injection Rate 20 (BPM)

ISIP: 2425 (PSIG) 5 Min SIP 2351 (PSIG)

Average Treating Pressure 2019 (PSIG)

Stimulated Yes Date 08/08/2007

# Zone 4

Name: Big Lime

Formation Stimulated With: 50% Quality Foam

Perforated from 4182' to 4190'

Number of Perforations 25

Perforation Size .44

Formation Broke Down at 4136 (PSIG)

Average Injection Rate 12 (BPM)

ISIP: 3411 (PSIG) 5 Min SIP 3133 (PSIG)

Average Treating Pressure 3071 (PSIG)

Stimulated Yes Date 08/08/2007

#### Well 826204 FINAL PRODUCTION

Final Production After Stimulati	on	33 - 34 5 38 5 2 48 5 6	Valvet 4 Not State		PRESENT
	BOD	MCFD.	Hours Tested	Rock Pressure	Hours Tested
Zone 1					
Zone 2					
Zone 3					
Final/Commingled Zones		801	48	820 psig	48



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

	Tracking	Number:	3126			
	Compan		Range Resources-Pine Mountain			
	File Num	ber:	BU-4608	BU-4608		
	Operatio	ns Name:	900004 W/PL			
	Operatio	n Type:	Gas/Pipeline			
	Drilling (	Report Type:	Original			
DR . Drilling Data	RILLING REPO	ORT (DGO-G	O-14)			
Date drilling commenced: 12/21/2010		Dri	lling Contractor:	Noah Horn #87		
Date drilling completed: 1/5/2011		Ri	Rig Type: ☑ Rotary ☐ Cable			
Driller's Total Depth (feet):	4930.00					
Log Total Depth (feet):	4936.00	Formation	n At Total Depth	Cleveland Shale		
2. Final Location Plat (as require	ed by 4 VAC25-1	50-360.C.)				
Permitted State Plane X: 104	05439.8400	Final Plat Sta	ate Plane X: 1	0405441.5700		
Permitted State Plane Y: 361	1650.0800	Final Plat St	ate Plane Y: 3	8611654.0500		
Plat Previously Submitted Or						
List of Attached Items:						
Description			FileName			
900004 final pla	t		900004 Final Pl	at.pdf		

## 3. Geological Data

Fresh Water At:

Depth (in feet)		Unit of Measure
130	.75	

Salt Water At:

Depth (in feet)	Rate	Unit of Measure
1205	damp	

Coal Seams:

List of Attached Items:

Description	FileName
900004 coals	900004_Coal.xls

Gas and Oil Shows:

List of Attached Items:

Description	FileName
900004 gas shows	Shows.xls

# 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run:

Hi Res GR/Dens/Temp/Audio/PE/Caliper Data Pack

Did logs disclose vertical locations of a coal seam?

 $\sqrt{}$ 

# 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName
900004 survey	Survey.xls

Form DGO-GO-14-E

Page 2 of 3

## 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
900004 casing	Casing.xls

#### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

_	_	- 41					
8.	1 1	rill	מו	re.	1	Λ	n
υ.	_				_	•	•

Compiled By:

Range Resources

List of Attached Items:

Description	FileName
900004 log	900004_Log.xls

#### 9. Comments

1	O	. S	ia	na	tı	ire

Permitee:

Range Resources-Pine Mountain

Date:

10/21/2011

Signed By:

Jonathan Horne

Title:

Engineering Tech

# INTERNAL USE ONLY

Submit Date:

10/21/2011

Status:

۸

Date:


3/1/2012

Final PDF Date:

3/5/2012

Form DGO-GO-14-E

Page 3 of 3



WELL LOCATION PLAT

DE LA COMPANS AND NUMBER 900004
COMPANY Range Resources Pine Mountain, Inc. WELL NAME AND NUMBER 900004
TRACT NO. 101 TOTA SOCIETY OF GROUPS SCALE $1'' = 400'$ DATE $12-21-2010$
COUNTY Buchangn DISTRICT Frater SCALE 1" = 400' DATE 12-21-2010
The Diet is a sow plat to the undated plat of Or O (1901 DCGUS) but a compared plat to the control of the contr
as the second of
Denotes the location of a well on united states topographic it applies to about
Denotes the location of a we'll on United States topographic Maps, scale 1 to 24,000, latitude and longitude lines being represented by border lines as shown
, ,

Licensed Professional Engineer or Lidensed Land Surveyor

Coal Seams		V-900004		1000		
		2.1		MINING IN	IAREA	10 July 2016
NAME	TOP	BOTTOM	THICKNESS	YES	NO	MINED OUT
COAL	15	16	1		NO	NO
COAL	110	112	2		NO	NO
COAL	263	265	2		NO	NO
COAL	485		2		NO	NO
COAL	835	837	2		NO	NO
COAL	1164		3		NO	NO
COAL	1900	1902			NO	NO

.

# Gas and Oil Shows

FORMATION	DEPTH	THICKNESS	IPF (MCFD/BOPD)	PRESSURE	HOURS TESTED
Dougnaliff	2022		NO		
Ravencliff Maxton	2923		NS NS		
	3488		NS NC		
Big Lime	4090		NS - de-		
Berea	4820		odor		

Survey Results

Depth of Survey	Direction/Distance/Degree From True Vertical
193'	1/40
408'	1/4°
594'	1/4 °
815'	1/2°
1001'	1/4°
1189'	1/2°
1405'	1/2°
1593'	3/4°
1814'	3/4°
2005'	1°
2196'	3 <sub>/4</sub> °
2395'	3/4°

Casing Program

Cusing Program	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date
Casing Type	Size	Interval		In Cubic Ft.	Yes/No	Cemented
Conductor	133/8"	0-40'	15"			
Water Protection	95/11	0-344'	121/4"	224 ft <sup>3</sup>	Yes	12/22/10
Coal Protection	7"	0-2286'	87/8"	492 ft <sup>3</sup>	Yes	12/31/10
Production Casing	41/2"	0-4903'	61/4"	374 ft <sup>3</sup>	No	01/06/11
Other Casing And						İ
Tubing Left In Well	23/8"	0-4248'				
Liners						

Packers Or Bridge Plugs Kind/Size/Set	Cement Baskets (ft)		
	84'		
	298'		
	3846' 4308'		

Driller's Log	V-900004						
		General .		Depth	Depth		
Geologic Age	Formation	Lithology	Color	Top	Bottom 1	Thickness	Remarks
		OVERBURDEN		0			
PENNSYLVANIAN		ÇOAL		15			
PENNSYLVANIAN		SANDSTONE		16			
PENNSYLVANIAN		COAL		110			
PENNSYLVANIAN		SANDY SHALE		112			
PENNSYLVANIAN		COAL		263			
PENNSYLVANIAN		SANDY SHALE		265			
PENNSYLVANIAN		SANDSTONE		290			
PENNSYLVANIAN		COAL		485			
PENNSYLVANIAN		SANDSTONE		487			
PENNSYLVANIAN		SANDY SHALE		515			
PENNSYLVANIAN		SANDSTONE		626			
PENNSYLVANIAN		SANDY SHALE		690			
PENNSYLVANIAN		SANDSTONE		784			
PENNSYLVANIAN		SANDY SHALE		815			
PENNSYLVANIAN		COAL		835	837		
PENNSYLVANIAN		SANDY SHALE		837	846		
PENNSYLVANIAN		SANDSTONE		846	878		
PENNSYLVANIAN		SANDY SHALE		878	3 1164		
PENNSYLVANIAN		COAL		1164	1167	' 3	i
PENNSYLVANIAN		SANDY SHALE		1167	1900	733	}
PENNSYLVANIAN		COAL		1900	1902		
PENNSYLVANIAN		SANDY SHALE		1902	2 2065		
PENNSYLVANIAN	RED ROCK	SHALE		2065	5 2081	16	ì
PENNSYLVANIAN		SANDSTONE		208	2222	2 141	
PENNSYLVANIAN	RED ROCK	SHALE		2222	2 2268	3 46	6
PENNSYLVANIAN		SANDY SHALE		2268	3 2650	382	2
MISSISSIPPIAN	RAVENCLIFF	SANDSTONE		2650	2910	) 250	)
MISSISSIPPIAN	MAXTON	SANDSTONE		2910	3478	3 568	}
MISSISSIPPIAN	LITTLE LIME	LIMESTONE		3478	3704	4 226	ò
MISSISSIPPIAN	BIG LIME	LIMESTONE		370	4 4090	386	3
MISSISSIPPIAN	WEIR	SILTSTONE		409	3 4340	3 250	)
MISSISSIPPIAN	WEIR SHALE	SHALE		434	0 469	350	3
MISSISSIPPIAN	SUNBURY	SHALE		469	0 477	5 8	5
MISSISSIPPIAN	BEREA	SANDSTONE		477	5 482	0 4	5
DEVONIAN	CLEVELAND	SHALE		482	0		

.



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

	Tracking N	umber:	3098	
	Company:		Range Resources-Pine Mountain	
	File Numbe	er:	BU-4608	
	Completio	n Report Type:	Original	
С	OMPLETION RI	EPORT (DGO	-GO-15)	
Well Type:	Gas/Pipeline	Date Well (	Completed: 1/20/2011	
Driller's Total Depth:	4930.00	Log's T	otal Depth: 4936.00	
Changes In Casing/Tubing from Approved Drilling Report  Description			FileName	
Description			FileName	
Stimulation Record				
Stimulation Status: 🗹 Stir	mulated GOB	☐Not Stimulate	ed Service Well	
Descripti	on		FileName	
900004 stime	ulation	900004 Stimulation.doc		
Final Production				
Descripti	ion	FileName		
900004 final production		Final_Prod.xls		

Notes:

<ol><li>Signat</li></ol>	ure
--------------------------	-----

Permittee: Range Resources-Pine Mountain 11/8/2011 Date:

Engineering Tech (Signature) Title: Jonathan Horne Ву:

(Company)

INTERNAL USE ONLY

Submit Date: 11/8/2011

> Date: 3/5/2012 Approved Status:

Final PDF Date: 3/6/2012

# STIMULATION RECORD

	Formation Stimulated With:	
Perforated 4823 to 4835 feet No. of Pe	erforations 25 Perforation	Size <u>.52</u>
Formation Broke down at: 1507 PSIG	Average Injection Rate: 25	BPM
Formation Broke down at: 1507 PSIG ISIP 0 PSIG 2 Min SIP 0 PSIG Avera	ge Downhole Injection Pressure	2022 PSIG
Stimulated: Yes  No Date Stimulated:		
ZONE 2: Weir	Formation Stimulated With:	
	erforations 19 Perforation	Size52
Formation Broke down at: 2204 PSIG	Average Injection Rate: 15	BPM
ISIP 1245 PSIG 2 Min SIP 1171 PSIG Avera	ge Downhole Injection Pressure	<u>2978</u> PSIG
Stimulated: Xes No Date Stimulated:		
ZONE 3: Big Lime	Formation Stimulated With:	60Q Foam
Perforated 3584 to 4128 feet No. of P	erforations 48 Perforation	Size .33
Formation Broke down at: 2978 PSIG	Average Injection Rate: 20.5	BPM
ISIP 1230 PSIG 2 Min SIP 0 PSIG Avera	ige Downhole Injection Pressure	2296 PSIG
Stimulated: Xes No Date Stimulated:		
ZONE 4: Maxton	Formation Stimulated With:	65Q Foam
Perforated 3008 to 3040 feet No. of P	erforations 21 Perforation	Size .42
Formation Broke down at: 2430 PSIG	Average Injection Rate: 30	BPM
SIP 1234 PSIG 2 Min SIP 0 PSIG Avera	age Downhole Injection Pressure	2820 PSIG
Stimulated: Xes No Date Stimulated:		
ZONE 5: Ravencliff	Formation Stimulated With:	75Q Foam
Perforated 2685 to 2697 feet No. of F	Perforations 25 Perforation	n Size .42
Formation Broke down at: 0 PSIG	Average Injection Rate: 0	BPM
ISIP 0 PSIG 2 Min SIP 0 PSIG Avera	age Downhole Injection Pressure	0 PSIG
Stimulated: Yes No Date Stimulated:	_	

Final Production After Stimula	tion	100		
	BOD	MCFD	Hours Tested	Rock Pressure
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones		527	3	400



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9700

	Tracking	g Number:	3127		
	Company:		Range Resources-Pine Mountain		
	File Nun	nber:	BU-4554		
	Operation	ons Name:	900005		
	Operation Type: Drilling Report Type:		Gas/Pipeline		
			Original		
D	RILLING REPO	ORT (DGO-G	O-14)		
. Drilling Data					
Date drilling commenced:	11/30/2010 D		illing Contractor: Noah Horn #87		
Date drilling completed:	12/6/2010	R	ig Type:☑Rota	ary	
Driller's Total Depth (feet):	5188.00				
Log Total Depth (feet):	5202.00	202.00 Formatio		h Cleveland Shale	
2. Final Location Plat (as requi	ired by 4 VAC25-	150-360.C.)			
Permitted State Plane X: 10	0407265.6100	Final Plat St	ate Plane X:	10407265.6400	
Permitted State Plane Y: 36	613102.6200	Final Plat St	ate Plane Y:	3613101.9200	
Plat Previously Submitted Or	· 🗀				
List of Attached Items:					
Description			FileNam	е	
900005 final p	900005 FINAL PLAT.pdf				

Form DGO-GO-14-E

Page 1 of 3

## 3. Geological Data

Fre	оh	14/5	tor	$\Delta t$
TIH.	~ 1	VVA.	16:1	MI.

Depth (in feet)	Rate	Unit of Measure

Salt Water At:

Depth (in feet)	Rate	Unit of Measure
Bopin (m. 1994)		,

Coal Seams:

List of Attached Items:

Description	FileName
900005 coals	900005_Coal.xls

Gas and Oil Shows:

List of Attached Items:

Description	FileName
900005 gas shows	Shows.xls

# 4. Electric Logs (As required by 4VAC25-150-280.A)

List all logs run:

Hi Res GR/Dens/Temp/Audio/PE/Caliper Data Pack

Did logs disclose vertical locations of a coal seam?

 $\checkmark$ 

# 5. Survery Results (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName		
900005 survey	Survey.xls		

## 6. Casing and Tubing Program

Form DGO-GO-14-E

Page 2 of 3

List of Attached Items:

Description	FileName		
900005 casing	Casing.xls		

## 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

8.	Dril	lers	Log

Compiled By:

Range Resources

List of Attached Items:

Description	FileName
900005 log	900005_Log.xls

#### 9. Comments

1	O.	S	a	n	а	ŧ٤	ı	re

Permitee:

Range Resources-Pine Mountain

Date:

10/21/2011

Signed By:

Jonathan Horne

Title:

Engineering Tech

# INTERNAL USE ONLY

Submit Date:

10/21/2011

Status:

Α

Date:

3/1/2012

Final PDF Date:

3/5/2012

Form DGO-GO-14-E

Page 3 of 3

WHI TOUNION FINE

reased Professional Engineer or Lieuwit are Survey to

Coal Seams		V-900005				
11.75 33		100		M	IINING IN	AREA
NAME	TOP	ВОТТОМ	THICKNESS	YES	NO	MINED OUT
COAL	51	53	2		NO	NO
COAL	185	186	1		NO	NO
COAL	420	422	2		NO	NO
COAL	685	687	2		NO	NO
COAL	850	852	2		NO	NO
COAL	1009	1011	2		NO	NO
COAL	1046	1048	2		NO	NO
COAL	1105	1107	2		NO	NO
COAL	1211	1213	2		NO	NO
COAL	1232	1234	2		NO	NO
COAL	1407	1409	2		NO	NO
COAL	2145	2147	2		NO	NO
COAL.	2302	2304	2		NO	NO

1

*¥* : •

Gas and Oil Shows

FORMATION	DEPTH	THICKNESS	IPF (	(MCFD/BOPD)	PRESSURE	HOURS	TESTED
				·			
	383		NS				
Ravencliff	2638		odor	•			
Ravencliff	3174		NS				
Maxton	3774			60 mcfd	į į		
Big Lime	4400	ı		84 mcfd	b		
Berea	5188	<b>;</b>		119 mcfd	t		
	5188 w/cs	g		158 mcfd	b		

Survey Results

Depth of Survey	Direction/Distance/Degree From True Vertical
195'	1/40
409'	1/40
600'	1/40
819'	1/40
1007'	1/40
1196'	1/40
1417'	1/20
1604'	1/40
1793'	1/40
2014'	1/4°
2202'	1/2°
2390'	1/2°
2638'	3/4°

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented
Conductor	13¾"	0-40'	15"			
Water Protection	95/8"	0-345'	121/4"	224 ft <sup>3</sup>	Yes	11/30/10
Coal Protection	7"	0-2584'	87/8"	624 ft <sup>3</sup>	Yes	12/03/10
Production Casing	41/2"	0-5136'	61/4"	411 ft <sup>3</sup>	No	12/08/10
Other Casing And						
Tubing Left In Well	23/8"	0-5078'				]
Liners						

Packers Or Bridge Plugs Kind/Size/Set	Cement Baskets (ft)
	84'
	294'
	4118' 4579'
•	
	i

Driller's Log	V-900005			1			
		General		Depth	Depth		
Geologic Age	Formation	Lithology	Color	Top	Bottom.	Thickness	Remarks
					•		
		OVERBURNDËN		0	19	19	
PENNSYLVANIAN		SANDSTONE		19	51		
PENNSYLVANIAN		COAL		51	53		
PENNSYLVANIAN		SANDSTONE		53	146	93	
PENNSYLVANIAN		SANDY SHALE		146	185	39	
PENNSYLVANIAN		COAL		185	186	- 1	
PENNSYLVANIAN		SANDSTONE		186	306	120	
PENNSYLVANIAN		SANDY SHALE		306	358	52	
PENNSYLVANIAN		SANDSTONE		358	420	62	
PENNSYLVANIAN		COAL		420	422	2	
PENNSYLVANIAN		SANDSTONE		422	640	218	
PENNSYLVANIAN		SANDY SHALE		640	685	45	
PENNSYLVANIAN		COAL		685	687	2	
PENNSYLVANIAN		SANDY SHALE		687	850	163	
PENNSYLVANIAN		COAL		850			
PENNSYLVANIAN		SANDSTONE		852	980	128	
PENNSYLVANIAN		SANDY SHALE		980			
PENNSYLVANIAN		COAL		1009			
PENNSYLVANIAN		SANDY SHALE		1011			
PENNSYLVANIAN		COAL		1046			
PENNSYLVANIAN		SANDSTONE		1048			
PENNSYLVANIAN		COAL		1105			
PENNSYLVANIAN		SANDSTONE		1107			
PENNSYLVANIAN		COAL		1211			
PENNSYLVANIAN		SANDSTONE		1213			
PENNSYLVANIAN		COAL		1232			
		SANDSTONE		1234			
PENNSYLVANIAN		COAL		140			
PENNSYLVANIAN				140			
PENNSYLVANIAN		SANDSTONE		1518			
PENNSYLVANIAN		SANDY SHALE		154			
PENNSYLVANIAN		SANDSTONE		160:			
PENNSYLVANIAN		SANDY SHALE		173			
PENNSYLVANIAN		SANDSTONE					2
PENNSYLVANIAN		COAL		214			
PENNSYLVANIAN		SANDSTONE		214			2
PENNSYLVANIAN		COAL		230			
PENNSYLVANIAN		SANDSTONE		230			
PENNSYLVANIAN	DE00000	SANDY SHALE		239			
PENNSYLVANIAN	REDROCK	SHALE		247			
PENNSYLVANIAN		SANDY SHALE		250			
PENNSYLVANIAN		SANDSTONE		263			
MISSISSIPPIAN	RAVENCLIFF	SANDSTONE		290			
MISSISSIPPIAN	MAXTON	SANDSTONE		315			
MISSISSIPPIAN	LITTLE LIME	LIMESTONE		374			
MISSISSIPPIAN	BIG LIME	LIMESTONE		396			
MISSISSIPPIAN	WEIR	SILTSTONE		438			
MISSISSIPPIAN	WEIR SHALE	SHALE		460			
MISSISSIPPIAN	SUNBURY	SHALE		497			6
MISSISSIPPIAN	BEREA	SANDSTONE		503		5 4	9
DEVONIAN	CLEVELAND	SHALE		508			



Commonwealth of Virginia

Department of Mines, Minerals, and Energy

Division of Gas and Oil

P.O. Drawer 159, Lebanon, VA 24266

Telephone: (276) 415-9650

	Tracking N	lumber:	3097	
	Company		Range Resources-Pine Mountair	
	File Numb	er:	BU-4554	
	Completic	on Report Type:	Original	
С	OMPLETION R	EPORT (DGO	-GO-15)	
Well Type:	Gas/Pipeline	Date Well (	Completed: 12/22/2010	
Driller's Total Depth:	5188.00	Log's T	otal Depth: 5202.00	
Description	U(1		FileName	
Changes In Casing/Tubin	g from Approved	Drilling Report		
		<u></u>		
Stimulation Record				
Stimulation Status: Stir	mulated GOB	☐Not Stimulate	ed Service Well	
Description			FileName	
900005 stimu	ulation	9	900005 Stimulation.doc	
Final Production				
Descripti	on		FileName	
900005 final production			Final_Prod.xls	
300000 miai pi				

Notes:

5. Signature

Ву:

Permittee: Range Resources-Pine Mountain

Date: 11/8/2011

(Company)

\_\_\_\_\_

Jonathan Horne

Title:

Engineering Tech

(Signature)

INTERNAL USE ONLY

Submit Date:

11/8/2011

Status:

Approved

Date:

3/5/2012

Final PDF Date:

3/6/2012

# STIMULATION RECORD

CONE 1: Berea	Formation Stimulated With: 75Q F	oam
Perforated 5054 to 5079 feet No. of Pe	erforations 23 Perforation Size	.52
Formation Broke down at: 2671 PSIG	Average Injection Rate: 38 BPM	
ISIP 335 PSIG 2 Min SIP 0 PSIG Average	Average Injection Rate: 38 BPM ge Downhole Injection Pressure 2770	PSIG
Stimulated: No Date Stimulated:		
ZONE 2: Weir	Formation Stimulated With: 75Q F	oam
Perforated 4526 to 4555 feet No. of Perforated 4526 to 4555 feet No. of Perforated N	erforations 24 Perforation Size	.52
Formation Broke down at: 3082 PSIG	Average Injection Rate: 38 BPM	
ISIP 296 PSIG 2 Min SIP 0 PSIG Avera	ge Downhole Injection Pressure 2611	PSIG
Stimulated: Yes No Date Stimulated:		
ZONE 3: Big Lime	Formation Stimulated With: 60Q F	oam
Perforated 4161 to 4345 feet No. of Perforated N	erforations 39 Perforation Size	.32
Formation Broke down at: 1881 PSIG	Average Injection Rate: 18 BPM	
ISIP 2219 PSIG 2 Min SIP 0 PSIG Avera	ge Downhole Injection Pressure 3388	PSIG
Stimulated: X Yes No Date Stimulated:		
ZONE 4: Maxton	Formation Stimulated With: 75Q F	oam
Perforated 3259 to 3287 feet No. of P	erforations 33 Perforation Size	.43
Formation Broke down at: 2716 PSIG	Average Injection Rate: 30 BPM	[
ISIP 1640 PSIG 2 Min SIP 0 PSIG Avera	age Downhole Injection Pressure 3177	PSIG
Stimulated: Yes No Date Stimulated:	12/22/2010	
ZONE 5: Ravencliff	Formation Stimulated With: 75Q I	Foam
Perforated 2909 to 2942 feet No. of P	erforations 37 Perforation Size	.43
Formation Broke down at: 1559 PSIG	Average Injection Rate: 30.5 BPM	1
ISIP 2468 PSIG 2 Min SIP 2235 PSIG Avera	age Downhole Injection Pressure 2917	PSIG
Stimulated: Xes No Date Stimulated:		

Final Production After Stimulatio	n		
BC	DD MCFD	<b>Hours Tested</b>	Rock Pressure
Zone 1			
Zone 2			
Zone 3			_
Final/Commingled Zones	1274	3	500



June 25, 2025

Mr. Ryan Hancharick Source Water & UIC Section Water Division U.S. EPA Region 3 Four Penn Center 1600 John F. Kennedy Blvd. Philadelphia, PA 19103

Mr. Hancharick:

EnerVest is submitting this additional information for the permit application in response to NOD, to renew proposed Permit #VAS2D955BBUC Class II-D fluid disposal well in the Prater area of Buchanan County, Virginia.

Please contact me with any questions and/or further requested information (276) 730-5617.

Sincerely,

Jon Lawson

Jon Lawson
Sr. HSE Specialist
jlawson@enervest.net



March 10, 2025

Mr. Jon Lawson Senior HSE Specialist EnerVest Operating, LLC 809 Happy Valley Dr. Clintwood, Virginia 24228

Re: Notice of Deficiency; EnerVest Operating, LLC (EnerVest) Permit Application; VAS2D955BBUC Underground Injection Control (UIC) Program; Class IID Injection Well 900146

Dear Mr. Lawson:

On January 22, 2025, the U.S. Environmental Protection Agency (the EPA) received your UIC permit renewal application for one (1) disposal injection well (Class IID) in Buchanan County, Virginia.

The technical review for the application began on January 22, 2025. Critical information regarding the wells within the Area of Review (AOR), zone of endangering influence, underground source(s) of drinking water (USDW), the injection well schematic, and the list of property owners around the injection well was found to be incomplete or missing. The EPA requires that EnerVest submit additional information to address certain deficiencies before we can continue processing the application. The deficiencies are as follows:

- 1. For all wells found to be within the AOR and identified on the maps within the permit application, the applicant must also submit wellbore records reasonably available from public records or otherwise known to the applicant on all wells within the AOR included on the maps. Specifically, key information for the BU-3236 (Haysi 26) and BU-3244 (Haysi 24) wells is not provided. While EnerVest did provide information including well name, well type, and the date the well was drilled, the following information is missing from the permit application:
  - well construction that includes casing and cement details, including demonstrated or calculated top of cement,
  - cement bond logs (if available), and
  - record of well completion and plugging (if applicable).
- 2. The EPA requests that a zone of endangering influence (ZEI) calculation be completed and included in the permit application to ensure the fixed radius ¼-mile AOR is

adequate. For more information on how to calculate the ZEI using the modified Theis equation, refer to 40 C.F.R. 146(a).

- 3. Although the permit application states that, "The proposed UIC well will be properly separated from all USDW's by thousands of feet of confining strata", no evidence of the location of the lowermost USDW is provided. The permit application does not identify any relevant USDW. The geologic name (if known) and depth to bottom of USDW which may be affected by injection is required to be included in the permit application. The depth of the lowermost USDW needs to be provided.
- 4. The injection well schematic requires clearly labeled depth of the lowermost USDW, injection zone location and name, and confining zone locations and names, as applicable to this injection well.
- 5. The list of property owners around the injection well is required to extend to ½-mile beyond the injection well. The table that was provided in this permit application only lists property owners within ¼-mile radius of the well.

Please send the requested information to Ryan Hancharick at R3 UIC Mailbox@epa.gov. Once the EPA has received the necessary information, we can proceed with processing the draft permit and statement of basis. Thank you for your cooperation on this matter. If you have any questions or concerns, please contact Ryan Hancharick at 215-814-3278.

Sincerely,

KAREN Digitally signed by KAREN CRUMLISH

CRUMLISH Date: 2025.03.10 13:17:02 -04'00'

Karen E. Crumlish, Chief

Drinking Water and Source Water Protection Branch



Commonwealth of Virginia Virginia Department of Energy Gas and Oil 3405 Mountain Empire Road, Big Stone Gap, VA 24219 Telephone: (276) 415-9700

**DRILLERS REPORT** 

Beginning Drilling Date: 01/01/1991 Ending Drilling Date: 4/9/2025

Sorted By: County Type: Completed

Counties: ALL

Operation Types: ALL

**Companies:** EnerVest Operating, LLC

**File Numbers:** Haysi #24 W/PL - BU-3244 - 450270324400

File # Permit #	Company Name Operation Name	API/US Well #	Quadrangle County	Coordinates	Started Completed	Operation Type Status	Form TD
BU-3244 7581-01	EnerVest Operating, LLC Haysi #24 W/PL	450270324400	PRATER BUCHANAN	10403562.0000 3616454.6700	12/27/2006 1/11/2007	Coalbed/Pipeline Producing	2454.00

DGODriller Page 1 of 1



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil

P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

Tracking	Number:	613	
_			

Company: Pine Mountain Oil & Gas

File Number: BU-3244

Operations Name: Haysi #24 W/PL
Operation Type: Coalbed/Pipeline

**Drilling Report Type:** Original

# **DRILLING REPORT (DGO-GO-14)**

	DIVILLING		JK1 (DGG-GG	-14)	
1. Drilling Data					
Date drilling commenced:	12/27/2006	Drilling Contractor:		Noah Horn	
Date drilling completed:	1/11/2007		· ·	: ☑ Rotary ☐ Cable Tool	
Driller's Total Depth (feet):	2,454		3 71		
Log Total Depth (feet):	2,451	_ Co	oal Seam At Total	Depth POCAHONTAS #2	
2. Final Location Plat (as rec	uired by 4 VAC	25-150	-360.C.)		
Permitted State Plane X 920	0,574	Fir	nal Plat State Plar	ne X: 920,577	
Permitted State Plane Y: 335,571		Fir	nal Plat State Plar	ne Y: 335,576	
Plat Previously Submitted Or					
List of Attached Items:					
Descrip	tion			FileName	
Haysi 24 Plat		Haysi 24 Plat.pdf			
3. Geological Data					
Fresh Water At:					
Depth	(in feet)		Rate	Unit of Measure	
	250		1.5	GPM	
Salt Water At:					
Depth	(in feet)		Rate	Unit of Measure	
	1,420		Damp		

Form DGO-GO-14-E Rev. 1/2007

#### Coal Seams

List of Attached Items:

Description	FileName
Haysi 24 Coal	Haysi 24 Coal.xls

#### Gas and Oil Shows

List of Attached Items:

Description	FileName
Haysi 24 Shows	Haysi 24 Shows.xls

#### **4. Electric Logs** (As required by 4VAC25-150-280.A.)

List all logs run: Hi Res GR/Dens/Temp/Audio/Pe/Caliper (Data Pack)

Did logs disclose vertical locations of a coal seam? ☐ Yes ✓ No

## **5. Survey Results** (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName
Haysi 24 Survey	Haysi 24 Survey.xls

#### 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
Haysi 24 Casing	Haysi 24 Casing.xls

#### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

Circ trace to surf on 8?"; grout w/ 23sx Cl A.; Circ 3 bbl to surf. Broke bit @ 1875', partial fishing success; several unsuccessful kick-plugs. Kick off @ 1800', broke cone off bit. Fished out cone. Trip into hole w/  $6\frac{1}{4}$ ", drill to TD. Circ 30+ bbl t

## 8. Drillers Log

Compiled By: Noah Horn

List of Attached Items:

Description	FileName
Haysi 24 Log	Haysi 24 Log.xls

## 9. Comments

10. Signature

Permitee: Pine Mountain Oil & Gas Date: 8/16/2007 (Company)

Signed By: Christian D. Moore Title: Permit/GIS Specialist (Signature)

INTERNAL USE ONLY

Submit Date: 8/16/2007


Status: Inspr Approved Date: 8/30/2007

Final PDF Date: 8/30/2007

Form DGO-GO-14-E

Page 3 of 3

Rev. 1/2007



WELL LOCATION PLAT

COMPANY Pine Mountain Oil & Gas, Inc. WELL NAME AND NUMB	ER <i>Havsi-24</i>
TRACT NO. W.C. Owens ELEVATION 2.016.91' QUADRANGLE Pro	nter
COUNTY <u>Buchanan</u> DISTRICT <u>Prater</u> SCALE <u>1" = 400'</u>	DATE <u>12-27-2006</u>
This Plat is a new plat; an updated plat; or a final location plat _	Χ
Denotes the location of a well on United States topographic Maps, scale	1 to
24,000, latitude and longitude lines being represented by border lines as	shown.
Denotes the location of a well on United States topographic Maps, scale 24,000, latitude and longitude lines being represented by border lines as	1 to

Licensed Professional Engineer or Licensed Land Surveyor

#### Coal Seams

					MI	
NAME	TOP	BOTTOM	THICKNESS	YES	NO	
Aily	876	877	1		NO	
Raven	964	965	1		NO	
Raven	975	976	1		NO	
Jawbone Rider	1079	1081	2		NO	
Jawbone	1114	1115	1		NO	
Tiller	1185	1186	1		NO	
Upper Seaboard	1302	1304	2		NO	
Upper Seaboard	1307	1308	1		NO	
Greasy Creek	1428	1431	3		NO	
Upper Horsepen	1565	1566	1		NO	
Middle Horsepen	1624	1625	1		NO	
War Creek	1698	1699	1		NO	
Beckley	1790	1791	1		NO	
Lower Horsepen	1825	1826	1		NO	
Poco 4	2160	2161	1		NO	
Poco 3	2192	2195	3		NO	
Poco 2	2257	2258	1		NO	

NING IN AREA				
MINED OUT				

Gas and Oil Shows

FORMATION	TOP	BOTTOM	THICKNESS	IPF	(MCFD/BOPD)	PRESSURE	HOURS TESTED
Open Hole TD				1.5N	1		

Survey Results

Depth of Survey	Direction/Distance/Degree From True Vertical
220'	$0^{\circ}$
420'	$0^{\circ}$
600'	0.5°
810'	0.5°
1020'	0.25°
1200	0°
1410'	0.25°
1620'	0.25°
1800'	0.25°
2010'	0.25°
2220'	0°

Casing Program

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented
Conductor	133/8"	0-16'	15"			
Surface	85/8"	0-311'	121/4"	208	No, Grouted	12/27/2006
Water Protection	41/2"	0-2401'	61/2/61/4"	464	Yes	1/11/2007
Tubing	23/8"	0-2307'				

Packers Or Bridge Plugs
Kind/Size/Set

#### Driller's Log

		General		Depth	Depth
Geologic Age	Formation	Lithology	Color	Тор	Bottom
PENN	Lee	SS, SH, Thin Coals		0	876
PENN	Lee	Coal		876	877
PENN	Lee	SS, SH, Thin Coals		877	964
PENN	Lee	Coal		964	965
PENN	Lee	SS, SH, Thin Coals		965	975
PENN	Lee	Coal		975	976
PENN	Lee	SS, SH, Thin Coals		976	1079
PENN	Lee	Coal		1079	1081
PENN	Lee	SS, SH, Thin Coals		1081	1114
PENN	Lee	Coal		1114	1115
PENN	Lee	SS, SH, Thin Coals		1115	1185
PENN	Lee	Coal		1185	1186
PENN	Lee	SS, SH, Thin Coals		1186	1302
PENN	Lee	Coal		1302	1304
PENN	Lee	SS, SH, Thin Coals		1304	1307
PENN	Lee	Coal		1307	1308
PENN	Lee	SS, SH, Thin Coals		1308	1428
PENN	Lee	Coal		1428	1431
PENN	Lee	SS, SH, Thin Coals		1431	1565
PENN	Lee	Coal		1565	1566
PENN	Lee	SS, SH, Thin Coals		1566	1624
PENN	Lee	Coal		1624	1625
PENN	Lee	SS, SH, Thin Coals		1625	1698
PENN	Lee	Coal		1698	1699
PENN	Lee	SS, SH, Thin Coals		1699	1790
PENN	Lee	Coal		1790	1791
PENN	Lee	SS, SH, Thin Coals		1791	1825
PENN	Lee	Coal		1825	1826
PENN	Pocahontas	SS, SH, Thin Coals		1826	2160
PENN	Pocahontas	Coal		2160	2161
PENN	Pocahontas	SS, SH, Thin Coals		2161	2192
PENN	Pocahontas	Coal		2192	2195
PENN	Pocahontas	SS, SH, Thin Coals		2195	2257
PENN	Pocahontas	Coal		2257	2258
PENN	Pocahontas	SS, SH, Thin Coals		2258	2451

Thickness	Remarks
876	
1	
87	
1	
10	
1	
103	
2	
33	
1	
70	
1	
116	
2	
3	
1	
120	
3	
134	
1	
58	
1	
73	
1	
91	
1	
34	
1	
334	
1	
31	
3	
62	
1	
193	



Commonwealth of Virginia Virginia Department of Energy Gas and Oil 3405 Mountain Empire Road, Big Stone Gap, VA 24219 Telephone: (276) 415-9700

#### **COMPLETION REPORT**

Beginning Completion Dt: 01/01/1991 Ending Completion Dt: 4/9/2025

Sorted By: Operation Types

Counties: ALL

Operation Types: ALL

**Companies:** EnerVest Operating, LLC

**File Numbers:** Haysi #24 W/PL - BU-3244 - 450270324400

County	File # Permit #	Company Name Operation Name	API/US Well #	Completion Date Quadrangle	Туре	Coordinates	Form	TD
BUCHANAN	BU-3244 7581-01	EnerVest Operating, LLC Haysi #24 W/PL	450270324400	2/8/2007 PRATER	Coalbed/Pipeline	10403562.0000 3616454.6700		2454.00

DGOCompletion Page 1 of 1



Commonwealth of Virginia Virginia Department of Energy Gas and Oil 3405 Mountain Empire Road, Big Stone Gap, VA 24219 Telephone: (276) 415-9700

#### **COMPLETION REPORT**

Beginning Completion Dt: 01/01/1991 Ending Completion Dt: 4/9/2025

Sorted By: Operation Types

Counties: ALL

Operation Types: ALL

**Companies:** EnerVest Operating, LLC

**File Numbers:** Haysi #26 W/PL - BU-3236 - 450270323600

County	File # Permit #	Company Name Operation Name	API/US Well #	Completion Date Quadrangle	Туре	Coordinates	Form	TD
BUCHANAN	BU-3236 7543-02	EnerVest Operating, LLC Haysi #26 W/PL	450270323600	1/4/2007 PRATER	Coalbed/Pipeline	10404298.0300 3615295.6300		2394.00

DGOCompletion Page 1 of 1



Commonwealth of Virginia
Department of Mines, Minerals, and Energy
Division of Gas and Oil
P.O. Box 1416; Abingdon, VA 24212

Telephone: (276) 676-5423

	T	racking Num	oer:	602		
	C	Company:		Pine Mountain Oil	& Gas	
	F	ile Number:		BU-3236		
	C	Operations Na	me:	Haysi #26 W/PL		
	C	Operation Type:		Coalbed/Pipeline		
	C	Completion Report Type:		Original		
	COMPLET	TON REPO	RT (DGO-	GO-15)		
Well Type:	Coalbed/Pipelir	ne <b>Da</b>	te Well Con	npleted: 1/4/2007		
Driller's Total Depth:	2,394	Lo	g's Total De	epth: 2,330		
I. Changes In Casing/Tubing from Approved Drilling Report						
	scription		FileName			
Haysi 26	Comp Casing		Ha	aysi 26 Comp Casii	ng.xls	
2. Stimulation Record						
Stimulated	] Not Stimulated	☐ Gob				
	scription			FileName		
Haysi 2	26 Stimulation		Haysi 26 Stimulation.doc			
3. Final Production						
Des	scription			FileName		
Haysi 2	26 Final Prod		ŀ	Haysi 26 Final Prod	l.xls	
I. Comments						
Notes:						
5. Signature						
Permittee: Pine Mount	ain Oil & Gas	Date:	8/16/2007	2:56:11 PM	(Company)	
		<del></del>				

Form DGO-GO-15-E

Rev. 1/2007

Ву:	Christian D. Moore	Title: Per	rmit/GIS Specialist	(Signature)
-----	--------------------	------------	---------------------	-------------

INTERNAL USE ONLY

Submit Date: 8/16/2007

Status: Inspr Approved Date: 9/4/2007

Final PDF Date: 9/4/2007

Form DGO-GO-15-E

**Casing Program** 

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented
Conductor	113/4"	0-52'	15"			
Surface	85/8"	0-310'	101/8"	110 sx	No	11/28/2006
Water Protection	41/2"	0-2341'	61/2"	215 sx	Yes	12/1/2006
Tubing	2 3/8"	0-2291'				

Packers Or Bridge Plugs
Kind/Size/Set

#### STIMULATION RECORD

ZONE 1: Poco 3, X seam x 2, Poco 2 & 1 Perforated 2126 to 2244.4 feet No. of Perforation 1	Formation Stimulated With:	Gel+N <sub>2</sub> Foam
Formation Broke down at: 2382 PSIG ISIP 1492 PSIG 5 Min SIP 1415 PSIG Avera	Average Injection Rate: 25.8	
Stimulated: Yes No Date Stimulated:	· ·	<u> 2000</u> 1310
Stillulated. A les I no Date Stillulated.	1/4/07	
ZONE 2: U & M Hpen, War Creek & L Hpen	Formation Stimulated With:	Gel+N <sub>2</sub> Foam
Perforated 1500 to 1765 feet No of Pe	erforations 24 Perforation	1 Size <u>0.33</u>
	Average Injection Rate: 23.6	
ISIP 1616 PSIG 5 Min SIP N/A PSIG Average	=	<u>2804</u> PSIG
Stimulated: Yes	1/4/07	
ZONE 3: Upper Seaboard x 2 & Greasy Creek	Formation Stimulated With:	Gel+N <sub>2</sub> Foam
Perforated 1193.5 to 1351.5 feet No. of Pe	erforations 25 Perforation	n Size 0.33
Formation Broke down at: 1497 PSIG	Average Injection Rate: 24.5	
ISIP PSIG 5 Min SIP PSIG Avera	ge Downhole Injection Pressure	3188 PSIG
Stimulated:  Yes	1/5/07	
ZONE 4: Jawbone Rider, Jawbone & Tiller Perforated 996.5 to 1099.5 feet No. of Perforation No. of Perforatio	Formation Stimulated With:	Gel+N <sub>2</sub> Foam
Perforated 996.5 to 1099.5 feet No. of Pe	erforations 30 Perforation	1 Size 0.33
Formation Broke down at: 1805 PSIG	Average Injection Rate: 26.3	BPM
ISIP 1016 PSIG 5 Min SIP N/A PSIG Average	ge Downhole Injection Pressure	
Stimulated: Yes	1/5/07	
ZONE 5: Aily & Raven x2	Formation Stimulated With:	Gel+N <sub>2</sub> Foam
	erforations 25 Perforation	1 Size 0.33
Formation Broke down at: 1985 PSIG	Average Injection Rate: 24	
ISIP 1634 PSIG 5 Min SIP 962 PSIG Avera	ge Downhole Injection Pressure	2427 PSIG
Stimulated:  Yes	1/5/07	

Final Production After Stimulation				
	BOD	MCFD	<b>Hours Tested</b>	Rock Pressure
Zone 1				
Zone 2				
Zone 3				
Final/Commingled Zones				



Commonwealth of Virginia Virginia Department of Energy Gas and Oil 3405 Mountain Empire Road, Big Stone Gap, VA 24219 Telephone: (276) 415-9700

**DRILLERS REPORT** 

Beginning Drilling Date: 01/01/1991 Ending Drilling Date: 4/9/2025

Sorted By: County Type: Completed

Counties: ALL

Operation Types: ALL

**Companies:** EnerVest Operating, LLC

**File Numbers:** Haysi #26 W/PL - BU-3236 - 450270323600

File # Permit #	Company Name Operation Name	API/US Well #	Quadrangle County	Coordinates	Started Completed	Operation Type Status	Form TD
BU-3236 7543-02	EnerVest Operating, LLC Haysi #26 W/PL	450270323600	PRATER BUCHANAN	10404298.0300 3615295.6300	11/20/2006 12/1/2006	Coalbed/Pipeline Producing	2394.00

DGODriller Page 1 of 1



Commonwealth of Virginia Department of Mines, Minerals, and Energy Division of Gas and Oil

P.O. Box 1416; Abingdon, VA 24212

Pine Mountain Oil & Gas

Telephone: (276) 676-5423

Haysi #26 W/PL

614

BU-3236

	-	on Type: Report Type:	Coalbed/Pip Original	peline	
	PORT (DGC	D-GO-14)			
1. Drilling Data					
Date drilling commenced:	11/20/2006	Drilling Contra	actor: Noa	ah Horn	
Date drilling completed:	12/1/2006	· ·	Rig Type: 🗹 Rotary 🔲 Cable Too		
Driller's Total Depth (feet):	2,394		, .,   -,		
Log Total Depth (feet):	2,330	Coal Seam At	Total Depth	POCAHONTAS #2	
2. Final Location Plat (as rec	uired by 4 VAC25-1	50-360.C.)			
Permitted State Plane X 92	Final Plat Stat	e Plane X: <u>9</u> 2	21,313		
Permitted State Plane Y: 334	Final Plat Stat	e Plane Y: 3	34,417		
☐ Plat Previously Submitted	Or				
List of Attached Items:					
Descrip		File	Name		
Haysi 26		Haysi 2	26 Plat.pdf		
3. Geological Data					
Fresh Water At:					
Depth	Depth (in feet)			Unit of Measure	

**Tracking Number:** 

Company:

File Number:
Operations Name:

Form DGO-GO-14-E Rev. 1/2007

Salt Water At:

Depth (in feet)

1,110

Rate

Damp

Unit of Measure

#### Coal Seams

List of Attached Items:

Description	FileName
Haysi 26 Coal	Haysi 26 Coal.xls

#### Gas and Oil Shows

List of Attached Items:

Description	FileName
Haysi 26 Shows	Haysi 26 Shows.xls

#### **4. Electric Logs** (As required by 4VAC25-150-280.A.)

List all logs run: Hi Res GR/Dens/Temp/Audio/Pe/Caliper (Data Pack)

Did logs disclose vertical locations of a coal seam? ☐ Yes ✓ No

#### **5. Survey Results** (As required by 4VAC25-150-280.B.2)

List of Attached Items:

Description	FileName
Haysi 26 Survey	Haysi 26 Survey.xls

#### 6. Casing and Tubing Program

List of Attached Items:

Description	FileName
Haysi 26 Casing	Haysi 26 Casing.xls

#### 7. Remarks

Use this space to note any conditions or occurrences, such as lost circulation, fishing jobs, junk left in hole, sidetracks, squeeze jobs, etc., not shown above. Include data and depth of condition/occurence.

No Circ on 8?" Hole, Grout w 30sx to surf. Circ 10 bbls to surf on 6½ hole.

#### 8. Drillers Log

Compiled By: Noah Horn

List of Attached Items:

Description	FileName
Haysi 26 Log	Haysi 26 Log.xls

#### 9. Comments

10. Signature

Permitee: Pine Mountain Oil & Gas Date: 8/16/2007 (Company)

Signed By: Christian D. Moore Title: Permit/GIS Specialist (Signature)

INTERNAL USE ONLY

Submit Date: 8/16/2007


Status: Inspr Approved Date: 8/30/2007

Final PDF Date: 8/30/2007

Form DGO-GO-14-E

Page 3 of 3

Rev. 1/2007



on the well plat dated 8-17-2006.

Well elevation determined by GPS Survey from BM MCD 229 FINAL PLAT

Area of Unit = 58.77 Ac.

Well Coordinates: (Clinchfield Coal Co.) N 34,143.85 E 52,282.72

#### WELL LOCATION PLAT

#### Coal Seams

		MINING IN AREA				
NAME	TOP	BOTTOM	THICKNESS	YES	NO	MINED OUT
Aily	808	809	1		NO	
Raven	895	896	1		NO	
Raven	901	902	1		NO	
Jawbone Rider	998	1000	2		NO	
Jawbone	1032	1034	2		NO	
Tiller	1098	1099	1		NO	
Upper Seaboard	1194	1195	1		NO	
Upper Seaboard	1217	1218	1		NO	
Greasy Creek	1349	1351	2		NO	
Upper Horsepen	1501	1502	1		NO	
Middle Horsepen	1570	1571	1		NO	
War Creek	1640	1641	1		NO	
Lower Horsepen	1764	1765	1		NO	
Poco 3	2126	2129	3		NO	
Unknown	2136	2137	1		NO	
Unknown	2145	2146	1		NO	
Poco 2	2209	2210	1		NO	

#### Gas and Oil Shows

FORMATION	TOP	BOTTOM	THICKNESS	IPF	(MCFD/BOPD)	PRESSURE	HOURS TESTED
Open Hole TD				Trac	ce		
Cased Hole TD					0		

**Survey Results** 

Depth of Survey	Direction/Distance/Degree From True Vertical
200	1/4°
400	1/2°
600	1/2°
800	1⁄4°
1000	1⁄4°
1200	1⁄4°
1400	1/4°
1600	1/2°
1800	1/2°
2000	3∕4°

**Casing Program** 

	Casing	Casing	Hole	Cement Used	Cemented To Surface	Date
Casing Type	Size	Interval	Size	In Cubic Ft.	Yes/No	Cemented
Conductor	113/4"	0-52'	15"			
Surface	85/8"	0-310'	107/8"	110 sx	No	11/28/2006
Water Protection	41/2"	0-2341'	61/2"	215 sx	Yes	12/1/2006
Tubing	2 3/8"	0-2291'				

Packers Or Bridge Plugs
Kind/Size/Set


#### Driller's Log


PENN         Lee         Coal         808           PENN         Lee         SS, SH, Thin Coals         809           PENN         Lee         Coal         899           PENN         Lee         SS, SH, Thin Coals         890           PENN         Lee         Coal         901           PENN         Lee         Coal         902           PENN         Lee         Coal         992           PENN         Lee         Coal         1032           PENN         Lee         Coal         1093           PENN         Lee         SS, SH, Thin Coals         1095           PENN         Lee         Coal         1192           PENN         Lee         Coal         1213           PENN         Lee         Coal         1213           PENN         Lee         SS, SH, Thin Coals         1351 </th <th></th> <th></th> <th>General</th> <th></th> <th>Depth</th>			General		Depth
PENN         Lee         Coal         808           PENN         Lee         SS, SH, Thin Coals         809           PENN         Lee         Coal         899           PENN         Lee         SS, SH, Thin Coals         890           PENN         Lee         Coal         901           PENN         Lee         Coal         902           PENN         Lee         Coal         992           PENN         Lee         Coal         1006           PENN         Lee         Coal         1032           PENN         Lee         Coal         1099           PENN         Lee         Coal         1194           PENN         Lee         Coal         1194           PENN         Lee         Coal         1212           PENN         Lee         Coal         1212           PENN         Lee         Coal         1342		Formation		Color	Тор
PENN         Lee         SS, SH, Thin Coals         809           PENN         Lee         Coal         895           PENN         Lee         SS, SH, Thin Coals         896           PENN         Lee         Coal         901           PENN         Lee         Coal         902           PENN         Lee         Coal         998           PENN         Lee         Coal         1006           PENN         Lee         Coal         1006           PENN         Lee         Coal         1032           PENN         Lee         Coal         1098           PENN         Lee         Coal         1098           PENN         Lee         Coal         1098           PENN         Lee         Coal         1192           PENN         Lee         Coal         1192           PENN         Lee         Coal         1213           PENN         Lee         Coal         1218           PENN         Lee         Coal         1343           PENN         Lee         Coal         1501           PENN         Lee         Coal         1502	PENN	Lee	SS, SH, Thin Coals		0
PENN         Lee         Coal         895           PENN         Lee         SS, SH, Thin Coals         896           PENN         Lee         Coal         901           PENN         Lee         SS, SH, Thin Coals         902           PENN         Lee         Coal         998           PENN         Lee         Coal         1003           PENN         Lee         Coal         1032           PENN         Lee         Coal         1098           PENN         Lee         Coal         1098           PENN         Lee         Coal         1098           PENN         Lee         Coal         1194           PENN         Lee         Coal         1194           PENN         Lee         Coal         1217           PENN         Lee         Coal         1218           PENN         Lee         SS, SH, Thin Coals         1218           PENN         Lee         SS, SH, Thin Coals         1351           PENN         Lee         Coal         1501           PENN         Lee         Coal         1502           PENN         Lee         Coal <td< td=""><td>PENN</td><td>Lee</td><td>Coal</td><td></td><td>808</td></td<>	PENN	Lee	Coal		808
PENN         Lee         SS, SH, Thin Coals         896           PENN         Lee         Coal         901           PENN         Lee         SS, SH, Thin Coals         902           PENN         Lee         Coal         998           PENN         Lee         SS, SH, Thin Coals         1006           PENN         Lee         Coal         1032           PENN         Lee         Coal         1098           PENN         Lee         Coal         1098           PENN         Lee         Coal         1099           PENN         Lee         Coal         1194           PENN         Lee         Coal         1199           PENN         Lee         Coal         1217           PENN         Lee         Coal         1217           PENN         Lee         Coal         1217           PENN         Lee         Coal         1349           PENN         Lee         Coal         1217           PENN         Lee         Coal         1349           PENN         Lee         SS, SH, Thin Coals         1351           PENN         Lee         SS, SH, Thin Coals </td <td>PENN</td> <td>Lee</td> <td>SS, SH, Thin Coals</td> <td></td> <td>809</td>	PENN	Lee	SS, SH, Thin Coals		809
PENN         Lee         Coal         901           PENN         Lee         SS, SH, Thin Coals         902           PENN         Lee         Coal         998           PENN         Lee         SS, SH, Thin Coals         1006           PENN         Lee         Coal         1032           PENN         Lee         Coal         1098           PENN         Lee         Coal         1194           PENN         Lee         SS, SH, Thin Coals         1194           PENN         Lee         Coal         1217           PENN         Lee         Coal         1217           PENN         Lee         Coal         1349           PENN         Lee         SS, SH, Thin Coals         1216           PENN         Lee         SS, SH, Thin Coals         1351           PENN         Lee         SS, SH, Thin Coals         1577           PENN         Lee	PENN	Lee	Coal		895
PENN         Lee         SS, SH, Thin Coals         902           PENN         Lee         Coal         998           PENN         Lee         SS, SH, Thin Coals         1000           PENN         Lee         Coal         1032           PENN         Lee         SS, SH, Thin Coals         1098           PENN         Lee         Coal         1098           PENN         Lee         SS, SH, Thin Coals         1099           PENN         Lee         Coal         1194           PENN         Lee         Coal         1194           PENN         Lee         Coal         1217           PENN         Lee         Coal         1217           PENN         Lee         Coal         1218           PENN         Lee         Coal         1349           PENN         Lee         Coal         1218           PENN         Lee         Coal         1349           PENN         Lee         Coal         1349           PENN         Lee         Coal         1349           PENN         Lee         Coal         1349           PENN         Lee         SS, SH, Thin Coals	PENN	Lee	SS, SH, Thin Coals		896
PENN         Lee         Coal         998           PENN         Lee         SS, SH, Thin Coals         1000           PENN         Lee         Coal         1032           PENN         Lee         SS, SH, Thin Coals         1098           PENN         Lee         Coal         1098           PENN         Lee         SS, SH, Thin Coals         1099           PENN         Lee         Coal         1192           PENN         Lee         Coal         1217           PENN         Lee         Coal         1218           PENN         Lee         Coal         1218           PENN         Lee         Coal         1218           PENN         Lee         Coal         1218           PENN         Lee         Coal         1349           PENN         Lee         Coal         1350           PENN         Lee         Coal         1500	PENN	Lee	Coal		901
PENN         Lee         SS, SH, Thin Coals         1000           PENN         Lee         Coal         1032           PENN         Lee         SS, SH, Thin Coals         1098           PENN         Lee         Coal         1098           PENN         Lee         SS, SH, Thin Coals         1192           PENN         Lee         Coal         1194           PENN         Lee         Coal         1217           PENN         Lee         Coal         1218           PENN         Lee         Coal         1218           PENN         Lee         Coal         1349           PENN         Lee         Coal         1349           PENN         Lee         Coal         1501           PENN         Lee         Coal         1502 <td>PENN</td> <td>Lee</td> <td>SS, SH, Thin Coals</td> <td></td> <td>902</td>	PENN	Lee	SS, SH, Thin Coals		902
PENN         Lee         Coal         1032           PENN         Lee         SS, SH, Thin Coals         1034           PENN         Lee         Coal         1098           PENN         Lee         SS, SH, Thin Coals         1099           PENN         Lee         Coal         1194           PENN         Lee         Coal         1217           PENN         Lee         Coal         1217           PENN         Lee         Coal         1218           PENN         Lee         Coal         1349           PENN         Lee         Coal         1501           PENN         Lee         Coal         1502	PENN	Lee	Coal		998
PENN         Lee         SS, SH, Thin Coals         1032           PENN         Lee         Coal         1098           PENN         Lee         SS, SH, Thin Coals         1099           PENN         Lee         Coal         1192           PENN         Lee         SS, SH, Thin Coals         1213           PENN         Lee         Coal         1214           PENN         Lee         Coal         1349           PENN         Lee         SS, SH, Thin Coals         1350           PENN         Lee         SS, SH, Thin Coals         1502           PENN         Lee         SS, SH, Thin Coals         1570           PENN         Pocahontas         SS, SH, Thin Coals         1640           PENN	PENN	Lee	SS, SH, Thin Coals		1000
PENN         Lee         Coal         1098           PENN         Lee         SS, SH, Thin Coals         1099           PENN         Lee         Coal         1194           PENN         Lee         SS, SH, Thin Coals         1217           PENN         Lee         Coal         1218           PENN         Lee         Coal         1349           PENN         Lee         SS, SH, Thin Coals         1349           PENN         Lee         Coal         1500           PENN         Lee         SS, SH, Thin Coals         1570           PENN         Lee         SS, SH, Thin Coals         1571           PENN         Pocahontas         SS, SH, Thin Coals         1762           PENN         Pocahontas         SS, SH, Thin Coals         2126           PEN	PENN	Lee	Coal		1032
PENN         Lee         SS, SH, Thin Coals         1099           PENN         Lee         Coal         1192           PENN         Lee         SS, SH, Thin Coals         1217           PENN         Lee         Coal         1218           PENN         Lee         SS, SH, Thin Coals         1349           PENN         Lee         Coal         1349           PENN         Lee         SS, SH, Thin Coals         1351           PENN         Lee         Coal         1501           PENN         Lee         SS, SH, Thin Coals         1570           PENN         Lee         Coal         1570           PENN         Lee         SS, SH, Thin Coals         1571           PENN         Lee         SS, SH, Thin Coals         1640           PENN         Lee         Coal         1764           PENN         Pocahontas         SS, SH, Thin Coals         2125           PENN         Pocahontas         SS, SH, Thin Coals         2125           PENN         Pocahontas         SS, SH, Thin Coals         2136           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas	PENN	Lee	SS, SH, Thin Coals		1034
PENN         Lee         Coal         1194           PENN         Lee         SS, SH, Thin Coals         1195           PENN         Lee         Coal         1217           PENN         Lee         SS, SH, Thin Coals         1218           PENN         Lee         Coal         1349           PENN         Lee         Coal         1351           PENN         Lee         Coal         1501           PENN         Lee         Coal         1570           PENN         Lee         Coal         1570           PENN         Lee         Coal         1570           PENN         Lee         Coal         1570           PENN         Lee         Coal         1640           PENN         Lee         Coal         1640           PENN         Lee         Coal         1764           PENN         Pocahontas         SS, SH, Thin Coals         1765           PENN         Pocahontas         SS, SH, Thin Coals         2126           PENN         Pocahontas         SS, SH, Thin Coals         2136           PENN         Pocahontas         SS, SH, Thin Coals         2137           PEN	PENN	Lee	Coal		1098
PENN         Lee         SS, SH, Thin Coals         1195           PENN         Lee         Coal         1217           PENN         Lee         SS, SH, Thin Coals         1218           PENN         Lee         Coal         1349           PENN         Lee         SS, SH, Thin Coals         1351           PENN         Lee         Coal         1501           PENN         Lee         SS, SH, Thin Coals         1572           PENN         Lee         Coal         1574           PENN         Lee         Coal         1646           PENN         Lee         Coal         1764           PENN         Lee         Coal         1764           PENN         Pocahontas         SS, SH, Thin Coals         1765           PENN         Pocahontas         Coal         2126           PENN         Pocahontas         SS, SH, Thin Coals         2126           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas         SS,	PENN	Lee	SS, SH, Thin Coals		1099
PENN         Lee         Coal         1217           PENN         Lee         SS, SH, Thin Coals         1218           PENN         Lee         Coal         1349           PENN         Lee         SS, SH, Thin Coals         1351           PENN         Lee         Coal         1501           PENN         Lee         SS, SH, Thin Coals         1570           PENN         Lee         Coal         1571           PENN         Lee         SS, SH, Thin Coals         1640           PENN         Lee         Coal         1640           PENN         Lee         Coal         1762           PENN         Pocahontas         SS, SH, Thin Coals         1765           PENN         Pocahontas         Coal         2120           PENN         Pocahontas         SS, SH, Thin Coals         2126           PENN         Pocahontas         SS, SH, Thin Coals         2136           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas	PENN	Lee	Coal		1194
PENN         Lee         SS, SH, Thin Coals         1218           PENN         Lee         Coal         1349           PENN         Lee         SS, SH, Thin Coals         1351           PENN         Lee         Coal         1500           PENN         Lee         SS, SH, Thin Coals         1570           PENN         Lee         Coal         1570           PENN         Lee         Coal         1570           PENN         Lee         Coal         1640           PENN         Lee         Coal         1640           PENN         Lee         Coal         1764           PENN         Pocahontas         SS, SH, Thin Coals         1765           PENN         Pocahontas         SS, SH, Thin Coals         2126           PENN         Pocahontas         SS, SH, Thin Coals         2136           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas         SS, SH, Thin Coals         2145           PENN         Pocahontas         SS, SH, Thin Coals         2146	PENN	Lee	SS, SH, Thin Coals		1195
PENN         Lee         Coal         1349           PENN         Lee         SS, SH, Thin Coals         1351           PENN         Lee         Coal         1501           PENN         Lee         SS, SH, Thin Coals         1570           PENN         Lee         Coal         1571           PENN         Lee         SS, SH, Thin Coals         1640           PENN         Lee         SS, SH, Thin Coals         1764           PENN         Lee         Coal         1764           PENN         Pocahontas         SS, SH, Thin Coals         1765           PENN         Pocahontas         SS, SH, Thin Coals         2126           PENN         Pocahontas         Coal         2136           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas         Coal         2145           PENN         Pocahontas         Coal         2145           PENN         Pocahontas         SS, SH, Thin Coals         2146           PENN         Pocahontas         SS, SH, Thin Coals         2146	PENN	Lee	Coal		1217
PENN         Lee         SS, SH, Thin Coals         1351           PENN         Lee         Coal         1501           PENN         Lee         SS, SH, Thin Coals         1502           PENN         Lee         Coal         1570           PENN         Lee         SS, SH, Thin Coals         1640           PENN         Lee         Coal         1641           PENN         Lee         Coal         1762           PENN         Pocahontas         SS, SH, Thin Coals         1763           PENN         Pocahontas         Coal         2126           PENN         Pocahontas         Coal         2136           PENN         Pocahontas         Coal         2137           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas         Coal         2145           PENN         Pocahontas         SS, SH, Thin Coals         2145           PENN         Pocahontas         SS, SH, Thin Coals         2146	PENN	Lee	SS, SH, Thin Coals		1218
PENN         Lee         Coal         1501           PENN         Lee         SS, SH, Thin Coals         1502           PENN         Lee         Coal         1570           PENN         Lee         SS, SH, Thin Coals         1640           PENN         Lee         SS, SH, Thin Coals         1641           PENN         Lee         Coal         1764           PENN         Pocahontas         SS, SH, Thin Coals         1765           PENN         Pocahontas         Coal         2126           PENN         Pocahontas         SS, SH, Thin Coals         2126           PENN         Pocahontas         SS, SH, Thin Coals         2136           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas         SS, SH, Thin Coals         2145           PENN         Pocahontas         SS, SH, Thin Coals         2145	PENN	Lee	Coal		1349
PENN         Lee         SS, SH, Thin Coals         1502           PENN         Lee         Coal         1570           PENN         Lee         SS, SH, Thin Coals         1571           PENN         Lee         Coal         1640           PENN         Lee         SS, SH, Thin Coals         1641           PENN         Pocahontas         SS, SH, Thin Coals         1762           PENN         Pocahontas         Coal         2126           PENN         Pocahontas         SS, SH, Thin Coals         2129           PENN         Pocahontas         SS, SH, Thin Coals         2136           PENN         Pocahontas         SS, SH, Thin Coals         2137           PENN         Pocahontas         Coal         2145           PENN         Pocahontas         SS, SH, Thin Coals         2145           PENN         Pocahontas         SS, SH, Thin Coals         2146	PENN	Lee	SS, SH, Thin Coals		1351
PENN Lee SS, SH, Thin Coals PENN Lee SS, SH, Thin Coals PENN Lee Coal 1640 PENN Lee SS, SH, Thin Coals PENN Lee Coal 1764 PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas Coal 2120 PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas Coal 2130 PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals	PENN	Lee	Coal		1501
PENN Lee SS, SH, Thin Coals  PENN Lee Coal 1640  PENN Lee SS, SH, Thin Coals 1641  PENN Lee Coal 1764  PENN Pocahontas SS, SH, Thin Coals 1765  PENN Pocahontas Coal 2126  PENN Pocahontas SS, SH, Thin Coals 2126  PENN Pocahontas Coal 2136  PENN Pocahontas Coal 2136  PENN Pocahontas SS, SH, Thin Coals 2136  PENN Pocahontas SS, SH, Thin Coals 2136  PENN Pocahontas Coal 2146	PENN	Lee	SS, SH, Thin Coals		1502
PENN Lee Coal 1640 PENN Lee SS, SH, Thin Coals 1641 PENN Lee Coal 1764 PENN Pocahontas SS, SH, Thin Coals 1765 PENN Pocahontas Coal 2126 PENN Pocahontas SS, SH, Thin Coals 2126 PENN Pocahontas Coal 2136 PENN Pocahontas SS, SH, Thin Coals 2136 PENN Pocahontas SS, SH, Thin Coals 2137 PENN Pocahontas Coal 2136 PENN Pocahontas Coal 2146	PENN	Lee	Coal		1570
PENN Lee SS, SH, Thin Coals PENN Lee Coal 1764 PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas Coal 2126 PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas Coal 2136 PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals	PENN	Lee	SS, SH, Thin Coals		1571
PENN Lee Coal 1764 PENN Pocahontas SS, SH, Thin Coals 1765 PENN Pocahontas Coal 2126 PENN Pocahontas SS, SH, Thin Coals 2129 PENN Pocahontas Coal 2136 PENN Pocahontas SS, SH, Thin Coals 2137 PENN Pocahontas Coal 2137 PENN Pocahontas Coal 2145 PENN Pocahontas SS, SH, Thin Coals 2146	PENN	Lee	Coal		1640
PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas Coal 2126 PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas Coal 2136 PENN Pocahontas SS, SH, Thin Coals PENN Pocahontas SS, SH, Thin Coals 2137 PENN Pocahontas Coal 2145 PENN Pocahontas SS, SH, Thin Coals 2146	PENN	Lee	SS, SH, Thin Coals		1641
PENN Pocahontas Coal 2126 PENN Pocahontas SS, SH, Thin Coals 2129 PENN Pocahontas Coal 2136 PENN Pocahontas SS, SH, Thin Coals 2137 PENN Pocahontas Coal 2145 PENN Pocahontas SS, SH, Thin Coals 2146	PENN	Lee	Coal		1764
PENNPocahontasSS, SH, Thin Coals2129PENNPocahontasCoal2136PENNPocahontasSS, SH, Thin Coals2137PENNPocahontasCoal2145PENNPocahontasSS, SH, Thin Coals2146	PENN	Pocahontas	SS, SH, Thin Coals		1765
PENNPocahontasSS, SH, Thin Coals2129PENNPocahontasCoal2136PENNPocahontasSS, SH, Thin Coals2137PENNPocahontasCoal2145PENNPocahontasSS, SH, Thin Coals2146	PENN	Pocahontas	Coal		2126
PENNPocahontasSS, SH, Thin Coals2137PENNPocahontasCoal2145PENNPocahontasSS, SH, Thin Coals2146			SS, SH, Thin Coals		2129
PENNPocahontasSS, SH, Thin Coals2137PENNPocahontasCoal2145PENNPocahontasSS, SH, Thin Coals2146	PENN	Pocahontas	, ,		2136
PENNPocahontasCoal2145PENNPocahontasSS, SH, Thin Coals2146	PENN	Pocahontas	SS, SH, Thin Coals		2137
PENN Pocahontas SS, SH, Thin Coals 2146			, ,		2145
	PENN				2146
	PENN	Pocahontas			2209

Depth		
Bottom	Thickness	Remarks
808	808	
809	1	
895	86	
896	1	
901	5	
902	1	
998	96	
1000	2	
1032	32	
1034	2	
1098	64	
1099	1	
1194	95	
1195	1	
1217	22	
1218	1	
1349	131	
1351	2	
1501	150	
1502	1	
1570	68	
1571	1	
1640	69	
1641	1	
1764	123	
1765	1	
2126	361	
2129	3	
2136	7	
2137	1	
2145	8	
2146	1	
2209	63	
2210	1	

	SURFACE BASE USDW INJEC	2000 1500	2000 1500	2000 1500	2000 1500	2000 1500	353.69 2000 1500 -2250	2000 1500	2000 1500	2000 1500	2000 1500	2000 1500	2000 1500	2000 1500	2000 1500	2000 1500	2000 1500	2000 1500	2000 1500	2000 1500	2000 1500	
	ressure WATER LEVEL						1211.95 353															
	DISTANCE, ft. pre	(1			•																1250 31	
	c			•			314.7 Note: add 14.7 to psig for psia	217 Note: injection is negative	10	2-	1 075	) -	- •	- 0	500000		DUUC	4250	1050	201		500 1430.831
)	WELL NAME			DATE OF ANALTSIS ***********************************	רוסו	SOUTHWACAGINGITAMOON	WELL AND FORMATION PARAMETERS	initial pressure at the top of the Injection formation, p(1) (psia)	njection rate, q (bwpd)	length of injection time, (months)	viscosity, mu (cp.)	specific gravity of liquid	formation volume factor, beta ( ) for aqueous liquids)			ps()	porosity, pni, ratio	surface elevation N.B. (II.)	depth to injection zone, (it)	end of cross-section, (It.)	CALCULATION OF CRITICAL PRESSURE RISE	depth of concern, feet below KB (ft.)

## HYDRAULIC HEAD RELATION TO SURFACE AND BASE OF USDW





1400

1200


600 800 DISTANCE FROM WELL, ft.


400

200

# RADIAL DISTRIBUTION OF PRESSURE AROUND WELL OF CONCERN

-255.3367	1.98E-06
linear term	E(i) term





#### 1.0 UNDERGROUND DRINKING WATER SOURCES

Underground sources of drinking water within the Area of Review are generally located within the unconsolidated alluvium/colluvium deposits and the associated Norton Formation along local stream elevation. Groundwater is typically found at depths within 300 feet of the topographic expression of the local stream grade.

The ground water user inventory conducted in the Area of Review identified no sources of drinking water.

Underground sources of drinking water would be expected to occur between depths of 200 feet and 760 feet related to the surface elevation of the SWD well, or approximately 3500 feet vertically above the target disposal zone.

#### 2.0 GROUNDWATER DEPTHS

As stated in Section 1.0, no groundwater drinking water sources or users were found to exist within the ¼-mile radius the proposed well. The driller's log for the nearby SWD well (BU-1614 23606) reported no occurrence of fresh groundwater when the well was drilled, only "damp hole conditions" at 100 feet and 775 feet below the ground surface. No measurable flow of fresh groundwater was observed at any depth during the drilling of this well.

A review of the driller's log and completion reports for the coal bed methane wells within  $\frac{1}{4}$ -mile radius of this proposed well 900146 (VAS2D955BBUC) provided the following conditions:

- **Haysi 4**: A fresh groundwater zone was encounted at 70 feet below ground surface with a 1 gpm/1"stream.
- Haysi 8: No fresh groundwater zones were encountered.
- Haysi 10: No fresh groundwater zones were encountered.
- Haysi 148: "Damp Hole" at 194 feet.

#### 3.0 GROUNDWATER PROTECTION

Groundwater and coal protection casings are proposed to be installed in Well 900146. These groundwater and coal protection casings are described as:

 13 3/8-inch conductor casing installed at ground level and cemented along its entire length to ground surface.


### Response to NOD UNDERGROUND DRINKING WATER REVIEW


#### **ATTACHMENT**


- В
- 9 5/8-inch water protection casing installed from ground depth through the groundwater zone and casings will be continuously cemented along its entire length to ground surface.
- 7-inch water and coal protection casing installed from ground level and continuously cemented along its entire length to ground surface.


These three (3) steel casings will be placed and individually cemented along their outside diameter from their set depth to ground surface. These three casings effectively seal the well's operations from the surrounding groundwater and coal seams.


The well's existing casing program and the placement of cement along the outside diameters of these casings will seal the well's operations from the surroundings, groundwater, coal seams, and the known gas production formations.











SURFACE OWNERSHIP MAP FROM COUNTY GIS 1/2 MILE FROM 900146

#### SURFACE OWNERS WITHIN 1/2 MILE OF 900146

ACCOUNT	OWNER	ADDRESS1	ADDRESS2	ADDRESS3	ZIPCODE1	DESCRIPT3	ACRES
12660	CF HIGHLANDS LLC		146 EAST MAIN ST	ABINGDON, VA	24210	AC 115	115
1797	THE NATURE CONSERVANCY		652 PETER JEFFERSON PKY STE190	CHARLOTTESVILLE, VA	22911	AC 163.541	163
9237	KISER, BUSTER WAYNE		1103 BUMSIDE STREET	HOPEWELL, VA	23860	AC 13	13
12647	CF HIGHLANDS LLC		146 EAST MAIN ST	ABINGDON, VA	24210	AC 26	26
12649	CF HIGHLANDS LLC		146 EAST MAIN ST	ABINDGON, VA	24210	AC 18	18
12514	OWENS, SAMMIE RAY & TERESA PAM		7611 RED BUD HWY	HONAKER, VA	24260	AC 4.7	4.7
12512	OWENS, BILLY RAY		696 LOWELL JONES RD	PINEYFLATS, TN	37686	AC 21.65	21.65
12476	OWENS, OCIE MAY & ANTHONY R COLEMAN		1883 CRANSNEST RD	VANSANT, VA	24656	AC 25	25
12477	OWENS, OCIE MAY & ANTHONY R COLEMAN		1883 CRANSNEST RD	VANSANT, VA	24656	AC 2	2
12109	AKERS, SHEILA A		PO BOX 341	GRUNDY, VA	24614	AC 37	37
12146	COLEMAN, DOUGLAS & LINDA LORETTA		2117 CRANES NEST RD	VANSANT, VA	24656	AC 8	8
12145	O'QUINN, RICE & EDGAR MAE	C/O BERNICE OQUINN	1423 OQUINN HOLLOW RD	VANSANT, VA	24656	AC 2.82	2.82
12145	O'QUINN, KIMBERLY NICOLE		1422 OQUINN HOLLOW RD	VANSANT, VA	24656	AC 2.82	2.82
20104	O'QUINN, BERENICE & ALICE JANE		1423 OQUINN HOLLOW RD	VANSANT, VA	24656	AC 3.87	3.87
2459	CHARLES, LESLIE RAY & SHAWNA JEANIN		PO BOX 476	HAYSI, VA	24256	AC 5	5
12454	DEEL, EUNICE FAY		7260 MEDICAL CENTER RD	AXTON, VA	24054	AC .22	0.22
4538	DEEL, EUNICE FAY		7260 MEDICAL CENTER RD	AXTON, VA	24054	AC .78	0.78
12405	DEEL, KERMIT & EUNICE FAYE		7260 MEDICAL CENTER RD	AXTON, VA	24054	AC .3	0.3
13105	CF HIGHLANDS LLC		146 EAST MAIN ST	ABINGDON, VA	24210	AC 5	5
13106	CF HIGHLANDS LLC		146 EAST MAIN ST	ABINGDON, VA	24210	AC 5	5
12144	O'QUINN, EDGAR MAE, JIMMY JERRY,		1289 OQUINN HOLLOW RD	VANSANT, VA	24656	AC 7.17	7.17
12144	O'QUINN, JIMMY JERRY, JIMMY ADAM,	c/o JIMMY OQUINN	1289 OQUINN HOLLOW RD	VANSANT, VA	24656	AC 7.17	7.17
3399	CF HIGHLANDS LLC		146 EAST MAIN ST	ABINDON, VA	24210	AC LOT	0.4
3113	COLEMAN, DOUGLAS & LINDA LORETTA		2117 CRANES NEST RD	VANSANT, VA	24656	AC 3	3
15588	YATES, JEFFERY LYN, DIANA KAY,		2169 CRANENEST RD	VANSANT, VA	24656	AC 3.25	3.25
378	O'QUINN, JIMMY JERRY, JIMMY ADAM,	c/o JIMMY OQUINN	1289 OQUINN HOLLOW RD	VANSANT, VA	24656	AC 3	3
12511	OWENS, SAMMIE RAY & DAVID SAMUEL		7611 RED BUD HWY	HONAKER, VA	24260	AC 10	10
17271	CF HIGHLANDS LLC		146 EAST MAIN ST	ABINGDON, VA	24210	AC 37.72	37.72
16888	BAILEY, EVERETT & TRULA		P.O. BOX 118	VANSANT, VA	24656	AC 15	15
16884	FLEMING, TOLLIE, KYLE & MELISSA		2056 ROSE RDG	CLINTWOOD, VA	24228	AC 16	16
5149	YATES, JEFFERY LYN & DIANA KAY		2169 CRANES NEST RD	VANSANT, VA	24656	AC 1	1
12119	O'QUINN, LOUIE & KAY		1098 DANCING WOLF RD	VANSANT, VA	24656	AC 68.5	68.5