

**Municipality/Organization:** City of Nashua, NH

**EPA NPDES Permit Number:** NHR041021

**Annual Report Number**

**& Reporting Period:** No. 13: 4/1/15 – 3/31/16



## **NPDES Phase II Small MS4 General Permit 2016 Annual Report**

### **General Information**

**Contact Person:** Stephen Dookran, P.E.

**Telephone #:** 603-589-3120

**Title:** City Engineer

**Email:** dookrans@nashuanh.gov

### **Certification:**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

**Signature:**

**Printed Name:** Stephen Dookran, P.E.

**Title:** City Engineer

**Date:** April 29, 2016





## **Introduction**

This is the thirteenth annual report to comply with the conditions of the 2003 Small MS4 General Permit. The City of Nashua (City) is aware that the Final of the issuance of the Draft 2013 Permit for Small MS4 General Permit for New Hampshire that was published in the Federal Register on February 23, 2013. The City submitted comments dated August 15, 2013 from Mayor Lozeau to Newton Tedder regarding the draft permit and are awaiting a response from the EPA. The City anticipates a final permit that sets goals achievable through a reasonable use of City resources.

The City continues to experience a lack of funding dedicated to providing maintenance to culverts, wetlands, brooks, catch basins, and drain lines and capital improvements to the drainage system. While the City's Wastewater Department through its sewer user fee has primarily supported the efforts required for the MS4 Permit, these funds should be directed only to the sanitary and combined sewer system, not the storm drainage system. This funding deficiency is expected to grow since the 2013 Draft Small MS4 General Permit puts further requirements relating to stormwater upon the City.

Knowing that legal authority was given to NH municipalities in 2008 to form stormwater utilities under RSA 149-I, the City applied for and received a grant from the NH Department of Environmental Services (NHDES), and, using additional City fund, completed a feasibility study for a stormwater utility in the City of Nashua. The feasibility study determined that a stormwater fee is a practical and advantageous option for Nashua because it would fairly distribute the cost of stormwater management amongst property owners, provide a stable source of funds dedicated to fulfilling mandated requirements for stormwater management, and allow for proactive maintenance of and necessary improvements to the drainage infrastructure. However, at this time, pursuing a stormwater fee will be delayed due to the difficult economic times felt by the property owners and the lack of citizens or elected officials to champion the cause.

## **Part I. Self-Assessment**

### **CSO Program**

The City of Nashua is under an EPA Consent Decree (Civil Action No. 05-376-PB), dated December 26, 2005 (based on the Long-Term Water Quality and Infrastructure Control Plan), to mitigate combined sewer overflows (CSOs). Currently, there are eight CSO outfalls that are a part of the city's sewer collection system, four that discharge to the Nashua River and four that discharge to the Merrimack River. CSOs have been identified as a probable source for the

Escherichia coli impairment within reaches of the Nashua and Merrimack Rivers located nearest to the city. While a statewide TMDL has been approved for all waterways impaired with Escherichia coli, the City continues to complete projects related to the Consent Decree, and as discussed below, are ongoing and will reduce the amounts of CSOs, and thus Escherichia coli being discharged into the Nashua and Merrimack Rivers.

The CSO program was designed based on the philosophy that urban runoff, particularly in the urbanized areas dictated by the MS4 Permit, contains pollutants that are harmful to the waterways. The City moved from a complete separation program to a hold and treat philosophy. The inner city areas are served by combined sewers. The stormwater runoff enters a sewer in the street that also conveys sanitary wastes. Up to a two year storm event, particularly the most polluted first flush, will be collected/stored and conveyed to combined sewage treatment facilities.

The 60 MGD Wet Weather Flow Treatment Facility (WWFTF), located at the Nashua Wastewater Treatment Facility (NWTF), to capture and treat combined sanitary and stormwater, continues to operate, reducing the occurrence of CSOs and the volume of combined flows that is discharged to the rivers. Also, more urban stormwater runoff from approximately 30 percent of the city, which is part of the combined flow, is now conveyed to the WWFTF where it will be treated before being discharged to the Merrimack River.

The construction of a CSO storage tank located near Burke Street was completed in December 2013. This 40,000 gallon tank will contains overflow up to a 2 year storm event and reduces the amount of combined sewage discharging to the Merrimack River.

Sewer separation work completed upstream of CSO 003 has eliminated the discharge of combined sewage at CSO 3 up to a 2 year storm event. A stormwater treatment train constructed in 2006 which included a Vortech swirl concentrator, a detention pond and a created wetland allows treated stormwater to be discharged to the Merrimack River.

An automated sluice gate within the CSO 006 regulator chamber to control flow during wet weather events continues to operate. The sluice gate allows the excess volume in the 108" Nashua River Interceptor to be used to store combined flow, reducing the frequency and volume of combined sewage overflowing into the Nashua River.

The drops over structures constructed on the North Merrimack River Interceptor continue to operate. These structures reduce discharges to the Merrimack River at CSO 005 by allowing combined sewage flow from a 2-year and higher storm event in sewer pipes on East Hollis and Crown Streets to flow directly into the larger interceptor that flows directly to the NWTF and the WWFTF where the combined flow is treated prior to being discharged into the Merrimack River.

Separation of the 60 acre combined sewer Harbor Avenue area resulted in reducing the volume of combined sewage flowing to the CSO 005 regulator on the Merrimack River. An additional benefit of this work is that localized flooding of combined sewage in the streets is eliminated.

The Screening and Disinfection Facility (SDF) at CSOs 005/006, the last CSO plan element, was completed and became operational during this reporting period. This CSO facility has the capacity to hold one million gallon, containing overflow up to a 2 year storm event, and reducing the amount of combined sewage discharging to the Merrimack River. In addition, this CSO facility screens and disinfects combined sewer overflows that are currently discharged untreated from CSO 005, located on the Merrimack River, and CSO 006, located on the Nashua River slightly upstream of its confluence with the Merrimack River. The new outfall for this facility is located on the Merrimack River.

The City documents the volume of combined sewer overflows discharging into the Nashua and Merrimack Rivers. An annual monitoring program provides information for the volume of discharge at each of the eight CSOs. Rainfall data is also recorded. A plan for the Post Construction Monitoring Program for the CSO program was submitted to the EPA for comment. Included in the program is testing of the Nashua and Merrimack Rivers to determine water quality.

The City continues to install low impact development elements on municipal owned properties in highly visible locations. The City is rehabilitating Main Street from Canal Street to West Hollis Street in a phased project. Within this reach of Main Street, impervious areas are being removed and being replaced with green space using planting elements such as landscape beds.

### **Public Education and Participation**

The City continues to be a member of the Nashua Area Stormwater Coalition. During the past year the group met twice times. The groups discussed successes and challenges in addressing their stormwater management programs and compliance with the Phase II regulations. The revised draft 2013 Phase II General Permit continues to be discussed.

The Paulie the Pickerel “Let Only Rain Go down the Storm Drain” logo continues to be used for marketing the stormwater management program in the city. Magnets with the logo continue to be distributed during educational presentations. Door hangers containing information about stormwater dos and don’ts were distributed during presentations and are available in locations frequented by residents in public buildings. In total, approximately 16 presentations were made to the public consisting of an elementary school math and science club, a four year old preschool classroom, and people of all ages at the Public Works Day Celebration in May 2015.

The Mine Falls Park Advisory Committee sponsored six Trail Days during the period. In addition to general park maintenance, trash and debris were removed from the waterways and banks of the Nashua River, Nashua Canal and Mill Pond. These events are well attended and include families, high school groups, business teams and the general public.

Updates of stormwater issues are reported at monthly meetings of the Board of Public Works. The Board of Public Works is a five member body of the elected officials that are responsible for the overall direction and performance of the Division of Public Works. This is a public meeting that is recorded and broadcasted repeatedly on the government access channel. The stormwater update discusses city-wide drainage issues, the progress made on addressing them, and any other items that are related to the management of stormwater.

The Nashua Conservation Commission (NCC) has taken an active role in disseminating information to the public via informational items included on the agendas. The NCC also welcomes and encourages public participation at the meetings. Information pertaining to a range of environmental concerns including stormwater management, invasive species, grant and funding opportunities, workshops, volunteer opportunities, shoreland protection, wetlands and vernal pools, master plans, best management practices, and active legislation is discussed.

The Nashua Telegraph continues to run articles on the water quality of area brooks, rivers and streams and the volunteer sampling program that is ongoing to determine the health of the waterways.

Two Designated River signs for the Merrimack River were installed near bridge crossings.

The waterways continue to have issues with invasive species. A plan is being developed for monitoring aquatic invasive species in the Nashua River, Mill Pond, and canal. Herbicide treatment in the Mill pond and canal is scheduled for June 2016. A survey of aquatic invasive species is planned for August 2016 to re-map their presence and extent so the management plan can be revised. Herbicide treatment in the Mill pond and canal is scheduled for June 2016.

In an effort to improve management of water resources and in response to findings by the Waterways Committee, the City created in 2015 a Waterways Manager position. The Waterways Manager works on environmental issues (water quality, invasive species management, waterfront brownfields remediation), flood risk mitigation (floodplain management, hazard mitigation planning, NFIP, CRS), manages or assists with the management of waterways infrastructure (hydropower facilities, dams, levee), facilitates and improves waterfront and waterways public access and recreation, and does public outreach related to waterways issues. The waterways manager also is working to ensure better coordination between the City and local, regional, state, and federal organizations and agencies on matters pertaining to waterways, waterfront, and floodplain management.

### **Illicit Discharge Detection and Elimination**

The Geographic Information System (GIS) mapping program of outfalls was updated with new information and corrected when discrepancies were found.

Culverts continued to be cleaned and maintained. When a new culvert was identified, the GIS mapping system was updated with accurate culvert information based on the field verification. Where necessary, maintenance work orders were generated.

During this reporting period, the City discontinued using the IntelliGov Work Order system. In its place the City has installed the Cartegraph Operation and Management System. This software includes a work order system that will track all work completed on the drainage system

Hazardous waste collection days, coordinated regionally by the Nashua Regional Planning Committee, occurred on April 18, May 3, June 4, August 1, October 3 and November 7, 2015. Approximately, 551 households from Nashua participated in these events.

## **Construction Site and Post-Construction Runoff Control**

The Nashua Land Use Code addresses land use planning issues through a variety of provisions related to stormwater management including the protection of wetlands, floodplain regulations, landscaping requirements, impervious surface requirements, open space requirements, and designs issues discussed during the development review process. The technical review process affords an interdisciplinary review of all applications submitted for Planning Board approval. Stormwater, drainage, and improved landscaping elements are included in discussions for every site and contribute to improving the stormwater directly or indirectly. The open space, impervious surface, parking and other zoning provisions are addressed as part of the process as well. The current land use code (with revisions incorporated dated September 1, 2012), is routinely discussed at staff meeting, noting areas where future amendments may be warranted.

Wetlands and wetland buffer areas are protected and proposals to impact these areas are carefully reviewed by the Nashua Conservation Commission who makes a formal recommendation to the Zoning Board of Adjustment. Wetland Buffer Markers continue to be required to be installed in the buffer areas of impacted wetlands by the Nashua Conservation Commission when proposed developments include wetland impacts. The purpose of the markers is to encourage residents not to dump debris in wetland areas.

The building permit process includes review of not only zoning and building issues, but proximity to local conservation lands and practical things to do or not do. For example, no construction materials shall be stored or left in the wetland buffer areas, best management practices to be followed during construction and site cleanup upon project completion.

Staff provides ongoing assistance to residents with flood insurance and floodplain management questions. This serves as an opportunity to educate the public about floodplain management and the relationship to stormwater management.

Staff routinely provided educational literature to the NCC and Planning Board on issues related to environmental protections such as stormwater management, erosion control and use of salt/sand in winter deicing applications.

## **Good Housekeeping**

Good housekeeping measures included the continuous street sweeping program. Sweepers operate 16 hours a day on week days from April 1 to June 1 and 8 hours per day until December 1. Winter salt and sand use was monitored and controlled.

Video inspections of culverts and the storm drain system using a CCTV system and a hand operated pole camera were completed. This equipment assisted in detecting infrastructure issues.

The Parks Department continues its practice of Integrated Pest Management (IPM) principles and reduced the amount of pesticides that was applied. The annual 2016 Pesticide Usage Report was submitted to the NH Department of Agriculture.

The IntelliGov Work Order Management System was retired during this reporting period and the Cartegraph Operations Management System was implemented to track work orders. Both systems allow entering and tracking of all work orders within the Division of Public Works, many of which are related to stormwater management.

Culverts continued to be cleaned and maintained. When a new culvert was identified, the GIS mapping system was updated with accurate culvert information based on the field verification. Where necessary, maintenance work orders were generated using the IntelliGov and Cartegraph systems.

Additional activities completed during the permit period are included in Part II of this report.

### **Impaired Waters**

To address Part I.C.1 of the General Permit, Table A is included in Appendix A. Listed in Table A are the water bodies where Nashua is listed as the Primary Town on the NHDES 2014 Draft List of Threatened or Impaired Waters that require a TMDL (303(d) list). Included in the table is the Best Management Practice to address the cause of impairment if the source of impairment has been identified by the NHDES.

The NHDES Final Report for Statewide TMDL for Bacteria Impaired Waters has been approved by the EPA. Certain segments of the Nashua and Merrimack Rivers and portions of Salmon Brook have been identified as being impaired for *Escherichia coli*. The CSO Program is also addressing this impairment in the Nashua and Merrimack Rivers. In order to address Part I.D, the schedule for waterbodies in Nashua identified as bacteria impaired waters covered by the approved statewide TMDL is listed in Table B, located in Appendix B.

Sampling for *E. coli* was completed once a month for seven months at four locations on the Nashua River. See Appendix C. For the portion of the Nashua River that runs through Nashua, the majority of the results for *E.coli* were in the excellent range ( $\leq 88$  cfu) with no results in the poor range ( $\geq 630$  cfu).

In addition, all marine surface waters in New Hampshire, therefore all surface waters in Nashua, are also included on this list due to statewide fish/shellfish consumption advisories issued because of mercury levels in fish/shellfish tissue.

### **Permit Compliance**

The City of Nashua has completed the required self-assessment and is in compliance with permit conditions.

## **Part II. Summary of Minimum Control Measures**

The summary of the activities completed in Permit Year 13 of the six Minimum Control Measures is listed in the attached table, Part II Summary of Minimum Control Measures. Planned activities for the next permitted year, April 2016 through March 2017, are also listed. Revisions to the Best Management Practices have been noted in the table.

## **Part III. Summary of Information Collected and Analyzed**

Volunteers with the Nashua River Watershed Association continue to monitor several locations in Nashua. Results of the sampling completed are included in the New Hampshire Volunteer River Assessment Program 2015 Nashua River Watershed Water Quality Report and can be found in Appendix C. For the portion of the Nashua River that runs through Nashua, the majority of the results for E.coli were in the excellent range ( $\leq 88$  cfu) with no results in the poor range ( $\geq 630$  cfu).

Staff at the Nashua Wastewater Facility also takes samples of the Merrimack River throughout the year as a requirement of their NPDES permit.

## **Part IV. Implementation Schedule**

The Stormwater Management Program Implementation Schedule for the Best Management Practices is outlined in the attached table. The schedule for the current year, Year 13, is shown in bold. The proposed schedule for Year 14 is also presented.

**Part II. Summary of Minimum Control Measures**

| <b>BMP ID#</b> | <b>Best Management Practice</b>                                                                         | <b>Measurable Goal</b>                                             | <b>Responsible Party</b>        | <b>Progress on Goals Permit Year 13</b>                                                                                                               | <b>Planned Activities Next Year</b>                                                                                                                                                                        |
|----------------|---------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------|---------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>1.00</b>    | <b>Public Education</b>                                                                                 |                                                                    |                                 |                                                                                                                                                       |                                                                                                                                                                                                            |
| 1.01           | Storm water education program for school children                                                       | Purchase Enviroscope Watershed/Nonpoint Source model               | DPW (1) - Amy Gill              | Presentations using the Enviroscope were completed the DPW celebration in May. A talk about current waterways issues was presented to the Lions Club. | Continue presenting in the schools and at other events. Assisting Nashua River Watershed Association with "Insect Investigation" activity covering river ecology and aquatic insect lesson April 28, 2016. |
| Revision       |                                                                                                         | Number of presentations given using Enviroscope                    |                                 |                                                                                                                                                       |                                                                                                                                                                                                            |
| 1.02           | Insert flyer in local newspaper describing city wide storm water program                                | Number of inserts distributed annually                             | DPW - Amy Gill                  | Local newspaper continued to publish articles on river water quality, volunteer water sampling, and waterbodies in general.                           | Continue to seek newspaper coverage on stormwater and water quality issues.                                                                                                                                |
| 1.03           | Create web page on City web site                                                                        | Web page online by 12/05                                           | DPW - Stephen Dookran, Amy Gill | The City web site was revamp during this period. Finalized stormwater information for web site. Status of CSO and stormwater projects listed.         | Review and update web page.                                                                                                                                                                                |
| Revision       |                                                                                                         | Web page online by 12/08                                           |                                 |                                                                                                                                                       |                                                                                                                                                                                                            |
| 1.04           | Create Public Service Announcements                                                                     | Run Announcement quarterly on cable TV channel access              | DPW - Amy Gill                  | Power point slides being revised.                                                                                                                     | Continue playing educational PowerPoint presentations on local and government cable access channels.                                                                                                       |
| Revision       |                                                                                                         | Number of days presentation runs                                   |                                 |                                                                                                                                                       |                                                                                                                                                                                                            |
| 1.05           | Create brochure and presentation to inform businesses and industrial users about illicit discharges     | Distribute to businesses and industrial users once every two years | DPW - Phil Appert               | Visits were made to SIU and deficiencies discussed with property owners. Discussion of stormwater BMPs included in visits.                            | Continue visiting SIUs.                                                                                                                                                                                    |
| 1.06           | Run three videos on Cable Access TV. "After the Storm", "Stormwater is Never Away" and "A River Reborn" | Number of times videos are run.                                    | DPW - Amy Gill                  | Public meetings where stormwater issues are discussed were replayed on local cable channel.                                                           | Continue to replay meetings.                                                                                                                                                                               |
| 1.07           | Create board for display at functions where the public is gathered.                                     | Number of times display is used.                                   | DPW - Amy Gill                  | Board used as tool during public presentations.                                                                                                       | Update board and continue to display board at various public events.                                                                                                                                       |
| 1.08           | Install Wetland Buffer Markers to encourage no dumping of debris in a wetland area.                     | 75 markers to be installed in 3 years.                             | DPW/CDD                         | Task complete. Wetland markers continued to be installed by developers as stipulations for approval by the Conservation Commission.                   | Installations of wetland markers will continue to be stipulated by the Conservation Commission as part of the approval process.                                                                            |

## Part II. Summary of Minimum Control Measures

| BMP ID#     | Best Management Practice                                                                                                      | Measurable Goal                                               | Responsible Party                            | Progress on Goals Permit Year 13                                                                                                                                                   | Planned Activities Next Year                                      |
|-------------|-------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------|----------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------|
| 1.09        | Mail letters to owners/residents that abut wetland to explain importance of wetland and encourage no dumping in wetland area. | Number of letters mailed to abutters                          | DPW - Amy Gill, NCC(7)                       | Letters and Nashua Conservation brochures were sent to homeowners where a concern about adjacent wetlands were identified.                                                         | Send out information to abutters of wetlands as needed.           |
| 1.10        | Design sign for brook/stream crossings                                                                                        | Percent design completed                                      | DPW - Amy Gill, NCC                          | Designated River Signs were installed at two locations on the Merrimack River.                                                                                                     | Design sign. Discuss concept with Nashua Conservation Commission. |
| 1.11        | Present Stormwater Management Program at Public Meetings                                                                      | Number of Presentations                                       | DPW- Amy Gill                                | Monthly Stormwater Issue update given monthly and EPA CSO reports presented quarterly at Board of Public Works meeting which is carried and replayed on Government access channel. | Continue monthly and quarterly updates.                           |
| 1.12        | Purchase and distribute Magnets with "Paulie the Pickerel" logo at public functions                                           | Number of magnets distributed                                 | DPW - Amy Gill                               | Magnets continue to be distributed in city offices and at public demonstrations using the Enviroscope.                                                                             | Continue to distribute magnets.                                   |
| 1.13        | Develop informative flyer about stormwater pollution and include in wastewater bills and display at public places.            | Number of flyers distributed                                  | DPW- David Simmons, Amy Gill                 | Inserts and doorhangers continue to be made available at public locations.                                                                                                         | Continue to distribute information flyers/doorhangers.            |
| <b>1a.</b>  | <b>Addition</b>                                                                                                               |                                                               |                                              |                                                                                                                                                                                    |                                                                   |
| 1.14        | Develop Power point to run on Public Access television                                                                        | Number of days presentation runs                              | DPW- Amy Gill                                | Power point slides updated.                                                                                                                                                        | Run informational slides on government cable channel.             |
| <b>2.00</b> | <b>Public Participation</b>                                                                                                   |                                                               |                                              |                                                                                                                                                                                    |                                                                   |
| 2.01        | Attach Storm Drain Markers in or near Catch Basins discharging to open water body                                             | 40% installed by 11/04, 80% installed by 11/05, 100% by 11/06 | DPW - Amy Gill, Pennichuck Water Works, Inc. | Previously placed markers inspected to determine durability of marker. Some markers replaced.                                                                                      | Continue to have public involved in applying markers.             |
| Revision    |                                                                                                                               | 50% installed by 10/08                                        |                                              |                                                                                                                                                                                    |                                                                   |

## Part II. Summary of Minimum Control Measures

| BMP ID#     | Best Management Practice                                                                                                                                        | Measurable Goal                                                                                    | Responsible Party               | Progress on Goals Permit Year 13                                                                                                                                                                            | Planned Activities Next Year                                                                        |
|-------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------|---------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------|
| 2.02        | Continue phone hotline service for stormwater related concerns                                                                                                  | Establish a hotline.<br>Record number of phone calls concerning drainage issues                    | DPW- David Simmons, NWTf(2)     | Hotline for drainage issues continues. Record violations and report to NHDES(3) and USEPA(4) as needed. Both the Intelligov Work Order Management System and Cartegraph OMS were used to track phone calls. | Continue hotline and Cartegraph OMS to track drainage issues.                                       |
| 2.03        | Meet with local communities, and the NHDOT(9). Meeting coordinated by the Nashua Regional Planning Commission (NRPC). Group called Nashua Stormwater Coalition. | Meet every two months for a total of 6 meetings per year                                           | DPW - Amy Gill, NRPC (8), NHDES | Two meetings were held with the Nashua Stormwater Coalition to discuss ongoing stormwater issues.                                                                                                           | Continue to meet with members of the surrounding communities to discuss stormwater issues.          |
| 2.04        | Create door hanger with tips on preventing stormwater pollution                                                                                                 | Number of door hangers distributed                                                                 | DPW - Amy Gill                  | Door hangers were made available at public areas.                                                                                                                                                           | Continue to distribute door hangers to the public.                                                  |
| 2.05        | Provide email links for stormwater related concerns                                                                                                             | Number of times email received                                                                     | DPW                             | Frequent emails received to report stormwater issues.                                                                                                                                                       | Continue to monitor emails.                                                                         |
| 2.06        | Request public input for ordinance revision to Stormwater Management and Wetlands sections                                                                      | Number of meetings held                                                                            | CDD (5)                         | Continued to obtain public comment on ordinances.                                                                                                                                                           | Continue to obtain public comment on ordinances.                                                    |
| <b>3.00</b> | <b>Illicit Discharge Detection and Elimination</b>                                                                                                              |                                                                                                    |                                 |                                                                                                                                                                                                             |                                                                                                     |
| 3.01        | Map outfalls and waters of the United States in Nashua city limits                                                                                              | Complete by 11/04. Count number of outfalls identified                                             | DPW - Amy Gill                  | Update GIS maps based on field verifications of drainage systems and outfalls, and completion of new drainage systems.                                                                                      | Continue to update GIS maps based on field verification of outfalls and newly constructed outfalls. |
| 3.02        | Prepare an Illicit Discharge Detection and Elimination (IDDE) Plan                                                                                              | Complete final plan 10/04                                                                          | DPW - Amy Gill                  | Continued to develop Draft IDDE.                                                                                                                                                                            | Complete IDDE Plan.                                                                                 |
| Revision    |                                                                                                                                                                 | Complete final plan 10/06                                                                          |                                 |                                                                                                                                                                                                             |                                                                                                     |
| 3.03        | Review illicit discharge ordinance                                                                                                                              | Amend ordinance as necessary by 12/ 07                                                             | DPW - Amy Gill                  | Ordinance reviewed. Language to amend ordinance discussed.                                                                                                                                                  | Begin process to make changes to ordinance if needed.                                               |
| 3.04        | Continue dry weather field survey of outfalls.                                                                                                                  | Complete survey of outfalls. Locate other outfalls in water bodies not included in survey by 11/04 | DPW - David Simmons, Amy Gill   | Continued to locate outfalls on smaller brooks and ponds. Identified undocumented outfalls recorded. Additional outfalls documented.                                                                        | Update outfall list as outfalls are located or newly constructed.                                   |

**Part II. Summary of Minimum Control Measures**

| <b>BMP ID#</b> | <b>Best Management Practice</b>                                                                                                                | <b>Measurable Goal</b>                                  | <b>Responsible Party</b>        | <b>Progress on Goals Permit Year 13</b>                                                                                                                                             | <b>Planned Activities Next Year</b>                  |
|----------------|------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------|---------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------|
| 3.05           | Conduct sampling of dry weather discharges and attempt to trace source of illicit discharge                                                    | Sample and identify source of suspect outfalls          | DPW - Amy Gill                  | Sampling of stream and brooks were completed.                                                                                                                                       | Sample suspect sources as needed.                    |
| 3.06           | Remove illicit discharges as budgetary funding allows                                                                                          | Track number of illicit discharges detected and removed | DPW - David Simmons, Jon Ibarra | Visual inspections of outfalls continue in trying to identify suspect discharges.                                                                                                   | Continue testing and tracking suspect discharges.    |
| 3.07           | Continue Regional Hazardous Waste Collection Day                                                                                               | Conduct 5 collection days per year                      | DPW - Sally Hyland, NRPC        | Hazardous waste collection days occurred on 4/18,5/2, 6/4, 8/1 ,10/3 and 11/7/2015. Approximately 551 households from Nashua participated in this regional event.                   | Schedule hazardous waste collection days.            |
| 3.08           | Track Hazardous Spills                                                                                                                         | Number of Spills identified                             | DPW - David Simmons             | No spills were reported during this reporting period.                                                                                                                               | Report on spills as necessary.                       |
| 3.09           | Conduct watershed audit for input in NRPC report                                                                                               | Complete audit                                          | DPW, CDD, NRPC                  | Audit completed.                                                                                                                                                                    |                                                      |
| 3.10           | Sample outfalls in water body RIV700061201-05, identified on the Impaired waters list                                                          | Number of outfalls sampled                              | DPW - David Simmons             | Waterway continues to be visually inspected. No suspect sources noted.                                                                                                              | Sample outfalls and trace source, if possible.       |
| <b>4.00</b>    | <b>Construction Site Runoff Control</b>                                                                                                        |                                                         |                                 |                                                                                                                                                                                     |                                                      |
| 4.01           | Review procedure for site plan review to consider if potential water quality impacts are included                                              | Complete review by Dec. 31 2005                         | CDD- Madeleine Mineau           | Land use ordinance revised and updated, effective September 2012. Staff routinely discusses land use code at staff meetings, noting areas where future amendments may be warranted. | Continue review of implementation of new ordinances. |
| 4.02           | Review requirements for construction operators to control demolition waste, chemicals, sanitary waste and other waste at the construction site | Complete review by Dec. 31 2005                         | CDD- Madeleine Mineau           | Land use ordinance revised and updated, effective September 2012.                                                                                                                   | Continue review of implementation of new ordinances. |

**Part II. Summary of Minimum Control Measures**

| <b>BMP ID#</b> | <b>Best Management Practice</b>                                                                                                                         | <b>Measurable Goal</b>                                                                                                | <b>Responsible Party</b> | <b>Progress on Goals Permit Year 13</b>                                                                                                                            | <b>Planned Activities Next Year</b>                                     |
|----------------|---------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|--------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------|
| 4.03           | Review existing city ordinances concerning stormwater management at construction sites                                                                  | Make recommendations for improvements by June 2006. Proceed through internal process to change ordinance by Dec. 2007 | CDD- Madeleine Mineau    | Land use ordinance revised and updated, effective September 2012.                                                                                                  | Continue review of implementation of new ordinances.                    |
| 4.04           | Develop standard drawings of runoff prevention BMPs to be used by site developers                                                                       | Produce document containing at least 7 alternative erosion protection measures by Dec. 2006                           | DPW - Amy Gill           | Sample drawings gathered and compile into standards.                                                                                                               | Index drawings and finalize drawings. Compile drawings electronically.  |
| 4.05           | Review procedures for inspection of construction sites to see if BMPs are in place and functioning correctly                                            | Complete review by Dec. 2006                                                                                          | CDD                      | CDD reviews construction sites of concern and as the availability of staffing allows.                                                                              | Continue review of inspection procedures and continue to inspect sites. |
| 4.06           | Review procedures for enforcement of improper functioning sediment and erosion control measures                                                         | Complete review by Dec. 2006                                                                                          | CDD                      | Enforcement procedures continued to be reviewed and revised.                                                                                                       | Continue review of inspection procedures.                               |
| <b>5.00</b>    | <b>Post Construction Runoff Control</b>                                                                                                                 |                                                                                                                       |                          |                                                                                                                                                                    |                                                                         |
| 5.01           | Review existing ordinance Sec. 16-145 which requires post development peak discharges be no greater than predevelopment discharges. Modify as necessary | Make recommendations for improvements by June 2006. Proceed through internal process to change ordinance by Dec. 2007 | CDD- Madeleine Mineau    | Land use ordinance revised and updated, effective September 2012.                                                                                                  | Continue review of implementation of new ordinances.                    |
| 5.02           | Review ordinance Sec 16-145 for groundwater recharge required on new site plans                                                                         | Make recommendations for improvements by June 2006. Proceed through internal process to change ordinance by Dec. 2007 | CDD- Madeleine Mineau    | Land use ordinance revised and updated, effective September 2012. Staff continues to make recommendations on improving the quality of landscaping plans submitted. | Continue review of implementation of new ordinances.                    |

**Part II. Summary of Minimum Control Measures**

| <b>BMP ID#</b> | <b>Best Management Practice</b>                                                                                    | <b>Measurable Goal</b>                                                            | <b>Responsible Party</b> | <b>Progress on Goals Permit Year 13</b>                                                                                                                                                        | <b>Planned Activities Next Year</b>                                          |
|----------------|--------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------|--------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------|
| 5.03           | Implement Annual Operations and Maintenance requirement for BMPs on private properties                             | Implement by Dec. 2007                                                            | CDD- Madeleine Mineau    | Land use ordinance revised and updated, effective September 2012.                                                                                                                              | Continue review of implementation of new ordinances.                         |
| 5.04           | Develop enforcement measures and assign internal staff to enforce requirements                                     | Implement by Dec. 2007                                                            | CDD                      | Review of enforcement procedures ongoing.                                                                                                                                                      | Continue review of requirements.                                             |
| <b>5a.</b>     | <b>Addition</b>                                                                                                    |                                                                                   |                          |                                                                                                                                                                                                |                                                                              |
| 5.05           | Install Low Impact Development items on Municipal Properties                                                       | Design and Construct on Riverside Street Property                                 | DPW - Steve Dookran      | Task complete. Additional rain gardens and green spaces have been designed for the Main Street Improvement project in downtown Nashua and Burke Street Sewer project.                          | Continue to design and install LID elements on municipally owned properties. |
| <b>6.00</b>    | <b>Municipal Good Housekeeping</b>                                                                                 |                                                                                   |                          |                                                                                                                                                                                                |                                                                              |
| 6.01           | Hazardous waste training program for applicable employees                                                          | Employees attend annual hazardous spill training program beginning May 2005       | DPW                      | DPW staff reviewed procedures for handling hazardous wastes.                                                                                                                                   | Continue to train employees and review procedures.                           |
| 6.02           | Storm water discharge training program for applicable municipal employees on preventing non-storm water discharges | Employees attend annual storm water discharge training program beginning May 2005 | DPW                      | EPA Stormwater Web Casts viewed by staff. Employees attended various conferences and seminars (APWA, NEWEA, NHDES Non-Point Source Pollution).                                                 | Continue to train employees.                                                 |
| 6.03           | Review program for handling fertilizer on city property                                                            | Complete review July 2005                                                         | DPW - Nicholas Caggiano  | Task complete.                                                                                                                                                                                 | Continue implementation of fertilization policies.                           |
| 6.04           | Continue litter management program by street sweeping entire City at least once a year.                            | Review program annually and record number of lane miles swept                     | DPW - Jon Ibarra         | Program began in March 2015. Entire City swept once, with commercial/arterial or other critical streets being swept up to 6 times per year, including sidewalks.                               | Continue street sweeping.                                                    |
| 6.05           | Review snow dumping procedure to allow snow storage in areas away from surface waters                              | Complete review July 2005                                                         | DPW - Jon Ibarra         | Program reviewed. Snow continues to be stored in areas where stormwater treatment is available before the melted snow is discharged to a water body. Area is swept during and after snow melt. | Review program annually.                                                     |

**Part II. Summary of Minimum Control Measures**

| <b>BMP ID#</b> | <b>Best Management Practice</b>                                                                                                                                                                                                                                                                                                                                 | <b>Measurable Goal</b>                              | <b>Responsible Party</b>     | <b>Progress on Goals Permit Year 13</b>                                                                                                                                                            | <b>Planned Activities Next Year</b>                                                       |
|----------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------|------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------|
| 6.06           | Continue city wide program to clean catch basins                                                                                                                                                                                                                                                                                                                | 100% of all catch basins cleaned once every 3 years | DPW - David Simmons          | At least 575 catch basins were cleaned.                                                                                                                                                            | Continue catch basin cleaning program.                                                    |
| 6.07           | Continue SSO(6) correction and mitigation program for SSOs that discharge to water bodies                                                                                                                                                                                                                                                                       | Record number of SSOs corrected.                    | DPW - David Simmons          | Two SSOs was reported that affected a water body.                                                                                                                                                  | Continue correction of SSOs.                                                              |
| 6.08           | Television inspection of storm drains as needed                                                                                                                                                                                                                                                                                                                 | Record number Inspect as needed                     | DPW - David Simmons          | The City continued to video inspect storm drains as needed.                                                                                                                                        | Continue inspection as needed.                                                            |
| 6.09           | Calibrate salt and sand truck spreaders                                                                                                                                                                                                                                                                                                                         | Complete annually before November 1st               | DPW - Jon Ibarra             | Calibrated salt and sand trucks in November 2015.                                                                                                                                                  | Calibrate trucks in fall 2016.                                                            |
| 6.10           | Review pooper scooper ordinance                                                                                                                                                                                                                                                                                                                                 | Review ordinance by July 2005                       | DPW- Amy Gill, Nick Caggiano | Ordinance reviewed and found adequate. "Mutt Mitt" dog convenience stations continue to be used by the public and are monitored and refilled.                                                      | Monitor the use of the dog convenience stations.                                          |
| 6.11           | Disseminate information contained within city developed Alternative Storm Water Management Methods guide for Storm Water Control                                                                                                                                                                                                                                | Make available to developers as guide by July 2004  | CDD/DPW                      | Low impact development ideas continued to be discussed with developers. Developers have proposed permeable pavement, infiltration systems, rain gardens and other LID components at various sites. | Continue discussion with developers about the advantages of LIDs.                         |
| Revision       |                                                                                                                                                                                                                                                                                                                                                                 | Make available by July 2005                         |                              |                                                                                                                                                                                                    |                                                                                           |
| 6.12           | Develop a ditch/swale cleaning program                                                                                                                                                                                                                                                                                                                          | Develop program by July 2005                        | DPW - David Simmons          | Swales continue to be inspected and cleaned as needed. Seasonal help continues to be hired to clean swales.                                                                                        | Clean swales as necessary.                                                                |
| 6.13           | Develop culvert maintenance program.                                                                                                                                                                                                                                                                                                                            | Develop and Implement program by 2007               | DPW - David Simmons          | Culverts were cleaned and inspected as needed.                                                                                                                                                     | Continue to locate culverts and clean culverts as needed. Update GIS system as necessary. |
| <b>7.00</b>    | <b>Impaired Waters</b>                                                                                                                                                                                                                                                                                                                                          |                                                     |                              |                                                                                                                                                                                                    |                                                                                           |
|                | The 2014 Draft List of Threatened or Waters that require a TMDL within the Limits of the City of Nashua, NH are listed in Appendix A. The NHDES Final Report for Statewide TMDL for Bacteria Impaired Waters has been approved by the EPA. Waterbodies in Nashua Identified as Bacteria Impaired Waters Covered by the Statewide TMDL are listed in Appendix B. |                                                     |                              |                                                                                                                                                                                                    |                                                                                           |

- (1) DPW - Division of Public Works, City of Nashua  
 (2) NWTF -Nashua Wastewater Treatment Facility, City of Nashua  
 (3) NHDES - New Hampshire Department of Environmental Services  
 (4) USEPA - United States Environmental Protection Agency  
 (5) CDD - Community Development Division, City of Nashua

- (6) SSO - Sanitary Sewer Overflow  
 (7) NCC - Nashua Conservation Commission  
 (8) NRPC - Nashua Regional Planning Commission  
 (9) NHDOT - New Hampshire Department of Transportation

Reporting Period  
4/2015 - 3/2016

## Part IV. SWMP Implementation Schedule

City of Nashua, NH

| BMP ID<br># | PERMIT YEAR 10 |              |         |                 | PERMIT YEAR 11 |              |         |                 | PERMIT YEAR 12 |              |         |                 | PERMIT YEAR 13 |              |         |                 | PERMIT YEAR 14 |              |         |                 |
|-------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|
|             | Spring<br>12   | Summer<br>12 | Fall 12 | Winter<br>12-13 | Spring<br>13   | Summer<br>13 | Fall 13 | Winter<br>13-14 | Spring<br>14   | Summer<br>14 | Fall 14 | Winter<br>14-15 | Spring<br>15   | Summer<br>15 | Fall 15 | Winter<br>15-16 | Spring<br>16   | Summer<br>16 | Fall 16 | Winter<br>16-17 |
|             |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.01        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.02        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.03        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.04        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.05        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.06        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.07        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.08        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.09        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.10        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.11        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.12        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.13        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 1.14        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 2.01        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 2.02        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 2.03        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 2.04        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 2.05        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 2.06        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
|             |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |

Part IV. SWMP Implementation Schedule

| BMP ID<br># | PERMIT YEAR 10 |              |         |                 | PERMIT YEAR 11 |              |         |                 | PERMIT YEAR 12 |              |         |                 | PERMIT YEAR 13 |              |         |                 | PERMIT YEAR 14 |              |         |                 |
|-------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|
|             | Spring<br>12   | Summer<br>12 | Fall 12 | Winter<br>12-13 | Spring<br>13   | Summer<br>13 | Fall 13 | Winter<br>13-14 | Spring<br>14   | Summer<br>14 | Fall 14 | Winter<br>14-15 | Spring<br>15   | Summer<br>15 | Fall 15 | Winter<br>15-16 | Spring<br>16   | Summer<br>16 | Fall 16 | Winter<br>16-17 |
| 3.01        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 3.02        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 3.03        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 3.04        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 3.05        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 3.06        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 3.07        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 3.08        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 3.09        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 3.10        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 4.01        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 4.02        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 4.03        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 4.04        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 4.05        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 4.06        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 5.01        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 5.02        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 5.03        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
|             |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |

Part IV. SWMP Implementation Schedule

| BMP ID<br># | PERMIT YEAR 10 |              |         |                 | PERMIT YEAR 11 |              |         |                 | PERMIT YEAR 12 |              |         |                 | PERMIT YEAR 13 |              |         |                 | PERMIT YEAR 14 |              |         |                 |
|-------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|----------------|--------------|---------|-----------------|
|             | Spring<br>12   | Summer<br>12 | Fall 12 | Winter<br>12-13 | Spring<br>13   | Summer<br>13 | Fall 13 | Winter<br>13-14 | Spring<br>14   | Summer<br>14 | Fall 14 | Winter<br>14-15 | Spring<br>15   | Summer<br>15 | Fall 15 | Winter<br>15-16 | Spring<br>16   | Summer<br>16 | Fall 16 | Winter<br>16-17 |
| 5.04        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 5.05        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 5.06        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.01        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.02        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.03        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.04        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.05        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.06        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.07        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.08        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.09        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.10        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.11        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.12        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |
| 6.13        |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |                |              |         |                 |

## **Appendix A**

Table A. 2014 Draft List of Threatened and Impaired Waters  
that requires a TMDL, Primary Town, Nashua, NH

**Table A. 2014 Draft List of Threatened or Impaired Waters that requires a TMDL(1)  
Primary Town, City of Nashua, NH**

| <b>Water Body<br/>NH AUID Number<br/>Size</b>                                                     | <b>Use Description</b>     | <b>Impairment<br/>Name</b>             | <b>TMDL<br/>Priority</b> | <b>Source Name</b>                                                                                                                      | <b>Best Management Practice</b>                                                         |
|---------------------------------------------------------------------------------------------------|----------------------------|----------------------------------------|--------------------------|-----------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------|
| Nashua River<br>Mine Falls Dam Pond<br>NHIMP700040402-02<br>60 acres (upstream of Mine Falls Dam) | Aquatic Life               | Chloride                               | Low                      | Commercial Districts (Shopping/Office) ; Highway/Road/Bridge Runoff (non-construction related); Municipal (Urbanized High Density Area) | Visual inspections of salt applications and snow storage at locations within watershed. |
|                                                                                                   |                            | Dissolved Oxygen Saturation            | Low                      | Source Unknown                                                                                                                          | To be determined once probable source identified by NHDES.                              |
|                                                                                                   |                            | pH                                     | Low                      | Atmospheric Deposition Acidity                                                                                                          | No action                                                                               |
| Nashua River -Nashua Canal Dike<br>NHIMP700040402-03<br>42.00 acres                               | Aquatic Life               | pH                                     | Low                      | Atmospheric Deposition Acidity                                                                                                          | To be determined once probable source identified by NHDES.                              |
|                                                                                                   | Primary Contact Recreation | Chlorophyll-a                          | Low                      | Source Unknown                                                                                                                          | Vortechnic unit installed upstream of one outfall. Stormwater detention pond            |
| Harris Pond/Pennichuck Brook, PWS<br>NHLAK700061001-04-01<br>72.079 acres                         | Aquatic Life               | Iron                                   | Low                      | Source Unknown                                                                                                                          | To be determined once probable source identified by NHDES.                              |
|                                                                                                   | Primary Contact Recreation | Cyanobacteria hepatotoxic microcystins | Low                      | Source Unknown                                                                                                                          | To be determined once probable source identified by NHDES.                              |
| Lyle Reed Brook<br>NHRIV700040402-04<br>3.688 miles                                               | Aquatic Life               | Oxygen, Dissolved                      | Low                      | Source Unknown                                                                                                                          | To be determined once probable source identified by NHDES.                              |
|                                                                                                   |                            | pH                                     | Low                      | Source Unknown                                                                                                                          | To be determined once probable source identified by NHDES.                              |
| Muddy Brook<br>NHRIV700061001-06<br>4.805 miles                                                   | Aquatic Life               | Oxygen, Dissolved                      | Low                      | Source Unknown                                                                                                                          | To be determined once probable source identified by NHDES.                              |
|                                                                                                   |                            | pH                                     | Low                      | Source Unknown                                                                                                                          | To be determined once probable source identified by NHDES.                              |

**Table A. 2014 Draft List of Threatened or Impaired Waters that requires a TMDL(1)  
Primary Town, City of Nashua, NH**

| <b>Water Body<br/>NH AUID Number<br/>Size</b>                                         | <b>Use Description</b>        | <b>Impairment<br/>Name</b> | <b>TMDL<br/>Priority</b> | <b>Source Name</b>        | <b>Best Management Practice</b>                               |
|---------------------------------------------------------------------------------------|-------------------------------|----------------------------|--------------------------|---------------------------|---------------------------------------------------------------|
| Unnamed Brook to Pennichuck<br>Brook (Boire Fields)<br>RIV700061001-09<br>0.986 miles | Aquatic Life                  | Oxygen,<br>Dissolved       | Low                      | Source Unknown            | To be determined once probable<br>source identified by NHDES. |
|                                                                                       |                               | pH                         | Low                      | Source Unknown            | To be determined once probable<br>source identified by NHDES. |
| Unnamed Brook<br>RIV700061001-12<br>0.286 miles                                       | Aquatic Life                  | Iron                       | Low                      | Source Unknown            | To be determined once probable<br>source identified by NHDES. |
|                                                                                       |                               | Oxygen,<br>Dissolved       | Low                      | Source Unknown            | To be determined once probable<br>source identified by NHDES. |
| Merrimack River<br>NHRIV700061002-14<br>3.714 miles                                   | Aquatic Life                  | pH                         | Low                      | Source Unknown            | To be determined once probable<br>source identified by NHDES. |
|                                                                                       | Primary Contact<br>Recreation | Creosote                   | Low                      | Contaminated Groundwater  | Cleanup by private firm                                       |
|                                                                                       |                               |                            | Low                      | RCRA Hazardous Waste Site | Cleanup by private firm                                       |
| Merrimack River<br>NHRIV700061206-24<br>5.151 miles                                   | Aquatic Life                  | Aluminum                   | Low                      | Source Unknown            | To be determined once probable<br>source identified by NHDES. |
|                                                                                       |                               | pH                         | Low                      | Source Unknown            | To be determined once probable<br>source identified by NHDES. |
|                                                                                       | Primary Contact<br>Recreation | Chlorophyll-a              | Low                      | Source Unknown            | To be determined once probable<br>source identified by NHDES. |

(1) Source: New Hampshire Department of Environmental Services (NHDES), Water Division, Watershed Management Bureau, New Hampshire, 2014 Draft 303(d) Surface Water Quality List.  
PWS - Pennichuck Water System,

## **Appendix B**

Table B. Waterbodies in Nashua Identified as  
Bacteria Impaired Waters Covered by the Statewide TMDL

Table B. Waterbodies in Nashua Identified as Bacteria Impaired Waters Covered by the Statewide TMDL

| Watershed       | Waterbody Name                                                  | Assessment Unit # | Primary Town | % Reduction to meet TMDL |                |
|-----------------|-----------------------------------------------------------------|-------------------|--------------|--------------------------|----------------|
|                 |                                                                 |                   |              | Single Sample            | Geometric Mean |
| Merrimack River | MERRIMACK RIVER                                                 | NHRIV700061002-14 | NASHUA       | 72%                      | 25%            |
|                 | MERRIMACK RIVER                                                 | NHRIV700061206-24 | NASHUA       | 96%                      | 35%            |
|                 | SALMON BROOK - HASSELLS BROOK -<br>OLD MAIDS BROOK - HALE BROOK | NHRIV700061201-05 | NASHUA       | 92%                      | no data        |
|                 | SALMON BROOK                                                    | NHRIV700061201-07 | NASHUA       | 96%                      | 90%            |
| Nashua River    | NASHUA RIVER - JACKSON PLANT DAM<br>POND                        | NHIMP700040402-05 | NASHUA       | 92%                      | no data        |
|                 | NASHUA RIVER                                                    | NHRIV700040402-08 | NASHUA       | 94%                      | complies       |
|                 | NASHUA RIVER                                                    | NHRIV700040402-09 | NASHUA       | 92%                      | no data        |

Source: Final Report New Hampshire Statewide TMDL for Bacteria Impaired Waters by New Hampshire Department of Environmental Services, September 2010

## **Appendix C**

Table C. Nashua River Watershed Association  
2015 Monitoring Results

**Nashua River Watershed Association  
2015 Sampling Results**

**Rainfall**      **.25" or more rain previous 3 days.**  
**Mixed or Borderline rain previous 3 days**

| E.Coli Monitoring Results |                         |                                         |       |      |       |       |       |       |      |
|---------------------------|-------------------------|-----------------------------------------|-------|------|-------|-------|-------|-------|------|
| Site ID                   | Monitor/Team            | Site Description                        | APRIL | MAY  | JUNE  | JULY  | AUG   | SEPT  | OCT  |
| NM0121                    | Insigna                 | Canal Street at Area Agency parking lot | 50.4  | 88.2 | 108.1 | 166.4 | 81.6  | 124.6 | 38.8 |
| NM0140                    | Sarno/Noble             | Main Street Bridge                      | 7.3   | 55.6 | 61.6  | 40.4  | 45.7  | 36.4  | 43.5 |
| MN0200                    | McDougall/Ruby/Wigfield | Nashua Technology Park                  | 12.1  | 93.2 | 83.3  | 39.9  | 214.2 | 33.2  | 48   |
| NM0875                    | Insigna                 | Mine Falls Park at boat launch          | 44.8  | 4.1  | 71.2  | 5.2   | 5.2   | <1    | 12.2 |

**Rating**

**Excellent**  
≤ 88

**Good**  
89-126

**Fair**  
127-630

**Poor**  
> 630

NHDES swimming standard is 126 (cfu)

Mass DEP **boating** standard is **630** cfu

| Dissolved Oxygen Monitoring Results |              |                         |       |     |      |      |     |           |     |
|-------------------------------------|--------------|-------------------------|-------|-----|------|------|-----|-----------|-----|
| Site ID                             | Monitor/Team | Site Description        | APRIL | MAY | JUNE | JULY | AUG | SEPT      | OCT |
| NM0121                              | Insigna      | Canal Street at Area    | 8.95  | 8   | 7.1  | 6.5  | 7.2 | 6.5       | 7.8 |
| NM0140                              | Sarno/Noble  | Main Street Bridge      | 7.45  | 5.2 | 6.0  | 6.4  | 7   | 6         | 7.8 |
| MN0200                              | McDougall/   | Nashua Technology Park  | 8.5   | 8.1 | 6.6  | 5.7  | 6.6 | 5.6       | 7.6 |
| NM0875                              | Insigna      | Mine Falls Park at boat | 8.7   | 7.9 | 6.9  | 6.3  | 5.9 | No sample | 7.1 |

**Rating**

Habitat for trout and other cold water fish(bold)

Habitat for bass and other warm water fish

**Excellent**  
>8.0mg/l  
>6.0 mg/l

**Good**  
6-8mg/l  
5-6mg/l

**Fair**  
5-6mg/l  
4-5mg/l

**Poor**  
<5  
<4

| Temperature Monitoring Results |              |                         |       |     |      |      |     |      |     |
|--------------------------------|--------------|-------------------------|-------|-----|------|------|-----|------|-----|
| Site ID                        | Monitor/Team | Site Description        | APRIL | MAY | JUNE | JULY | AUG | SEPT | OCT |
| NM0121                         | Insigna      | Canal Street at Area    | 9     | 16  | 19   | 23   | 22  | 20   | 12  |
| NM0140                         | Sarno/Noble  | Main Street Bridge      | 9     | 16  | 17.5 | 20.5 | 20  | 16   | 9.5 |
| MN0200                         | McDougall/   | Nashua Technology Park  | 11    | 18  | 21   | 23   | 23  | 21   | 12  |
| NM0875                         | Insigna      | Mine Falls Park at boat | 9     | 16  | 19   | 24   | 22  | 22   | 12  |

**Rating**

Habitat for trout and other cold water fish(bold)

Habitat for bass and other warm water fish

**Excellent**  
<12  
<15.5

**Good**  
12-18  
15.5-22

**Fair**  
18.1-22  
23-28

**Poor**  
>22  
>28