

Municipality/Organization: Town of Holliston

EPA NPDES Permit Number: MAR041122

MaDEP Transmittal Number: W-041092

**Annual Report Number
& Reporting Period:** March 08-March 09

NPDES PII Small MS4 General Permit Annual Report

Part I. General Information

Contact Person: Paul D. Le Beau

Title: Town Administrator

Telephone #: 508-429-0608

Email: lebeaup@holliston.k12.ma.us

Certification:

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Signature:



Printed Name: Paul D. Le Beau

Title: Town Administrator

Date:

1/27/2010

Part II. Self-Assessment

The May '08 Annual Town Meeting resulted in the passage of a new Stormwater and Land Disturbance By-Law as well as amendments to the zoning by-law for earth removal, illicit discharge and compact residential development in the village center. The EPA publication "After the Storm: A Citizen's Guide to Understanding Stormwater" was distributed at the Town Meeting as well as summary of the local by-law provisions impacting any activity which disturbs over 10,000 s.f of soil or more (over 250 s.f. of land with 10% or greater slope), commercial and industrial sites with over 500 s.f. of paving and alteration of "high impact" land uses such as gas stations. Those changes became effective September 2. The Planning Board adopted regulations to implement the Stormwater Management and Land Disturbance By-Law on September 25th after a public hearing on August 28th. In March 2009, the Planning Board adopted changes to its subdivision regulations incorporating additional Low Impact Development techniques for stormwater management and infrastructure construction. These include provisions that are more stringent than the DEP Stormwater Management Handbook design criteria.

We as a staff continue to subscribe to publications such as Stormwater and Public Works as well as the Center for Watershed Management's newsletter. We also continue to participate, as do our volunteer members, in professional development training such as that offered through the Mass. Association of Conservation Commissions, Citizen Planner Training, Mass. Association of Planning Directors, American Planning Association, Mass. Highway Association, and New England Water Works Assoc. (located in Holliston).

Representatives in the Highway Department, Water Department, Planning Board, Conservation Commission, Board of Health and Selectmen's office continue to work together to discuss progress made on the program and establish new goals. Over the past year, we have made a lot of progress in the areas of self and public education as well as improving the physical plants at town owned buildings. The Police Station reconstruction was completed and a new stormwater management system is in place there.

Part III. Summary of Minimum Control Measures

1. Public Education and Outreach

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 5 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 6
1A	Establish a classroom education program.	ConCom, Water		Continue Program. Added cable access TV educational programming (Safety and Environment).	Continue Program. Continue cable access TV educational programming.
1B	Distribute brochures and fact sheets to residents and businesses	ConCom, Selectmen		Continue distribution at meetings and via town mailings and at 'Celebrate Holliston' annual community event.	Update website as appropriate.
1C	Publish articles on stormwater protection in local papers.	ConCom/ Planning Board	In progress	Legal notices and local press expected for erosion control ordinance and LID by-law (late '07)	Continuing as adjustments are contemplated.
1D	Develop stormwater section on town website	Selectmen	www.townofholliston.us	Town Website has an established stormwater management area. It can be accessed by going to www.townofholliston.us	Update website as necessary.
1E	Create stormwater educational display	Water Department/ BOH	In progress	Ongoing. Posters placed in land use section of Town Hall.	Ongoing.

1a. Additions - none

2. Public Involvement and Participation

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 5 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 6
2A	Establish a stormwater hotline	ConCom	Record number of calls	Covanta Energy has established its own Holliston Transfer Station hotline.	Ongoing
2B	Distribute stormwater educational material during public meetings	Selectmen/ Planning Board	Copies of materials attached.	Stormwater information available on town website.	Update website as necessary.

2C	Conduct river and pond cleanups	ConCom	Associates undertaking cleanups of all waterways in the town	The Conservation Commission is investigating EPA funding for long-term solution to Lake Winthrop water quality issues.	Ongoing. Phase I study completed. Available for review.
2D	Mark storm drains	Highway	50% of drains marked by year 5	Will inspect stencils for clarity and re-paint as necessary	Will inspect stencils for clarity and re-paint as necessary
2E	Native Tree/shrub planting program.	ConCom	Tree replacement	The Commission requires that native trees be used in wetland replication or remediation. The Conservation Associates continue to plant native species on conservation lands.	Planning Board site plan review and subdivision regs. now have native species preferences for private site development.

2a. Additions – The Town will evaluate the feasibility of installing “No dumping” signs in areas prone to bulky item dumping. Dog Officers have been active in issuing non-criminal disposition fines with regard to dog waste and education regarding same (Town by-law provisions adopted in May 2005).

3. Illicit Discharge Detection and Elimination

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 5 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 6
3A	Develop primary storm drain system map	Highway	100% of system mapped on GIS	Ongoing. As-builts of new residential subdivisions being solicited.	Continue to update as needed.
3B	Complete mapping of stormwater outfalls	Highway	All outfalls mapped by Year 5.	Ongoing.	100% complete.
3C	Illicit discharge prohibition bylaw	Planning Board, Board of Health		Currently under the jurisdiction of the Holliston Board of Health regulations as well as by-law provisions enacted in 2008.	Investigate strengthening regulations. Have had vehicle washing complaints.
3D	Develop illicit discharge detection and elimination plan	Highway, Board of Health	Outfalls examined by year 5. Sources traced and documented	Will start inspections during dry season. Concentrating in priority areas.	On-going, yearly inspections.

3a. Additions. Town trash contractors will continue to provide curbside pickup of leaves and yard wastes (ongoing annual). Information made available on local cable access television.

3E	Hold Annual Hazardous Waste Day (HHHW).	Selectmen	Annual event planned	We held a HHHW day last fall and part of a multi-town consortium.	Ongoing annual participation.
3G	Evaluate stormwater discharge to rare or endangered species habitats	ConCom	Locating habitats is an on-going process	MNHESP estimated habitat map shows certified vernal pools and estimated polygons. Vernal pool certification is ongoing.	Continue to participate and partner with Massachusetts Natural Heritage Program BioMap Project, especially in site development review.

4. Construction Site Stormwater Runoff Control

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 5 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 6
4A	Develop erosion control bylaw	Planning Board, Building Inspector	Bylaw at Town Meeting by end of year 2.	Conservation Commission rules and regulations adopted 2005. Planning Board regulations strengthened 2007 and by-law adopted May 2008.	Implementation of by-law on-going. Regulations adopted include fee schedule and enforcement provisions.
4B	Establish a procedure for the receipt of information submitted by public	Planning Board, ConCom, Board of Health	Record number of phone calls and complaints	Information regarding all local regulations are currently on the Town website with links to other resources.	Interdepartmental referrals of land use issues for follow-up (BOH, ConCom, Planning Board and Building)
4C	Develop guidance for erosion controls	ConCom/Planning Board	Inspection checklist and document inspections	Requirements are cited in Orders of Conditions for ConCom and decisions by Planning Board. Erosion controls are inspected by Agent(s) after installation.	Look to strengthen guidelines within by-laws and regulations.

4a. Additions – Consider by-law provisions limiting development on steep slopes. Review 100% of plans and SWPPP for construction projects 1-5 acres. Goal: Inspect 100% of projects within the regulated area that discharge to the MS4. Define procedures for issuing and tracking permits. Erosion control is covered by Land Disturbance By-law (over 250 s.f. disturbance over 10% slopes).

5. Post-Construction Stormwater Management in New Development and Redevelopment

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 5 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 6
5A	Develop stormwater management control bylaw	Planning Board, Building Inspector	Bylaw at Town meeting by end of year 2.	By-law adopted May 2008 as noted above in self-assessment.	Investigate strengthening provisions through LID by-law or additional regulation amendments

5B	Develop and implement inspection program	Planning Board, Highway, ConCom, Building Inspector	Copies of maintenance reports, inspections completed and results	O&M Plans are required for detention basins and stormwater systems for developments.	Inspected during sub-division installation and yearly thereafter. Reports to Highway Dept required for commercial sites. Ongoing.
5C	Develop BMP design standards	Planning Board, Building Inspector	Improved bylaws as adopted	Adopted by Planning Board in 2007 and 2008 after a series of hearings.	Ongoing as BMP's are field-tested.

5a. Additions - In July after a series of public hearings, the Planning Board adopted stormwater regulations that will regulate all residential subdivisions (2 or more lots) as well as commercial site development (multi-family, commercial and industrial development). The Board of Health has rescinded their stormwater regulations as a result. Additional by-law provisions were adopted May 2008. Defined procedures for issuing and tracking permits adopted shortly after in 2008 and 2009.

6. Pollution Prevention and Good Housekeeping in Municipal Operations

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 3 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 4
6A	Comply with DEP policy for vehicle washing at town owned facilities	Highway	Vehicle wash unit	The Highway Department has installed a vehicle wash point that incorporates a water recycling and filtration system. This facility is open to all town departments.	Done
6B	Ensure compliance for floor drain systems	Highway	Modification of floor drain systems	All town buildings with floor drain discharges have been plugged and are no longer used.	Done
6C	Evaluate and implement stormwater BMP for police station parking lot runoff	Police, Highway	Police station retrofit.	Article on May Town Meeting Warrant and ballot question on May election ballot for renovations to the Police Station passed.	Bidding process underway. Construction expected to begin late 07.
6D	Clean catch basins	Highway	Clean basins	On going program. All basins cleaned annually. Continue practice in place.	Yearly
6E	Sweep streets	Highway	Sweep Streets	On going program. All streets swept yearly and additionally as necessary. Continue practice in place.	Yearly

6F	Develop an inspection and maintenance plan	Highway	Records of inspections and maintenance.	Schedule posted at the Highway garage. Done routinely. Continue practice in place.	Yearly
----	--	---------	---	--	--------

6a. Additions

6I	Prevent stormwater contact with fueling station	Highway		Fuel blanket at the site and ongoing preventative measures in place.	Spill kits available
6J	Evaluate sediment loading to wetlands	Highway		Corrected with new washdown system which has been installed.	

7. BMPs for Meeting Total Maximum Daily Load (TMDL) Waste Load Allocations (WLA) << if applicable >>

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 3 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 4
7A	Develop a water quality strategy for 303d waters	Highway, Selectmen	Strategy developed	Still in progress. Not yet started.	Not done
7B	Implement BMPs from Water quality strategies	Highway, Selectmen		Still in progress. Not yet started.	Not done

7a. Additions – none

7b. WLA Assessment

Through improvements at the Highway Department and with the addition of a new washdown unit all town vehicles are now washed at the Highway Department. This will decrease the waste load allocation on many wetland areas in town including ones adjacent to the Highway Department, Fire Station, Police Department. Water Department foundry and Golf Course. Additionally, the Water Department has removed the stored material behind the foundry eliminating the migration of silt into neighboring sensitive wetland areas.

Part IV. Summary of Information Collected and Analyzed

Part V. Program Outputs & Accomplishments (OPTIONAL)

Programmatic

Stormwater management position created/staffed	(y/n)	No (contract services)
Annual program budget/expenditures	(\$)	0 (Developer escrow accounts funds contractors)

Education, Involvement, and Training

Estimated number of residents reached by education program(s)	(# or %)	Unknown
Stormwater management committee established	(y/n)	Yes
Stream teams established or supported	(# or y/n)	No
Shoreline clean-up participation or quantity of shoreline miles cleaned	(y/n or mi.)	N/A
Household Hazardous Waste Collection Days		
days sponsored	(#)1	One scheduled for July. Plus participation in consortium
community participation	(%)	Varies
material collected	(tons or gal)	Varies (annual report available)
School curricula implemented	(y/n)	Yes

Legal/Regulatory

		In Place Prior to Phase II	Under Review	Drafted	Adopted
Regulatory Mechanism Status (indicate with "X")					
▪	Illicit Discharge Detection & Elimination	BOH regs for subdiv.			X
▪	Erosion & Sediment Control	BOH regs for subdiv.			X
▪	Post-Development Stormwater Management	Planning Board regs for subdiv.			X
Accompanying Regulation Status (indicate with "X")					
▪	Illicit Discharge Detection & Elimination	BOH regs for subdiv.			X
▪	Erosion & Sediment Control	BOH regs for subdiv.			X
▪	Post-Development Stormwater Management	BOH			X

Mapping and Illicit Discharges

Outfall mapping complete		(%)	100
Estimated or actual number of outfalls		(#)	300
System-Wide mapping complete		(%)	100
Mapping method(s)			
▪ Paper/Mylar		(%)	
▪ CADD		(%)	100
▪ GIS		(%)	100
Outfalls inspected/screened		(# or %)	100%
Illicit discharges identified		(#)	0
Illicit connections removed		(#)	0
		(est. gpd)	
% of population on sewer		(%)	0
% of population on septic systems		(%)	100

Construction

Number of construction starts (>1-acre)	(#)	5
Estimated percentage of construction starts adequately regulated for erosion and sediment control	(%)	100%
Site inspections completed	(# or %)	100%
Tickets/Stop work orders issued	(# or %)	1
Fines collected	(# and \$)	
Complaints/concerns received from public	(#)	1

Post-Development Stormwater Management

Estimated percentage of development/redevelopment projects adequately regulated for post-construction stormwater control	(%)	100%
Site inspections completed	(# or %)	100%
Estimated volume of stormwater recharged	(gpy)	??

Operations and Maintenance

Average frequency of catch basin cleaning (non-commercial/non-arterial streets)	(times/yr)	1/yr
Average frequency of catch basin cleaning (commercial/arterial or other critical streets)	(times/yr)	1/yr
Total number of structures cleaned	(#)	2,600
Storm drain cleaned	(LF or mi.)	89 miles
Qty. of screenings/debris removed from storm sewer infrastructure	(lbs. or tons)	240 tons
Disposal or use of sweepings (landfill, POTW, compost, recycle for sand, beneficial use, etc.)		Compost recycling
Cost of screenings disposal – Compost Screening	(\$)	\$7,400
Grinding brush and stumps -3,400 cubic yards	(\$)	\$4,000
Average frequency of street sweeping (non-commercial/non-arterial streets)	(times/yr)	1/yr
Average frequency of street sweeping (commercial/arterial or other critical streets)	(times/yr)	1/yr
Qty. of sand/debris collected by sweeping	(lbs. or tons)	605 tons
Disposal of sweepings (landfill, POTW, compost, beneficial use, etc.)	(location)	Recycling Ctr.
Cost of sweepings disposal	(\$)	0
Vacuum street sweepers purchased/leased	(#)	0 (1 - mechanical)

Vacuum street sweepers specified in contracts	(y/n)	No
---	-------	----

Reduction in application on public land of: ("N/A" = never used; "100%" = elimination)			
▪ Fertilizers	ALL ORGANIC MATERIAL USED	(lbs. or %)	50 %
▪ Herbicides		(lbs. or %)	100 %
▪ Pesticides		(lbs. or %)	100 %

Anti-/De-Icing products and ratios	NaCl, CaCl ₂ , MgCl ₂ CMA Kac, KCl, Sand	State bid specs.
Pre-wetting techniques utilized	(y/n)	No
Manual control spreaders used	(y/n)	Yes
Automatic or Zero-velocity spreaders used	(y/n)	No
Estimated net reduction in typical year salt application	(lbs. or %)	15%
Salt pile(s) covered in storage shed(s)	(y/n)	Yes
Storage shed(s) in design or under construction	(y/n)	No. In place.